
HP 3000 Computer Systems



MPE V Tables Manual for MPE V/E, Version G.01.00



HP 3000 Computer Systems

MPE V TABLES MANUAL for MPE V/E, Version G.01.00



19447 PRUNERIDGE AVENUE, CUPERTINO, CA 95014

Part No. 32033-90040 E0185

CAUTION

The normal checks and limitations that apply to the standard MPE users are bypassed in Privileged Mode. It is possible for a Privileged Mode program to destroy file integrity including the MPE operating system software itself. Upon request Hewlett-Packard will investigate and attempt to resolve problems resulting from the use of Privileged Mode code. This service is available on a time and materials billing basis. However, Hewlett-Packard will not support, correct, or attend to any modifications of the MPE operating system software.

NOTICE

The information contained in this manual is proprietary and may not be disclosed to third parties. The terms and conditions of release of this information to the recipient are governed by the agreement executed at and between Hewlett-Packard and the recipient regarding the HP 3000 internal MPE V System Table Structures, including the MPE V Tables Manual for MPE V Operating System.

Hewlett-Packard does not warrant the accuracy or completeness of the information contained in this manual. Hewlett-Packard may make revisions to the MPE operating system or CPU firmware that may affect the information and specifications contained herein. Hewlett-Packard shall have no obligation to provide the recipient with notification of revisions, corrections, or updates regarding the information contained herein.

Hewlett-Packard shall not be responsible for any loss or damage to the recipient, its customers, or any third party caused by the recipient's use of the information provided herein.

LIST OF EFFECTIVE PAGES

The List of Effective Pages gives the date of the current edition, and lists the dates of all changed pages. Unchanged pages are listed as "ORIGINAL". Within the manual, any page changed since the last edition is indicated by printing the date the changes were made on the bottom of the page. Changes are marked with a vertical bar in the margin. If an update is incorporated when an edition is reprinted, these bars and dates remain. No information is incorporated into a reprinting unless it appears as a prior update.

First Edition	• • • • • • • • • •	January 1985
Effective Pages		Date
A T T		TANI 1095

PRINTING HISTORY

New editions are complete revisions of the manual. Update packages, which are issued between editions, contain additional and replacement pages to be merged into the manual by the customer. The date on the title page and back cover of the manual changes only when a new edition is published. When an edition is reprinted, all the prior updates to the edition are incorporated. No information is incorporated into a reprinting unless it appears as a prior update.

The software date code number printed alongside the date indicates the version level of the software product at the time the manual edition or update was issued. Many product updates and fixes do not require manual changes, and conversely, manual corrections may be done without accompanying product changes. Therefore, do not expect a one-to-one correspondence between product updates and manual updates.

First Edition JAN 1985 G.01.00

CONTENTS

PREFACE	xix
CHAPTER 1 MEMORY LAYOUT	
Fixed Low Memory (Series 44/48/64/68)	1-1
System Global Area	1-3
SysGlob Extension	. 1-15
SYSDB Words	. 1-18
SysGlob Word Definitions	. 1-18
Allow Mask Format	. 1-20
Logging Related Locations	. 1-21
FLAGX	. 1-21
Process Stop List General Layout	1-22
Entry Format	1-22
Pre-assigned Entries	1-22
Tre-assigned Entries	1_22
Initial Memory Allocation	1 24
Bank 0	1 26
Bank 1	. 1-23
CHAPTER 2 MEMORY MANAGEMENT TABLES	
Segment Table Structure	2-1
Pointers and DST #'s of Segment Table Components	2-2
Standard Object Identifier Format	2-3
DST Entry Formats	2-3
OCT Factor Formats	2-5
CST Entry Formats	2-3
ST Entry Field Descriptions	
CSTBLK Format	2-0
Program Blocks and the CSTXMAP	2-/
Entry Format - CST Extension Block	2-7
Fixed DST Entry Assignments	
Swap Tables	
SWAPTAB Entry 0 Format	
SWAPTAB Unassigned Entry Format	
Segment Locality Lists (SLL)	
SLL Header Format	. 2-14
SLL List Entry Format	. 2-15
Special Request Table	
Main Memory Region Headers and Trailers	. 2-18
Global Region Trailer	. 2-19
Global Region Header (Available Regions)	. 2-19
Subregion Header (Available Regions)	2-20
Global Region Header (Reserved Regions)	2-21
Subregion Header (Reserved Regions)	2-22
Global Region Header (Assigned Regions)	2-22
Cubracian Handar (Assigned Pagians)	2-23
Subregion Header (Assigned Regions)	2-24
Subregion Header (Cached Regions)	2 24
Region Header and Trailer Field Descriptions	. 2-20
Space Allocation Structures	. 2-28

CHAPTER 3 DISC LAYOUT

System Disc Layout	3-1
Disc Label (Sector 0 of Disc)	1-4
System Volume	1-4
Serial Volume	, . }~6
Slave Volume	1-9
Defective Tracks Table (Sector 1 of Disc)	-11
Defective Sector Table (DSCT Sector 1 of Disc)	-12
Reserved Area Bit Map (Sector 4 of the System Disc)	-13
Disc Cold Load Information Table (Sectors 28-30)	-14
INITIAL Program CST Map	-19
SYSDUMP/INITIAL Communication Record	-2n
Cold Load Information Table Extension	-22
Virtual Disc Space Management Structures	-22 -23
Virtual Disc Space Management Table 3-	-23
General Structure	-23
VDSMTAB Entry 0 Format	-24
VDSMTAB General Entry Format	-25
Volume Table	-25 -26
Typical Private Volume Entry	-20 -27
Typical System Volume Entry 3-	. 2 R
	~~
CHAPTER 4 DIRECTORY	
Introduction to the Directory	- 1
Overview of Directory	
Overview of Directory	-2
Directory Data Segment	-2 -3
Directory Data Segment	-2 -3 -5
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4	-2 -3 -5
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4-	-2 -3 -5 -6
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4-	-2 -3 -5 -6 -10
Directory Data Segment	-2 -3 -5 -6 -10
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4-	-2 -3 -5 -6 -10 -11
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4-	-2 -3 -5 -10 -11 -12
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4-	-2 -3 -6 -10 -11 -12 -14
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4-	-2 -3 -5 -6 -10 -11 -12 -14 -16
Directory Data Segment	1-2 1-3 1-5 1-6 1-6 11 11 11 12 12 14 16
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- Group Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4-	1-2 1-3 1-5 1-6 10 11 11 12 12 14 16 17
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4- Volume Set Definition Entry 4-	1-2 1-3 1-5 1-6 10 11 12 12 14 16 17
Directory Data Segment	-2 -3 -5 -6 -6 -10 -11 -12 -14 -16 -17 -18 -19 -20
Directory Data Segment Directory Pointer Area Directory Space Data Segment (DIRSDS) Directory Structure Directory Definitions Index Block Prefix (10 Words) Index Entry (6 Words) Account Entry (%36 Words) Group Entry (51% Words) File Entry (File Pointer) (6 Words) User Entry (19 Words) User Attributes/Capabilities Volume Set Definition Entry GVSLINKAGE GVSINFO 4 4 4 4 4 4 4 4 4 4 4 4 4	1-2 1-3 1-5 1-6 11 11 12 14 16 17 18 19 20
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4- Volume Set Definition Entry 4- GVSLINKAGE 4- GVSINFO 4- GVSVOLFLAGS 4-	1-2 1-3 1-5 1-6 10 11 12 12 14 16 17 18 19 20 20
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4- Volume Set Definition Entry 4- GVSLINKAGE 4- GVSINFO 4- GVSVOLFLAGS 4- GVSVOLINFO 4-	1-2 1-3 1-5 1-6 10 11 12 12 14 16 17 18 20 20
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4- Volume Set Definition Entry 4- GVSLINKAGE 4- GVSVOLFLAGS 4- GVSVOLINFO 4- Volume Set Class Entry 4-	1-2 1-3 1-5 1-6 10 11 12 12 14 16 17 18 19 20 20 20 21
Directory Data Segment 4 Directory Pointer Area 4 Directory Space Data Segment (DIRSDS) 4 Directory Structure 4- Directory Definitions 4- Index Block Prefix (10 Words) 4- Index Entry (6 Words) 4- Account Entry (%36 Words) 4- Group Entry (51% Words) 4- File Entry (File Pointer) (6 Words) 4- User Entry (19 Words) 4- User Attributes/Capabilities 4- Volume Set Definition Entry 4- GVSLINKAGE 4- GVSINFO 4- GVSVOLFLAGS 4- GVSVOLINFO 4-	1-2 1-3 1-5 1-6 10 11 11 12 14 16 17 18 20 20 21 22

CHAPTER 5 LOCK RESOURCES			
SIR# Allocation DST %53		 	 5-!
Sir's Ordered by Sir Number		 . .	 5-1
Sir's Ordered by Ranking		 	 5-2
SIR Table Information		 	 5-3
SIR Entry Formats			 5-4
RIN Table General Layout (Initialized State)			5-5
Allocation and Locking of Local RINS			
Allocation and Locking of File RINS			
Allocation and Locking of Global RINS		 	 5-8
CHAPTER 6 FILE SYSTEM			
File System Overview		 	 6-
Buffers		 	 6-2
Table Formats			 6-3
File System Section of PCBX (PXFILE)		 	 6-1
Overhead			
PXFILE Control Block Table (PXFCBT)			
Available Block			
Active File Table (AFT)			
File Control Block Table (CBTAB)		 	 0-1.
Vector Table			
Control Block Area			
Access Control Block (ACB)			
Logical Access Control Block (LACB)		 	 6-1
Physical Access Control Block (PACB)		 	 6-2
File Control Block (FCB)			
File Label (FLAB)		 	 6-4
File Multi-Access Vector Table (FMAVT)		 	 6-5
Zero Entry Format		 	 6-5
Typical Entry Format		 	 6-5
System Global Area (SYSGLOB)		 	 6-5
SIRs, Locks, and Deadlocks		 	 6-5
Shared CBT DST		 	 6-5
CHAPTER 7 PROCESS TABLES			
Process Control Block Table Structure and Format		 	 7-
Fixed Cells Related to PCB		 	 7-
PCB Entry 0 Format			
Unassigned PCB Entry Format			
Assigned PCB Entry Format			
Process Control Block Extension (PCBX) Structure and	Format	 	 7-
PCBX General Structure			
PXGLOB Format			
PXFIXED Assignments		 	 7-1
PXFIXED Expansion Bitmap		 	 7_1
File System Section of PCBX (PXFILE)			
THE DYSIGH DECIION OF FCDA (FAFILE)		 	

Overhead	
PXFILE Control Block Table (PXFCBT)	
Available Block	
PCBX for Core Resident System Process Stacks	
Process To Process Communication Table	
Subsystem Reserved DL Area	
FORTRAN Logical Unit Table (FLUT)	7-21
CHAPTER 8 JOB TABLES	
Job Tables Overview	. 8-1
Job Master Table Structure (JMAT)	. 8-2
Job Master Table Entry (JMAT)	
Job States	
Process Job Cross Reference Table (PJXREF)	
Job Process Count Table (JPCNT)	
Job Cutoff Table (JCUT)	
Job Information Table (JIT)	
Allow Mask Format	
Job Directory Table (JDT)	
Job Data Segment Directory Entry (In JDT)	
Job Temporary File Entry (In JDT)	
File Equation Table Entry (In JDT)	
Job Line Equation Entry	
Job Control Word Table (JJCW)	
Aoptions and Foptions Word Breakdown	
PMASK Word Breakdown	
UCOP Request Queue (DST#9)	
UCOP Entry Format	
CHAPTER 9 RELOCATABLE OBJECT CODE	
USL Files Introduction	9-1
Record 0 and Overall USL File Format	
Data Descriptors, Passed Parameters	
Pascal	
Entry Type 0	
Entry Type 1	
Entry Type 2	. 9-8
Entry Type 3	9-11
Entry Type 4	9-11
Entry Type 5	9-14
Entry Type 6	9-15
Entry Type 7	9-17
Entry Type 8	9-19
Entry Header Format	9-21
Header Type 0	9-22
Header Type 1	9-22
Header Type 2	9-23
Header Type 3	9-23
Header Type 4	9-24
Header Type 5	9-24

	ስ ገና
Header Type 6	9-23
Header Type 7	9-23
Header Type 8	9-20
Header Type 9	9-27
Header Type 10	9-29
Header Type 11	9-29
OI File Format	9-30
torage Management	9-31
entry Point Directory	9-32
Cypical Directory Entry	9-33
Procedure Information Block	9-34
Headers	9-35
CHAPTER 10 PREPARED OBJECT CODE	
Program File Format	10-1
Flags	10-3
Elags?	10-4
CST Demanning Array	10-4
Seament Descriptor Array	10-4
Clobal Area Format	10-4
External List	10-3
Entry Point List	0-01
Code Segment With Patch Area	10-7
Datch Area	10-7
PMAP Information	10-8
DMAP Type Table	10-8
PMAP Records	10-9
Type 0 Segment PMAP Record	10-9
Type 1 Procedure PMAP Record	10-9
Type 2 Secondary Entry PMAP Record	10-10
SI File Format	10-11
Storage Management	10-13
Entry Point Directory	10-13
Typical Directory Entry	10-14
Code Segment Linkage Structure	10-15
Deference Table Structure	10-17
Reference Table (256 Maximum Entries)	10-18
Code Segment With Patch Area	10-15
Patch Area	10-19
PMAP Information	10-20
PMAP Type Table	10-20
PMAP Records	10-21
Type 0 Segment PMAP Record	10-2
Type 1 Procedure PMAP Record	10-2
Type 2 Secondary Entry PMAP Record	10-22
CHAPTER 11 LOADER	
	1 1
MPE Loader	11
Loader Segment Table (LST) Overview	11-

LST Overview											11-1
XLST Overiew				• •	• •	• •	• •	•	• •	• •	11-1
Loader Segment Table Primary DB				• •	• •	• •	• •	•	• •	• •	11-2
Directory Entries		• • •	• • •	• •	• •	• •		•	• •	• •	11-3
Loader Cache		• • •		• •	• •	• •	٠.	•	• •	• •	11-4 11-10
Cache Data Segment Format			• • •	• •	• •	• •		•	• •	• •	11-10
Bucket Format	• • •	• • •	• • •	• •	• •	• •	• •	•	• •	•	11-10
Loader Communication Table (LCT)	• • •	• • •	• • •	• •	• •	• •	• •	•	•	• •	11-10 11 11
Form Incoming to Loader (Load/Allocate Program)	• • •		• • •	• •	• •	• •	• •	•	•	• • :	1 1
Form Incoming to Loader (Load/Allocate Procedure		• • •	• • •	• •	• •	• •	• •	•	•	• • •	11-11
Form Returned (No Error)	.,	• • •		• •	• •	• •	• •	•	•	• • •	11-12
Form Returned (Error Occurred).	• • •	• • •		• •	• •	• •	• •	• •	•	• • •	11-13
Logical Segment Transform Table (LSTT)	• • •			• •	• •	• •	• •	• •	•	• • !	11-13
5				• •	• •	• •	• •		•	• • •	11-14
CHAPTER 12 PRIVATE VOLUMES / SERIAL DISC	С										
Mounted Volume Table (MVTAB)											12-1
Private Volume User Table (PVUSER)						• •	• •	• •	•	• •	12-1
Bind Names Data Segment			• • •	• •	• •	• •	• •	• •	•	• •	12-4
Serial Disc Tables and Data Structures			• • •	• •	• •	• •	• •	• •	•	• •	12-0
Data Record Format	• • •	• • •		• •	• •	• •	• •	• •	•	• •	12-0
End of File Format	• • •	• • •		• •	• •	• •	• •	• •	•	• •	12-0
Contiguous Block Format	• • • •	• • • •		• •	• •	• •	• •	• •	•		12-7
Hole Format	• • • •	• • •	• • •	• •	•	• •	• •	• •	•	1	2-10
Gap Table Format	• • •	• • • •	• •	• •	•	• •	• •	• •	•	i	2-10
SDISC Extra Data Segments	• • •	• • • •	• •	• •	•	• •	• •	• •	٠	1	2-11
										1	2-13
Serial Disc Organization					•		•			1	1 15
Serial Disc Organization	• • • •	• • •	• •						•	1	2-15
Serial Disc Organization	• • • •		• •	• •	•	• •	• •		•	1	2-15
CHAPTER 13 I/O	• • • •	• • •	• •	• •	•	• •	• •		•	1	2-15
CHAPTER 13 I/O I/O Table Linkage					•	• •	• •		•	1	2-15
CHAPTER 13 I/O I/O Table Linkage				• • •			• •		•	1	2-15 13-1 13-2
CHAPTER 13 I/O I/O Table Linkage	• • • •			• • •			• •			1	2-15 13-1 13-2
CHAPTER 13 I/O I/O Table Linkage	• • • •			• • •	•		• •		•	1	2-15 13-1 13-2 13-3
CHAPTER 13 I/O I/O Table Linkage	• • • •			• • •	•					1	2-15 13-1 13-2 13-3 13-4
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices)										1	2-15 13-1 13-2 13-3 13-4 13-5 13-5
CHAPTER 13 I/O I/O Table Linkage					•		• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •		1	2-15 13-1 13-2 13-3 13-4 13-5 13-5
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices.								• • • • • • • • • • • • • • • • • • • •		1	2-15 13-1 13-2 13-3 13-4 13-5 13-5 13-6
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices. Entry for Tape Drives							• • • • • • • • • • • • • • • • • • • •				2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices. Entry for Tape Drives Entry for Disc Drives											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT)											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7
CHAPTER 13 I/O I/O Table Linkage Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Disc Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7 13-8 13-9
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format											2-15 13-1 13-2 13-3 13-4 13-5 13-5 13-6 13-7 13-7 13-8 13-9 13-9
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7 13-8 13-9 13-9
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices. Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX)											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7 13-9 13-9 13-9
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices. Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX) Overview of Data Segment											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-8 13-9 13-9 13-9 3-10 3-11
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX) Overview of Data Segment Zero Entry											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-8 13-9 13-9 13-9 3-10 3-11
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX) Overview of Data Segment Zero Entry Typical Entry Typical Entry											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-8 13-9 13-9 13-9 3-10 3-11 3-12
CHAPTER 13 I/O I/O Table Linkage Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format. Logical Device Table Extension (LDTX) Overview of Data Segment Zero Entry Typical Entry Typical Entry Typical Entry Typical Entry Typical Entry										1	2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7 13-8 13-9 13-9 13-9 13-10 3-11 3-11 3-12 3-12
CHAPTER 13 I/O I/O Table Linkage Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX) Overview of Data Segment Zero Entry Typical Entry Typical Entry Typical Entry Typical Entry Typical Entry Terminal Entry Serial or Foreign Disc Entry											2-15 13-1 13-2 13-3 13-4 13-5 13-5 13-6 13-7 13-7 13-9 13-9 13-9 13-11 3-11 3-12 3-13
CHAPTER 13 I/O I/O Table Linkage . Device Reference Table (DRT) Driver Linkage Table (DLT) Logical-To-Physical Device Table (LPDT) Entry 0 . Typical Entry (Virtual Devices) Typical Entry (All Real Devices) Entry for Terminal-Like Devices Entry for Tape Drives Entry for Disc Drives Logical Device Table (LDT) Overview of Data Segment Zero Entry Format Typical Entry Format Logical Device Table Extension (LDTX) Overview of Data Segment Zero Entry Typical Entry Typical Entry											2-15 13-1 13-2 13-3 13-4 13-5 13-6 13-7 13-7 13-9 13-9 13-9 13-11 3-11 3-12 3-13 3-14

Device Class Table (DCT)	15
Overview of Data Segment	15
Header Entry Format	15
Device Class Table Typical Entry Format	16
Discussion	16
Terminal Descriptor Table Typical Entry Format	18
interrupt Linkage Table (ILT) for HP-IB Systems	19
Device Information Table (DIT)	21
DIT for HP-IR Systems	21
DIT Terminology for HP-IB Systems	22
Device Information Table (DIT) for CIPER	.77
DIT for Channel Devices	-23
DIT for 7905/7906/7920/7925	-21
From and Retry Information	-29
CS 80 Disc Device Information Table (DIT)	- 30
DIT for 7970 Magnetic Tane	- 34
DIT for 7976 Magnetic Tane	- 30
Card Reader DIT	- 39
Card Peader DIT Field Definitions	-4U
Device Information Table for HP-IR Card Reader	-41
2608 Line Printer DIT (HP-IR Systems)	-43
2608 Line Printer Status	-43
UP 26194 or 2613 Line Printer DIT (HP-IR Systems)	-40
HP 26804/26884 DIT	-48
I/O Status Block	- 20
Disc Request Table and Disc Requests	-33
DISCREOTAR 13°	-33
Disc Request Table	-54
Disc Pequest Table Entry () Format	-54
Disc Request Flement Format	-55
I/O Queue (IOO) Table Layout	-28
I/O Queue Flement (IOO)	-00
I/O System Status Returns	-62
I/O Queue Flement for 7976A Magnetic Tape	-04
I/O Queue Flement (IOO) for CIPER	-00
HP-IR CIPER Physical Driver Request Codes	-6/
CIDED Driver Peturn Status Codes	-67
2608 Line Printer I/O Queue Element (HP-IB Systems)	-68
2608 Line Printer Request Codes	-/1
2619A & 2631 Line Printer I/O Queue Element (HP-IB Systems)	- / Z
2610 Line Printer Request Codes	-/3
2631 Line Printer Request Codes (HP-IB)	- / 0
I/O Queue Flement for HP-IR Card Reader	-//
CS 80 Disc Request I/O Queue Element (IOO)	- / 9
CS 80 Integrated Cartridge Tage Request	-82
SRIJE Table I avout	-83
Table Element Allocation (SBUF)	-80
ICS Global	-88
ICS Global Cells With Initial Values	-90
CS 80 Disc Interrupt Linkage Table (ILT)	-91

CHAPTER 14 SPOOLING

Input Device Directory/Output Device	Dir	ecto	orv.																	14-
Overview of Table Structure						·		•	• •	• •	•	• •	•	• •	•	•	•	•	• •	14-
Entry 0 (Overall Table Definitions)						•	• •	•	• •	• •	•	• •	•	• •	•	•	•	•		1/-
Typical Head Entry			•	•	•	•	• •	•	• •	• •	•	• •	•	• •	•	•	•	•	• •	14-
Typical Subentry		• •	•	•	• •	•	• •	•	• •	• •	•	• •	٠	• •	•	• •	•	•	• •	14-
SPOOK Tape Format	• •	• •	• •	•	• •	•	•	•	• •	• •	٠	• •	•	• •	•	• •	•	•	• •	14-
Label Record	• •	• •	• •	•		•	• •	•	• •		•	• •	•		•		•	•	• •	14-0
File Directory	• •		• •	•		•	• •	•	• •	• •	•	• •	•	• •	•		•	•	• •	14-0
Device and Class Directory	• •	• •	• •	•	• •	•	• •	•	•	• •	•	• •	•	• •	•		•	•	• •	14-
Logical Device Entry	• •	• •	• •	•	• •	•	• •	•	•	• •	•	• •	•	• •	•		•	•	• •	14-
Logical Device Entry	• •	• •	• •	•	• •	•	• •	•	•		٠	• •	•		٠		•	•		14-
Device Class Entry	• •	• •	• •	•		•	• •	•	•		•		٠	• •	•		•	•		14-8
Spoolfile Format	• •	• •		•		•	• •	•	•		٠		•		•		•	•		14-8
Spoolfile Block Format	• •	• •	• •	٠	• •	•		٠.	•		•		•		٠		•	•		14-8
Spoolfile Record Format	• •	• •		•		•			•		•		•							14-8
User Labels Information	• •			•					•				•							14-9
CILA DIED 45 TIMES COLUMN					_															
CHAPTER 15 UNIFIED COMMAND	LAN	NGI	U A (GE	(U	INC	CL)													
70 - 1 7 C																				
Reply Information Table (RIT)																				15-1
Message System General Description .														_						15-2
Message Catalog												_		_						15-2
MAKECAT Program									_											15-4
Message System CATALOG.PUB.SYS	S .																			15-5
Message Set Directory																				15-6
HELP Subsystem														Ī		. •	•	•	•	15-7
UDC Directory																				15-8
UDC's COMMAND.PUB.SYS										•	•	•	•	•	• •	•	•	• •	٠	15_0
CI Stack Definition							•	•	•	• •	• •	•	• •	•	• •	•	•	• •	٠,	13-7 15-11
Field Definitions					•	• •	•	• •	•	•	• •	•	• •	•	• •	•	•	• •	• 1	15-11
Association DST Layout		• •	• •	• •	•	• •	•	• •	•	•	• •	•	• •	٠	• •	•	•	• •		13-12
Application Message Facility	• •	• •	• •	• •	•	• •	•		• •	•	• •	•	• •	•	• •	•	•	• •	. 1	13-13
NLS Message Catalog/DST Overview .	• • •	• •	• •	• •	•	• •	•	• •	• •	•	• •	•	• •	•	• •	•	•		٠.	13-14
Formatted Catalog File Structure	• • •	• •	• •	• •	•	• •	•	• •	• •	•	• •	•	• •	•		•	•		. 1	15-14
Cache Directory	• • •	• •	• •	• •	•	• •	•	• •	• •	•	• •	•	• •	•	• •	٠	٠	• •	. 1	5-15
Message Cache Format	• • •	• •	• •	• •	٠	• •	•	• •		٠	• •	٠		٠		•	•		. 1	5-16
Message Cache Format		• •	• •	• •	•	• •	•	• •		•	• •	•	٠.	•		•	•		. 1	5-17
Data Format	• • •	•	• •	• •	•	• •	•	• •	• •	•	• •	•		٠		•	•		. 1	5-18
Message DST (MDST) Structure		•	• •	• •	•	• •	٠	• •		٠		•		•		•	•		. 1	5-18
Message DST Overview		•	• •	• •	•	• •	•			٠		•		٠	٠.	•	•		. 1	5-18
Message DST Overhead		•	• •	• •	•	• •	٠			•		٠		•			•		. 1	5-19
Message DST Resident Cache Area		•	• •	• •	•		•			•		•							. 1	5-20
MDST Cache Directory		•			•					•									. 1	5-21
MDS1 Message Cache Format	. 	•			٠														. 1	5-22
CHAPTER 16 SYSDUMP/INITIAL																				
CONFDATA File																				16-1
Record 0 of CONFDATA File (CTAB	0) .																			16-1
Record 1 of CONFDATA File (CTAB)																			16-2
NITIAL/PROGEN Communication DS7	Γ																			16-4
Defdata Table Lookup File													٠	-	•	•	•	•	•	16-5

Defdata Table Lookup File Header Format								• •.				•		•		16	-5 -5
Defdata Table Lookup File Entry Format				•	• •	• •	• •	• •	• •	•		•	• •	•	• •	16	_ R
DEVDATA.PUB.SYS				•	• •	• •	• •		• •	٠		•	• •	•	• •	16	- S
Overview		• •	• •	•	• •		• •	• •		•		•	• •	•		16	_ Q
Parameter Record	• • •		•	•	• •		• •	• •		•	• •	•	• •	•		16-	10
Driver Table				•	• •	• •	• •	• •	• •	•	• •	•	• •	•	• •	16-	11
SYSDUMP Format				•	• •	• •	• •			•		•	• •	٠		16-	11
WSC Table Format			•	•		• •		• •		•		•		٠		16-	13
Series 64/68 WCS Table Format		• •	•	•		• •		• •		٠		•		٠		10-	13
Store Tape Format			•			• •				٠		٠		٠		. 10-	14
First Volume			•			• •				•		٠	• •	•		. 10-	14
Subsequent Volumes			•			• •				•		٠	• •	•		. 10-	10
End of Volume			•	• •		• •	• •	• •		•		٠	• •	٠	• •	. 10-	1 /
CHAPTER 17 MISCELLANEOUS																	
Labeled Tape Subsystem																. 17	-1
Tane Label Table														•		. 17	-6
LCB Entry Format														٠		. 17	-8
VCB Entry Format																. 17-	10
Volume Recognition																. 17-	12
Opening a File																. 17-	12
Reading and Writing Files																. 17-	12
Closing Files																. 17-	13
Store-Restore																. 17-	13
Miscellaneous																. 17-	13
Breakpoint Table																. 17-	·14
PCB Breakpoint Extension Table																. 17-	-15
Breakpoint Entry Table																. 17-	-15
Active Entry																. 17-	-16
Timer Request List (TRL)																. 17-	-19
MPE User Logging	•	•														. 17-	-21
General Design Overview	• • •	•	•	•												. 17-	-21
Hardware Environment	• • •	•	•	• •	• •	•	•	•								. 17-	-21
Software Environment	• •	•	•	• •	• •	• •	• •	•	•	• •	٠					. 17-	-21
Design Narrative	• •	•	•	• •	• •	• •	• •	•	•	• •	•	•				. 17-	-21
Error Recovery Description	• •	•	• •	• •	• •			•	•	• •	•	• •	• •	•	•	17-	-22
Design Structures	• •	• •	• •	• •	• •	• •	• •	•	•	• •	•	• •		•	•	17-	-23
User Logging Table	• •	• •	• •	• •	• •	• •	• •	•	•	• •	•	• •	• •	•	•	17.	-23
User Logging Table	• •	• •		• •	• •			•	•	• •	•	• •	• •	•	•	17.	-29
User Logging Buffer	• •	• •	• •	• •	• •		• •	•	•		•	• •	•	•	•	17.	-39
User Logging Identifier Table	• •	• •	• •	• •	• •	• •	• •	•	• •	• •	•	• •	•		•	17.	-43
Logging Record Format	 OTFAI			• •	• •	• •	• •	•	• •	• •	•	• •	•		٠	17.	-46
Measurement Information Table (MEASINFO	JIAI	3)		• •	• •	• •	• •	•	• •	• •	•		•	• •	•	. 17	- 40
CHAPTER 18 MESSAGE FILES																	
Message File Data Structures																. 1	8-1
File Structure																. 1	8-1
Block Structure																. 1	8-2
Record Format																. 1	8-2
Header Format																. 1	8-3
Message Access Control Block																. 1	8-3

MMSTAT Definitions														1	8-
File System Basic IPC Definition	ns													1.9	2_1
General Benavior														1.9	? _ 1
Port Data Structures														1.8	₹-1
Port Data Segment														1.9	2 _ 1
Port With Two Outstanding	Messages													1.8	₹-1
Port Number														1 8	2 - 1 4
Port DST Number Array														1 8	2 – 1 4
Port Data Segment Global A	rea													1 8	2-1
Port														1 0	14
Message Queue Entry (MQE)														1 2	1-11
riie System Message Files														1 2	1-11
Timer List Entry (TLE)														1 2	-19
MMSTAT Definitions												•	• •	1.8	- 1 3
									•	• •	• •	• •	• •		
CHAPTER 19 MPE MEMORY R	ESIDEN'	T ME	SSAG	E FA	CIL	ITY	•								
Overview of Facility														. 1	9-1
Message Intrinsics														1	Q_1
SENDMSG														1	0_1
PORTSTATUS														1	0_1
RECEIVEMSG														1	9-2
Supporting Data Structures														1	0_2
Message Harbor Table														. 1	9-3
CHAPTER 20 MMSTATS EVENT															
MMSTAT Event Group 0 (Memory	· · · · · · · · · · · · · · · · · · ·	· · ·	 Ezzame			• •	• •	• •	•	• •		• •		. 2	0-1
Event 0	Manage	memt	Eveni	8) .	• •	• •	• •	• •	•	• •	• •	• •		. 20	0-4
Event 1	• • • •	• • •	• • •		• •	• •	• •	• •	•	• •	• •	• •	• •	. 20	0-4
Event 2	• • • •	• • • •	• • •		• •	• •	• •	• •	•	• •	• •		• •	. 20	0-5
Event 4	• • • •	• • •	• • •	• • •	• •	• •	• •	• • •	•	• •	• •		• •	. 20	0-6
Event 5	• • • •	• • • •	• • •		• •	• •	• •		•	• •	• •	• •	• •	. 20	0-7
Event 6	• • • •	• • • •	• • •	• • •	• •	• •	• •		•	• •	• • •		• •	. 20	0-8
Event 7 (%7)	• • • •	• • • •	• • •		• •	• •	• •		•	•	• • •			. 20	U-9
Event 8 (%10)	• • • •	• • • •	• • •		• •	• •	• • •		•	•	• • •		• •	. 20	J-9
MMSTAT Event Group 1 (Memory	Manage	 .)	• • •	• • •	• •	• •	• • •		• •	•	• •		• •	. 20-	-10
Event 12 (%14)	Wanage.	.,	• • •	• • •	• •	• •	• • •	• • •		•			• •	. 20-	-11
Event 13 (%15)	• • • • •		• • •	• • •	• •	• •	• • •	• •	• •	•		•	• •	. 20-	-11
Event 14 (%16)	• • • • •		• • •	• •	• •	• •	• • •	• •	٠.	•	• •	•	• •	. 20-	-11
Event 15 (%17)	• • • • •	• • • •	• • •	• •	• •	• •	• • •	• •	٠.	•	• •	•	• •	. 20-	-12
Event 16 (%20)	• • • • •		• • •	• •	• •	• •		• •		•	• •	•	• •	. 20-	-12
Event 17 (%21)		• • • •		• •	• •	• •				•	• •	•	• •	. 20-	-13
Event 18 (%22)		• • •		• •	• •	• •			٠.	•	• •	•	• •	. 20-	-13
Event 18 (%22)	• • • • •	• • •		• •	• •	• •		• •		•	٠.	•		. 20-	-13
Event -20 (-%24)	• • • • •	• • •		• •	• •	• •				•		•		. 20-	-14
Event -21 (%25)				• •	• •	• •				•		•		. 20-	-14
Event -21 (%25)	• • • • •			• •	• •	• •		• •	٠.		٠.			. 20-	-14
Event -23 (-%27)		• • •			• •	• •		٠.						. 20-	-15
MMSTAT Event Group 4 (Scheduli	 na)			• •	• •	• •				٠.			•	. 20-	15
Event 40 (%50)				• •	• •	• •	• • •				٠.		•	. 20-	

						20 17
MMMSTAT Event Group 5 MMSTAT Event Group 6 (FILESYS)			 	• • • • • •		20-17
Event -60(%74)						
Event -61(%75)						
Event -60(%74)			 			20-19
Event -61(%75)						
Event -62(%76)						
Event -63(%77)			 			20-21
Event -64(%100)						
Event -65(%101)			 			20-23
Event -66(%102)						
Event -67(%103)						
Event -68(%104)			 			20-25
Event -69 (%105)			 			20-25
MMSTAT Event Group 7 (FILESYS						
Event -70 (%106)			 			20-26
Event -71 (%107)			 			20-26
Event -72 (%110)						
Event -74 (%112)						
Event -75 (%113)						
Event -76 (%114)			 			20-28
Event -77 (%115)						20-29
Event -78 (%116)						20-29
Event -79 (%117)		• • • •	 			20-30
MMSTAT Event Group 8			 			20-31
Event -80 (%120)						
Event -81 (%121)						
Event 83 (%123)						
Event 84 (%124)						
Event 86 (%126)			 			20-33
Event 87 (%127)						
Event 88 (%130)						
Event 88 (%130)						
MMSTAT Event Group 9 (Disc I/O						
Event 90 (%132)	Requests		 			. 20-33 20-35
Event -98 (%142)						
MMSTAT Event Group 10						
Event 100 (%144)						
Event 101 (%145)			 			. 20-36
MMSTAT Event Group 11			 		. .	. 20-37
Event -110 (%156)			 		· · · · · · ·	. 20-37
Event -111 (%157)			 		· · · · · · ·	. 20-37
MMSTAT Event Group 12			 			. 20-38
Event 120 (%170)			 			. 20-38
Event 125 (%175)			 · · · · ·		. 	. 20-38
MMSTAT Event Group 13			 · • • • •			. 20-39
Event 139 (%213)			 			. 20-39
MMSTAT Event Group 14 (CS/300	0)		 			. 20-40
Event 140 (%214)			 . 			. 20-40
Event 142 (%216)			 . 			. 20-41
Event 144 (%220)			 			. 20-42
Event 146 (%222)			 			. 20-42

Event 147 (%223)	
Event 149 (%225)	. 20-43
1MSTAT Event Group 15 (CS/3000)	. 20-4
Event 150 (%226)	. 20-4
Event 152 (%230)	
Event 153 (%231)	
Event 154 (%232)	
Event 155 (%233)	
fMSTAT Event Group 16	
Event 160 (%240)	
IMSTAT Event Group 19	
Event 191 (%277)	
Event 192 (%300)	
Event 193 (%301)	
Event 194 (%302)	
Event 195 (%303)	
IMSTAT Event Group 20	
Event 200 (%310)	. 20-52
Event 201 (%311)	
IMSTAT Event Group 21 Process Creations and	
Terminations Logical Process Table	
Event -211 (%323)	20-53
IMSTAT Event Group 22	20-5
Time Stamp of Event Trace Enable and Disable	20-34
Event 221 (%335)	
Event 221 (6333)	. 20-34
Event 222 (%336)	
Event -223 (-%337)	20-53
Event -224 -(%340)	. 20-56
Event -225 (-%341)	. 20-56
Event -226 (-%342)	. 20-56
Event -227 (-%343)	
Event -228 (%344)	20-57
Event -229 (-%345)	20-57
IMSTAT Event Group 23 (Terminal I/O)	20-58
Event 230 (%346)	20-58
Event 231 (%347)	20-58
Event 232 (%350)	20-59
Event 233 (%351)	20-59
Event 234 (%352)	
Event 235 (%353)	
Event 236 (%354)	
Event 237 (%355)	
Event 238 (%356)	20-61
[MSTAT Event Group 24 (Power Fail)	20-62
Event 240 (%360)	20-62
HAPTER 21 ROOTFILE LAYOUT	
eneral Rootfile Layout	21_1
Root File Label 0	
Root File Labels 1 and 2	21-2
Root File Label 3	
KOOL FIRE LAUCH 3	71-6

Root File- Next Label	21-7
Item/Set Read/Write Table Format	21-8
Root File Record 0	21-9
Root File Record 1	21-10
Root File- Next Record	21-11
Data Set Control Blocks (DSCB)- General Layout	21-12
Data Set Control Block (Global Area)	21-13
Data Set Control Block (Item Numbers)	21-14
Data Set Control Block (Record Definition Item Displacement)	21-14
Data Set Control Block (Path Table)	21-15
General Data Set Layout	21-15
Data Set User Label 0	21-16
Data Set Records	21–16
CHAPTER 22 DISC FREE SPACE MAP	
Disc Resident Data Structures	22-1
Bit Map	22-1
Descriptor Table (DT)	22-1
Virtual Memory Resident Data Structures	22-2
Disc Free Space Data Segment	22-2
CHAPTER 23 MPE DISC CACHING	
Disc Caching Overview	23-1
Disc Caching Tables Overview	23-4
Cache Directory Table	23-6
Header Entry	23-7
Device Entry	23-10
Mapped Domain Entry	23-13
Logical Disc Request Table	23-16
Logical Disc Request Entry	23-17
CHAPTER 24 NATIVE LANGUAGE SUPPORT	
NL/3000 INTERNAL TABLE STRUCTURE	24-1
Native Language Support (NLS) Table Overview	24-1
Native Language Table (NLT)	24-2
NLT Overhead Table	24-3
NLT Installed Language Table Format	
NLT Installed Character Set Table Format	
NLT Character Attributes Table	
Language DST	
LDST Overhead table	
LDST Translation Tables	
LDST Collating Sequence Table	
Overview	
Class One Languages	
Class Two Languages	
Class Two Languages	24-11
Class Three Languages	

2:1 Character Mapping Table.				 										 24	-1	3
1:2 Character Mapping Table.																
Class Four Languages																
LDST Custom Data Table Format				 										24	-1	6
LDST National Special Table														24	-1	7
Date Formats for Japan and Taiwan.				 									 	24	-1	7
National Dependent Table Formats.													 	24	-1	8
Japanese Date Format																
Taiwanese Date Format																

PREFACE

The second edition of the MPE V/E Tables Manual describes the internal table organization of the MPE V operating system. It is intended for the technically sophisticated user with Privilege Mode capability. We strongly discourage modifying the table structure because you may destroy the operating system. The following caution applies:

CAUTION

The normal checks and limitations that apply to the standard MPE users are bypassed in Privileged Mode. It is possible for a Privileged Mode program to destroy file integrity including the MPE operating system software itself. Upon request Hewlett-Packard will investigate and attempt to resolve problems resulting from the use of Privileged Mode code. This service is available on a time and materials billing basis. However, Hewlett-Packard will not support, correct, or attend to any modifications of the MPE operating system software.

The major highlights of this edition include:

- A new chapter (24), "Native Language Support". It includes all of the character sets to support the installed languages.
- Expanded Chapter 15. It now includes Native Language Support Application Message Facility.
- A new table, DEFDATA Table. It describes the default configuration for for HP-IB devices. This table is located in Chapter 16.
- A new table, Process Job Cross Reference Table. It determines the job/session main process (Command Interpreter) for any process on the system. This table is located in Chapter 8.
- Additional fields support cartridge tape, job scheduling and all other features of release G.01.00.
 Many chapters reflect these changes.

We hope you will find this edition informative. Your comments and suggestions are welcome via the "Reader Comment Sheet" at the back of this manual.

Memory Layout

CHAPTER 1 MEMORY LAYOUT

Fixed Low Memory (Series 44/48/64/68)

X		DEC
0	CSTB (BASE OF CST TABLE)**	10
	XCSTB (POINTER TO CURRENT EXECUTING PROGRAM BLOCK)	
2	DSTB (BASE OF DST TABLE)**	į2
3	0	3
4	CPCB (CURRENT PCB INDEX)**	4 >PCB REL
5	QI (INITIAL Q FOR ICS)**	5
61	ZI (INITIAL Z FOR ICS)**	[6
71	SYSTEM INTERRUPT MASK WORD**	7
10	DRTBANK (BANK OF DRT TABLE)	18
11	DRTADDR (BASE OF DRT TABLE)	9
12	DBBANK (FOR INITIAL'S STACK) *	110
13	DB (FOR INITIAL'S STACK) *	11
14		112
15		13
16		14
17		15
20		116
21	LR (INTERRUPT INTERVAL)+	17
22 1	EMPLR (TEMP STORAGE OF LIMIT REG)+	
23	LR (SYSTEM CLOCK LIMIT REGISTER) **	[19
24 / /		//// 20

Menory Layout

Fixed Low Memory (Series 44/48/64/68) (Cont.)

25 1	R (TIME	SINCE L	ST SOF	TIMER	INTERRUPT)**	21
26	SCST	(SYSTEM	CLOCK :	STATUS)	k*	122
27	SCLC	(SYSTEM	CLOCK	LAST COL	JNT)**	123
0-37						24-3

NOTE: All pointers are absolute addresses.

G.01.00 1- 2

G.01.00 1- 1

Menory Layout

System Global Area

SYSGLOB CST	OCTAL	1	2	3	4	5	6	7	8	9	0	1	1	3	1	1 5	NAME
CST BASE	- :					SYS	GLO	8									-
3					C	ST	BAS	Ε									сѕт
SURPTAB BASE SLL	2				D	ST	BAS	Ε									DST
TOQ BASE TOQ BASE TOQ BASE TOQ BASE TOQ BASE TOQ BASE TOQ BUT TOQ BUT	3				P	СВ	BAS	E									PCB
6 SBUF BASE BUF 7 ICS QI ICS 10 LPDT BASE LPDT 11 SHON BASE SHON 12 TRL BASE TRL 13 JCUT BASE SIR 14 SIR BASE SDCTAB 15 JPCNT BASE JPCNT 16 TBUF BASE BUF 17 DISC REQUEST BASE DRQ 20 FIRST FREE MEHORY ADDRESS 21 TIME OF LAST CYCLE 23 RESERVED	4				SHA	PTF	18 E	ASE									SLL
1	5				I	OQ	BAS	E									100
10	6				SB	UF	BAS	E									BUF
11	7					I	S	I									ICS
TRL BASE	10				LP	DT	BAS	E									LPDT
13	11				SMC	IN E	BASE	:									SMON
14	12				1	RL	BAS	E									TRL
15	13				JC	UT	BAS	ξE									SIR
16 TBUF BRSE BUF 17 DISC REQUEST BRSE DRQ 20 FIRST FREE MEMORY ADDRESS 21 22 TIME OF LAST CYCLE 23 RESERVED	14					IR	BAS	SE									SOCTAB
DISC REQUEST BASE DRQ PIRST FREE MEMORY ADDRESS TIME OF LAST CYCLE RESERVED	15				JPC	NT	BAS	SE.									JPCNT
20 FIRST FREE MEMORY ADDRESS 21 22 TIME OF LAST CYCLE 23 RESERVED	16				TE	UF	BRS	SE.									BUF
FIRST FREE MEMORY ADDRESS 21 22 TIME OF LAST CYCLE 23 24 RESERVED	17			0	ISC	RE	QUE	ST	BAS	E				••••			DRQ
21 22 TIME OF LAST CYCLE 23 RESERVED	20				·				MEN	ine	. 00	000					
TIME OF LAST CYCLE 23 24 RESERVED	21				۲,	.ns		VEE.	IICI	יאטו	, ni	יאטינ	. 33				_
23	22							۰			·uci	-					
	23					١.	LUE	UF	LH	31 (.161	Œ					
25 Break Point Flag BPTF	24					1	RESI	RV	D								
	25				В	eal	k Pi	oin	ŧ F.	lag							BPTF

Memory Layout

System Global Area (Cont.)

1.		
26	VDSMTAB BASE	VDSMTAB
27	STATIC FENCE	
30	CURRENT CST BLOCK INDEX	CSTBX
31	MEASIO BASE	MEASIO
32	DISPLACEMENT TO CODE =@CST(0)-@DST(0)	DFC
33	DISPLACEMENT TO SHARABLE = @CST(LAST)-@DST(0)	DFS
34	Snon Index	
35	ABS ADDRESS (SYSDIT(8))	DIT8
36	Reserved	SBANK
37	ABS ADR OF PMBC TABLE FOR LST/STT CHECKING	SBASE
40	RESERVED FOR INITIAL (VDSENTRY)	
41	RESERVED FOR INITIAL (VDSMAP)	
42	SRITAB BASE	SRTTAB
43	SPECQ HEAD	SPECQHEAD
44	Number of Available Regions	HOLECOUNT
45	# PAGES IN LARGEST CURRENTLY AVAILABLE REGION	MAXRVAILREG
46	MAKE OVERLAY CANDIDATE INFORMATION	MOCINFO
47	NUMBER OF MEMORY BANKS CONFIGURED -1	NBANKS
50	SCHEDULER TO RWAKE MESSAGE	SCHEDTORNAKENSG
51	POINTER TO CSTBLK TABLE	CSTXBLCKPOINTER
52	AWAKE TO SCHEDULER MESSAGE	RWAKETOSCHEDMSG
53	WAIT TO SCHEDULER MESSAGE	!
54	CURRENT ACTIVITY'S PRIORITY	CURACTPRI

G.01.00 1- 4

G.01.00 1- 3

System Global Area (Cont.)

		·	
	/55	BUSY TABLE POINTER	BUSY
		HEAD TABLE POINTER	HEAD
	57	TAIL TABLE POINTER	TAIL
	60	# OF SIO PROGRAMS EXECUTING	SIOCOUNT
	61	PARITY ERROR FLAG (MEM PE)	PARITY
	62	Impeded queue head for message buffer (PIN)	IOMSGPIN
	63	I/O Message system error flags (0:1) - No SYSBUF avail for I/O error logging (1:1) - No SYSBUF for IOMESSAGE (GENMSG)	IOLOGQX
RESERVED FOR I/O	64	# OF TERMINALS READING	RDCOUNT
SYSTEM	65	# OF TERMINALS WRITING	NRTCOUNT
	66	DSET B	CRIO
	67	LAST TIMER	CRIO
	70		CRIO
	71	HIGHEST DRT NUMBER	HSYSDRT
	72	POWERFAIL	POWERFAIL
	73	SYSTEM UP FLAG	SYSUP
	\74	SYS CONSOLE LOGICAL DEVICE NUMBER	CONSLIDEV
4	/ 75	COLD LOAD COUNT	CLOADID
	76	SHARED FCB DST	SHFCBDST
	77	MONITORING FLAGS	
RESERVED FOR FILE SYSTEM	100 101	MAX # OF SPOOL SECTORS	MAXSSECT
	1 1		i

G.01.00 1- 5

System Global Area (Cont.)

1.		1
102	CURRENT # OF SPOOL KILOSECTORS	NUMSSECT
\104	# SECTOR/SPOOLFILE EXTENT	 EXTSSECT
105	MAX CODE SEGMENT SIZE	
106	MAX # OF CODE SEGMENTS/PROCESS	į
107	MAX STACK SIZE (MAXDATA)	<u> </u>
110	DEFAULT STACK SIZE	!
111	MAX EXTRA DATA SEGMENT SIZE	!
112	MAX # EXTRA DATA SEGMENTS/PROCESS	!
113	DST number for MESSAGE buffers	<u> </u>
114	UPDATE LEVEL	UPDATEL
115		FIXL
116	VERSION LEVEL	VERSION
117	DEFAULT CPU TIME LIMIT	<u> </u>
120	# OF SECONDS TO LOGON	<u> </u>
121	JOBSYNCH BITS (13:3)	
122	EXTERNAL PLABEL OF INITIATE	!
123	INTERNAL PLABEL OF INITIATE	<u> </u>
124	MAXSYSDST	!
125	MAXSYSCST	!
126	Ldev for SL.PUB.SYS HODA for SL.PUB.SYS	!
127	LODA for SL.PUB.SYS	!
130	(DIRECTORY)	ļ
131	(DISC ADDRESS)	!
1		1

G.01.00 1- 6

Меногу Layout

Memory Layout

System Global Area (Cont.)

132	SPOOLINDEX	
/133	EXT LABEL FOR SHOWCOM	
134		
135	CS IOWAIT PLABEL	
RESERVED (FOR CS 136	CS FIX LEVEL	
137	CS VERSION	
\ \140	CCLOSE PLABEL	
141	LOGICAL PROCESS TABLE (PROGEN)	0
142		
143	LOGICAL PROCESS TABLE (UCOP)	2
144	LOGICAL PROCESS TABLE (PFAIL)	3
145	LOGICAL PROCESS TABLE (DEVREC)	4
146	LOGICAL PROCESS TABLE (DRUSG)	5
147	LOGICAL PROCESS TABLE (STMSG)	6
150	LOGICAL PROCESS TABLE (LOG)	7
151	LOGICAL PROCESS TABLE (LOAD)	8
152	LOGICAL PROCESS TABLE (IOMESSPROC)	9
153	LOGICAL PROCESS TABLE (SYSIOPRDC)	10
154	LOGICAL PROCESS TABLE MEMLOGP	11
155	EXTERNAL PLABEL OF "TERMINATE"	
156	INTERNAL PLABEL OF "TERMINATE"	

System Global Area (Cont.)

			1
	157	EXTERNAL PLABEL OF "COMMANDINTERP"	l
	160	INTERNAL PLABEL OF "COMMANDINTERP"	
	161	EXTERNAL PLABLE OF "SPOOLIN"	İ
	162	INTERNAL PLABLE OF "TRACEO"	i
	163	EXTERNAL PLABEL OF "TRACEO"	
	164	INTERNAL PLABEL OF "SPOOLIN"	
	165	EXTERNAL PLABLE OF "SPOOLOUT"	l
	166	INTERNAL PLABEL OF "SPOOLOUT"	i
	167	3 WORD	
!	170	LOGGING	
	171	MASK	
	172	STATE DST# - BUFFER O	
	173	STATE DST# - BUFFER 1	
	174	BUFFER LENGTH (SECTORS)	ļ
	175	FREE AREA POINTER	ļ
	176	FLAGX	
RESERVED FOR	177	# RECORDS WRITTEN IN BUFFER O	ļ
LOGGING	200	# RECORDS WRITTEN IN BUFFER 1	
	201	FILE SIZE (BLOCKS) - 1ST HALF	
	202	FILE SIZE (BLOCKS) - 2ND HALF	
	203	(LOG FILE SIZE)	
	204	(BLOCKS)	
	205	LOG FILE NUMBER (LOGFILENUM)	
İ	206	NUMBER OF LOGGING [BLOCKS WRITTEN (1ST HRLF)]	İ
İ	207		İ
			ĺ

G.01.00 1- 7

G.01.00 1- 8

RESERVED FOR DS/3000 (SET TO ZERO)

DISC STATUS

RONESS

MAXQUEUE

DEFAULTQUEUE

LAST DISC SIO ERROR

JOBPRI

327 330

331

332

333

334

DSBREAK PLABEL

PVPROC PIN

PV RECOGNITION COUNT

Base of last memory word

VMOUNT FLAGS

LAST MEMORY

ADDRESS

IAUTOIALLION

360

/363

1365

System Global Area (Cont.)

366	
367	
\370	
371	MSG CATALOG LDEV
372	MESSAGE CATALOG DISC ADDRESS
373	MSG DST
374	CONSMPLINE' PLABEL
375	CONSMRJE PLABEL
376	SYSTEM LEVEL UDC FLAG (1 = SYS UDC'S EXIST)
377	SYSOB RELATIVE POINTER TO SYSGLOB EXTENSION
400	CPU NUMBER (Set by softdump)
401	MICROCODE MEMORY LOCATIONS
402	*NOTE THAT THE CONTENTS DEPEND ON THE TYPE OF CPU THAT MPE IS RUNNING AND WHETHER A DUMP, POWERFAIL, OR CMTL B/HALT HAS OCCURRED

The following locations refer all systems:

```
X1410 = S - BRNK
1411 = Z
1412 = STRTUS
1413 = PB - BRNK
1414 = PB
1415 = P
1416 = PL
1417 = CIR
1420 = High Bank
X1401 = DUNDDEVDRT

02 = X

03 = DL

04 = DB - BANK

05 = DB

6 = Q

7 = SM
```

The following locations refer exclusively to the Series 37:

```
X1421 = MICROCODE VERSION MUMBER
BIT (0:2) 00 = MASTER RELEASED
10 = PENDING RELEASE
11 (2:6) BASE LEVEL (1-64)
BIT (8:8) PATCH LEVEL (1-99)
X1422 = FLAGS/MISC
```

G.01.00 1- 13

Memory Layout

BIT (0:1) 1 IF ON ICS
BIT (1:1) 1 IF IN DISPATCHER
BIT (2:1) LOGICAL/PHYSICAL
I IF LOGICAL
BIT (3:1) 1 IF CHANNEL PROGRAM IS RUNNING BIT(4:1) SPLIT BRNK FLAG 1 IF SPLIT BIT(5:3) UNUSED BIT(8:8) LAST STOP CODE

x1423/7377 = CHANNEL PROGRAM RREA FOR BOOTING SOFTWARE
 (USED ONLY DURING BOOT).

The following are assignments after software has been loaded and launched:

X1540/1617 = ROM INPUT BUFFER FOR TERMINAL I/O
1520/1677 = ROM DUTPUT BUFFER FOR TERMINAL I/O
1700/1710 = ROM CONTROL BUFFER FOR TERMINAL I/O
1711/1737 = ROM CONTROL B INTERFRCE BUFFERS

The following assignments refer to the Series 30/33/39/40/42/44/48/64/68:

30/33/39/40/42/44/48

X1421 = CPX1 REGISTER 1422 = CPX2 REGISTER

X1421 = SYSTEM HALT # 1422 = ISR (INTERRUPT REGISTER) X1515 = SYSTEM INTERRUPT MASK 1516 = DRT 0 1517 = DRT 1 1520 = DRT 2 1521 = DRT 3 X1515 = NIR REGISTER

37/64/68

64/68

1516 = DRT 0
1517 = DRT 1
1520 = DRT 2
1521 = DRT 3
1522 = DRT BHNK
1523 = DRT HODRESS OFFSET
1524 = ENT HODRESS OFFSET
1524 = INTERRUPT MASK FOR IMBO
1525 = INTERRUPT MASK FOR IMBO
1526 = INTERRUPT MASK FOR IMBO
1527 = INTERRUPT MASK FOR IMBO
1527 = INTERRUPT MASK FOR IMBO

All Systems:

1740 = START OF SYSGLOB EXTENSION

G.01.00 1- 14

Memory Layout

SysGlob Extension

%200 words long; Pointer found at SysDB + %377

	I	ı
z 0	SWAP QUEUE DELAY (*100MS)	SHAPQDELAY
1	BANK OF FIRST REGION IN LINKED MEMORY	FIRST
2	BASE OF FIRST REGION IN LINKED MEMORY	REGION
3	GARBAGE COLLECTION ENABLE FLAG	GARBCOLLENAB
4	MOVE THRESHOLD (IN PAGES, FOR GARB COLL)	MOVETHRESH
5	MAIN MEMORY PAGE SIZE (IN WORDS)	
6	VDS PAGE SIZE	
7	LAST NAKE ROOM TIME	
10		
11	MEMORY PRESSURE DURATION THRESHOLD	
12	NATIVE LANGUAGE TABLE (NLT) DST #	
13	RESERVED FOR NATIVE LANGUAGE SUPPORT	
14	BAUD RATE OF THE SYSTEM CONSOLE	
15	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
16	PLABEL FOR REMOTE'MPE	
17	PLABEL FOR GETDS'NODENAME	
56		
57	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
60	PLABEL USERLOG (EXTERNAL)	
61	PLABEL USERLOG (INTERNAL)	
62	PLABEL RECLOG (EXTERNAL)	
i		

Memory Layout

SysGlob Extension (Cont.)

63	PLABEL RECLOG (INTERNAL)	
64	PLABEL RESTART (EXTERNAL)	
65	PLABEL RESTART (INTERNAL)	
66	PMBC LOW CORE BANK # (USER)	
67	PMBC LOW CORE ADDRESS (USER)	
70	RESERVED FOR IMAGE	
71	RESERVED FOR MEASIO 12 MIOCNT	*
72	LOADER CACHE SEGMENT NUMBER	
73	PLABEL 3270 (EXTERNAL)	
74	VERSION	
75	UPDATE	
76	FIX	
77	COUNT OF TAPE CONTROLLERS USING MERSIO	
100	PORT DATA SEGMENT NUMBER	
101	RESERVED FOR SECOND PORT DATA SEGMENT	
102	SYSTEM FPMAP OPTION FLAG	SYSFPMAP
103 104 105 106 107 110	GLOBAL ALLOU Mask	
111	RESERVED	
117		
120	SYS PORT PROCESS PCB RELATIVE INDEX	
121	GLOBAL AFT DST NUMBER	

SysGlob Extension (Cont.)

				1
122	INITIAL/PROGEN COMM. DSEG NU	MBER	(Ch.	16)
123	INITIAL SYSTEM STARTUP OPT	ION		
124	PORT'MRX'SER'COUNTER			
125				i
127	CURRENTLY UNASSIGNED			
130	(DS, NETWORK MGMT, APPLICATION SE	RVICE	ES)	
131				
132				
133				
134				
135				
136				
137				
140				
141				
142				
143				
144				
145	RESERVED FOR SPL			
146	PATH FLOW			
147	ANALYZER			
150				
151	CURRENTLY UNASSIGNED			.
200				
	'			

G.01.00 1- 17

* MIDCNT = MERSIDCOUNT (3 BITS)
** MERSFLAGS (15:1) = 1 ==> MONITOR ENABLED (14:1) = 1 ==> BUFFER FLIP/FLOP (13:1) = 1 ==> EOT ON MONITOR TAPE

SYSDB Words

```
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
Address | Bank
```

Address is the whole word with "Bank" masked out to 00000.

Systems that have HPE V/E microcode (all 6% systems, 4% systems with new boards) can have a non-zero bank number. Systems running pre-NPE V/E microcode can only use bank 0, therefore the pointer will look like:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 Address

SysGlob Word Definitions

ADDRESS	NAME	FUNCTION
DB+55	BUSY	- SYSDB relative pointer to BUSY TABLE for I/O resources
DB+56	HEAD	 SYSDB relative pointer to table containing head pointers to I/O resource queues
DB+57	TAIL	 SYSDB relative pointer to table containing head pointers to tail of I/O resource queues
DB+60	SIO COUNT	- Number of I/O Programs currently executing
D8+72	POWER FAIL	- O-no power fail
		1-system disc recovery 2-all other disc recovery
		3-all other device recovery
DB+73	SYSUP	- System is up and operable
DB+74	CONSLDEVN	 System console logical device number
DB+400	CPU NUMBER	- Set when system aborts

G.01.00

Memory Layout

JOBSYNCH job synchronization via jobsynch (sysglob+121(8))

(13:1) - JOBSREADY - set by DEVREC & MORGUE (via procedure STARTDEVICE) indicating a ready job. This prevents UCOP from going to a наit state when a job is just наde ready.

(15:1) - DEVFREED - set by DEALLOCATE when device count goes to 0.

NOTE - Both bits above used for synchronization of job-made-ready or devicefreed when UCOP is running.

(14:1) - JOBSWAITING- set by UCOP just before maiting if any job is maiting for list device. Signals DEALLOCATE to awake UCOP when a device is freed.

Memory Layout

Allow Mask Format

The Allow mask for MPE V is expanded to six words. There is a mask in each user's JIT and in the SYSGLOB area. The Allow mask contains enough bits for a one-to-one correspondence to every present OPERRIOR type command, or any future OPERRIOR command. When a user is ALLOWed any OPERRIOR command or RSSCIATED to a device (which will use OPERRIOR type commands) then the corresponding bit(s) in the mask in that user's JIT for that command is set. If the ALLOW or RSSCIATE was done on a global scale, then the bit(s) in the mask of the SYSGLOB area is/are updated.

The following EQUATEs define the mask bit for each operator command.

The first set of commands define the operator commands dealing with devices.

When adding a new command to this set of EQURTEs, be sure to add a corresponding move statement in LOGIMAGE, even if the command will not be logged.

	<u>Hord</u>	<u>Bit</u>	<u>#</u>
ABORTIO ACCEPT DOWN GIVE GIVE HEADOFF HEADON REFUSE REPLY STARTSPOOL TAKE UP MPLINE DSCONTROL	000000000000	0 1 2 3 4 5 6 7 8 9 10 11 12	0 1 2 3 4 5 6 7 8 9 10 11 12
UPPER LIMIT->DEV	ICE CO	MMANDS	
ABORTJOB RLLOW RLTFILE RLTJOB BRERKJOB DELETE DISRLLOW JOBFENCE LIMIT SUSPENDSPOOL SUSPENDSPOOL OUTFENCE RECALL RESUMESPOOL STREAMS COMSOLE	000111111111111111111111111111111111111	13 14 15 0 1 2 3 4 5 6 7 8 9 10 11 12 13	13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28

SYSDB 300

317

Entry Fornat

Preassigned Entries entry #

Process Stop List General Lavour

STOP BITS REPRESENTING WHICH PROCESSES TO STOP ON "SHUTDOWN" # PROCESS ENTRIES 1ST PROCESS ENTRY 2ND PROCESS ENTRY

LAST PROCESS ENTRY

process

devrec

stop bit #

G.01.00 1- 22

Allow Hask (Cont.)

	Hord	811	Ħ
HARN HELCOME HON HOFF VIOUNT LINGUNT LISTOUNT JOSSECURITY DOUNLOAD HIDENBLE HIDDISABLE LOG FOREICH LING HISTOURN HIDENBLE HIDDISABLE LOG SHOULDON HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN HISTOURN H	HOC 1122222222222222222222222222222222222	14 15 01 23 45 67 89 10 11 12 13	301 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45
OPENQ SHUTQ DISCRPS	2 2 3	14 15 2	46 47 48

Logging Related Locations

SYSDB 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

STATE = 0 if respective buffer empty 1 if respective buffer is current 2 if respective buffer is full

BGZYZ				FL	AGX	
	2 - /////	3 4 5	6 7 //////	8 9 10 ///////	11 12 13 SF HF BUF	14 15 SL SD

SF = 1 if soft failure
HF = 1 if hard failure
BUF = 0 if current log buffer is buffer 0
= 1 if current log buffer is buffer 1
SL = 1 to indicate a switch in log buffers (from 0 to 1 or from 1 to 0)
SD = 1 to indicate shutdown in progress

G.01.00 1- 21

Memory Layout

Bank O	
Low Core memory	
>DRT	(Only on 64/68 if Pri-
System Global area	vilege Mode Bounds Checking is enabled.)
Firmware area	
SYSGLOB Extension	
DST/CST/CSTX	
ICS	
PMBC	(Only for 64/68 if Pri-
ILT/DIT	vilege Mode Bounds Checking is enabled.)
DLT	
Resource Tables	
CST Block	
>Memory Measurement Info	
VDSM Table	
Job Process Count	
> PRI/SEC MSR	
>PCB	
> Suap Table (SLL)	
>Special Request Table	
>Job Cutoff Table	
>⊺imer Request List	
>System Buffers	
>LPDT	
>100	
>SIR	
>MON Table	

Memory Layout

Initial Memory Allocation

This section is a description of the method used by INITIAL to allocate memory for MPE tables and code segments in MPE V/E. All memory allocated by INITIAL is permanently allocated. All non-core resident code and data is put on disc before exiting INITIAL:

At the most basic level INITIRL will try to build memory to look exactly as diagrammed below. There are, however, several ways in which to deviate from this structure. Before going into the sources of these deviations, it is necessary to point out which portions of memory are used by INITIRL during the restart and therefore cannot be used by MPE until INITIRL has finished.

Before INITIAL begins to allocate any memory space, it relocates its core resident code, its code segment swapping area and its stack to the highest configured memory space. Additionally, it uses the last X326 words of bank O on series 4x machines for its 1/0 buffer area and temporary code segment table. After INITIAL has built all of core resident MPE (tables and code), it builds the disc resident MPE tables. Since some of the disc resident tables may be too large to be built in INITIAL's stack, these tables are built in unused memory space. Therefore, in addition to the memory space required for INITIAL's code, INITIAL's stack and core resident MPE, there must be enough space left in which to build the largest of the disc resident tables.

For Series 6x machines with the MPE V/E firmware, INITIAL will build the tables with ""signs by then out of Bank O if necessary. For all other tables, INITIAL will essentially build nenory in the order shown below. There nay be an unused fragment of menory between the DRT's and the system global area which INITIAL will fill with the smaller tables. Neither the tables narked with an asterisk nor the code segments will ever be put in this area. NOTE: INITIAL will build all tables on 32-word boundaries.

If the system being built by INITIAL is configured with 128K words or 160K words of memory then INITIAL's stack will be in bank 1 (the code also on a 128K word memory size). If INITIAL is occupying part of bank 1 and the space is needed for a core resident NPE code segment or to build a disc resident table then INITIAL will print the error message "ERROR #350 OUT OF MEMORY".

Except for the exceptions stated above, for every allocation of memory INTINL will first try to allocate any remaining space between the DRT's and SYSDB. It will then try the next available space in bank 0, then the next available space in bank 1. If it were necessary it could continue searching until all all banks were checked for available space.

Innediately before exiting INITIAL, INITIAL lays down all the memory region headers and trailers as shown below. For any one bank of memory there will only be one block of core resident MPE, regardless of its contents. The only block of core resident MPE that does not have a reserved region global header is in bank 0. It does have the reserved region global trailer though, Before placing any code outside bank Othe first 24 words of every bank (except bank O) is reserved for the region global header.

G.01.00

G.01.00 1- 24


Bank O (Cont.)	
Core Resident CST's in CST order	
Reserved Region Global Trailer	
Rvailable Region Global Header	
Australia Manager	
Rvailable Memory	
Rvailable Region Global Trailer	
NOTE: The > means these tables can move out of Bank O if necessary.	
Bank 1	
Reserved Region Global Header	
Core Resident CST's and tables marked with ">" that didn't fit in BRMK O	
Reserved Region Global Trailer	
	·
G.01.00 1- 25	
	·
	·

Memory Layout

CHAPTER 2 MEMORY MANAGEMENT TABLES

Segment Table Structure

The current location and state of each data segment and loaded code segment is maintained in the Segment Table. This table is partitioned into three separate tables as shown in Figure 2-1. The partitions are based on the segment classes: a segment is a data segment, a segment is a system SL segment, or a segment is part of a program. The structure and format of each partition is described in the following.



Overall ST Structure

G.01.00 2- 1

Memory Management

Pointers and DST #'s of Segment Table Components

% 2 absolute address of entry 0 of the DST. % 21002 sysbase relative index of entry 0 of DST. DST number 2 is the DST Table dst #.

X O absolute address of entry O of System SL.
X1001 sysbase relative index of entry O of System SL.
X1032 displacement from DST base of entry O of System SL (i.e. GCST(last) - @DST(O) = DFS).
DST number 4 is the CSTX Table DST #.

X 1 absolute address of entry 0 of current program. X1033 displacement from DST base to first CSTX entry SL. DST number 4 is the CSTX Table DST #.

iv. CSTXMAP

%1051 sysbase relative index of entry O of CSTXMAP. DST number 43 (%72) is CSTXMAP Table DST #.

G.01.00 2- 2

Memory Management

Standard Object Identifier Format

٥			2	3	4	5	6	7	8	9	10	11	12	13	14	15
	T	/P	E	I					CST	ВЦ	(
		-				08	JEC	T)	UME	ER						

OBJIDENTIFIER(0).(0:4) ==> TYPE = 0 Object is a Data segment = 1 Object is a n SL segment = 2 Object is a Program segment = 3 Object is a Cache Domain

DST Entry Formats

DST/CST Entry O Format



Memory Management

DST General Entry Format

Case (i) DST Entry for a Present Data Segment

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
WORD 0	R O R SIZE/4	FIRMINFO
WORD 1	D IR II IS IN IF IS IC IMI C IO IN IT IO IM IY IO IDI VMALLOC V IC II IK ID II IS IR I I I I I P I IE I	FLAGS
WORD 2	BANK	MMBANK
WORD 3	BASE	MMBASE


Case (ii) DST Entry for an Absent Data Segment

HORD O	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 - - - - - - - R O R SIZE/4	FIRMINFO
WORD 1	D IR I S M F S C W C O M T O WHOLLOC V C I K D I S R I V P I E	FLAGS
MORD 2	LDEV # HODA	HODA
WORD 3	LODA	LODA

CST Entry formats

CST General Entry Format

Case (1) CST Entry for a Present SL Segment or CSTX Segment



CASE (ii) CST Entry For An Absent Segment SL or CSTX Segment

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
MORD 0		FIRMINFO
HORD 1		FLAGS
WORD 2	LDEV # HODR	HODA
MORD 3	LODA	LODA

Case (iii) DST/CST Free Entry

		X10000	0		
TABLE	RELATIVE	OFFSET	TO NEXT	FREE ENTRY	
TABLE	RELATIVE	OFFSET	TO PREV	IOUS FREE E	HTRY
/////	////////	//////	////////	///////////////////////////////////////	////

Refer to the Logical Segment Table Format in Chapter 11 for more information on XCST.

G.01.00 2- 5

ST Entry Field Descriptions

A = 1 ==> segment absent

N = 1 ==> segment privileged

R = 1 ==> segment privileged

R = 1 ==> segment being traced

DCV = 1 ==> segment being traced

DCV = 1 ==> segment is being traced

DCV = 1 ==> segment is e a stack

NOD = 1 ==> a segment nodification (exp., contr.) is pending

FMTP = 1 ==> a segment is end to this segment is in progress

VMPRGECHT = N of virtual nemory pages allocated to this segment

TIL = 1 ==> segment is in notion in


SYS = 1 ==> segment is in notion in

SYS = 1 ==> segment is a system segment

CDRE = 1 ==> segment is core resident

MD = 1 ==> write disabled

CSTBLK Format



The table is initialized to minus one in each entry. When selected, the entry is replaced by a DST-relative index to the entry MO of the CST extension block. This is the the overhead entry for the associated program.

G.01.00

Memory Management

Program Blocks and the CSTXMAP

Since programs can be dynamically loaded and unloaded, the segment table must be kept packed or fragmentation would occur. Thus, the block of ST entries for a program segment begins at an ST entry number that changes if a program which was loaded before it gets unloaded. To manage this dynamic structure, an auxiliary structure, the CSTMTHP is used. A program is identified by its index, CSTMEIX, into this map. The program's current beginning physical ST entry number is equal to equal to CSTMTP (CSTMEIX).

Entry Format - CST Extension Block



The value of CSTMEIX is established when a CST extension block is allocated. This index into the array CSTMMAP is maintained in the PCB of each process sharing the block.

Memory Management

Fixed DST Entry Assignments

OCTAL		DECIMAL	TABLE NAME
0	 	0	
1	CST	1	CST
2	DST	2	DST
3	PCB	3	PCB
4	CSTX	4	CSTX
5	SYSTEM GLOBAL AREA	5	SYS
6	CORE	6	CORE
7	ICS	7	ICS
10	SYSTEM BUFFERS	8	SBUF
11	UCOP REQUEST QUEUE	9	UCRQ
12	PROCESS-PROCESS COMMUNICATION TABLE	10	PPCOM
13	I/O QUEUE	11	IOQ
14	TERMINAL BUFFERS	12	TBUF
15	LOGICAL-PHYSICAL DEVICE TABLE	13	LPDT
16	LOGICAL DEVICE TABLE	14	ЮT
17	DRIVER LINKAGE TABLE	15	DLT
20	I/O RESOURCE TABLES	16	BUSY, HEAD, TAIL
21	SECONDARY MSG TABLE	17	SECHSGTAB
22	LOADER SEGMENT TABLE	18	LST
23	TIMER REQUEST LIST	19	TRL
24	DIRECTORY	50	DDS

Memory Management

DST (Cont.)				
OCTAL	l	DECIMAL	TABLE NAME	
25	DIRECTORY SPACE	21		
26	RIN TABLE	22	RIN	
27	SWAPTABLE (SLL)	23	SUAPTAB	
30	JOB PROCESS COUNT	24	JPCNT	
31	JOB MASTER TABLE	25	JMAT	
32	TAPE LABEL TABLE	26	VDD	
33	LOG TABLE	27	LOGTAB	
34	REPLY INFORMATION TABLE	28	RIT	
35	VOLUME TABLE	29	VTAB	
36	BREAKPOINT TABLE	30	STOP	
37	LOG BUFFER1	31		
40	LOG BUFFER2	32		
41	LOG ID TABLE	33	LIDTAB	
42	ASSOCIATE TABLE	34		
43	CST BLOCK	35	CSTBLK	
44	JOB CUTOFF TABLE	36	JEUT	
45	SYSTEM JIT	37	SJIT	
46	SPECIAL REQ TABLE	38	SRT	
47	VIRTUAL DISC SPACE MANAGEMENT TABLE	39	VDSMTAB	
50	DEVICE CLASS TABLE	40	DEVCLASS	
51	Reserved Kernel	41		

Memory Management

DST (Cont.)

44. 144			
OCTAL	,	DECIMAL	TABLE NAME
52	ILT	42	ILT
53	SIR TABLE	43	SIR
54	FMAVT	44	FMAVT
55	IMPUT DEVICE DIRECT	45	IDD
56	OUTPUT DEVICE DIRECT	46	ODD
57	WELCOME MESSAGE #1	47	LOGONDSTN1
60	WELCOME MESSAGE #2	48	LOGONDSTN2
61	CS DATA SEGMENT	49	CSTAB
62	PROCESS-JOB CROSS REFERENCE	50	PJXREF
63	SYSTEM JDT	51	TOLEYS
64	COMMAND LOGON DST	52	CILOGDST
65	MOUNTED VOL. SET TRBLE	53	MVTRB
66	PRI.VOL. USER TABLE	54	PVUSER
67	RESERVED KERNEL	55	
70	DISC REQUEST TABLE	56	DISCREQTAB
71	MSG HARBOR TABLE	57	MSGHARBTAB
72	PRIMARY MESSAGE TABLE	58	PRIMMSGTAB
73	MEASUREMENT INFO TABLE	59	MEASINFOTAB
74	FIRST FREE DST	60	
	•	•	

G.01.00 2- 9 G.01.00 2- 10

Memory Management

Suap Tables

The SWAPTAB is a core resident memory management table used to keep track of the locality lists of the competing processes. The PCB entry for a process has a SWAPTAB relative pointer to the header entry for the process.

SWAPTAB DST# = 23 (%27)

%1004 System table pointer to SWAPTAB entry 0.

NOTE: The number of entries configured will be 3 greater than the number configured via SYSDUMP. (Entry 0 consumes 3 entries).

SWAPTAB Entry O Format

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
0	# ENTRIES CONFIGURED	0
1	ENTRY SIZE (6)	1
2	# RVAILABLE ENTRIES	2
3	TABLE RELATIVE INDEX OF FIRST FREE ENTRY	3
4	TABLE RELATIVE INDEX OF LAST FREE ENTRY	4
5	HIGH WATER MARK	5
6	# PRIMARY ENTRIES (0)	6
7	HEAD OF IMPEDED QUEUE (PCB RELATIVE)	7
8	TAIL OF IMPEDED QUEUE (PCB RELATIVE)	10
9	# CURRENTLY IMPEDED PROCESSES	11
10	MAX # OF IMPEDED PROCESSES	12
11	CUMULATIVE # OF IMPEDED PROCESSES	13
12		14
	:	
17		21
		1

Memory Management

SWAPTAB Unassigned Entry Format

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
0	x100000
1	TABLE RELATIVE INDEX OF NEXT FREE ENTRY
2	TABLE RELATIVE INDEX OF PREV. FREE ENTRY
3	0
4	0
5	0


 $\mbox{\rm fin}$ assigned entry in the suaptab is a process' SLL header or a nember of a process' SLL. These formats are now described.

Segment Locality Lists (SLL)

The system maintains for each process a segment locality list (SLL) of the segments belonging to that process' current working set. The process' SLL consists of a header and list of entries. The header and list entries are taken from the SMAPTAB.

A process' SLL is located via the process' PCB entry. PCB01 contains the SLL relative index of the process' SLL header.

SURPTAB



G.01.00 2- 13

Memory Management

SLL Header Format

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
0		SCHEDTOIONSG
1	TABLE RELATIVE INDEX OF FIRST ENTRY IN LIST	FIRSTINX
2	///////////////////////////////////////	
3	TABLE RELATIVE INDEX OF MEMORY REQUEST ENTRY	MEMREQINX
4	# ENTRIES IN PROCESS' SLL	SEGCOUNT
5	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	

- SLL(SLLHERDINK+O)
 .(1:1) SWRED, Swap Required Flag
 .(2:1) MRSNED, Has Memory Flag
 .(3:1) INTIDC, Intilalize locality to minimum
 .(4:1) PARFIN, Process partially swapped in
 .(5:1) STRIPV, Start swap over Flag
 .(6:1) SWIP, Swap In Progress Flag
 .(8:8) IOCNT, Segment read completions until awake

G.01.00 2- 14

Memory Management

SLL List Entry Format

	0, 1, 2, 3, 4, 5, 6, 7, 8, 9,10,11,12,13,14,15	
0	PCB RELATIVE INDEX OF THE NEXT INPEDED PIN	NEXTIMPPIN
1	TABLE RELATIVE INDEX TO NEXT ENTRY IN LIST	NEXTINX
2	TABLE RELATIVE INDEX TO PREV. ENTRY IN LIST	PREVINX
3	- OBJECT IDENTIFIER -	STT, OB1DE2C
4		SLL'OBJNUM
	N S D L B F S T F L D	SLL'FLAGS

SLL(SLLINX+O) NEXTIMPPIN, next make present deferred queue PCB Index

SLL(SLLINX+1) MEXTINX, next SLL entry SLL(SLLINX+2) PREVINX, previous SLL entry

SLL(SLLINX+3) SLL'OBJDESC, 1st word of object identifier

SLL(SLLINX+4) SLL'OBJNUM, 2nd word of object identifier

SLL(SLLINX+5)

- 5)
 .(0:1) MAPSEG, process' CST mapping segment (LSTI)
 .(1:1) STK, process' stack entry
 .(2:1) DISCIDISEG, disc I/O pending on this segment
 .(3:1) LOCKED, segment locked in memory
 .(4:1) BLKLK, request for blocked lock
 .(5:1) FROZE, segment frozen in memory
 .(6:1) SLIITI, process queued for this segment
 .(7:1) LOSS, loss this entry
 .(8:1) FRZREQ, request tegment to be frozen
 .(9:1) LKREQ, request to lock segment in memory
 .(10:1) DCCNIFLEG,
 .(10:1) PREFETCHCOUNT,

NOTE:
The Swap Table will be configured with at least twice the number of configured PCBs.

Memory Management

Special Request Table

Used for passing data segment size change info and for keeping a list of devices maiting for a segment to arrive in memory.

X1042 - SRT relative index to entry # 0 X1043 - SRT relative index to the head of the queue

NOTE: The number of entries configured will be 3 greater than the number configured via SYSDUMP. (Entry #0 consumes 3 entries).

SRT Entry O Format

0	# ENTRIES CONFIGURED
1	ENTRY SIZE (6)
2	# AVAILABLE ENTRIES
3	TABLE REL. INDEX OF 1ST FREE ENTRY
4	TABLE REL. INDEX OF LAST FREE ENTRY
5	HIGH WATER MARK
6	# PRIMARY ENTRIES
7	HEAD OF IMPEDED QUEUE (PCB REL.)
8	TAIL OF IMPEDED QUEUE (PCB REL.)
9	# CURRENTLY IMPEDED PROCESSES
10	# MAXIMUM IMPEDED PROCESSES
11	CUMULATIVE # OF IMPEDED PROCESSES
12	
	;
17	

Main Memory Region Headers and Trailers

Main memory is partitioned into regions. Each region is in one of four states: available, reserved, assigned, or cached.

An available region is available for consumption by the free space allocation nechanism. An available region consists of neighboring subregions, each of which is either a hole or an overlay candidate. An available region is linked into the available region list.

A reserved region is a main memory region which is in the transition state from available to assigned. A reserved region has been cleaned, and there is a pending disc read of a segment into the region.

Assigned regions are occupied by present segments. Available and reserved regions consist of one or more adjacent subregions. Region headers and trailers are partitioned into global and local components. The global region header/trailer is only valid for the first/last subregion in regions consisting of more than one subregion.

The region headers and trailers of available, reserved, and assigned regions contain the state and control information pertaining to the current or planned contents of the region.

Cache domains are another form of assigned regions and are designated as such in the subregion header. If the cache domain is "mapped" (I/O pending against it) then the object identifier will have a non-zero value in the second word of the segment identifier field. If the second word of the segment identifier field is zero, then this region is a cache domain that is unmapped. (Refer to Chapter 23 for further information regarding Disc Caching.)

The following entry format is for data segment size changes:

٥	NEXT ENTRY FOR DATA SEGMENTS
1	
2	
3	NEW DATA SEGMENT SIZE
4	READ DISPLACEMENT
5	MOVE COUNT

The following is the format for devices waiting on a segment: (The region header for the segment contains an SRT relative index to this entry. If more that 5 devices are waiting on this segment, another entry will be linked to this entry.

0	NEXT ENTRY OF QUEUED DEVS ON SEG
	I IOONX
1	
2	XMIGOI
3	IOQINX
4	IOQINX
5	XMIDOI

NOTE:


The number of primary configured entries will be equal to the total number of LDEVs configured. The number of secondary entries will be configured to be at least the same as the number of PCBs configured. Data segment change entries are secondary type, while devices queued entries will be primary entries.

G.01.00 2- 17 G.01.00 2- 18


Меногу Management

Header length = 24 Trailer length = 4

Global Region Trailer



Global Region Header (Available Regions)



Memory Management

Subregion Header (Available Regions)

RB-15	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	SAS
RB-14	SUBREGION SIZE	SS
RB-13	V SUBREGION DISPLACEMENT IN MAIN MEM. PAGES	SD
RB-12	WRITE REQUEST POINTER	WREQP
RB-11	- OBJECT IDENTIFIER -	OBJIDENT
RB-9	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-8	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
R8-7	LDEA HODU	HODR
RB-6	Low Order Disk Address	LODA
RB-5	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-4	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-3	(11111111111111111111111111111111111111	
RB-2	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-1	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
	1	1


Memory Management

Global Region Header (Reserved Regions)

RB-24 REGION RSSIGNMENT STATE RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS RRS	i
R8-23 REGION SIZE RS	
RB-22 ON GOING I/O COUNT IOC	ENT
N E O Q I E G M R N	TMSG
	TINFO
RB-19 COMPLETION MESSAGE COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM COM C	iphsg
RB-18 MAKE PRESENT DEFERRED QUEUE (PCB INDEX) MPQ	LINK
RB-17 RELEASE PAGE COUNT PAG	ECNT
RB-16 SPECIAL REQUEST TABLE PTR (SRT TABLE REL) SPE	CREQTABPTR

Memory Management

Subregion Header (Reserved Regions)




G.01.00 2- 21

G.01.00 2- 22

Memory Management

Global Region Header (Assigned Regions)



Henory Hanagement

Subregion Header (Assigned Regions)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
R8-15	SÚBRÉGIÓN ÁSSIGNMENT STATÉ	SAS
	C R R ////////////////////// I A E O /////////////////////// O	
	C F C //////////////////////////////	
RB-14	SUBREGION SIZE	SS
RB-13	V SUBREGION DISPLACEMENT IN MAIN MEM. PAGES	SD
RB-12	WRITE REQUEST POINTER	WREQP
RB-11	- ORJECT IDENTIFIER -	OBJIDENT
	diaget Identifies	
RB-9	FREEZE COUNT LOCK COUNT	LKFZCNT
RB-8	WRITE DISABLE COUNT 1/0 FROZEN COUNT	WDIOFZCHT
RB-7	LDEV HIGH ORDER DISC ADDRESS	HODA
RB-6	LOW ORDER DISC ADDRESS	LODA
RB-5	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-4	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
RB-3	TIME OF	ARRTIME
	ARRIVAL	
RB-1	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	

Subregion Header (Cached Regions)

R8-15	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	SRS
RB-14	SUBREGION SIZE	SS
RB-13	V SUBREGION DISPLACEMENT IN MAIN MEM. PAGES	SD
RB-12	WRITE REQUEST POINTER	WREQP
R8-11	- OBJECT IDENTIFIER -	OBJIDENT
RB-9	PREVIOUS CACHED REGION (ADDRESS OF PD	PD
	FIELD OF PREVIOUS CACHED REGION)	
RB-7	LDEV HIGH ORDER DISC ADDRESS	HODA
RB-6	LOW ORDER DISC ADDRESS	LODA
R8-5	NEXT CACHED REGION (ADDRESS OF ND	ND
	FIELD OF NEXT CACHED REGION)	
RB-3	TIME OF	ARRTIME
	ARRIVAL	
RB-1	DISC ADDRESS CSL(8)	CACDADISP

G.01.00

Memory Management

PCB relative index of the HEAD of the make present MPOLINK

PRGECNT, Release Page Count =# of extra pages to release before processing initiation nessage.

SPECREQTABPTR, A Special Request Table relative index to the list of devices queued on this segment.

SAS.

Subregion Assignment State .(0:1) Cached region .(1:1) Referenced .(2:1) Recover Overlay Candidate .(13:3) I/O Status from region fetch

SS. Subregion Size

SD.

Subregion Displacement .(0:1) Displacement Count Valid Flag .(1:15) # Pages to Base of Region

Write Request Pointer = DRQ Relative Index of Disc Write Request when the Data Segment in the Subregion is in Notion Out When the region belongs to a cached domain which is mapped (i. e. OBJIDENT = 30000/non zero number) this word is non zero. If the cached domain is not mapped UREQP is zero. UREOP.

OBJIDENT, Object Identifier- has standard object identifier format

LKFZCNT, Lock and freeze count
.(0:8) Number of times region has been frozen
.(8:8) Number of times region has been locked

WDIOFZCNT, Infreeze count .(0:8) Not used .(8:8) Number of times region has been infrozen

For regions belonging to cached domains, the above two words contain the absolute address of the PD field in the previous region belonging to a cached domain.

HODA, High order disc address in virtual memory of this

LODA. Low order disc address in virtual memory of this

region

Next cached domain link for cached domain regions only. Contains the absolute address of the ND field of the next cached region.(2 $\mu ords$)

G.01.00 2- 27

Memory Management

Region Header and Trailer Field Descriptions

Region Assignment State
(0:1) Region Ressigned Flag
(1:1) Region Reserved Flag
(2:1) Region Revallable Flag
(3:1) Region Cleaned Flag
(4:1) Size Change Pending Flag
(5:1) Region Locked Flag
(5:1) Region Flozer Flag
(7:1) Region Flozer Flag
(7:1) Region Flozer, Region flap Flag
(3:1) LSIT segment, Region flap Flag
(9:6) Not used
(15:1) Blocked Lock Migration in Proge RAS. .(15:1) Blocked Lock Migration in Progress Flag

On-Going I/O Count = # of on-going I/O's in the region which must complete before the initiation message can be processed. IOCNT,

Initiation Message

.(0:1) Message Processed Toggle Suitch
.(1:1) Message Externally Disabled Flag
.(2:1) Message On-going I/D Disabled Flag
.(3:1) Queue Segnent Read Disc Request Flag
.(4:1) Incore Move Request Flag
.(5:1) Expansion Request Flag
.(5:1) Garbage Collection Flag
.(7:1) Message Morted Flag
.(8:1) Release Residual Pages Flag
.(8:1) Release Residual Pages Flag
.(9:1) Ok to start completion flag
.(10:5) Not used
.(15:1) Message Valid Flag INITHSG,

Initiation Message Auxiliary Information = DRQ relative index of segment read disc request if INITMSG. QREADREQ=1 INITINFO.

or or = +/- Displacement to initiation message for moves and expansions.

COMPMSG, Completion Message

.(0:1) Message Processed Toggle Switch .(1:1) Segment Modification Required .(2:1) Block Lock Request .(3:1) Send Scheduler A Message .(4:1) Huaken A Device .(5:1) Message Aborted .(6:9) Rwailable .(15:1) Message Valid Flag

G.01.00 2- 26

Memory Management

ARRTIME, Arrival time, contains the time at which the segment contained in the region became present

CRCDADISP Valid only for regions containing a cached domain, this word represents the disc address (in one word) of the segment contained in the region. This word which exists in each member of a linked list of cached domains, is used as the target word during the LLSH instruction.

Space Allocation Structures

As of MPE V/P and V/E, one doubly linked list structure is used instead of the multiple lists ordered by size as in MPE IV. Sysglob locations %250 through %253 contain the respective head and tail (bank & address) of the available region list. These four nords have in essence replaced the RRSBM and RRL data structures in MPE IV. Menory allocation and deallocation is handled through PUTOMARL and TAKEOFFARL. The search for an available region of the desired size is done via the LLSM instruction. The format of the list is the following:

Sysglob 7250 & 7251 points to the absolute address of the NEXT LINK field (two words) in the first available region on the list. The NEXT LINK field in the first available region points to the absolute address of the NEXT LINK field in the second available region and so on. It is worth nentioning that in addition to having a NEXT LINK field, each available region also contains a PREVIOUS LINK pointer, which wakes management of the list both easier and faster.

System Disc Layout (Cont.) CHAPTER 3 DISC LAYOUT SECTOR # -----ISECTOR # System Disc Layout SECTOR # SECTOR # DISC COLD LOAD INFORMATION TABLE DISC LABEL DISC COLD LOAD INFORMATION TABLE 29 DEFECTIVE TRACKS/SECTOR TABLE 35 DISC COLD LOAD INFORMATION TABLE COLD LOAD CHANNEL PROGRAM FOR HP-IB 36 30 SYSDUMP/INITIAL COMMUNICATION RECORD 31 MEM DUMP CHANNEL PROGRAM FOR HP-IB 37 DISC COLD LOAD INFO. TABLE EXT. 32 DISC COLD LOAD INFO. TABLE EXT. CODE FOR
INITIAL PROGRAMS
"BOOTSTRAP"
SEGMENT VARIABLE LENGTH FOLLOWS IMMEDIATELY AFTER BOOTSTRAP SEGMENT LOW CORE (CST POINTER, QI, ZI, POINTER) TEMPORARY CST (INITIAL PROGRAM) INTERNAL INTERRUPT HALTS BOOTSTRAP STACK REMRINDER OF SIO COLD LORD PROGRAM G.01.00 3- 2 G.01.00 3- 1

Disc Layout

Disc Layout

Disc Layout

System Disc Layout (Cont.)

SYSDB

NOTE: INITIAL
TRIES TO
ALLOCATE
DIRECTLY AFTER
THE FREE SPACE
HAP. HOMEVER,
THIS HAY
VARY DEPENDING
ON DELETED
OR REASSIGNED
TRACKS X130/131 SYSTEM DIRECTORY VIRTUAL MEMORY AREA INITIAL PROGRAM SEGMENTS (EXCEPT BOOTSTRAP SEG) SYSTEM FILES (FROM COLD LOAD TAPE) VOLUME TABLE
INITIAL PROGRAM STACK
REMAINING INITIAL CODE SEGMENTS USER FILES

Disc Layout

Disc Label (Sector O of Disc)

System Volume

Words 0-5 contain the ascii string "SYSTEM DISC " for the system disc, only. ٥ 0 0 |DISCSUBTYPE|6 DISC TYPE COLD LOAD ID IF WORD X11 CONTAINS A "1" A FORMER SYSTEM VOLUME HAS BEEN SCRATCHED. "0" "0" 12 10 13 VOLUME NAME 12 14 13 15 16 UNUSED ICF HCS 25 IMAGE POINTER HEAD SECTOR

G.01.00 3- 5

Disc Layout

Master Volume (Cont.)

		SHC. 7		
	25 26 27 30	GROUP NAME	21 22 23 24	
	31 32 33 34	VOLUME SET NAME	25 26 27 28	HEADER
VS VTAB HEADER +	35		29	
8 ENTRIES	36	O VCOUNT 3 VMRSK	30	
VSET DEFN IN SYSTEM DIRECTORY	37 40	VOLUME Wame	31 32 33 34	VOLUME ENTRY O
	43		- 35	•
	44		36	:
	45		37	•
	'	•	1	
	!	:	ı	VOLUME ENTRY
	116		78 	7
	170		 120	
	171	Disc Free Space map OK flag	121	
	172	DISC FREE SPACE DESCRIPTOR TABLE CHECKSUM	1	
	173	DISC FREE SPACE DESCRIPTOR TABLE DIRTY FLAG	123	
	174	•	124	
	 175	DISC FREE SPACE DESCRIPTOR TABLE ADDRESS -	125	
	176		 126	
	177 177	DISC FREE SPACE BITMAP ADDRESS	127	
	1-		İ	

SC = 1 ==> SCRATCH VOLUME MV = 1 ==> MASTER VOLUME OF PV SET.

SR = 1 ==> SERIAL DISC

VOL NAME

SERIAL DISC INFO

Disc Layout

Serial Volume (Cont.)

27 123 RESERVED FOR FUTURE HCS 1221 182 123 183 HEAD SECTOR 84


* MEDIA TYPE is the device subtype for all serial volumes except cartridge tape. For cartridge tape, this field is always 0 (the HP 9110 subtype), despite a different actual cartridge tape subtype. This allows both forward and backward interchangeability of cartridges between the HP9110 and HP 9144.

Master Volume

|6 TYPE 11|12 SUB-TYPE 15|6 SC = SCRATCH 6|SC|MV|SR| VOLUME -NV = MRSTER 7|
VOLUME = 1 -SR = SERIAL 10|
VOLUME 11| **GENERATION INDEX** 0 |10 |11 |12 |13 121 13 14 15 16 INITIAL DATE 114 |15 O IF NOT -- MASTER 17| DIRBASE DIRSIZE 116 VOLUME 20|

G.01.00 3-7

Slave Volume




Slave Volume (Cont.)



G.01.00 3- 9 G.01.00 3- 10

Disc Layout

Defective Tracks Table (Sector 1 of Disc) (Not Used On CS-80 Discs)



NOTE: The situation where there are two entries for the same track, n, one having a DTC of 0 (suspect) and the other having a DTC 3 (reassigned) results from a situation where the disc driver could not "read" (unreadable) the address of the particular track.

Disc Layout

<u>Defective Sector Table (DSCT -- Sector 1 of Disc)</u> (the DSCT exists on device type 3 (CS-80) discs, except cartridge tape)


	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
٥	NUMBER OF ENTRIES IN THE TABLE	0
X 1	INDEX TO THE FIRST ENTRY (6)	1
X2	ENTRY SIZE (2)	2
X3	MAXIMUM NUMBER OF ENTRIES (61)	3
Z4	O (RESERVED)	4
X 5	O (RESERVED)	5
26	FIRST DEFECTIVE SECTOR ENTRY (DOUBLE-WORD LOGICAL SECTOR ADDRESS)	6
X10	SECOND ENTRY	8
X12	THIRD ENTRY	10
•		
•	· :	
X176 X177	MAXIMUM DEFECTIVE SECTOR ENTRY	126 127

Unlike the DIT, entries in the DSCT are not permanent. Once a suspect sector is handled by INITIAL, SDISC, or VINIT, its entry is renoved from the table. Thus, this table contains only unprocessed suspect sectors.

Reserved Area Bit Map (Sector 4 of the System Disc)

The first 400 sectors of the system disc are reserved for Initial's use. This area contains permanent data structures for the boot. It is also used as a temporary storage area for data during sparing. All other system volumes and private volumes reserve only the first 10 sectors of the disc. They do not have a reserved area bit map.

The bit map contains 1 bit per sector. A '1' means the sector is free.



G.01.00 3- 13

Disc Cold Load Information Table (Cont.)

W of global RINS

43

45

Disc Cold Load Information Table (Sectors 28-30)

٥	POINTER TO TABLE INFORMATION	FAEFTR >
1	POINTER TO TEMPORARY CST INFO	TCSTPTR
2	# OF ENTRIES TO READ ON DISC COLD LOAD	NREAD
3	# OF CODE SEGMENTS IN INITIAL	NVTCST'
4	INITIAL'S DB VALUE	INITOB
5	INITIAL'S DL VALUE	INITOL
6	INITIAL'S Z VALUE	INITZ
7	,	PTINI
8	INITIAL'S S VALUE	INITS
9	SYSDISC TYPE SUBTYPE	DISCTST
10	COLD LOAD ID	COFD, FOMD, ID,
11	LOG FILE NUMBER	LOG'FILE'NUM'
12		DIRADR
13	ADDRESS	DIKHUK
14	LDEV 1 VIRTUAL MEMORY	 VIRMEMADDR
15	DISC ADDRESS	ATKIIEIIMDDK
16	# LOG PROCS	
17	LOG ID'S	
18		 RINADR
19		KTHHDK
20	DIRECTORY SIZE	DIRSECT
21	#SECTORS IN VIRTUAL MEMORY REGION OF LDEV 1	SECTORS IN LDEVIVE
22	UNUSED	
23		RINSECT
24		RINS
1		ı

G.01.00 3- 14

Disc Cold Load Information Table (Cont.)

Disc Layout

Disc Layout

- 1			
25	W of global RINS	GRINS TL=Tape cold load	
26	TL RL RY	LOAD MODE RL=Reload	
27	HIGHEST VOL # # OF VOLUMES	RY=recovery H'VOL'	
28	DISC COLD LOAD ENTRY POINT	DISCENTRY	
29	SYSTEM DISC DRT MUMBER	SYSDISCORT	
30	JOB MASTER TABLE	JMATLOC	
31	DISC ADDRESS	JIHILUL	
32	IDD DISC ADDRESS	TODLOC	
33	100 0100 HOMESS	ADDECCE	
34	ODD DISC ADDRESS	ODOLOC	
35		355 230	
36	WELCOME MESSAGE (DST 47 10)	LOGONLOC1	
37	DISC ADDRESS	LOGONLOCY	
38	WELCOME MESSAGE (DST 48	LOGONLOC2	
39	DISC ADDRESS	2000.0002	
40	LOG ID ADDRESS		
41			

LOG TAB ADDRESS

LOG ID SIZE LOG TRB SIZE

FREFTR+O <-----SIZE IN HORDS *DRIVER MEMORY ADDRESS TABLE DISC ADDRESS SIZE IN WORDS FREETR+5 MEMORY ADDRESS *CTRB0 DISC ADDRESS SIZE IN WORDS FREFTR+10 MEMORY ADDRESS *CTAB DISC ADDRESS SIZE IN WORDS FREFTR+15 *
COMMUNICATION SUBSYSTEM
DRIVER
TABLE DISC ADDRESS SIZE IN WORDS FRFFTR+20 *
COMMUNICATION SUBSYSTEM
DEFINITION
TABLE

MEMORY ADDRESS

DISC ADDRESS

G.01.00 3- 15

Disc Layout

Layout Disc Layout

Disc Cold Load Information Table (Cont.)

. ININ 	i
 - - (INITIAL'S SEGMENTS)	FAEFTR+80
DISC ADDRESS	
DEFDI MEMORY ADDRESS TABLE Look-	-UP
SEGMENT SIZE	FAEFTR+75

INITIAL Program CST Map

LOGICAL CST#	PHYSICAL <u>CST#</u>	SEGMENT NAME
o .	1	ININ \
1	2	BOOTSTRAP > core resident
2 3	4	RESIDENT /
3	4	MAINSEG1 \
4	5	MAINSEG1A
5	6	CONFIGURE
6	3 4 5 6 7	DEFCTRACKS but present in core
4 5 6 7	10	SETUP at completion of
10	ii	TAPEIO cold load
11	12	FILEIO (COLO 1555
12	13	DISCSPACE /
13	14	DIRECTORY1
14	15	DIRECTORY2
15	16	SL PROGRAM
16	17	PROCESS
17	20	MAINSEG1B
20	21	MAINSEG2
21	22	MAINSEG3
22	23	MAINSEG4

 $\star {\it code}$ segment swapping starts at completion of MRINSEG1

SYSDUMP/Initial Communication Record (Sector 31)

٥	MIT VERSION	
1	MIT UPDATE	
2	MIT FIX	
3	VERSION	
4	UPDATE	
5	FIX	
6	EXP SYSTEM NR.	
7	HIGHEST DRT	
8	HIGHEST LDEV	
9	HIGHEST VOL/# OF VOLS	
10	# OF ADD'L DRIVERS	
11	COLD LOAD COUNT	
12	FILES DUMPED	F=(13:1)Set if FOS Sysdump
13	SERIAL DISC LOAD FIDS	D=(14:1)Set if future date Sysdump
14	TAPE RECORD SIZE	3-(15:1)Set IF Serial disc Systemp
15	DISC COLD LOAD ENTRY	
16	MAX INITIAL SEG SIZE	
17	SPARE	
18	SPARE	
19	SPARE	
20	DEV CLASS TAB SIZE	
21	TERM DESCRIPTOR SIZE	
22	OLD VTAB SIZE	
23	OLD INFO SIZE	
24	CS TABLE SIZE	
		I

G.01.00 3- 20

SYSDUMP/Initial Communication Record (Cont.)

25	TRBLE LOOKUP BUF SIZE
26	TABLE LOOKUP BUF ENTRIES
27	SYSTEM TAPE LDEV W
28	SPARE
29	SPARE
30	CONVERSION BITS WORD 1 M
31	CONVERSION BITS HORD 2
32	CONVERSION BITS WORD 3
33	CONVERSION BITS WORD 4
34	SPARE
35	SPARE
36	SPARE
37	SPARE
38	SPARE
39	SPARE
40	LOG FILE NUMBER

M = (15:1) MPE Version 0 = MPE (G.00.00) 1 = MPE (G.01.00)

Cold Load Information Table Extension

The Cold Load Information Table Extension is a part of the Cold Load Information Table that has no use in booting the system. It exists for different system level processes to hold information that would only be created during a RELOAD. A good example of this is the system log file number. This is only created on a RELOAD, and changed whenever a log file is full or a boot (other than a RELOAD) is performed.

In order to protect the Cold Load Info Table, the extension was created. In this way NO I/Os should be performed to the Cold Load Information Table during HPE operation. However to process data into the Cold Load Info Extension a process wust use the access routine "PROCESS'COLD'LORD'INFO". The exact calling sequence can be found in KERWELD.

The Cold Load Information Extension is 2 sectors long and immediately follows the SYSDUMP/Initial Communication Record starting at sector address #31 on logical device 1.

The assigned entries are as follows:

	·	0
RESERVED FOR FUTURE SYS	TEM NOT	2
RESERVED FOR FOLIARE 313	HEH USE	٠
	*	20
SYSTEM LOGGING FILE NUMBER		21
NETWORK MANAGEMENT LOGGING FILE NUMB	ER	22
METWORK MANAGEMENT TRACE FILE MUMBER		23
FULL/PARTIAL COMMAND DUMP DATE		24
		25
***************************************		26
NOT CURRENTLY ASSIGNED		27
		28
	 	255

G.01.00 3- 22

G.01.00 3- 21

Disc Lavout


Virtual Disc Space Management Structures

Disc space for data segments is allocated from reserved regions of system volumes which have been assigned the virtual memory supporting (VMS) attribute. The data structure used for accounting and management of the virtual disc space of the various VMS volumes is the Virtual Disc Space Table (VDSMTAB). This structure consists of a circular list of entries, one for each VMS volume. Each entry contains the information defining the state of the virtual memory region on that volume.

Virtual Disc Space Management Table

VDSMTABD DSTM = 39 (X47) VDSMTABPTR = Rbsolute(X1026) = SYSGLOB X26

General Structure



Disc Lavout

VDSMTAB Entry O Format


VDSMTABOO	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	TABLE LENGTH
VDSHTRB01	# SYSTEM VOLUMES WHICH HAVE VIRTUAL MEMORY	VMSVOLUMECNT
VDSMTAB02	INDEX OF NEXT ENTRY TO ALLOCATE FROM	STARTENTRY
VDSHTAB03	VM PAGE SIZE (512)	VMPAGESIZE
VDSMTAB04	# SECTORS/VH PAGE (4)	SECTORSPERVMPAGE
VDSMTAB05	OFFSET FROM ENTRY TO BITMAP (%20)	OFFSETTOBM
VDSHTRB06	TOTAL # VM PAGES CONFIGURED IN SYSTEM	
VDSMTABO7	LEAST # OF VM PAGES THAT HAVE EVER BEEN AVAIL.	
	VDSMTAB X10-X17 UNASSIGNED	1

VDSMTAB General Entry Format

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
Word O	INDEX OF NEXT ENTRY IN CIRCULAR LIST NEXTINLIST
Hord 1	LDEV# LDEV
Word 2	STARTING SECTOR OF DEVICE'S HOSTARTSECTOR
Word 3	VIRTUAL MEMORY REGION LOSTARTSECTOR
Word 4	# SECTORS IN DEVICE'S TOTAL SECTOR
Word 5	VIRTUAL MEMORY REGION COUNT
Hord 6	# PAGES IN DEVICE'S VIRTUAL MEMORY REGION TOTAL PAGECNT
Word 7	# OF PAGES RVAILABLE IN DEVICE'S VM REGION PAGESAVAILABLE
Hord X10	# OF VALID WORDS IN DEVICE'S BIT MAP BMLENGTH
Hord X11	SIZE OF SMALLEST RECENT MISS SMALLESTMISS
WORD %12	SMALLEST NUMBER OF PAGES EVER AVAILABLE
X13-X20	UNASSIGNED
	DEVICE'S VIRTUAL MEMORY BIT MAP
	***COMMENT: A bit on in a device's VMBIT MAP ==> Corresponding VM page is free.

Volume Table

SIR #22=126 OST #29=135




G.01.00 3- 25

G.01.00 3- 26


Disc Layout

Typical Private Volume Entry



Disc Layout

Typical System Volume Entry



CHAPTER 4 DIRECTORY

Introduction to the Directory

SYSGLOB cells:

DIRBRSE <----absolute disc addr of base [SYSGLOB+X130 RND X131]

Directory on disc consists of a contiguous area:

DIRBASE -> DIRECTORY BITMAP DIRBASE+3 -> DIRECTORY DATA Entries and Indices

The bitnap defines the available/used sectors in the directory. If the directory is <= 6112 sectors, then the bitnap uill occupy 3 sectors. If the directory size is > 6112 sectors, then the bitnap uill occupy 32 sectors uith DIRBNSE pointing to the 30th sector of the bitnap. A zero bit in the bitnap represents a used sector. Words 0 and 1 of the bitnap are ignored.

Directory entries contain pointers which are sector displacements relative to DIRBASE. Entries and indices are grouped into "blocks".

The capacities for accounts/groups/users/files are dependent on their block sizes.


* SYSSAIBSIZE SYSAUIBSIZE SYSAGIBSIZE SYSGFIBSIZE SYSGVSIBSIZE System acct index block size (3 sectors)
Rcct. user index block size (1-3 sectors)
Rcct. group index block size (1-3 sectors)
Group file index block size (3 sectors)
Group volume set definition ind. blk. size(1 sector)
Rcct. entry block size (3 sectors)
User entry block size (2 sectors)
Group entry block size (2 sectors)
Group entry block size (2 sectors)
File entry block size (2 sectors)
Volume set definition entry block size (1 sector)
Maximum of above. (used to initialize DDS.)

SYSAEBSIZE SYSUEBSIZE SYSGEBSIZE SYSGEBSIZE SYSVSERST7F SYSMAXBSIZE

*These values are used once for the creation of the (root) system, account index or new systems. This root index is always at address DIRBASE+3.

G.01.00 4-1

Overview of Directory




Overview of Directory


G.01.00

Directory

Directory Data Segment



Directory Data Segment (Cont.)



Directory

Directory

Directory Pointer Rrea [DR or DB] DST=20(10) STR=8(10)

	l					
1	LDEV DIRECTORY BASE	139/161	DIRBASE	,		
1	RODRESS OF PAGE IN BUFFER	140/162	DIRBASE	2'		
	DIRECTORY PAGE IN BUFFER	141/163	CONTENT	3		
	DB ADDRESS OF 1ST ELEMENT	142/164	LPNTR			
	STARTING ADDRESS OF BUFFER	143/165	IOPNTR			
1	# VALID PAGES IN BUFFER	144/166	NUMVALI)		
	DI 18	145/167	D=DIRTY	FURG	, B=BAD	ELEMENT
		146/168			OTE:	
**	W WORDS USED IN BLOCK	147/169	USED	**		AND
	BLOCK SIZE (SECTORS)	148/170	BSIZE		ENTRIES	
	BLOCK SIZE (WORDS)	149/171	BNSIZE	*	INDEXES	DNLY
		150/172	BFACTOR			
	I P TY ELEMENT SIZE BLOCK SIZE (NORDS) (SECTORS)		MISCHD			
	NUMBER OF ELEMENTS	152/174	XCOUNT			
	NUMBER OF ACCESSORS	153/175	PCOUNT			
	ENTRY TOTAL	154/176	ETOTAL			
	O P TY ENTRY SIZE BLOCK SIZE	155/177	EMISCUD			
		156/178	PINDEXP			
	F	157/179				
Ï		158/180	PNRME	TY =	0-FILE	
		159/181			2-RCCT 3-USER	-
į		160/182		I =	4-VSD	/ BLDCK
	•					BLOCK

G.01.00 4- 5

Directory Space Data Segment (DIRSDS)

SIR=8

DST = 21 (X25)

	0123456789012345	
0	Logical device Bit map	
1	base sector address	DS'BASE
2	Ptr to last avail word in buff	DS'LAST'WORD
3	Ptr to first word in buffer	DS'FIRST'WORD
4	Size in sectors of directory	DS'DIR'SIZE
5	DIEISIPI	DS'FLAGS
6	First current sector in buff	DS'CUR'SECTOR
7	Disc address of current part	
10	of bit map in the buffer	DS' ADDR
11	Size of buffer in words	DS'SIZE
12	Next requested sector	DS'REQ'SECTOR
13	Last sector in bit map	DS'LAST'SECTOR
14	System saved potr to last	DS'SYS'LAST
15	System saved potr to first	DS'SYS'FIRST
16	System saved current sector	DS'SYS'CUR
17	Saved directory size	DS'SYS'SIZE
20	LDEV that last error occurred	DS'ERROR'LDEV
21	Type of error that occurred	DS'ERROR'TYPE

G.01.00 4- 6

Directory

This section of the bit map DST is occupied by up to 3 sectors of bit map. It is swapped in 3 sectors at a time as needed. DS'FIRST'HORD is updated to search for space in the bit map. When it reaches DS'LAST'HORD for the second pass, the next 3 sectors of bit map will be swapped in.

Descriptions:

מתם יצת

This is the address of the section of bit map that is currently in the buffers. For example, this address will usually be the same as DS'BRSE. If we need to page in more sectors of bit map than the first three, then this address will be subsequently larger than DS'BRSE.

This is the base address of the directory bit map. If the directory is greater than 6112 sectors, then this address will be 29 sectors less than the address found in the Cold Load Information table on disc.

This is the current bit map sector number of the first sector in the buffer area. Its value can range from 1 to 30. This number minus one added to D3'BRSE will result in D3'RDDR.

If this bit is on, the directory allocation and deallocation is off and only a WARMSTART will turn this bit off. The bit is turned on if an I/O error occurs on a directory bit map sector or if we find data integrity problems with the bit map, i.e. if we attempt to deallocate a sector that is already deallocated.

Directory

This is the size (sectors) of the directory area. This size includes only the last 3 sectors of the bit map. If the directory is greater than 6112 sectors, then this size does not include the extra 29 sectors of bit map. It can also be thought of as the number of bits in the bit map.

This bit is set if the bit map sectors in the buffer have been modified in any may. When more sectors must be brought into the buffers, or if we switch to a different domain (system to PV, PV to system) this bit is interrogated to determine if the sectors presently in the buffers must be first written to disc.

DS'ERROR'LDEV

The LDEV in which the last directory error occurred.

This word describes the type of directory bit map error that occurred. Its

- 0 No error
 1 I/O error on a urite
 2 I/O error on a read
 3 Attempting to deallocate space that is already deallocated
 4 Directory space management is already disabled

A directory space management error is currently in progress.

A DST relative pointer to the word in the bit map buffer that we will interrogate next when directory space is needed. When the system first comes up, this word is always initialized to DS'MERDER+2 (i.e. to point to the first word in the bit map). On subsequent bit map sector reads, it is set to DS'MERDER since subsequent sectors will not have the 2 word overhead that exists in the first sector of the bit map.

This word contains numerous flags. See individual descriptions.

DS'LAST'SECTOR

This is the total number of active bit map sectors. This number will range from 1 to 32.

DS'LAST'HORD

This is the current number of bit map word in the buffer. It can range from 1 to %577 + DS'HEADER. If there exists 3 full sectors in the buffer, then it will have the value %600 + DS'HEADER - 1 or %621. It is compared to SS'FIRST'BURD to determine if we have hat the end of the current buffer

DS'PERM'DISABLE

If this bit is set, then directory allocation/deallocating is permanently disabled. This bit should not be set.

This is the next sector to begin reading in up to 3 bit map sectors. It is updated by 2 or 3 and the read procedure will bring in up to 3 sectors starting from this sector. If this sector is set to be greater than DS'LBST'SECTOR, then it is reset to 1. Rfter the sectors are read in, DS'CUR'SECTOR is set the DS'REG'SECTOR.

DS'STZE


This is the size in words of the bit map buffer area. It is always a nultiple of a sector (128 words). It will usually have the value of X600. Legal values are X200, X400 and X600.

DS'SYS'LAST, DS'SYS'FIRST, DS'SYS'CUR & DS'SYS'SIZE

The values of DS'LRST'NORD, DS'FIRST'NORD, DS'CUR'SECTOR and DS'SIZE will be stored in these locations when the directory space management switches from the system directory to a private volume directory. And, of course, when DSN switches back to system domain, the above mentioned values are reinitialized with these values.

Directory Structure

INDEX BLOCK



The Index Block prefix points back to the previous higher level. The Index Block entries point to the entry blocks.

G.01.00 4- 9

Directory

Directory Definitions


smallest allocatable record ("phys.recd")-currently sector. integral# of pages; contains contiguous indices or entries. pointer to entry block, containing name of 1st entry. information-containing "object" may contain pointer to an >PAGE >BLOCK >INDEX

>ENTRY index block

>POINTER 15-bit positive relative page number (relative to directory

base).
>DDS - directory data segment.
>ELEMENT - a generic name for index or entry.

Index Block Prefix (10 Words)




*The count is incremented by each access that uses and relies upon a pointer to the index block, i.e., it is guaranteed not to be purged while the count is not = 0.

G.01.00 4- 11


Directory

Index Entry (6 Words)


G.01.00 4- 10



Account Entry (X36 Words)




Account Entry (Cont.)



If 1, system level UDC's exist (only in "SYS" account) If 1, account level UDC's exist for account

G.01.00 4- 13

Group Entry (X51 Words)



G.01.00

Directory

Group Entry (Cont.)

	1	1
27	GCAPABILITY	23 GROUP CAPABILITY
30	GLINKAGE	24 GROUP DIR. BASE LINKAGE
31	GVSDIPNTR	25 GROUP VOL SET DEFN INDX
32	GHVSHRME	26 HOME VOL SET NAME
33	-	27
34	GHVSANAME	 28 (Definition's acct name)
35	-	29
36		 30
37		 31
40	- GHVSGNAME -	(Definition's group name) 32
41	-	 33
42		 34
43		 35
44	- GHVSVSNAME -	l (Definition's vol set name) 36
45	-	 37
46	GSAVEFIPNTR	 38 SAVE CELL FOR GFIPHTR
47	GHOUNTREFCNTR	39 GROUP BIND COUNTER
50	0	40 GSPARE
- 1		_

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

GLINKAGE


Directory

Group Entry (Cont.)

(0:1) (8:8)	= 1; = 0;	HVS is in	System Domain Private Volume Domain or Not Bound Bound


			JP SI													
		ļ			l			1	l		l	l	l	l	1	l
	P	1///	R	R	R	l R	l R	I A	I A	i A	i a	i A	ÌШ	iш	iu	iu
25	!	1///	RNY	AC	RL	GU	IGL	IRNY	IAC	IAL	i GU	IGL	IANY	Ar I	İΩI	icu
								1	l							
		1 L	L	L	ΙL	L	l X	ΙX	l x	ΙX	i x i	S	l s	2	İS	2
26	GL	ANY	AC	AL	GU	IGL	ANY	AC	AL	GU	GL	RNY	AC	AL	GÜ	GĽ
			1			I	1	1	i	i		1		-		

File Entry (File Pointer)(6 Words)




B - Bad file label (0:1) = 0 - not defective = 1 - defective

User Entry (19 Words)



User Attributes/Capability



G.01.00 4- 17

G.01.00 4- 18

Directory

Volume Set Definition Entry

			!					!	
		0 1 2 3			3VSNAME			0 1 2 3	VOLUME SET NAME
TY =	0	4	TYIAI2		7	MVTABX		4	GVSLINKAGE
		5	VOL COUNT 4		7	VMASK		15	GVSINFO
VOLUME ENTRY O	1	6 7 10 11			/OLUME			6 7 8	MEMBER VOLUME NAME(1ST ENTRY IS MASTER VOLUME)
(6 WORDS)	' ¦	12	0				14 M	10	GVSVOLF LAGS
	١	13	PSEUDO SUBT	YPE		VTABX		11	GVSVOLINFO
VOLUME ENTRIES 1 - 7	1	14			:			12	
	ĺ	57			•			47	
		60	!					48	
		61						49	
		62	į	GV S1	VOLUME			50	MEM. VOL. NAME
		63						51	MINE.
		64	GVSV0LFL	igs	(MEMBER	VOLUME FLA	GS)	52	
		65	GVSVOLINE	0	(MEMBER	VOLUME INF	0)	į53	
		66	GVSDREFC	IT	(DEFN.	REF. CHTR.)		54	
		67		0					SPARE
								•	

TY = 0 VOLUME SET DEFINITION
= 1 VOLUME CLASS
MYTABX: MOUNTED VOLUME TABLE INDEX (IF MOUNTED)
VOL COUNT: NO. OF VOLUMES
VMASK: VOLUME MASK
M = 0 NOT MOUNTED
= 1 MOUNTED
VMABX: VOLUME TABLE INDEX

G.01.00 4- 19

Directory

GVSLINKAGE

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	1!
T	A]		NOT	[m	KBATY	:		
1		ı		USE	D			l							

T - TYPE

0 = Volume Set Definition
1 = Volume Set Class
R - RLLDGRIMG FLAG
0 = not initially allocating (not 1st user of set)
1 = 1st user of set allocating resources (transitional)
MVTABX - Mounted Volume Table Index
0 if volume set not logically mounted

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
	VOL	CNT		 	Ni U:	DT Sed					٧S	MASK			

VOLCNT - Number of members in set VSNRSK - Bit mask of volume member usage Order is from right to Left i.e., bit 15 is 1st member, bit 14 is 2nd member ...

GVSVOLFLAGS

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
		NOT USED														Į Ħ
Į																1

M - Member Mounted Flag O = not mounted 1 = mounted

GVSVOLINFO

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
		DISC PSEUDO SUBTYPE							 			۷1	RBX			
ĺ																

DISC PSEUDO-SUBTYPE = (Actual type *16) + actual subtype. VTABX - Volume Table Index

1 1 1 1 1 1 011:2:314:5:617:8:910:1:213:4:5 O VOLUME CLASS NAME GVCNAME 2 GVCLINKAGE 4 VOLUME CLASS IDENTIFICATION GVCINFO 5 VOLUME CLASS INFORMATION GVCPNAME 6 PRRENT VOLUME SET DEFINITION GYCPANAME ACCOUNT OF PARENT DEFINITION 10 11 9 12 10 13 111 GVCPGNAME GROUP OF PARENT DEFINITION 14 112 15 113 16 14 17 15 GVCPVSNAME VSNAME OF PARENT DEFINITION 20 21 17 0 22 18 0 55

G.01.00 4- 21

Directory

GVCLINKAGE

	2													
T	 1////	////	////	///	////	////	///	///	////	////	////	////	////	///

T - TYPE
1 = Volume Set Definition
0 = Volume Set Class


GVCINFO

0 1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
V	LCHT			NI U	OT SED					VC	MASK			

VOLCHT - Number of members in set
VCMRSK - Bit mask of volume member usage (VOLUME CLASS MRSK)
Order is from right to left
— i.e. bit 15 is 1st member, bit 14 is 2nd member ...

Volume Mask Format

- USED IN MYTAB, PVUSER, FILE CONTROL BLOCK (FCB), VOLUME SET/CLASS DEFINITION, VOLUME SET VTAB. - 8-BIT MASK.



G.01.00 4- 22

CHAPTER 5 LOCK RESOURCES

SIRW Allocation DST 253

Sir's	Ordered	by	Sir	Number

2. 0.0.00	a by bar manage	
SIR #	RANK	SIR MAME
1	10	LOAD PROCESS
ż	335	CACHE CONTROL
3	91	IDD
4	92	000
- 2	50 50	PROCESS TREE STRUCTURE
ě	50 60	SCHEDULING QUEUE
٩	70	CST ENTRIES
5 6 7 8	80	SYSTEM DIRECTORY
9	90	LPDT
		LDT
10	85	
11	110	STORAGE IN OVERLAY AREA
13	130	JPCHT
14	140	JCUT
15	27	JMAT_
16	5	FMRVT
17	22	LOADER SEGMENT TABLE
18	180	ADD
19	190	SP00L
20	200	MESSAGE CATALOGUE
21	210	RIT
22	220	VOLUME TRBLE
23	230	WELCOME MESSAGE SIR
24	240	ASSOCIATION TABLE
25	250	CS ALLOCATE
26	260	LOGGING BUFFER
27	83	PV MVTRB
28	280	MERSSIR
29	290	PV USER TABLE
30	300	INAGE
31	310	KSBN
32	320	USER LOGGING
33	330	DEBUG BREAKPOINT TABLE
34	340	PCB
35	350	SUB-QUEUE MRPPING TABLE
36	360	CILOG
37	25	FILE INTEGRITY
38	380	RIN
38 39	360 390	TAPE LABELS
	390 87	DEVICE CLASS TRBLE
40 41	400	Reserved
	400 401	Cold Load SIR
42	401	ist JOB
43		16T JUB 2nd JOB
44		Sua 200
•	•	•

G.01.00

Sir's Ordered by Ranking

RANK	SIR #	SIR NAME
5	16	FMRVT
10	.1	LOAD PROCESS
22	17	LOADER SEGMENT TABLE
25	37	FILE INTEGRITY JMAT
27	15	
50	5 6	PROCESS TREE STRUCTURE SCHEDULING QUEUE
60	9	CST ENTRIES
70	7 8	SYSTEM DIRECTORY
80 83	27	PV MVTAB
85	10	LDT
87	40	DEVICE CLASS TABLE
87 90	9	LPDT
90 91	3	IDD
92	4	000
110	11	STORAGE IN OVERLAY AREA
130	13	JPCNT
140	14	JCUT
180	18	VDD
190	19	SPOOK
200	20	MESSAGE CATALOG
210	21	RIT
220	22	VOLUME TABLE
230	23	WELCOME MESSAGE
240	24	ASSOCIATION TABLE
250	25	CS ALLOCATE
260	26	LOGGING BUFFER
280	28	MERSSIR
290	29	PV USER TABLE
300	30	INAGE
310	31	KSAM
320	32	USER LOGGING
330	33	DEBUG BREAKPOINT TABLE
335	2	CACHE CONTROL
340	34	PCB
350	35	SUB-QUEUE MAPPING TABLE
360	36	CILOG
380	38	RIN
390	39	TAPE LABELS
400	41	Reserved

G.01.00 5- 2

Lock Resources

SIR Table Information

The system internal resource table is located in non-linked memory (resident table). The SIR table is used to protect critical system elements against access by more than one process, i.e., it provides a "lock out" mechanism. Each critical system resource (usually a table) is assigned a specific SIR number. Procedures are provided within MPE to lock (GETSIR) and unlock (REISIR) the SIR. Processes attempting to obtain a SIR that is not available are inpeded by the system. The SIR table entries form the head of a linked list in this case. If nore than one process becomes impeded, word 15 of the PCB entry is used to add the "new" process to the growing list. The method of uninpeding the process depends on the SIR type.

A SIR does not respect process priority and operates in a FIFO manner. When a process is added to the end of the queue, the priority of the holder of the SIR and the priority of all intervening processes are increased. They are increased to the priority of the nexly requesting process.

To get SIRs, arrange the SIRs in ascending order by rank. To release SIRs arrange the SIRs in descending order by rank. For example:

GETSIR (LDT) **Rank=85** GETSIR (DDD) **Rank=92**

RELSIR (ODD) **Rank=92** RELSIR (LDT) **Rank=85**

Lock Resources

SIR Entry Formats

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15


	0 free
0	1 (not locked)
0	2
0	3
	1
PCB index of holder	O SIR locked
0	1 (no impeded processes
0	2
0	3
	! !
PCB index of holder	0 SIR locked
SIR QUEUE LENGTH	1 (impeded processes)
HEAD OF IMPEDED LIST(PCB relative)	2
TAIL OF IMPEDED LIST(PCB relative)	3
[1

P = PINM PIN = PCB table entry number SIR QUEUE LENGTH- number of processes queued for this SIR

The SIR table is indexed by SIRW, with each SIRW corresponding to a unique, pre-assigned system internal resource. Entry #0 is not used. Inpeded lists are established by using the SIR table entry (2) as the head of the list and PCB(15) for elements. PINs are always used as pointers, with 0 indicating end of list.

Lock Resources

Allocation and Locking of Local RIMS




G.01.00 5- 6

Lock Resources

Lock Resources


Allocation and Locking of File RIMS



P≖pin#

Lock Resources

Allocation and Locking of Global RINS



P=pinW

INDEX OF PASSWORD = RELATIVE TO BASE OF SECONDARY
TABLE

G.01.00 5- 8

G.01.00 5- 7

File System Overview

I/O to files is done by reference to file numbers, which are assigned by calling the FOPEN intrinsic. This establishes an initial "point of attachment", which may be described as a connection between a program (i.e., process) and that particular point in a particular file at which the next FRERD or FIRITE mould cause data to be transferred. A point of attachment is described by a control block, of which there are several different kinds (described later). Control blocks may exist in the process's oun stack or in an extra data segment assigned by the file system. In order to find control blocks quickly, a pointer scheme called vectors is used. R control block is uniquely described by a vector, which consists of two words with the first word containing a segment number and the second word containing a word offset into the control table of the vector table entry which describes the location of the control block within that segment. The entire assemblage, consisting of eight overhead words, the vector table, and all of the control blocks to which it points, comprises the entire segment; if in a stack, it occupies part of the PXFILE part of the PCBX.

The point of attachment is described by a "physical access control block", or PACB, which will exist as a result of an FOPEN to any file (except \$MULL). Any required I/O buffers are associated with the PACB; refer to Section 2.1.

RII FOPENs specifying "multi-access" for all processes running under a single plot use a single PRCB for references to a multi-access file. Rithough all these are attached to a single point in the file, the type of attachment (i.e., ROPIOINS) may be different. So, each FOPEN specifying a multi-access file establishes a "logical access control block", or LRCB, which contains the point-of-attachment local values. The use of a single boffer (i.e., PRCB) ensures that references by various processes or against various FOPENs within one process are dealt with in strict sequential order. Note that references to a file by other jobs, or by other processes not specifying multi-access, will be through other PRCBs, whose buffers will be read or written at the pleasure of the file system; in order to ensure any sort of coherence to such shared references, the jobs must use global RINS and FLOCK and FUNLOCK the file. \$\$TDIN, \$\$TDLIST, and spoolfiles are opened multi-access automatically. access automatically.

In the case of disc files, there is another kind of control block: the file control block (FCB). It contains copies of information read from the file label, such as the end-of-file pointer, the extent map, and the record and block structure. The EOF pointer is updated in the FCB as the file is uritten, and all changes made to the FCB are posted to the file label when the file is closed. An FCB is shared by all jobs in the system which reference

G.01.00

File System

Table Formats

This section gives a detailed discussion of the main tables constructed and used by the file system. The location and overall structure of each table is given, in addition to the table format and a discussion of each field in the table. Table indices at the right of the table are in octal. Index names apply to the entire word; if in parentheses, the names are defined in the file system listing but not explicitly used there.

File System Section of PCBX (PXFILE)

The PXFILE area is a subsection of the PCBX. It is a contiguous, expandable and contractible block of storage that is managed by the file system primarily for its own use. Other subsystems, namely 152 and DS, also make use of the PXFILE section. In doing so they must conform to the conventions of the file

The overall structure of the PXFILE area is:

	•
DVERHEAD	(FIXED)
CONTROL BLOCK TABLE	(VARIABLE)
RVAILABLE	(VARIABLE)
ACTIVE FILE TABLE	(VARIABLE) DL-5

File System

The file number assigned by an FOPEN is an index into the Available File Table (AFT), a table of six-word entries which is at the end of the PXFILE part of the PCBX. Two double words are vectors to the PRCB and (if it exists) the LRCB.

AFT entries can also reside in a global AFT extra data segment. If the file was opened Global AFT (specified in the ROPTIONS) and the program is privileged, then the AFT is placed into this global AFT DST. Any accesses to the file are identical to local AFT's. All accesses to the file opened global must be done from privilege mode code. The file system intrinsics distinguish this file by a negative file number. Again, these files are identical in every other way except for where the AFT entry resides.

Because control blocks are shared among processes, it is necessary to have a scheme for coordinating access to them. A control block is "locked" by a process which requires exclusive access to it for a time. Other processes which attempt to lock the block will find it already locked, and will be impeded and queued. It may also be necessary to lock an entire control block table so that a process can create or destroy a control block in it, or lock or unlock an existing control block in the table.

Another table used by FOPEN is the File Multi-Access Vector Table (FMRVI). This table exists in a system extra data segment and is used by all jobs and processes in the system. When a file is being FOPENed with multi-access specified, the FTRNYI is searched; if the file is already open, the FTRNYI gives the PRCB vector for the prior reference for each job.

Buffers

A bit in AOPTIONS specifies, when a file is opened, whether access is to be buffered or unbuffered. If unbuffered, data is transferred directly between the I/O device and the user's buffer (usually in his stack), which will be frozen in menory for the duration of the transfer. If buffered, the data is noved between the user's buffer and a file system buffer to which the I/O is

Buffers are associated with the PACB, attached to it as an appendage.

G.01.00

File System

Overhead

The part labeled Overhead contains information that pertains to the entire section. It is addressed via the pointer at DL-3.

0 1 7 8 15		
PXFILE SIZE IN WORDS	- 0	PXFSIZE
LAST DOPEN ERROR NO. LAST COPEN ERROR NO.	1	
N	2	
LAST DS AFT	3	
SLAVE AFT NUMBER	4	
LAST KOPEN ERROR NUMBER LAST FOPEN ERROR NUMBER	5	
AFT SIZE IN WORDS	6	PXRFTSIZE
	7	
CS TRACE FILE INFO	8	(PXCTRINFO)
LAST RESPONDING NO-WAIT I/O AFT ENTRY NUMBER	9	PXFLEFTOFF
1ST USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	10	PXFCBT1
2ND USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	11	(PXFCBT2)
3RD USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	12	(PXFCBT3)
4TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	13	(PXFCBT4)
5TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	14	(PXFCBT5)
6TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	15	(PXFCBT6)
7TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER	16	(PXFCBT7)
8TH USER (NOBUF) CONTROL BLOCK TABLE OST MUMBER	17	(PXFCBT8)

Partial word field identifiers are:

PXFDOPEN	= PXFILE(1).(0:8)#,	last DOPEN error code
PXFCOPEN	= PXFILE(1).(8:8)#,	last COPEN error code
PXFNOCB	= PXFILE(2).(0:1)#,	no CB's in PXFILE CBT'
PXFKOPEN	= PXFILE(5).(0:8)#,	last KOPEN error code
PXFFOPEN	= PXFILE(5).(8:8)#,	last FOPEN error code

Discussion:

PAFAFTST7F

This is the size (in words) of the Active File Table (AFT). The size is in words to simplify calculating the size of the available block.

DYFCRT1_8

These are the DST numbers of the user (NOBUF) control block tables. A DST number of 0 indicates that no data segment is allocated.

PXFCOPEN

This contains the last COPEN error number. Not used by the

PXFCTRINFO

This contains information pertinent to the CS trace file. Not used by the file system.

PHENOPEN

This contains the last DOPEN error number. Not used by the file system.

PAFDSINFO

Reserved for DS. Not used by the file system.

PAFFOPFIA

This contains the last FOPEN error number. If it is zero then the last FOPEN successfully completed; otherwise the last FOPEN was unsuccessful and the number is the file systen error number.

PKEKOPEN

This contains the last KOPEN error number. KSRN is partly embedded in the file system, and an FOPEN failure on a KSRN file can be caused by a failure to open either the key file or the data file. This error number is used in conjunction with PXFFOPEN to determine which file caused the KSRN open failure. This error number is not used by the file system.

PXFLEFTOFF

This is the AFT entry number of the last file/line that completed a nowait I/0; if zero then no nowait I/0 has been completed. This cell is maintained solely by and for the IDMATI intrinsic.

PAFNOCE

This bit signifies that control blocks are not to be created in the PMFILE control block table. This bit is set by the MOCB parameter to the CMERTE intrinsic or the :RUM command. This feature permits the user to have as much stack space as possible; otherwise the file system will take several hundred words of stack for the PMFILE control block table.

PXFSIZE

This is the size (in words) of the complete PMFILE area. It is the sum of the overhead block, the control block table, the active file table and the available block.

G.01.00

File System

Rctive File Table (RFT)

The part labeled Active File Table contains information used by the file system (or CS, DS, etc.) to grossly characterize the file access and, most importantly, to give the location of the control blocks.

The overall structure of the AFT is:

ENTRY N (FIXED, 6 MORDS) DL-9 (FIXED) DL-5 **ENTRY 1**

where N = PXFAFTSIZE/6.

The length of the RFT is specified by PMFRFTSIZE. Unused entries are all zeros. When the table is full it is expanded by taking space from the Rvailable block.

The RFT is negatively indexed by file number: the entry at DL-9 corresponds to file number 1, the entry at DL-15 corresponds to file number 2, etc.

The structure of the global AFT DST, described in Section 2 is as follows:



PXFILE Control Block Table (PXFCBT)

Addressing within a PMFILE control block table is somewhat more complicated than addressing an extra data segment CBT since the table does not begin at DB+O. Rs a result all pointers within the table are table relative; the starting address of the table must be added to a pointer to generate a final DB-relative address. This addressing convention is consistently applied to all control block tables.

When the control block table is expanded, space is taken from the AVAILABLE area. If no space is available then the PXFILE area is expanded and the acquired space is added to the AVAILABLE area.

The part labeled Rvailable is used to provide space when the Control Block Table or the Active File Table is expanded. These two tables grow towards each other, and when more space is needed it is simply taken from the Rvailable Block.

When the Available area is exhausted, the PMFILE area is expanded, the AFT is relocated and the new space is added to the Available Block.

Currently the PXFILE area is only expanded; it is never contracted.

6.01.00 6- 6

File System

The structure of a file system AFT entry is:

0 1 2 3 4 5 15		
ENTRY TYPE N	0	
PHYSICAL ACB DST NUMBER	1	RFTPRCBOST
PHYSICAL ACB ENTRY ADDRESS	2	AFTPACBENTRY
LOGICAL ACB DST NUMBER	3	AFTLAC80ST
LOGICAL ACB ENTRY ADDRESS	4	AFTLACBENTRY
NO-WAIT I/O IOOM	5	AFTIOQX

The entry format depends on the entry type; the file system uses entry type

The following partial word field identifiers are used:

Discussion:

AFTIOOX

This is the IOQ index of the pending nouait I/O (if any). This is applicable if the file was opened with the NOWRIT option specified. Also, CS and DS have the same capability and use this cell in a consistent manner. This is because the IOWRIT intrinsic services the file system as well as CS and DS, and is the principal user of this cell. If the IOWR is negative, then one of two possibilities exist. If the file is a message file, then file IOQN is the accessor's reply port. If the file is a standard MPE file, then a read was done to a nonexistent extent and this is simply a stub inserted by the file system.

AFTLACBOST

This is the DST that the Logical RCB (LRCB) if it exists. This is applicable if the file was opened with the multi-access option specified.

AFTLACBENTRY

This is the word offset into the control block table of the LACB vector table entry, applicable if the file was opened with the multi-access option specified.

RETNULL

This bit signifies that the file is \$NULL and that there are no control blocks.

RETPROPRIET

This is the DST that contains the Physical ACB (PACB). A PACB exists for all files except \$NULL.

AFTPACBENTRY

This is the word offset into the control block table of the PRCB vector table entry. This will be nonzero for all files except \$NULL.

RETTYPE

This is the AFT entry type number. At present the following entry types are defined:

O - file system
1 - remote file
2 - DS (nowait I/O disallowed)
3 - DS (nowait I/O allowed)
4 - CS

5 - CS 6 - KSRM 8 - Message File

Remote file RFT entry:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	ı
FSTYPE UNUSED MR	0
LINE NUMBER	1
REMOTE FILE NUMBER	2
PENDING FCLOSE DISPOSITION FROM FOPEN	3
UNUSED	4
IOGX	5

RFT 0
FSTYPE - This value will be 1 for remote files.
RR - Set if the file was opened multi-access.
RFT 1 - Local line number of remote file.
RFT 2 - File number of the remote file.
RFT 3 - Pending disposition of the file. Set when file was FOPEN'd and will possibly be used as the FCLOSE disposition.
RFT 5 - No wait I/O Queue Index.

G.01.00 6- 9

File System

CS Line entry:

```
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
--|--|--|--|--|--|--|--|--|--|--|
FYPE | U| U|ID| B| UNUSED
                LOGICAL DEVICE NUMBER
          VECTOR TO MULTIPLE IOQ INDICES
                                                             2
                                    UNUSED
TR | I| R| DIAL|
                                                             3
                    MISC'DST
                 IOQX ( CIO only )
                                                             5
```

RFT 0
FTYPE - This value will be 4 or 5. R 5 signifies that the line has an autodialer attached.

H - The line has been opened with no waiting on I/O requests.

ID - Line is a multipoint control or 3270 station.

B - Line was opened with buffering.

RFT 1 - Logical device number of the line.

RFT 2 - Vector to Multiple IOQ indices.

TR - Bit O on signifies tracing enabled. Bit 1 on signifies

trace all.

I - On if line is currently connected.

R - Signifies that this CS device is an SCCP device.

DIRL - O = Dial on urite, answer on read.

1 = Answer on urite, dial on read.

2 = Always dial.

3 = Never dial.

DST number of the line's misc data segment.
 If <> 0, then it is the system DB address of a single request IOQ entry. IOWAIT uses this word to pass the IOQ index of the completed request for this RFT to CSIOWRIT.

File System

DS AFT entry:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
	٥
DATA SEGMENT NUMBER	1
DSDCB INDEX UNUSED	2
LDEV NUMBER	3
PREVIOUS AFT POINTER	4
IOQX ·	5

RFT 0
FSTYPE - This field will have the value 2 or 3.
C - On if DSOPEN called by CXDSLINE or REMOTE'HELLO.
H - On if Haster PTOP RFT.
P - On if PTOP related.
R - On if remote main process.
RFT 1 - DS data segment table pointer.
RFT 2 - DSDSCB Index - DS data segment control block index.

AFT 1 AFT 2 AFT 3 AFT 4 AFT 5

- Logical device number. - Preceding DS open RFT Pointer. - IDQX - Same as described above.

G.01.00 6- 10

File System

File Control Block Table (CBTAB)

A file control block table can be located in two places: (a) as a subpart of the PKFILE area, as discussed in Section 3.1.2; or (b) in a data segment. Although putting control block tables in PKFILE has the advantage of providing rapid access, it detracts from the space for the user's stack; so the larger control blocks (or optionally, all control blocks) are put into extra data segments. On the other hand, referencing extra data segments may result in an absence trap, which is slow. Extra data segment control block tables are of three kinds: expandable, nonexpandable, and shared FCB. Monexpandable CBI's are used for a single PRCB with buffers, i.e., where the control block is large or where the control block can't be local to a single process (for nulti-acces). Expandable (or NOBUF) CBI's are used for shall control blocks, as LMCB's, PRCB's with no buffers, and FCB's which are local to a single process. A list of the expandable CBI's associated with a process is kept in the overhead area of PKFILE (cf. Section 3.1.1). When a shall control block is needed, these CBI's are checked in order to see if one of then has room. Shared FCB CBI's are similar to expandable CBI's except that they belong to the system rather than to a single process; the system keeps a list of DSI's which it has assigned for this purpose.

The overall structure of a control block table is:

.....

OVERHEAD	(FIXED, 8 WORDS
VECTOR TABLE	(VARIABLE)
CONTROL BLOCK RREA	(VARIABLE)

Overhead

The part labeled Overhead contains information pertaining to the entire

() 1	l 	2	6	7							1	15					
_				TABLE	SIZE	I	IN	МО	RD:	\$		 		٥	CB	TSIZ	Έ	
				DST MUMBE	R CON	ITA	AIN	NIN	G	TABL	£	 	•••	1	CB	TOST	×	
j	YPE	1		VECTOR	TABLE	S	SIZ	ZE	IN	MOR	DS	 		2				
					LOCK	ΡI	IN					 		3	CB	TPIN	1	
į	. 1											 		4	CB	TCOM	TRO	Ĺ
				IMPED	ED QU	Æυ	UE	HE	AD			 		5	(C	BTQU	EUE)
				IMPED	ED QU	Æυ	UE	TR	IL			 		6				
				UNI	JSED							 		7				

Other identifiers used:

CBTTYPE = CBTAB(2).(0:2) Control block table type
CBTVTSIZE = CBTAB(2).(2:14) Vector table size
CBTLOCKBIT= CBTCONTROL.(0:1) Lock bit

Discussions

CRIDSTX

This is the DST number of the data segment that contains the control block table. If the table is contained in a stack, i.e. in the PMFILE area, then this is the DST number of the stack and not 0.

CRILOCKRIT

If the entire control block table is locked, then this bit is set. No locking count is kept since control blocks are locked only once from FCRENTECB and FDELTTECB when control blocks are added to and deleted from the table. The procedure LOCK'CB does not lock the control block because it runs PSEUDODISABLED during the critical times.

CBTQUEUE

This is the impeded queue for the table and has the same format as the impeded queue for a control block in the table. There is no second impeded queue because that facility is used exclusively for BRERK requests against the PRCB for \$STDIM/\$STDLIST.

G.01.00 6- 13

CETPIN This is the PIN number of the process that has the control block locked.

COTSIZE

This is the size in words of the table. It is initialized when the table is created and changed when the table is expanded. At present a table is never contracted, even though this is possible.

This field is the type of the control block table. Possible values are:

0 - stack [PXFILE] 1 - MOBUF (expandable) 2 - System shared FCB 3 - Buffered (Contains a single PACB)

This is the size, in words, of the vector table area in the control block table. It does not reflect the number of entries used or unused. CRTVTST7F

NOTE: All PIN's are kept as the word offset into the PCB table and as the actual PIN number.


G.01.00

File System

Vector Table

The part labeled Vector Table contains information used to locate and lock or unlock control blocks in the control block table.

The overall structure of the vector table is:



where N = (CBTVTSIZE/8)-1.

An unused vector table entry will have zeros in all the words of the entry. A used vector table entry will have a nonzero value in the first word of the entry (the control block address is necessarily nonzero).

The general structure of a vector table entry is:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 		VT'ADR
L B COUNT UNUSED	1	VT'CONTROL
LOCK PIN	2	VT'PIN
HIGH PRIORITY HEAD PIN	3	VT'QHEAD
HIGH PRIORITY TAIL PIN	4	VT'QTRIL
LOW PRIORITY HEAD PIN	5	VT'SAVEDHEAD
LOW PRIORITY TAIL PIN	6	VT'SAVEDTAIL
UNUSED	7	

File System

File System

CBTTYPE

The following partial word identifiers are used:

VT'LOCK'BIT = VT'CONTROL.(0:1)
VT'BREAK'BIT = VT'CONTROL.(1:1)
VT'COUNT = VT'CONTROL.(2:6)

Discussion: VT'908

Control block address is the table relative address of the control block associated with the vector table entry. It is a word displacement from the beginning of the control block table.

This bit signifies that we are in the middle of break mode. This is used for the PRCB of \$STDIM/\$STDLIST from a terminal session only. VT'BREAK'BIT

VT'LOCK'RTT

This bit is set whenever the control block is locked.

VT'COUNT

This is the count of the number of times that the control block has been locked by the process identified in VT'PIN. If it is zero, then the control block is not locked.

VITOTH

Contains the PIN of the process which has exclusive access to the control block. Other processes attempting to access the block will be impeded and

VT'OUFUE

The high priority impeded queue is a double word of PINs that are the head and tail of the impeded queue of processes waiting for access to the control block. Processes are impeded and unimpeded by the file system using the normal mechanisms available under MPE.

VT'SAVEDQUEUE


The low priority impeded queue is a double word of PINs and has the same format as VTQUEUE. The only time this word is used is when the control block is in BREAK mode, which can only happen to an ACB corresponding to \$STDIN/\$STDLIST. It is used to save the current VT'QUEUE when the control block goes into BREAK mode and to restore VT'QUEUE when the control block goes back into non-BREAK mode.

NOTE: R11 PIN's are stored as offsets within the PCB table and not as actual PIN numbers.

Control Block Area

The part labeled CONTROL BLOCK RREA contains the control blocks used by the file system.

To facilitate storage management, all control blocks have the same overall structure:



where N = Size-1.

Partial word field identifiers are:

= CB.(0:2)#, = CB.(2:14)#; control block type number. control block size

Discussion:

This is the first word of a control block; the format is common for all control blocks. $\label{eq:control} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray$ CBDESCRIP

CBSIZE

CBTYPE

0 - Garbage 1 - FCB 2 - PACB 3 - LACB

When a control block table is created the initial control block area is completely allocated to a single control block of type garbage. When space is requested for a new control block the control block area is scanned (using a first fit algorithm) for a garbage control block that is as large as the size requested. The space for the new control block is taken from this garbage control block and the space remaining becomes the new garbage control block area.

G.01.00 6- 17

File System

When space is returned it becomes a new garbage control block. To reduce fragmentation the new garbage control block is combined with either of the two neighboring control blocks if they are of type garbage.

If space is requested and no garbage control block is large enough to contain the new control block then the control block area and control block table are expanded by a sufficient amount. If expansion is not possible, some other control block table must be used.

Access Control Block (ACB)

Virtually every file system intrinsic constructs an RCB as its first action. When using the multi-access option, each accessor shares a single PRCB. However each accessor is permitted to view the shared file in a slightly different manner than the other accessors. For example, one accessor may access the file in a read-only mode while the other accessors may access the file in a read-urite mode. To do this, each accessor must, during his access, have a slightly different RCB.

The PACB holds information that is global to all accessors of the file. The LACB holds information that is local to each accessor of the file. At the beginning of a particular access, an ACB is constructed by calling LDC-RCB, which copies information from both the LACB and the PACB. At the end of the access, the ACB is released by calling UNLOC'RCB; this updates the PACB and LACB from the ACC since some of the fields may have been modified due to the access. This scheme nearly eliminates EXCHANGEDB's to access the various data segments.

G.01.00 6- 18

File System

Logical Access Control Block (LACB)

All LACEs have the same structure:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

	•
3 COMPLETE LACE SIZE	0
FILE NUMBER	1
FILE NAME - 1ST CHAR. FILE NAME - 2ND CHAR.	2
FILE NAME - 3RD CHAR. FILE NAME - 4TH CHAR.	3
FILE NAME - 5TH CHAR. FILE NAME - 6TH CHAR.	4
FILE NAME - 7TH CHAR. FILE NAME - 8TH CHAR.	5
FOPTIONS	6
AOPTIONS	7
RECORD SIZE IN BYTES	10
BLOCK SIZE IN HORDS	11
SPARE	12
CARRIAGE CONTROL CODE	13
EOF PG LN ST FK TC T8 88 CAR D8 EOF T EOF M	14
C TEL ICL Q TERMINAL STOP CHARACTER	15
ERROR CODE	16
LAST I/O TRANSMISSION LOG	17
	+

Partial word field identifiers are:

= LACB.(2:14)#, size in words = LACB(2).(0:8)#, terminal stop character LACBSIZE LACBSTOPCHAR

See ACBROPTIONS. LACBAOPTIONS LACBBSIZE See ACBBSIZE.

File System

LACBERROR

LACACTL See ACBCTL.

LACBENUM See ACBFNUM.

See ACBFOPTIONS. LACBFOPTIONS

See ACBERROR.

LACBMODE See ACBNODE. See ACBNAME. LACENAME1~8

This is the DST and vector table entry for the Physical ACB (PACB) for the file. file. LACBPACE

LACBRSIZE See ACBRSIZE.

This is the size, in words, of the LACB. All LACBs are eighteen (decimal) words long. LACBSIZE

See BCBISTRTE LACBSTATE

See ACBSTOPCHAR. LACBSTOPCHAR

See ACBTLOG. LACRILLOG

Physical Access Control Block (PRCB)

The overall structure of the PACB is:

BRSIC PACE	(FIXED)
BUFFERING Extension	(VARIABLE

The buffering extension is optional; it is present if and only if the file is accessed with buffering. There are thus two possible formats for an RCB:

- 1. No buffers; the buffering extension is not present.
- PACB buffers; the buffering extension is present and the buf-fers are in the buffering extension.

If multiple PACB buffers exist, there will be a buffering extension for each, immediately preceding the buffer. The basic PACB (or MOBUF PACB) is copied into the the ACB as words 0 through X63; an ACB "extension" is then generated in words X64 – X67. The resulting ACB thus has the following format:

6.01.00 6- 21

File System

The above words, 0-X63, are physically located in the PRCB of the file. Below, words X64-X67, are used by file system intrinsics- and are placed onto the stack by the procedure LDC'RCB when locking the RCE. Therefore, the buffering extension, if pres-ent, will immediately follow word X63 of the actual RCB in the Control Block Table of the file.

52	DST RELATIVE OFFSET TO PACE	64
53	DST RELATIVE OFFSET TO LACE	65
54	DST RELATIVE OFFSET TO ACB IN THE STACK	66
55	STACK RELATIVE OFFSET TO DB	67
,		

The following identifiers are used when referring to an ACB:

(ACBSIZE)	= ACB.(2:14)#.	size in words
acbenum	= ACB(1).(8:8)#,	file number
acbname	= ACB(2)#,	file name
ACBNRME1	= ACBDBL(1)#,	file name - first half
ACBNAME2	= ACBDBL(2)#,	file name - second half
ACBFORTIONS	= ACB(6)#,	FOPTIONS
ACBAOPTIONS	= ACB(7)#.	AOPTIONS
ACBRSIZE	= ACB(8)#,	record size (bytes)
ACBBSIZE	= ACB(9)#.	block size (words)
Spare	= ACB(10)#,	Unused
ACBCTL	= ACB(11)#,	carriage control word
ACBLSTATE	= ACB(12)#,	local state flags
ACBEOF	= ACBLSTATE. (1:1)#,	end of file sensed
ACBLPCTL	= ACBLSTATE. (2:2)#,	page and line control
ACBPAGECTL	= ACBLSTATE. (2:1)#,	page control
ACBLINECTL	= ACBLSTATE. (3:1)#,	line control
ACBSTREAM	= ACBLSTATE. (4:1)#,	stream I/O
ACBFKEYS	= ACBLSTATE. (5:1)#,	restore function keys
ACBXMITCRLF	= ACBLSTATE. (6:1)#.	transmit CR. LF to user
ACBTBLOCK	= ACBLSTATE. (7:1)#.	disable block mode
ACBBINARYIO	= ACBLSTATE. (8:1)#.	8-bit terminal transfers
ACBCARRIAGE	= ACBLSTATE. (9:1)#.	carriage control flag
(ACBDEFBLOCK)		default blocking
ACBREADCODE	= ACBLSTATE. (11:4)#,	input EOF check
ACBREADTYPE	= ACBLSTATE. (11:2)#,	input EOF type
ACBREADHIDDE	= ACBLSTATE. (13:2)#;	input EOF type
ACBROOM	= ACB(13)#,	node word
ACBRODE	= ACBNOON. (0:8)#.	node setting
	#= ACBNODU. (0:1)#,	
ACBSETMODE	= ACBHODN. (4:4)#.	Signifies CIR overflow FSETMODE bits
ACBTAPEERROR	= ACSMODN. (4:1)#.	
ACBINHIBERLE	= ACBMODN. (5:1)#,	report recovered tape error
ACBOUIESCE	= ACBMODN. (6:1)#,	inhibit terminal CR/LF
ACRSTOPCHAR	- ACBMODU.(8:8)#.	critical output verify
- 19 M V - M - M 13733		terminal stop character

File System

26	FCB VECTOR	32
27		33
28	TOTAL NUMBER OF LACE'S	34
29	BK DEVICE TYPE LAST LOGICAL I/O STATUS	35
30	LOGICAL DEVICE MUMBER	36
31	PF HIT CURRENT BUFFER TAPE DISPLACE NO. BUFFERS	37
32	CURRENT RECORD MORD INDEX	40
33	BUFFER SIZE	41
34	VIRTUAL LOGICAL DEVICE NO.	42
35	FMMVT INDEX	43
36	NUMBER OF INPUT LACE'S	44
37	MAME TYPE FILE DISPOSITION	45
38	ACCESS BIT MAP BLOCKING FACTOR	46
39	S M Q R D AE RU ABR ME SEOFS EOFS	47
40		50
41	SPOOLED DEVICE FORTIONS	51
42	SPOOLED DEVICE ADPTIONS	52
43	IDD OR ODD INDEX	53
44		54
45	NO-WAIT DISK RODRESS	55
46	UNUSED	56
47	NO-MAIT LOGICAL DEVICE	57
48		60
49	P1P2 USED BY FDEVICECONTROL	61
50	UNUSED	62
51	UNUSED	
•	977925	63

G.01.00 6- 23

G.01.00 6- 24

٥١	2																
								COMP	LETE	ACB	\$12	Έ					. 0
1											FI	LE I	UMBE	R			1
2		FIL	E N	AME	- 13	T CH	AR.			FΙ	LE N	AME	- 2N	D CH	AR.		2
3		FIL	E N	ME	- 3R	D CH	AR.		l	FI	LE N	AME	- 41	н сн	AR.		3
4		FIL	E N	PME	- 51	н сн					LE N	AME	- 61	H CH	AR.		4
5		FIL	E M	ane	- 71	H CH	AR.			FΙ	LE M	AME	- 81	H CH	AR.		5
6							1	FOPT:									6
7	ROPTIONS													7			
8													10				
9						BI	LOCK	SIZE	IN)S						11
10	***************************************										12						
11	CARRIAGE CONTROL CODE										13						
12	CONTROL IN LOT THE ARE THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE AREA TO A THE ARE											14					
13	Fi and a land												15				
14							ER	ROR	CODE								16
15							1/0	TRAN	SMIS	SION	LOC	;					17
16																	20
17							FILE	POI	NTER							-	21
18													•			Ì	22
19				(URRE	NT V	ARIA	BLE I	BLOCI	KHU	MBER	1				İ	23
20																İ	24
21						RECO	RD T	ransi	FER (COUN	T					İ	25
22																j	26
23						8L0	CK TI	RANSI	ER (OUN	T					İ	27
24																	30
25					HIG	HEST	BLO	CK M	MBER	ST	ARTE	D				İ	31
1																i	••

G.01.00 6- 22

ACBERROR		ACB(14)#.	error code
ACBTLOG		RCB(15)#.	last I/O transmission log
ACBEPTR		ACBOBL(08)#,	current record number
ACBBLK		ACBOBL(09)#,	current variable block
ACBRTFRCT	8	ACB08L(10)#,	logical record TFR count
ACBBTFRCT		ACBDBL(11)#.	block transfer count
RCBHIBLK		ACBDBL(12)#,	highest block started
ACBECBY		ACBDBL(13)#,	FCB Vector table entry
RCBSHCNT		ACB(28)#.	# of LRCBs
ACBSTATU		ACB(29)W,	access class, status, etc.
ACBBREAK	:	ACBSTATU. (1:1)#,	break (\$STDIN/LIST only)
ACBDTYPE	Ξ	ACBSTATH. (2:6)#,	device type
ACBACCCL	:	ACBSTATH. (2:3)#,	device access class
	:	ACBSTATU. (5:3)#.	device sub-class
ACBSUBCL ACBSTATUS		ACBSTATU. (8:8)#,	last logical I/O status
		ACBSTATU. (8:5)#,	qualifying status part
ACBOSTATUS			general status part
ACBGSTATUS		ACBSTATU. (13:3)#,	Ldev number of file
RCBDADDR	=	ACB(30)#,	buffer data & misc. flags
ACBBUFX	£	ACB(31)#,	privileged access only
ACBPRIV		ACBBUFX. (0:1)#,	
ACBHIT		ACBBUFX.(1:1)#,	buffer hit flag
ACBCURRBUF		ACBBUFX.(4:4)#,	current buffer nor.
ACBNUMBUFS		ACBBUFX.(12:4)#,	number of buffers less 1
ACBBUFUSED		ACB(32)#,	used block word count
ACBBUFSIZE		ACB(33)#,	buffer size (words)
ACBSPVDEV		RCB(34)#,	spooled virtual device
ACBFMAVTX		ACB(35)#,	FMRVT index
ACBSHCHTIN	3	ACB(36)#,	Number of input LRCB's
ACBONTO		ACB(37)#,	type & disposition
ACBONTYPE	E	ACBONTD. (0:8)#,	name type for dir. search
ACBDISP	z	ACBONTD.(8:8)#,	file disposition
ACBAMLD	=	ACB(38)#,	access mask & LDEV
ACBACCESS	=	ACBAMLD.(0:8)#,	access mask
ACBBLKFACT	=	ACBAMLD.(8:8)#,	Blocking factor of file
RCBGSTW		ACB(39)#,	spool control flags
ACBSPOOLED		ACBGSTW. (0:1)#,	spooled device flag
ACBSPOOLIO	=	ACEGSTU. (0:2)#,	spooled IN/OUT
ACBSPSQ	=	ACBGSTW. (2:2)#,	squeeze flags
ACBSPSQZ		ACBGSTW.(2:1)#,	file squeezed
ACBSPRSQ		ACBGSTW. (3:1)#,	request to squeeze
ACBSPDSQ		ACBGSTW. (4:1)#,	squeeze just done
ACBNOWAITEOF		RCBGSTW. (8:1)#,	EDF advanced?
ACBNOHAITHODE		ACBGSTH. (9:1)#,	last I/O: O=read, 1=urite
ACBABORTREAD		RCBGSTH. (10:1)#,	abort broken re-read?
ACBNEWEOF		ACBGSTW. (11:1)#,	EOF advanced - tape file
		ACBGSTN. (12:2)#,	for saving ACBEOFS
ACBSRVEEOFS		ACBGSTW. (14:2)#,	EOF flags - :EOD/:
ACBEOFS		RCB(40)#,	spooled dev type/recsize
ACBSPTYRC		RCBSPTYRC.(0:6)#,	spooled dev type
ACBSPTYPE		: ACBSPTYRC.(6:10)#,	spooled dev rec size
ACBSPREC			spooled dev FOPTIONS
ACBSPFOPT		: ACB(41)#,	spooled dev ROPTIONS
ACBSPAOPT		RCB(42)#,	
ACBSPXDDX		RCB(43)#,	IDD/ODD index Nowait disc address
ACBNOWAITDA	•	ACBDBL(22)#,	MONATE DIRE ADDLESS

```
Spare = ACB(46)#,

RCBMOWRITLDEV = RCB(47)#,

RCBP1P2 = RCBOBL(24)#,

RCBP1 = RCB(48)#,

RCBP2 = RCB(49)#;
                                                                                           Unused
                                                                                           Nowait logical device
Used by FDEVICECONTROL
Discussion:
ACRESORTRESO
```

This flag is used to abort a broken terminal re-read. The flag is set via the RBORT parameter to FUNBRERK. If the flag is set then the RERO PENDING message will be aborted along with the re-read. This feature is needed to handle the BREAK...: RBORT, etc. situation. This is the access class part of the device type number. The following are legal values: ACBACCCI.

0 - direct (e.g. disc)
1 - serial input (e.g. card reader)
2 - parallel input/output (e.g. terminal)
3 - serial input/output (e.g. magnetic tape)
4 - serial output (e.g. line printer)

This is the access bit map for the file. The following are the bit definitions of this eight-bit field: **RCBBCCESS**

(0:1) - unused (1:1) - unused (2:1) - read (3:1) - append (4:1) - urite (5:1) - lock (6:1) - execute (7:1) - save

This access security is determined by the ACCCHECK intrinsic and enforced by the file system.

This is the ROPTIONS in effect for this file access. ACBROPTIONS

This bit controls full eight bit transfers on the 2644 page mode terminal. It is adjusted by FCONTROL(26) and FCONTROL(27). **ACBBINARYIO**

This is the block number of the current variable record format block. Applicable if the record format is nat block variable.

This is the blocking factor for the file. It is the number of records in a block. Legal values range from 1 to 255.

G.01.00 6- 26

G.01.00 6- 25

File System

This is the break mode flag. It is applicable if the RCB is for \$STDIN or \$STDLIST. If set it means that the BRERK key has been hit and that the CI should have high priority access to the RCB. The flag will be cleared when a RESUME or ABORT is issued.

This is the block size, in words, of the file. ACBBSIZE

ACBBREAK

ACBDISP

This is the total number of blocks transferred to and from the file. The initial value is ${\tt OD}.$ **ACBBTFRCT**

This is the word index, relative to the base of the block, for the selected record within the block. This is applicable if the file access is buffered. **RCBBUFUSED**

This bit signifies that the file has carriage control. It is the same as the carriage control bit in RCBFOFIONS if the file is spooled. If not spooled, the bit is zero, and IONOVE will pass the FWRITE carriage control parameter directly to the driver rather than embedding it as the first character of the output record. ACBCARRIAGE

This is the CONTROL parameter from the last FWRITE. This value is pertinent if the file was opened with car-ACBCTL

This is the buffer number (O-relative) containing the most recently referenced record. Rpplicable if the file access is buffered. ACBCURRBUF

This is the logical device number of the file. For a disc file this is the logical device number of the first extent. ACBDADDR

This bit signifies that the file is to be accessed with default blocking. The bit is initialized from the FDPEN stateburd STATE. It does not need to be in the ACB; it is mentioned here only to signify that the bit is effectively used due to the way RCBLSTATE is initialized from STATE. **ACBDEFBLOCK**

This is the file close disposition derived from the FOPEN call. The only way this can be specified is via a file equation. The legal values are the same as those for FCLUSE.

File System ACBONTYPE

ACBDTYPE

ACBB! K

ACBRI KERCT

This is the file reference format type number and is derived from the FOPEN call. The following are legal $\ensuremath{\mathsf{Legal}}$ values:

0 - full name 1 - account name absent 2 - group and account name absent 3 - null name

This information is needed by FRENAME.

This is the device type number of the file. The following are legal values (octal):

0 - noving head disc 1 - fixed head disc

7 - fixed need disc 7 - foreign disc 10 - card reader 11 - paper tape reader 20 - terminal

20 - terminal
24 - card reader/interpreter/punch
26 - SSLC
27 - programmable controller
30 - magnetic tape
31 - serial disc
40 - line printer
41 - card punch
42 - paper tape punch
43 - CRLCOMP 500 plotter
45 - CRLCOMP 700 plotter
45 - CRLCOMP 700 plotter

This bit is set when EOF has been sensed. ACBEOF

This is the type of EOF detected on TM(X). This field consists of two bits: ACREDES

(0:1) - super colon (i.e. EOF for \$STDINX) (1:1) - regular colon (i.e. EOF for \$STDIN)

Applicable for multi-access to \$STDIM(X) only.

This is the error number for the file. It is used by all intrinsics except FOPEN. When an error is detected the error number is placed in this cell. The error number is cleared at the beginning of each callable intrinsic except FCHECK (which reads it). ACBERROR

This is the FCB vector for the file. Applicable only to disc files. ACRECE

This bit controls the definition of the f1 and f2 function keys on the 2644 page mode terminal; it is ACBFKEYS

adjusted by FCONTROL(32) and FCONTROL(33). (Obsolete function)

ACBENUM

File	System

File number, range from 1 to 255. Used mostly for calling routines that access things such as labels by file **ACBFOPTIONS** This is the FOPTIONS in effect for this file access. This is the sequential access record pointer; it contains the next sequential record number. The initial value is 00. This value is used only by the FREAD, FURTIE and FUPDATE intrinsics. Mowever the value is waintained by all data transferring file system intrinsics. ACREPTR **ACREMONTY** This is the entry index into the file multi-access vec-tor table (FMMVT). This is valid if the file access tor table (rmm is multi-access. These are miscellaneous state flags. These are "global" in nature in that they are the same for all accessors in a multi-access environment. The constituent bits are described individually. **ACRGSTATE** This is the general part of the last I/O status for the file. The following are the legal values: **ACBGSTATUS** 0 - pending 1 - successful 1 - SUCCESSIU 2 - end of file 3 - unusual condition 4 - irrecoverable error ACBHIBLK This is the highest block number for which an anticipatory read has been issued, and is applicable if the file access is buffered. The initial value is -10. This is the buffer hit flag. If set it indicates that the last read or write request was serviced without any physical I/O required. This flag is used only for performance measurement. The code which manipulates it is optional to the file system, and is controlled by compiler toggle X3. ACBHIT ACBINHIBORUS This bit controls the termination of lines written to the terminal. If not set then each line is terminated with a CR and LF; if set then no line termination characters are used. This bit is valid if the file is a terminal file; it is adjusted by FSETMODE. This is the line control bit. If not set then each line is post-spaced; if set then each line is prespaced. This bit is used by line printers and terminals only. It is adjusted by FCONTROL(1) and FWRITE with the appropriate carriage control. ACBLINECTL G.01.00 6- 29 File System device when control is returned to the user. This bit is adjusted by FSETMODE. ACBREADCODE This field consists of the input EOF checking type and mode, and is used to generate the P1 parameter to RTTRCHIO. These fields are described individually. ACBREADMODE This field controls the input EOF checking mode. It is 00 for reading \$STDIN, 01 for reading \$STDINX, and 10 for the command interpreter. This field controls the input EOF checking type. It is 01 for JOBs, 10 for SESSIONs, and 00 for DATA. ACBREADTYPE ACBRST7F This is the file's record size in positive bytes. **ACBRIFRCT** This is the total number of records transferred to and from the file. The initial value is 00. This field is used to save during BREAK mode processing. $\ensuremath{\mathsf{The}}$ **ACBSAVEEOFS** This is the total number of LACBs that exist for this PACB. Valid if the file access is multi-access. ACRISHENT **ACBSHCNTIN** This is the total number of input-only LACBs that exist for this PACB. Valid if the file access is This is the total LACB and total input-only LACB counts, each of which is described separately. ACBSHCNTS This is the size, in words, of the RCB. The complete size (including buffers) may be calculated from the DST size containing the RBC. It does not include the buffering extension, if present. ACRST7F ACBSPACPT This is the AOPTIONS for the spooled d Applicable if the file access is to a spooled device. device. This is the FOPTIONS for the spooled device. Applicable if the file access is to a spooled device. **ACBSPOOLED** This is the spooled device flag. If set then the file access is to a spooled device. **ACBSPOOLIO** This field is a combination of the spooled device flag and the input/output mode of the spooled device. Legal values are: 00 - not spooled 01 - illegal 10 - input spooling 11 - output spooling

ACBLPCTL This are the line and page control bits, which are described separately. These are miscellaneous state flags. They are "local" in nature in that they may be different for each accessor in a nulti-access environment. Bits (9:6) are initialized from the stateword local variable called STRTE in FOPEN; the ten remaining bits are initialized individually. The constituent bits are described individually. ACRISTATE ACBNODE These are miscellaneous mode flags. The constituent bits are described individually. **ACRMONE** This is the local file name. The name is eight bytes in length with trailing blanks added. This flag when set indicates that a new tape mark should be written before the tape is rewound or backspaced. Rpplicable only to magnetic tape files. ACBNEWEDE **ACBNOURITED** This bit is used to save the value of the local EOF advanced flag NEUEDF in 10H00VE between the 1/0 initiation and 1/0 completion calls. This flag is applicable if the file is accessed in nowait I/0 mode. This cell is used to save the I/0 mode between nowait I/0 initiation and completion calls. If the bit is set then the last I/0 request was a write; otherwise it was a read. This cell is pertinent if the file is accessed in nowait I/0 mode. **ACBKOURITHODE ACBNUMBUFS** This is the number of buffers, less one, used for the file access. Applicable if the file access is buffered. This is the page control bit. If not set then a page is assumed to consist of 60 lines (auto page eject); if set then a page is assumed to consist of 66 lines (no auto page eject). This is used primarily for line printers but is also valid for terminals; these are the only devices for shich this is valid. This bit is suited by FCOMTROL(1) and FURTIE with the appropriate carriage control. ACBPAGECTI. **ACRPRIV** This flag when set indicates that the file is privileged in that it has a negative file code; the user must be in privileged mode to access it. **ACBOSTRTUS** This is the qualifying part of the last I/O status for the file. The values are unique for each general status part. See I/O System IMS for all legal values. **ACBQUIESCE** This bit controls critical output verification. If set, buffered output is guaranteed to have been written to the G.01.00 File System This is the record size, in bytes, of the spooled device. Applicable if the file access is to a spooled device. ACBSPREC This is the device type (from the LDT) of the spooled device. Applicable if the file access is to a spooled ACBSPTYPE ACBSPTYRC This cell contains the spooled device type and record size, which are described separately. This is the logical device number of the spooled device. Applicable if the file access is to a spooled device. ACBSPVDEV This is the index into the IDD or ODD for a spoolfile. Applicable if the file access is to either a spooled device or a spoolfile. **RCRSPXDOX** This is the last I/O status for the file. It comes from the I/O status part of the IOCB returned by RTTRCHIO. Not all RTTRCHIO calls update this cell. **ACBSTATUS**

This is the record termination character used for terminal reads. This character can be changed via FCONTROL(25). This bit signifies inter-block garbage for disc files. If set, the block size is a multiple of 128 words and therefore there is no garbage data between blocks. This fact is used to improve multirecord I/O by mapping the request into as few ATTACHIOs as possible. ACBSTREAM

ACBSTOPCHAR

ACBSUBCL This is the sub-class part of the device type number. The sub-class is unique for each access class. The following are the legal sub-class values for each device class:

> 0 - direct
> 0 - noving head disc
> 1 - fixed head disc
> 7 - foreign disc
> 1 - serial input
> 0 - card reader
> 1 - paper tape reader
> 2 - parallel input/output
> 0 - terminal
> 4 - card reader/punch
> 6 - SSLC
> 7 - programmable content 7 - programmable controller
> 3 - serial input/output
> 0 - magnetic tape
> 7 - serial disc 4 - serial output

0 - direct

G.01.00 6- 31

0 - line printer 0 - line printer
1 - card punch
2 - paper tape punch
3 - CRLCOMP 500 plotter
4 - CRLCOMP 600 plotter
5 - CRLCOMP 700 plotter

This bit controls the reporting of recovered magnetic errors. If not set the recovered errors are not reported to the user; if set then recovered errors are reported to the user by returning CLL and error number 39, Valid if the file is a magnetic tape file. This bit is additional bestermore. ACSTAPFERROR adjusted by FSETMODE.

This bit controls block mode transfers on the 2644 page mode terminal. This bit is adjusted by FCONTROL(28) and FCONTROL(29). ACBTBLOCK

This is the last I/O transmission log for the file. It cones from the I/O transmission log part of the IOCB returned by ATTACHIO. Not all ATTACHIO calls update this cell.

This is the volume table index for the file. Applicable if the file is a disc file. ACEVDADDR

This bit controls CR and LF insertion into the user buffer on the 2644 page mode terminal. This bit is adjusted by FCONTROL(30) and FCONTROL(31). ACBXMITCRLF

If present, the PACB buffering extension contains from one to sixteen block buffers each having the following format:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15		
IOQ ENTRY INDEX	0	BLKIOQX
BLK LDEV NUMBER U R D W M P	1	BLKFLAGU
IOCB - STATUS	2	BLKLSTAT
IOCB - TRANSMISSION LOG	3	BLKTLOG
DIASK NUMBER	4	BLKBLOCK
BLOCK NUMBER	5	
BLOCK SECTOR ADDRESS	6	BLKDADOR
BLUCK SECTUR HUDRESS	7	
D. 201 FILES	8	BLKEXTBASE
BLOCK EXTENT BASE	9	
BLOCK EXTENT SIZE	10	BLKEXTSIZE
UNUSED	11	
	12	BLKBUFFER
BUFFER		
	l	

Other identifiers used:

= BLK(1)#, Flag and LDEV word
= BLKFLRGW.(0:8)#, block logical device number
= BLKFLRGW.(0:8)#, block I/O flags
= BLKFLRGW.(10:1), Block from unalloc. extent
= BLKFLRGW.(11:1), FRENDBRCKWARD (not used)
= BLKFLRGW.(12:1), I/O status not checked
= BLKFLRGW.(13:1)#, last I/O was write?
= BLKFLRGW.(13:1)#, buffer modified?
= BLKFLRGW.(15:1)#, I/O in progress?
= BLKFLRGW.(14:2)#, I/O complete - not dirty
= BLKFLRGW.(14:2)#, I/O complete - not dirty BI KEI OCU BLKFLAGA BLKLDEV BLKFLAGS BLKUNALLOCEXT BLKREVERSE BLKDONTHAIT BLKIOCOMP BLKIOCOMP BLKIOCB = BLKDBL(1)#. IOCB

G.01.00 6- 34

G.01.00 6- 33

File System

Discussion: BLKBLOCK

RI KDONTURTT

ACBTLOG

This is the block number of the data contained in the buffer. A value of -1D indicates that the buffer is

This is the actual file system buffer space. Each buffer is exactly one file block in size. BLKBUFFER

BLKDADDR This is the block's logical device and sector number.

This flag is set if the contents of the buffer has been modified. When the block buffer is re-used this flag is checked to see if the block needs to be written to the BLKDIRTY

This bit will be on if the I/O was already completed via "DONT'WAIT" but the status has not been checked yet. Check the status before using the block in the buffer.

This is the sector address of the extent base in which the block resides. This is used for disc caching. BLKEXTBASE

The size, in sectors, of the extent in which the block resides. This is used for disc caching. BLKEXTSIZE

BLKFLAGS These are the miscellaneous flags associated with the block, which are described separately.

This is the IOCB returned by the I/O system when the block I/O has completed. On a blocked I/O request this is obtained from the RTTRCHIO call; on an unblocked I/O request this is obtained from WRITFORIO. RIKTOCH

REKTOCOMP

This is the buffer modified flag (BLKDIRTY) and the I/O in progress flag (BLKIOPEND), which are described separately. This field is usually interrogated to see if it contains the value 2, which means that the buffer has been modified but not yet written to the device.

BLKI00UT This is the mode of the I/0 operation for the block. It is set by a write and cleared by a read.

This is the I/O in progress flag. It is set if the I/O is pending; it is cleared when the I/O has completed. BLKIOPEND

BLKIOQX

This is the IOQ index of the unblocked I/O request for the block. It is used as the argument to WAITFORIO, which ensures the completion of the I/O request.

This is the logical device number of the block. (Valid only for disc files.) BLKLDEV

File System

BLKUNALLOCEXT

The I/O status part of the IOCB consists of the PCB number and the error code for the completed I/O $\,$ BLKLSTRT

The transmission log part of the IOCB is the number of words or bytes transferred by the the I/O request. BLKTLOG

BLKREVERSE

This bit would indicate that we are reading back- wards from a tape. However, currently FREADBACK- WARDS can only be performed unbuffered.

This bit signifies that the block was "read" from an unallocated extent. Actually, the buffer was simply cleared with fill characters. Therefore, if a write is attempted to the block residing in this buffer, it must pass through FCONVBLK to allocate the extent first.

File Control Block (FCB)

The FCB coordinates access to a file on a sharable device. At present the only sharable device is a disc, so only disc files have FCBs.

The information contained in an FCB is derived from the file label. The FCB is used to hold this information, rather than the file label, since it can be accessed more quickly.

There are two strategies to choose from in deciding where to place the FCB. If the file has been opened exclusive and no other process could possible share this file, then the FCB is placed into the PXFILE area (or in a MOBUF expandable CBT if it won't fit in the PXFILE area or if the program is run with MOCD). If the file could possible be shared, then the FCB is always placed in a shared control block table. The number of a data segment containing a list of shared file system data segments is kept in system global location 1075 octal. The size of the FCB depends on the naximum number of extents specified at FDCEM; there are 44 (octal) words plus two per extent. There will be at least one extent, since the file label always exists in the first extent. The FCB extent map is in terms of logical device and sector number. The extent map in the file label is in terms of volume rather than logical device; the map is converted by VTRBOLDEV when the label is read, and converted back by LDEVIOVINB when the label is uritten to disc.

12 12 14 15

The File Control Block has the following format:

'	ו ט	2	3		- /		8		12	13	14	15		
0	1	1			C	OMP	LETE	FCB	SIZ	E			! 0	
1					S	PAR	ε						1	
2					F	OPT	IONS						2	FCBFOP- Tions
3				DEV	TCE	SPE	CIFI	CATI	ON				3	FCBDEVICE
4	PREV	. LOC	K	DEV.	TYP	E	C		ĮD	EVIC	E SU	BTYPE	4	
5				NC	. O PI	ENS	FOR	OUT	PUT				5	
6				NC	. OPI	ENS	FOR	RNY	MOD	E			6	
7					RI	N N	UMBE	R					7	FCBRIN
8					EXCL	USI	VE S	TATU	5				10	
9	CI			HV1	ABX	Ī		VH	ASK				11	STAT FCBPVINFO
10					CTI		****						12	FCBFLIM
11					rıu		INIT						13	
		****											-1	

G.01.00 6- 37

File System

File Control Block (Cont.)

12	UNUSED	14	
13	UNUSED	15	
14		16	FCBEOF
15	END OF DATA POINTER	17	
16	NO. USER LABELS WRITTEN NO. USER LABELS AVAIL.	20	FCBUSERLBL
17	EXTENT SIZE IN SECTORS	21	FCBEXTSIZE
18	BLOCKING FACTOR SECTORS PER BLOCK	22	
19	SECTOR OFFSET TO DATA DISP NO. EXTENTS - 1	23	
20	LAST EXTENT SIZE IN SECTORS	24	FCBLRST-
21	NO. OPENS INPUT MODE	25	EXTSIZE
22	GROUP NAME - 1ST CHAR. GROUP NAME - 2ND CHAR.	26	FCBGN
23	GROUP NAME - 3RD CHAR. GROUP NAME - 4TH CHAR.	27	
24	GROUP NAME - 5TH CHAR. GROUP NAME - 6TH CHAR.	30	
25	GROUP NAME - 7TH CHAR. GROUP NAME - 8TH CHAR.	31	
26	ACCT NAME - 1ST CHAR. ACCT NAME - 2ND CHAR.	32	FCBAN
27	ACCT NAME - 3RD CHAR. ACCT NAME - 4TH CHAR.	33	
28	ACCT NAME - 5TH CHAR. ACCT NAME - 6TH CHAR.	34	
29	ACCT NAME - 7TH CHAR. ACCT NAME - 8TH CHAR.	35	
30		36	FCBSTART
31	START OF FILE BLOCK NUMBER	37	
32		40	FCBEND
33	CURRENT NUMBER OF DATA BLOCKS IN THE FILE	41	
34	INMAPA AP AREL AM ALAN ALAN ALAN ALAN ALAN ALAN ALAN	42	FCBNUM-
35	NUMBER OF OPEN AND CLOSE RECORDS (MESSAGE FILE)	43	OPENCLSREC
36	LOGICAL DEVICE NUMBER	44	FCBEXTHAP
37	FIRST EXTENT SECTOR HUMBER	45	

6.01.00 6- 38

File System

LOGICAL DEVICE NUMBER | LAST EXTENT SECTOR NUMBER

Other identifiers used:

= FCB.(2:14)#, size in words
= FCB(4).(0:2)#, previous lock state
= FCB(4).(2:6)#, sevice type
= FCB(4).(12:4)#, pending crunch disposition
= FCB(5).(0:8)#, no. accessors - output
no. accessors - fCB(9).(0:1)#, pv class flag
= FCB(9).(0:1)#, pv class flag
= FCB(9).(0:1)#, pv class flag
= FCB(9).(0:8)#, no. labels written
= FCB(16).(0:8)#, no. labels available
= FCB(16).(0:8)#, no. labels available
= FCB(16).(0:8)#, sectors per block
= FCB(19).(0:3)#, sectors per block
= FCB(19).(0:3)#, pending disposition
= FCB(19).(11:5)#, no. extents less 1
= FCB(21).(8:8)#, label LDEV

= FCB(36).(0:8)#, label LDEV FCBSIZE FCBLKS1 FCBDTYPE FCBCRUNCH FCBCRUNCH FCBSUBTYPE FCBOCNTOUT FCBCLASSFLG FCBMYTABX FCBYMASK FCBVMASK FCBLBLEOF FCBLBL FCBBLKFACT FCBSECTPBLK FCBSECTOFF FCBSECTOFF FCBDISP FCBNUMEXTS FCBOCNTIN FCBLABEL FCBLDEV

Discussion:

FCBACBV

This is the DST of the ACB that was created at the same time as the FCB. This is used in conjunction with FCBNEWFCBDST when relocating the FCB. TCROCROST

This is the vector table entry of the RCB that was created at the same time as the FCB. This is used in conjunction with FCBNEWFCBV when relocating the FCB.

FCBAN This is the account name of the file. It is eight bytes in length with trailing blanks added.

This is the blocking factor of the file. It is the number of logical records in a physical block. Legal values mange from 5 to 255. FCBBLKFACT

File System

This specifies the device on which the file resides. If it is positive then it represents a logical device number; if negative it represents a (negative) device class index. **FCBDEVICE**

This is the pending FCLOSE disposition for the file. Legal values are: FCBDISP

0 - no change 1 - save permanent 2 - save temporary and rewind 3 - save temporary but do not rewind

- invalid file (file label access error)

This bit governs if space will be returned beyond the EOF upon the last FCLOSE of the file. FCBCRUNCH

0 - no change 1 - return space beyond EOF

This is the device type number of the first extent of the file. See ACBOTYPE for a list of legal values. FCROTYPE

FCBEND Block number of the file's EOF, relative to FCBSTART. FCBEOF

This is the end-of-file pointer for the file. It is a double integer representing the number of records in the file. It can also be viewed as the record number of the next record past EUF.

FCBEXCLSTRT This is the exclusive status of the file access. If -1 then the file is being accessed exclusively; otherwise it is the number of semi-exclusive accessors.

FCBEXTNAF This is the extent map of the file. The number of ex-tents is specified by FCBNUMEXTS; a OD extent descriptor indicates that the extent has not been

FCBEXTSIZE

This is the extent size, in sectors, of the file. All extents in the file except possibly the last have this size. This is a logical value, and legal values range from 1 to 65515 sectors. This restricts the maximum file size to 2097120 sectors (268,431,360 words).

FCBFLIM This is the end-of-space pointer for the file. It is a double upond integer representing the maximum number of records (fixed length record format) or blocks (undefined or variable length record format) in the file.

FCBFOPTIONS This is the FOPTIONS in effect for the file. File System

This is the group name of the file. It is eight bytes long with trailing blanks added. FCBGN

FCBLABEL. This is the logical device and sector number of the file label, which is the same as the first extent descriptor.

This is the size, in sectors, of the last extent in the file. If the file has one extent then this is the same as FCBEKNSIZE; otherwise this value may be different from FCBEKNSIZE. This is the size of the last physical extent for the file; it is not the size of the last allocated FCBLASTEXTSIZE

extent.

This is the number of user labels allocated for the file. Since each label is a sector long, this is also the number of sectors allocated for user labels. FCBLBL

This is the end-of-data pointer for the user labels. It is analogous to FCBEOF in that it represents the number of labels written. The initial value is 0. FCRIRIFOR

This is the logical device number of the first extent of the file. FCBLDEV

This is the previous lock state of the file and is derived from the file label. Legal values are: FCBLKST

0 - no accessors

1 - read 2 - write 3 - read/write

If the file resides on a private volume, then this field represents the mounted volume table index of the volume set entry on which the file resides. FCRMVTRAX

This is the DST of the new FCB for the file. It is used in conjunction with FCBACBDST to move the FCB to a system (shared FCB) control block table when the second accessor is established. If this value is zero then there is no new FCB; if nonzero then a new FCB has been **ECRNEWECROST**

This is the vector table entry of the new FCB for the file. It is used in conjunction with FCBRCBV to move the FCB to a system (shared FCB) control block table when the second accessor is established. If this value is zero then there is no new FCB; if nonzero then a new FCB has been created. FCBNEWFCBV

This is the maximum number of extents, less one, allowed for the file. It is not the number of extents **FCBNUMEXTS**

G.01.00 6- 41

File System

FCRSECTORE

presently allocated, which is always determined by counting nonzero entries in the extent map.

FCBNUMOPENCISREC Number of open and close records in the message file.

This is the number of accessors for the file. Riternatively it can be viewed as the number of PRCBs created for the file. FCBOCHT

This is the number of file accessors having input **FCROCHTIN**

FCBOCHTOUT This is the number of file accessors having output

This is the RIN number used to support dynamic locking (i.e. FLDCK and FUNLOCK) for the file. If there is no dynamic locking then this number is zero. **FCARIN**

This is the sector offset from the file label to the first block of the file. This is not necessarily equal to FGBLBL+1 since an integral number of blocks are allocated for the file and user labels.

FCRSECTPRIK This is the number of sectors in a block for the file.

This is the size, in words, of the complete FCB. It includes the extent map. $\label{eq:condition} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begin{subarray}{ll} \end{subarray} % \begi$ FC8SIZE

Block number of the file's start, excluding the file label block. **FCBSTART**

FCRSURTYPE This is the device subtype number of the first extent.

This field describes the user labels for the file. It consists of FCBLBL and FCBLBLEOF, described separately. FCBUSERI BI

FCBVNASK

If the file resides on a private volume set, this bit mask signifies which volume of the set in which the file resides. Bit 15 is on it resides on the first volume, bit 14 if on the second, etc.

G.01.00 6- 42

File System

File Label (FLAB)

7 8 12 13 14 15

The file label has the following format:

0 1 2 3

	V 1 2	3	,		٠	•	-		17 13		
į	FILE NAME	- 1ST	CHAR.	Ī	FILE	NAME		2ND	CHAR.	0	FLLOCNAME
	FILE NAME	- 3RD	CHAR.	Ī	FILE	NAME	-	4TH	CHAR.	1	
	FILE NAME	- 5TH	CHAR.	1	FILE	NAME	-	6TH	CHAR.	2	
	FILE NAME	- 7TH	CHAR.	I	FILE	NAME	-	8TH	CHAR.	3	
į	GROUP NAME	- 1ST	CHAR.	Ī	GROUP	NAME	-	2ND	CHAR.	4	FLGRPNAME
	GROUP NAME	- 3RD	CHAR.	Ī	GROUP	NRME	-	4TH	CHAR.	5	
	GROUP NAME	- 5TH	CHAR.	ī	GROUP	NAME	-	6TH	CHAR.	6	
	GROUP NAME	- 7TH	CHAR.	ı	GROUP	NAME		8TH	CHAR.	7	
	ACCT NAME	- 187	CHAR.	!	ACCT	NAME		2ND	CHAR.	10	FLACCTNAME
	ACCT NAME	- 3RD	CHAR.	I	ACCT	NAME		4TH	CHAR.	11	
	ACCT NAME	- 5TH	CHAR.	ı	ACCT	NAME		6TH	CHAR.	12	
	RCCT NAME	- 7īH	CHAR.	i	ACCT	NAME	-	81H	CHAR.	13	
	CREATOR NA	ME - 1	ST CHAR.	I	CREAT	OR NA	ME	- 21	ND CHAR.	14	FLUSERID
	CREATOR NA	ME - 3	RD CHAR.	1	CREAT	OR NA	ME	- 4	TH CHAR.	15	
	CREATOR NA	ME - 5	TH CHAR.	ı	CREAT	OR NA	ME	- 6	TH CHAR.	16	
į	CREATOR NA	ME - 7	TH CHAR.	1	CREAT	OR NA	ĦΕ	- 8	TH CHAR.	17	
į	LOCKHORD	- 1ST	CHAR.	Ī	LOCK	HORD	- ;	2ND	CHAR.	20	FLLOCKHORD
į	LOCKHORD	- 3RD	CHAR.	ŀ	LOCK	MORD		TH	CHAR.	21	
į	LOCKHORD	- STH	CHAR.	ı	LOCK	HORD	- 1	STH I	CHAR.	22	
	LOCKWORD	- 7TH	CHAR.	1	LOCK	HORD	- :	BTH	CHAR.	23	
			0504055		40707					24	FLSECMX
			SECURIT	7	UHIKI	Ā				25	
	FILE LANGU	AGE AT	TRIBUTE						SR S	26	

File System

File Label (Cont.)

COPOTTON BOTT		
CREATION DATE	27	FLCREATE
LAST ACCESS DATE	30	FLLASTACC
LAST MODIFICATION DATE	31	FLLASTMOD
FILE CODE	32	FLFILECODE
C MVTABX VMASK	33	FLPVINFO
S R L X SUBTYPE DISC TYPE R/W	34	FLLOCK
NO. USER LABELS WRITTEN NO. USER LABELS AVAIL.	35	FLUSERLBL
	36	FLFLIM
FILE LIMIT IN BLOCKS	37	
	40	FLFCBVECT
FCB VECTOR	41	
CHECKSUM	42	FLCHECKSUM
COLD LOAD ID	43	FLCLID
FOPTIONS	44	FLFOPTIONS
RECORD SIZE IN BYTES	45	FLRECSIZE
BLOCK SIZE IN WORDS	46	FLBLKSIZE
SECTOR OFFSET NO. EXTENTS -1	47	
LAST EXTENT SIZE IN SECTORS	 50	FLLASTEXT-
EXTENT SIZE IN SECTORS	51	SIZE FLEXTSIZE
••••••••••	 52	FLEOF
END OF DATA POINTER	 53	
VOLUME TABLE INDEX	54	FLEXTMAP
	j 1 55	

	File System	File System		
<u>File Label (Cont.)</u>		FLCLASSFLG		file secure bit STORE/RESTORE released bit Class flag bit
<u>:</u>		FLINTABX Flynask (Flstore)	= FLPVINFO.(4:4)#, = FLPVINFO.(8:8)#, = FLAB(28).(0:1)#,	Mounted volume table index Volume mask
VOLUME TABLE INDEX		FLRESTORE (FLLOAD) FLEXCL	= FLAB(28).(0:1)#, = FLAB(28).(1:1)#, = FLAB(28).(2:1)#, = FLAB(28).(3:1)#,	file being stored file being restored file loaded exclusive access
LAST EXTENT SECTOR MUMBER		FLSR FLSRL	= FLAB(28).(0:2)#, = FLAB(28).(0:3)#,	S & R bits S, R, & L bits
:		(FLSRLX) Flsubtype Fldtype	= FLAB(28).(0:4)#, = FLAB(28).(4:4)#, = FLAB(28).(8:6)#,	S, R, L, & X bits device subtype device type
FILE ALLOCATION TIME	154 FLALLOCTIME 155	FLSTATUS (FLLBLEOF) (FLLBL) FLSECTOFF	= FLAB(28).(14:2)#, = FLAB(29).(0:8)#, = FLAB(29).(8:8)#, = FLAB(39).(0:8)#,	Hrite/read status no. labels Hritten no. labels available sector offset to data
FILE ALLOCATION DATE	156 FLALLOCDATE	FLHUNEXTS FLLABEL FLYTAB	= FLAB(39).(11:5)#, = FLABD8L(22)#, = FLABD8L(22)#,	no. extents less 1 label VTAB and sector
		r Ly inc	= FLR8(44).(0:8)#,	label VTRB index
START OF FILE BLOCK NUMBER	160 FLSTART 161	Discussion: FLACCTHAME	This is also seems	una unum un aku dita. Ta is sisaka
	162 FLEND	FUNCTION	bytes in length with	nt name of the file. It is eight trailing blanks added.
BLOCK NUMBER OF END OF FILE	163	FLALLOCDATE	Date that the file was	s allocated on this system.
NUMBER OF OPEN AND CLOSE RECORDS (MESSAGE FILE)	164 FLNUMOPENCLSREC	FLALLOCTIME	Doubleword containing located on this system	g the time that the file was al- m.
manus or or an one close Records (Resonde FILE)	165	FLBLKSIZE	This is the block size	e, in sectors, of the file.

FLCHECKSUM LAST FILE MODIFICATION TIME FLHOOTINE

176

This is the exclusive-OR checksum of the file label (excluding words 34, 42, and 43 octal) and is used for error detection. Each time the file label is read from disc the check sum is calculated and compared against the value recorded in the file label. Similarly, each time the file label is uritten to the disc the check sum is calculated and inserted into the file label. 167 1 170 UNUSED 173 DEVICE NAME - 1ST CHAR. | DEVICE NAME - 2ND CHAR. 174 FLDEVNOME FLCLID

File System

This is the cold load number in effect the last time that the file was accessed. This should always be the current cold load number. If it is not, it means that the system crashed while the file was open and that the data in the file label should be "reset" (principally the FCB vector FLFCBVECT).

This is the creation date of the file. It is in the format defined by the intrinsic CRLEMDAR. FLCREATE

Other identifiers used:

G.01.00 6- 45

DEVICE NAME - 3RD CHAR. | DEVICE NAME - 4TH CHAR. DEVICE NAME - 5TH CHAR. | DEVICE NAME - 6TH CHAR.

DEVICE NAME - 7TH CHAR. | DEVICE NAME - 8TH CHAR. | 177

G.01.00 6- 46

File System This is the FOPEN device specification that was used when the file was created. This information is needed when new extents are allocated. FLDEVNAME FLOTYPE This is the device type number of the first extent of the file; see RCBDTYPE for a list of legal values. This value is determined by configuration. FLEND Number of current data blocks (that is, the end of file block number relative to the start of file). This is the end-of-file pointer for the file. It is a double word integer representing the number of records in the file. It can also be viewed as the record number of the next record past EOF. FLEOF This is the exclusive access flag for the file. If set it means that the file has been opened exclusively by a single accessor. If not set then the file is potentially accessible by others. FLEXCL FLEXTHAP This is the extent map of the file. The number of extents is specified by FLMUMEXTS; a OD extent descriptor indicates that the extent has not been This is the extent size, in sectors, of the file. All extents in the file, except the last, have this extent size. This is a logical value, and legal values range from 1 65535 sectors. This limits the maximum file size to 2097120 FLEXTSIZE If nonzero, this is the vector of the FCB for the file. If zero, the file is not being accessed. $\label{eq:first} % \begin{array}{ll} & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ for the file } \\ & \text{ fo$ FLFCBVECT **FLFILECODE** This is the file code of the file. Known values are: User Subprogram Library Basic Data Basic Program Basic Fast Program Relocatable library Program File 1024 1025 1026 1027 1028 1029 1031 Program File Segmented Library View Form File View Fast Forms File View Reformat File Cross Loader RSCII File (SRVE) Cross Loader RSCII File (DISPLRY) Edit Quick File Edit KEEPD File (COBOL) Edit TEXT File (COBOL) TDP Diary File 1035

```
TDP Proof Marked QMARKED
TDP Proof Marked non-COBOL File
TDP Proof Marked COBOL File
TDP Workfile (COBOL)
RIE Punch File
1056
1057
1058
1059
1060
1070
1080
1083
1084
1090
1100
1101
1102
11103
1110
 1112
1114
1130
1131
1132
1133
1139
1140
1141
1145
```

TOP Workfile (CDBOL)
RTE Punch File
QUERY Procedure File
KSRM Key File
GRAPH Specification File
User Logging Log File
Self-describing File
HPURDR Document
HPHURD Document
HPHURD Longing Log File
HPURDR Offiguration File
HP 2601 Environment File
IDS/3000 Form File
ITS/3000 Form File
ITS/3000 Environment File
IDS/3000 Form File
ITS/3000 Environment File
FRS/3000 Environment File
FRS/3000 Environment File
FRS/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/3000 Log File
HPED/30 1146 1147 1148 1149 1152 1153 Reserved
Reserved
Compressed SLRTE File
Expanded SLRTE Workfile
Store File for RRPID/3000 Utility DICTOBU
Code File for Iransact/3000 Compiler
Code File for Iransact/3000 Compiler
Code File for Inform/3000 Compiler
HOPESK Distribution list
HOPESK Text
Term Type File
Term Vertical Fornat Control File
Network Configuration File
Network Configuration File
Network Log File
RNDDE
NODE
NODE
NODE
VE File Reserved 1156 1157 1158 1159 1166 1167 1177 1178 1192 1193 1194 1211 1212 Move VC File DIF File Language Definition File Character Set Definition File Formatted Application Message Catalog 1226 1227 1228 1229 1230 1235 1236 Reserved

G.01.00 6- 47

G.01.00 6- 48

Pathflow STRTIC File Pathflow DYNAMIC File 1258

8000 8099

Reserved for RPL

This is the end-of-space pointer for the file. It is a double integer representing the maximum number of records (fixed length record format) or blocks undefined or variable length record format) in the file. FLFLIM

FLFOPTIONS This is the FOPTIONS of the file.

This is the group name of the file. It is eight bytes long with trailing blanks added. FLGRPNAME

This is the volume table index and sector number of the file label, which is the same as the first extent descriptor. FLLABEL

FLLASTACC This is the last access date of the file. It is in the format defined by the intrinsic CALENDAR.

This is the last modification date of the file. It is in the format defined by the intrinsic CRLEMDAR. FLLASTMOD

This is the size, in sectors, of the last extent in the file. If the file has one extent, then this is the same as FLEXISIZE; if the file has more than one extent, then this value nay be different from FLEXISIZE. This is the size of the last physical extent for the file; it is not the size of the last allocated extent. FLLASTEXTSIZE

This is the number of user labels allocated for the file. Since each label is a sector long, this is also the number of sectors allocated for user labels. FLLBL

This is the end-of-data pointer for the user labels. It is analogous to FLEOF in that it represents the number FLLBLEOF

is analogous to of labels written.

This is the LOADED flag for the file. If set, it means that the file is a loaded program or SL file and cannot be modified except by a privileged accessor. This flag is set and cleared by the loader, not the file system. FLLOAD

This identifies the word containing the lock bits, which are described separately. FLLOCK

This is the lock word of the file. It is eight bytes long with trailing blanks added. If it is all blanks, then the file does not have a lockword. FLLOCKWORD

G.01.00 6- 49

File System

FLRECSIZE

FLSR

This is the local name of the file. It is eight bytes long with trailing blanks added. FLLOCHAME

FINDDTTME Last time the file was modified.

This is the number of extents, less one, allowed for the file. It is not the number of extents allocated. Legal values range from 0 to 31, i. e., 1 to 32 extents. FLNUMEXTS

FLNUMOPENCESREC Number of open and close records in the message file.

FLPVINFO File label private volume information. This is in the same format as the FCBPVINFO.

This is the record size of the file in negative bytes.

This is the RESTORE flag for the file. If set, it means that the file is being RESTOREd and cannot be accessed. RESTORE also sets the STORE bit for the file (FLSTORE); see FLSR for a full description of the use of these bits. This flag is set and cleared by STORE/RESTORE, not the file system. FLRESTORE

This is the security natrix of the file. The bits are organized into five groups of six bits each. (Bits 0:2 are not used.) The groups correspond to the access types: READ, RPPEND, WRITE, LOCK, and EXECUTE. Within each group, each bit specifies who may have the access: RNY, RCCOUNT MGR, ACCOUNT LIB- RARIAN, GROUP, GROUP LIBRARIAN, CREATOR. FLSECHX

This is the sector offset from the file label to the first block of the file. This is not necessarily equal to FLBL+1 since an integral number of blocks are allocated for the file and user labels. FLSECTOFF

This is the file security enforcement flag for the file. If not set, then the file has been RELERSEd and the security matrix FLSECIMS should be ignored. If set, then secure as specified by the security matrix. FISECURE

This is the STORE and RESTORE flags for the file, which are described separately. STORE and RESTORE decode the two-bit field to indicate their operation. Legal values are:

O - file not in use by either STORE or RESTORE

1 - illegal value 2 - file being STOREd 3 - file being RESTOREd

The file system interprets the leftmost bit as indicating that the file is being accessed by either STORE or RESTORE. The rightmost bit is interpreted as indicating what access should be permitted: 0 (file being STOREd) allows read access; 1 (file being RESTORED) allows no

G.01.00 6- 50

File System

This is the STORE, RESTORE and LORDED flags for the file, which are described separately. $\label{eq:lorder} % \begin{array}{ll} \left(\left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac{1}{2}\right) + \left(\frac$ FLSRL

This is the STORE, RESTORE, LOADED and exclusive flags for the file, which are described separately. FLSRLX

This flag is used by STORE/RESTORE. If a file is STOREd with the ";RELERSE" keyword, STORE will set this flag in the tape copy of the file label. RESTORE will allow any user to access such files, regardless of the file's normal security. If this bit is off in the tape copy of the file label, RESTORE applies normal security checks (as defined by the information in FLSECHX and FLSECHE). This bit is zero for files on disc.

Block number of the file's start, excluding the file FISTART

FLSTATUS

FLSRRELEASE

FLSTORE

0 - no accessors 1 - read 2 - write 3 - read/write

This is the STORE/RESTORE flag for the file. If set it means that the file is being either STOREd or RESTOREd. The RESTORE bit (FLRESTORE) must be interrogated to determine which operation is taking place; see FLSR for a full description of the use of these bits. This flag is set and cleared by STORE/RESTORE, not the file system.

This is the device subtype number of the first extent of the file. This value is determined by FLSUBTYPE configuration.

This is the creating user name of the file. It is eight bytes long with trailing blanks added. FLUSERID

This field describes the user labels of the file. It consists of FLLBL and FLLBLEOF, which are described FLUSERLBL sists of separately.

This is the volume table index of the first extent of the FLVTAB

File System

File Multi-Access Vector Table (FMRVT) DST(254)

The FMRVI is used to locate shared PRCB's for files opened multi-access. When an old disc file has been opened multi-access, the FMRVI is searched to determine if the file has previously been opened. The JITOSI and the DADDR found in the FMRVI are compared to the JITOSI of the job and the DADDR of the device or disc file being opened multi-access. If an entry exists for the file, then the PMCB can be easily located for that file. If this is the first process opening the file, then an entry is created and inserted into the FMVAT for the file.

Spoolfiles are opened multi-access, therefore, they will have entries in the FMRVT. \$STDIM and \$STDLIST also have entries in the FMRVT since they too are opened multi-access.

Zero Entry Format

CURRENT TABLE SIZE	O FM'CURR'SIZE
ENTRY SIZE = 6	1 FM'ENTRY'SIZE
MAXIMUM TABLE SIZE	2 FM'MAX'SIZE
0	3
0	4
0	5
	-

Descriptions:

FM'CURR'SIZE The current size of the FMRVT in words. This value increases in increments of %200 words until FM'MAX'SIZE is reached.

FM'MAX'SIZE

The maximum allowable size in words that the FM'CURR'SIZE can get. The current value of this is X4000. FM'MAX'SIZE can be changed only by changing the code in Initial. The open of the multi-access file is failed if this maximum is reached.

FM'ENTRY'SIZE Size in words of an FMRVT entry, 6 words at present.

Typical Entry Format



FH'DEVTCE

= FMAVT(0).(2:1)#, Device bit = FMAVT(0).(1:1)#, Global multi-access bit = FM'DADDR(0).(0:8)#, Logical device number of file

Descriptions:

FM'DADDR The disc address of the file label for disc files. For device files, the disc address is zero.

FM'DEVICE This bit is 1 for device files and 0 for disc files.

FM' LDEV Logical device number of device files or the LDEV of the disc containing the file label for disc files.

The DST number of the JIT for the job that has the file open. If this field is nonzero, then only processes in the family tree of this particular job can open the file. This field is zero if the file was open global multi-access. FM' JTTDST

This bit is 1 if the file was opened global multi-access, this allows multi-access to the file between jobs. FM'GLOBAL

FM' PACBV

The PACB vector for this multi-access file. Used to easily find the Physical Access Control Block for files opened

multi-access

G.01.00 6- 53

File System

Shared CBT DST

In sysglobal X76 (RBSDLUTE X1076) there exists the shared Control Block Table DST number. This DST holds a list of shared CBT's. Shared CBT's are used to keep any and all file system control blocks that have the potential to be shared between processes. Any disc file opened shared will have its FCB kept in one of these CBT's. Rlso, all terminal PRCB's will be stored in a system shared CBT so that an extra data segment is not wasted. This is possible because all terminal access is performed NDBUF, which means that the PRCB will be a minimal PRCB and can be placed in these CBTs. Lastly, any file opened with global file access will have all its control blocks placed into these system CBT's.

The format of the system shared CBT DST is similar to a Control Block Table. It has the same words of overhead and the data (the list of DST's) starts in the next word after the overhead. The system CBT's are created one at a time as needed. Usually, there are only a few DST's in the list.

TRBLE SIZE IN WORDS (X200)	٥
DST NUMBER OF THIS TABLE	1
0	2
0	3
0	4
0	5
0	6
0	7
1ST. SHARED CBT DST NUMBER	10
2ND. SHARED CBT DST NUMBER	11
•	
:	
118TH. SHARED CBT DST NUMBER	177
	!

System Global Area (SYSGLOB)

The file system uses several words in the system global area for its own

SHFCBDST = SYSDB-X76,
MONITOR = SYSDB-X77,
MRNSSECT = SYSDB-X100,
MUTSSECT = SYSDB-X102,
EXTSSECT = SYSDB-X102,
EXTSSECT = SYSDB-X102,
EXTSSECT = SYSDB-X104,
SPOOLINDEX = SYSDB-X132,
CLOSEPLBL = SYSDB-X135,
CSTOURT PLBEL
CSTORTE = SYSDB-X135,
CSTOURT PLBEL
CSTORTE = SYSDB-X135,
DSCHNPLBBL = SYSDB-X135,
DSCHNPLBBL = SYSDB-X135,
DSCHNPLBBL = SYSDB-X135,
DSCHNPLBBL = SYSDB-X135,
DSCHNPLBBL = SYSDB-X135,
DSCHNPLBBL = SYSDB-X136,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
SYSDB-X137,
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRBEL
DSCLUSS PLRB shared CBT DST no. monitoring flag word max W spoolfile sectors current W spoolfile sectors # sectors/spoolfile extent # sectors/spoolfile extent class spool index CSIOWATT PLABEL CS CCLOSE PLABEL - FPROCTERM DSCHECK PLABEL DSOPEN PLABEL

SIRs, Locks, and Deadlocks

The file system uses two SIRs: the File SIR, which is intended to protect file label integrity, and the FMRVT SIR, which is to guarantee the integrity of the FMRVT. Since the file system locks these resources and also locks control blocks, deadlocks can occur if locking is done in the wrong order. Not only must the file system handle locking correctly, but the entire ensemble of the file system, its callers, and its callees must do so also. These include KSRM, which has a SIR of its own, SYSDUMP, and STORE, which lock the file SIR because they tweak bits in file labels. The presently accepted order is:

Get FMAVT SIR Lock ACB Get File SIR Lock FCB

It may not be necessary to do all of these things in any particular procedure. In modifying a procedure, you should be sure that any of these locks which you change are consistent not only mithin your own code, but also with its callers and callees.

G.01.00 6- 54

Process

CHAPTER 7 PROCESS TABLES

The operating system maintains state, control, and accounting information on each process. The data structures for this purpose are the process control block table (PCB; core resident, 1 entry per process) and the process control block extension (PCBX; contained in the process' stack below DL). Process related information which must be accessible when the process' stack is not present in main memory is maintained in the process' PCB entry. All other process related information is maintained in the process' PCB.

A process is identified in the system by its PCB entry number, referred to as its PIN (process identification number), or by its PCBPT=(PIN)*(PCB entry size).

The structure of the PCB table, PCB entry format, PCBX structure, and PCBX format are specified in this chapter.

Process Control Block Table Structure and Format

Fixed Cells Related to PCB

- 4 PCB relative index of current process' PCB entry %21003 SYSGLOB relative address of the PCB table base The bank & address are represented as per the MPEV ERS. %21271 PCB relative address of head of dispatching queue's PCB
- entry %1272 PCB relative address of tail of dispatching queue's PCB entry

Process

PCB Entry O Format

0	# OF CONFIGURED ENTRIES
1	ENTRY LENGTH (#25)
2	# OF UNASSIGNED ENTRIES
3	TABLE RELATIVE INDEX TO FIRST UNASSIGNED ENTRY
4	TABLE RELATIVE INDEX OF LAST FREE ENTRY
5	HIGH WATER MARK
6	NUMBER OF PRIMARY CONFIGURED ENTRIES (0)
7	HEAD OF IMPEDED QUEUE PCB RELATIVE INDEX
8	TAIL OF IMPEDED QUEUE PCB RELATIVE INDEX
9	NUMBER OF CURRENTLY IMPEDED PROCESSES
10	NUMBER OF MAXIMUM IMPEDED PROCESSES (CURRENT)
11	CUMULATIVE NUMBER OF IMPEDED PROCESSES(CURRENT)
12	0
13	0
14	0
15	0
16	0
17	0
18	0
19	٥
20	0
	1

G.01.00

G.01.00 7- 1

Process

Unassigned PCB Entry Format

0)			
1	TABLE	RELATIVE	INDEX	TO	NEXT	UNASSIGNE	ENTRY
				٠			•
				:			
20			;	(17	7777		

Note: Only word 1 and word 20 are valid for an unassigned PCB entry.

Assigned PCB Entry Format

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
·i	A F R S I S P C S H H R S I T I	RESABORTINFO
PCB01	SLL RELATIVE ADDRESS OF PROCESS' SEGMENT LOCALITY LIST	SLLPTR
PCB02	A / D / XDS DST# B / .	DBXDSINFO
РСВОЗ	A S O C STK DST#	STKINFO
PCB04		HAKEMASK
PCBO5	FATHER'S PCB INDEX	FATHERINFO
PCB06		SONINFO
PCB07	BROTHER'S PCB INDEX	BROTHERINFO
PC808		PIINFONIMPPIN
PC809	L BHS PPC S PTYPE S HK SK ST HB CY BK I	PROCSTATE
PCB10	EVENT FLAGS [HS	EVENTFLAGS
PCB11	SEGIDENTIFIER OF LAST REFERENCED	LASTREFSWAPSEG
PCB12	- SHAPPABLE CODE SEGMENT	
	D L C D E I C A I Q S	QUEUEINGINFO

G.01.00 7-3

G.01.00 7- 4

G.01.00

user, son of main user, main user, main, task system system, UCOP .(9:1)

M, mourning wait. RG, global RIN wait. RL, local RIN wait.

.(2:14)

.(0:1)

.(2:1)

.(10:1)

PCB04

7:
SI, set when the Dispatcher (and PSEUDOINT) should be aware of a pending soft interrupt. HK, hard kill pseudo interrupt SK, soft kill pseudo interrupt SI, stop pseudo interrupt HB, hibernate pseudo interrupt CY, control-y pseudo interrupt BK, break pseudo interrupt .(11:1) .(12:1) .(13:1) .(14:1) .(15:1)

EVENTFLAGS, one for each wait class in PCBO4 \mbox{WS} , wake up waiting switch set if an awake is missing. PCR10 . (0:15) .(15:1)

LASTREFSWAPSEG, segment identifier of last referenced swappable code segment. PCB11 . (0:32)

(QUEUING INFO) .(0:1) .(1:1) .(2:1) .(3:1) .(4:1) .(5:1) .(6:1) .(7:1)

(QUELING INFO)
DISPQ ==> on dispatching queue
L scheduling class
C scheduling class
D scheduling class
E scheduling class
E scheduling class
INTER ==> process is interactive
CURER ==> process is core resident
RSOFT, Rllow soft interrupt. R value of 1 implies that user soft interrupts will be processed. R zero value inhibits user soft ints (they are queued). This bit is managed by FINISTRIE and FINIEXII intrinsics.
Process' scheduling priority .(8:8)

PCB14 .(0:16) PBX, CSTX block map index of process' program.

MAPOST, OST entry number of the CST mapping PC815 . (0:16)

PCB16 .(0:16) PIMPPIN, PCB relative index of previous impeded PIN.

NIMPPIN. PCB relative index of next impeded PIN. PCB17 .(0:16)

BPTLINK, breakpoint link for process PCB18 .(0:16)

PCB19 .(0:16) NQPTR, PCB relative index of next proc in disp queue

PCB20 .(0:16) PQPTR,PCB relative index of prev proc in disp queue Process

.(5:1) .(6:3)


Process Control Block Extension (PCBX) Structure and Format

G.01.00 7- 6

Process Control Block Extension (PCBX) General Structure

3: blocked

STOV, stack overflow bit PTYPE, process type O: user



PXGLOB Format

The PXGLOB portion of the pcbx is for job information, and contains the same job related information for all processes belonging to the same job.

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
	0
DB-a=SEG. REL DB VALUE	1
USER ATTRIBUTES	2
JMAT INDEX	3
JPCNT INDEX	4
JCUT INDEX	5
SB R TY D I // // // STACK DUMP FLAGS	6
////////////////////// NATIVE LANGUAGE	7
ACTUAL JOB INPUT LDEV	8
ACTUAL JOB OUTPUT LDEV	9
JDT DST INDEX	10
JIT DST INDEX	11
	DB-a-SEG. REL DE VALUE DB-a-SEG. REL DE VALUE USER ATTRIBUTES JHAT INDEX JPCNT INDEX JCUT INDEX SB R TY D I // ///// STACK DUMP FLAGS ///////////////////////////////////

R = restart bit
I = job in/list interactive
D = job in/list duplicative
PY = job type
0 = undefined
1 = session
2 = job
3 = task
2 = reserved:
SB= stun bit ; used for stack underflow simulation for ICF44 or ICF55.

G.01.00 7- 9

PXFIXED Assignments

The PXFIXED portion of the pcbx-contains specific information and control information.

1		
٥	c-b PXFIXED SIZE	0
1		1
2		2
3	INITIAL Q(Q-DB)	3 LM MDST existed
4		4 LP LOADPROCed
5		5 .AT(0:1)-Arith.
6	AT LT ST CY CT // // // U L C G A LMJLP	6 .ST(2:1)-System
7		.CY(3:1)-Ctl-Y 7 :CT(4:1)-Code
10		U User UDC exist 8 L Logging
11		9 G Global RIW acquired
12		10 V 0:1 RESERVED FOR
13	P S EXTRA DATA SEGMENT DST INDEX	CST EXPANSION 11 1:1 = 1 IF ABORT IN PROGRESS
14		12 < 7:1 = 0 IF HAVE R/W
15	MAXIMUM STACK SIZE(MAXDATA LIMIT)	10 1 100.20
16	ARITHMETIC TRAP MASK	= 1 OTHERNISE 14 8:8 = CSI # OF SEG
17	ARITHMETIC TRAP PLABEL	INITIALLY EXECUTED 15 \ AT PROCCREATION
20		16
21	SYSTEM TRAP PLABEL	17
22	CONTROL Y PLABEL	18
23		19
24		20
25	IMAGE TRAP PLABEL	21
26	RESERVED	22
27	CUR.MAX STACK SIZE(largest value ever for Z-DL)	23
	G.01.00 7- 10	I

Process

Process

PXFIXED Assignments (Cont.)

60	/ D / D RESERVED FOR FUTURE SOFT INT USE / C / S / Y / I	48 	
61	TRLX INDEX FOR KERNEL TIMEOUT PROCEDURE	49	JOB TYPE:
62	TY JOB/SESSION NUMBER	50	1=SESSION 2=JOB
63	<(reserved)>	51	2-300
64	RESERVED FOR FUTURE USE	52	
65	RESERVED FOR FUTURE USE	53	
66	RESERVED FOR FUTURE USE	54	
67	RESERVED FOR FUTURE USE	55	
70	[CA] [2]	56	
71	TIMEOUT TRLX	57	
72	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	58	
73	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	59	
74	PCLASSMASK	60	
75	PROCQUESTOPWORD	61	
76	PROCSTOPTIME	62	
77		63	
	UNUSED	ı İ	
114	PXFIXED EXPANSION BITMAP	İ	
117		İ	
	1		

NOTES: P = 1 if opened by priv user S = 1 if data segment is sharable

PCLASSHASK = BIT MASK OF CLASSES THIS PROCESS HAS ENABLED PROCQUESTOPWORD.(0:4) = PROCESS PRIORITY: 7 => L QUEUE 6 => C QUEUE 2 => D QUEUE 1 => E QUEUE

PXFIXED Assignments (Cont.)

30	PROCESS EPU TIME	24
31	(MSEC)	25
32	MAXIMUM DATA SEG SIZE USED(IN SECTORS)	26
33	TOTAL VIRTUAL STORAGE USED(IN SECTORS)	27
34	CURRENT EXTRA DATA SEGMENT SPACE	28
35	MAXIMUM EXTRA DATA SEGMENT SPACE	29
36	PRIV MODE BOUNDS FLAGS STOV COUNT	30
37	PROCESS EXECUTION TIME REMAINDER (IN MSEC)	31
40	SET TO-1 WHEN IN BREAK MODE*	32
41	CONTINUE FLAG (:CONTINUE COMMAND)**	33
42	ACTUAL SIZE OF VIRTUAL SPACE ALLOCATED TO STACK	34
43	ERROR LEVEL	35
44	INTRINSIC ERRORS	36
45	INTRINSIC ERRORS	37
46	INTRINSIC ERRORS	38
47	INTRINSIC ERRORS	39
50	INTRINSIC ERRORS	40
51	INTRINSIC ERRORS	41
52	TSLR, virtual time since last rescheduled	42
53	TSTB, virtual time since transaction began	43
54	TSSWAPIN, virtual time since swapin	44
55	TSLA, virtual time since last absence	45
56	TSLD, virtual time since last deallocation	46
57	QCNT, quantums used since transaction began	47

G.01.00 7- 11

G.01.00 7- 12

.(4:12)= RERSON STOPPED: 1 => STOP SEG FRULT
2 => STOP DISC URIT
3 => BLOCKED I/O, NON TERMINAL
4 => TERMINAL RERD
5 => STOP INPEDE
6 => STOP RETIVE
PROCESTOPTIME = DBL UND TIMESTAND OF UNEWN PROCESS STOPPED FOR

REASON GIVEN IN PROCQUESTOPHORD

DCY

A DELRYED CONTROL Y IS PENDING (THIS BIT IS CHECKED BY ININ DN BOUNDS VIOLATION TO DETERMINE IF GOT: 1) TRUE BOUNDS VIOLATION OR 2) AN INDUCED BOUNDS VIO THAT INDICATES THAT THE CONTROL Y TRAP PROCEDURE MAY NOW

OSI STATE OF THE "ASOFT" PCB BIT WHEN CONTROL Y
TRAP WAS ENTERED. ASOFT = 1 ALLOWS USER SOFT
INTERRUPTS AGAINST THE PROCESS. IT IS SET TO
ZERO WHEN THE CONTROL Y HARDLER IS ENTERED.
IT IS SET TO ITS PRIOR STATE WHEN THE USER
CALLS RESEITONTROL.
* SET TO COMMAND ENTERED DURING BREAK OR ENCOUNTERED
DURING FLUSHING).

** CONTINUE FLAG VALUES

0 = NO CONTINUE IN EFFECT
1 = CONTINUE JUST ENCOUNTERED
2 = CONTINUE IN EFFECT FOR THIS COMMAND

CV FIAG

PCBXFIXED(56).(1:1)

= SET BY PSEUDOINT WHEN THERE IS A PENDING CONTROL Y WHICH CRWNOT BE PROCESSED BECAUSE OF SYSTEM CODE OR PRIVILEGED CODE. ININ CHECKS THIS BIT ON BOUNDS YDILATION OR

SI FLAG

 SPECIFIES THE STATE OF THE USER INTERRUPT FLAG WHEN THE CURRENT CONTROL Y WAS PROCESSED. PCBXFIXED(56).(3:1)

G.01.00 7- 13

Process

Overhead

The part labeled Overhead contains information that pertains to the entire section. It is addressed via the pointer at DL-3.

7 8 PXFILE SIZE IN WORDS O PXFSIZE LAST DOPEN ERROR NO. | LAST COPEN ERROR NO. LAST DS AFT 3 SLAWE AFT NUMBER LAST KOPEN ERROR NUMBER | LAST FOPEN ERROR NUMBER **RET STZE IN HORDS** 6 PXRFTSTZF CS TRACE FILE INFO (PXCTRINFO) LAST RESPONDING NO-WAIT I/O AFT ENTRY NUMBER 9 PXFLEFTOFF 1ST USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER 10 PXFCBT1 2ND USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER 11 (PXECRT2) 3RD USER (MOBUF) CONTROL BLOCK TABLE DST NUMBER 12 (PXFCBT3) 4TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER 13 (PXFCBT4) 5TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER 14 (PXFCBT5) 6TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER 15 (PXFCBT6) 7TH USER (NOBUF) CONTROL BLOCK TABLE OST NUMBER 16 (PXFCRT7) 8TH USER (NOBUF) CONTROL BLOCK TABLE DST NUMBER | 17 (PXFCBT8)

Partial word field identifiers are:

= PXFILE(1).(0:8)%, = PXFILE(1).(8:8)%, = PXFILE(2).(0:1)%, = PXFILE(5).(0:8)%, = PXFILE(5).(0:8)%, = PXFILE(5).(8:8)%, PXFDOPEN PXFCOPEN PXFNOCB PXFFOPEN

Process

PXFIXED Expansion Bitmap

The PXFIXED bitmap and expansion area is for use in accounting of extra data segments acquired by the process.

File System Section of PCBX (PXFILE)

The PXFILE area is a subsection of the PCBX. It is a contiguous, expandable and contractible block of storage that is managed by the file system primarily for its own use. Other subsystems, namely CS and DS, also make use of the PXFILE section. In doing so they must conform to the conventions of the file system.

The overall structure of the PXFILE area is:

OVERHEAD	(FIXED)		
CONTROL BLOCK TABLE	(VARIABLE)		
AVAILABLE	(VARIABLE)		
ACTIVE FILE TABLE	(VARIABLE) DL-5		

G.01.00 7- 14

Process

Discussion: PXFRFTSIZE

PXEDOPEN

This is the size (in words) of the Active File Table (AFT). The size is in words to simplify calculating the size of the available block.

These are the DST numbers of the user (MDBUF) control block tables. A DST number of 0 indicates that no data segment is PXFCBT1-8 tables. A i allocated.

PXFCOPEN This contains the last COPEN error number. Not used by the

This contains information pertinent to the CS trace file. Not used by the file system. PXECTRINEO

> This contains the last DOPEN error number. Not used by the file system.

PXFDSINFO Reserved for DS. Not used by the file system.

This contains the last FOPEN error number. If it is zero then the last FOPEN successfully completed; otherwise the last FOPEN was unsuccessful and the number is the file sys-PXFFOPEN

ten error number.

This contains the last KOPEN error number, KSRM is partly embedded in the file system, and an FDPEN failure on a KSRM file can be caused by a failure to open either the key file or the data file. This error number is used in conjunction with PMFFOPEN to determine which file caused the KSRM open failure. This error number is not used by the file system. PXEKOPEN

This is the AFT entry number of the last file/line that completed a nowait I/0; if zero then no nowait I/0 has been completed. This cell is maintained solely by and for the PXFLEFTOFF

PXENDOR

This bit signifies that control blocks are not to be created in the PXFILE control block table. This bit is set by the NOEB parameter to the CREATE intrinsic or the :RUN command. This feature permits the user to have as much stack space as possible; otherwise the file system uill take several hundred words of stack for the PXFILE control block table.

PXFSIZE

This is the size (in words) of the complete PXFILE area. It is the sum of the overhead block, the control block table, the active file table and the available block.

G.01.00

G.01.00

PXFILE Control Block Table (PXFCBT)

Addressing within a PXFILE control block table is somewhat more complicated than addressing an extra data segment CBT since the table does not begin at DB+O. Rs a result all pointers within the table are table relative; the starting address of the table must be added to a pointer to generate a final DB-relative address. This addressing convention is consistently applied to all control block tables.

When the control block table is expanded, space is taken from the RVAILABLE area. If no space is available then the PXFILE area is expanded and the acquired space is added to the RVAILABLE area.


The part labeled Available is used to provide space when the Control Block Table or the Rotive File Table is expanded. These two tables grow towards each other, and when more space is needed it is simply taken from the Rvailable Block.

When the Rvailable area is exhausted, the PXFILE area is expanded, the AFT is relocated and the neu space is added to the Rvailable Block.

Currently the PXFILE area is only expanded; it is never contracted. For more information refer Chapter 6 beginning with Active File Table page 6-7.

Process

PCBX For Core Resident System Process Stacks



There is no PXFILE area.
 The PXFIXED area is much smaller than a normal PCBX.

G.01.00 7- 18

G.01.00

Process

Process To Process Communication Table

This table is used as the communication link by which father and son processes communicate with one another via the nailbox scheme. This table contains two words per entry and is indexed by PCBM (entry index 0 is meaningless). Each two word entry of index N essentially relates where, as well as how much, nail may be found for a process N with respect to communications between N and his father process.

ENTRY FORMAT

MORD COUNT MAIL WORD OR DST#

> word 0 = the # of mail words to the M of mail words to be transferred. the only word of mail itself if word 0 = 1 otherwise it contains the DSTM of the extra data segment where "word count" words of mail exist.

NOTE: Assume process S is the son of process F. Then the process to process communication table index which will be used for mailbox communication between son S and father F will be that of the son (i.e. S).

Process

Subsystem Reserved DL Area

REMAINING DL AREA DB-12 RESERVED FOR SORT/MERGE DR-10 RESERVED FOR TRACE, TOOLBOX, & BUSINESS BASIC | DB-9 DB-11 EXTERNAL PLABEL OF OUTER BLOCK DR-10 เกล-8 RESERVED FOR TRACE & SYMBOLIC DEBUG DB ADDRESS OF STLT DB-6 iDB-6 08-5 RESERVED FOR COBOL DB-5 DB-RESERVED FOR COBOL DB-4 DR-3 RESERVED FOR COBOL DB-3 DB-RESERVED FOR FORMATTER & PASCAL DB-2 DB ADDRESS OF FLUT i D8-1 08-

DB AREA

FORTRAN Logical Unit Table (FLUT)

The segmenter is responsible for the preparation and initialization of a FORTRAM logical unit table. This is done when a program is prepared if that program contains at least one program unit that references a logical unit. The location of the FUIT is in the secondary DB area and the address of this location is contained in DB-1.

The FLUT is formatted as per the following example:

DB-1	X	
D8+X	3 0 	
	'^	

 	4 5 6 7 8 9 10 	11 12 13 14 15

CHAPTER 8 JOB TABLES

Job Tables Overview

- Job Master Table (JMRT): One entry per job/session. Contains information needed to get the job/session running. Entry is created at the introduction of job/session.
- Job Information Table (JIT): One DST per job/session. Contains information needed by the job/session as it is executing.
- Process Job Cross Reference Table (PJKREF): One DST per system.

 Used to determine the job/session main process (command interpreter) for any process on the system.
- Job Process Count Table (JPCNT): One entry per job/session. Entry number used to index into the JIR to lock job resources.
- Job Directory Table (JDT): One DST per job/session. Contains the following sub-tables used by descendants of job/session. Must obtain JIR (by using JPCNT index) before accessing JDT. Sub-tables:

 1. Data Segment Directory Directory of sharable DSTs used by tain JIR (by Using Jerum a Data Segment Directory -job/session Temporary File Directory File Equation Table Line Equation Table Job Control Word Table
- Job Cut-off Table (JCUT): Stores total CPU time limit of job/session and accumulates the CPU time that job/session uses.

Ucop Request Queue: A queue of Process Identification Numbers that are terminating.

G.01.00

Job Master Table Structure (JMAT)

SIR = 15(10) = 217 DST = 25(10) = 231 ZEROTH ENTRY 0 1 2 3 4 5 6 7 8 9101112131415 max JMRT size (words/128) current JMRT size (words/128) :VMOUNT state saved for WARMSTARTs JMRT entry size (38) DB pointer to first entry (38) MAXST7F I CURSIZE YMOUNT INFO | ENTRY SIZE ENTRY POINTER DB pointer to word 0 of head entry in scheduling queue DB pointer to word 0 of tail entry in scheduling queue next assignable session #, TY=1 SCHEDULING HERD POINTER SCHEDULING TAIL POINTER TYI SCOUNTER next assignable batch #, TY=2 JCOUNTER TYI LG=1, logoff in progress SEC=0,high;=3,low JOBSECURITY maximum number sessions C E 11 LG|SEC |/////|SFENCE/|JOBFNCE|9 SLIMIT 12 SNUM current number sessions JLIMIT maximum # batch jobs 15 THUM 13 current # batch jobs JMAT SCHEDHEAD 16 14 DB pointer to word zero. HORKAREA 15 SFENCE is session fence 17 (23MDS) 20 451 ------38

Job Tables

JMAT (Cont.) FNTRY 1 75 113 LAST ENTRY SCHEDULING QUEUE

HAITING SESSIONS
FIFO WITHIN HIPRI/INPUT PRIORITY
[ERROR JOBS] FIFO WAITING JOBS
FIFO WITHIN HIPRI/INPUT PRIORITY Job Tables

Job Master Table Entry (JMAT)

1 1 1 1 1 1 0 1:2:3 4:5:6 7:8:9 0:1:2 3:4:5 0 state
0 = free entry
1 1 = introduced, in
STRRTOEVICE
2 X70 =scheduled in scheduled job queue. :D|I:G:A|U:C: INPRI job/session number job/session # X40 = waiting, job in scheduling queue X60 = initial, UCOP has created JSMP 2 = executing, JSMP finished initial. = terminating. = suspended. = duplicative = interactive 8 9 10 account name 11 12 I = Interactive
(G = group password
((QUIET node, if state=2)
(R = account password
(U = user password
(0 = password validated(STARTDEVICE)
(1 = nust validate
(1 = nust validate 13 14 15 16 17 15 { password (INITJSMP)
R = reserved 20 21 22 |16 |17 |18 group logon nam C = JLIST is device class index 23 JIN device 119 JLIST device Julian date (CRLENDAR) 25 121 ty = 1 - session 2 - job time (CLOCK) 22 26 | 27 | 30 i language : XPRI 24 Main pin 25 32 CPU lim. (O deflt, -1 no lim.) 26 33|S|R:N:FT :OUTPRI : NUMCOPIES 27 ORIGIIN/ORIGILIST is ORIGIN/ORIGILIST is used as a scheduling link by UCOP when state= %40 or %70. DB relative ptr. Last entry in list contains zero (0) 28 34 ORIGJIN i29 ORIGILIST

JMAT (Cont.)

36	JMAT CREATOR PIN	30
37	- - - - - - - - - - - - - - - - - - -	31
40	Reserved	32
41	Reserved	33
42	Reserved	34
43	Reserved	35
44	Unused	36
45	Unused	37

Used with the programmatic creation of sessions.

P=Programmatic logon W=WAITTILLON N=NOWAIT

0|1:2:3|4:5:6|7:8:9|0:1:2|3:4:5

R = RESTART N = SEQUENCED S = ORIGJIN is spooled.

FT = funny terminal
OO - regular term.
O1 - regular term.,
special logon
10 - RPL term.
11 - RPL term.

G.01.00 8- 5

Job Tables

Process Job Cross Reference Table (PJXREF)

DST = X62

TABLESIZE = #PCB entries + 1

0	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1	J/S NUMBER OF PIN 1
2	J/S NUMBER OF PIN 2
n	J/S NUMBER OF PIN n
n+1	J/S NUMBER OF PIN n+1

This table is only used by the SHOWQ command. The entries in the table are set up through PROCREATE and modified by NORGUE.

The job/session number is in the format:

A completely zero entry is either from a system process or a currently unused

Job States

JOB STATES - JMAT ENTRY WORD O. (0:6)

SHOWJOB - Displays job states by scanning JMAT DST (X31)

LOGON USES ALL STATES EXCEPT "SUSPEND"

STATE NO.	STATE	PROCESS	SEGMENT	PROCEDURE(S)
1	INTRO	DEVREC JSMP SPOOLER	MURSERY	STARTDEVICE ->PUTJMAT ->ALLOCENTRY IN SEGMENT ALLOCUTIL
X70	SCHED	UCOP	JOBSCHED	CXSTSTREAM SCHEDULEDSCHED
X40	-URIT	DEVREC JSMP	NURSERY	STARTDEVICE ->SCHEDULEJOB
		SPOOLER	SPOOLING	SPOOLSTUFFIN ->SCHEDULEJOB
X60	INIT- IALIZAT- ION	UCOP	UCOP	LAUNCHJOB
2	EXEC	JSMP	NURSERY	INITJSMP
3	TERMIN- ATING	JSMP	MORQUE	TERMINATE ->EXPIRE -> CLEAMUPJOB
0	FREE Entry	JSMP	MORQUE	TERMINATE ->EXPIRE -> CLEANUPJOB ->DEALLOCENTRY IN ALLOCUTIL
4	SUSP	JSMP	OPLON	CXBREAKJ08

For states INTRO and WAIT,

DEVREC => logon command originated on terminal or other unspooled device.

SPOOLER => logon command originated on spooled device.

JSMP => logon command is the result of the execution of a :STRERM command. (This also includes USER processes which have done programmatic :STRERMs.)

G.01.00 8- 6

Job Tables

Job Process Count Table (JPCNT)

(1 Bit Entry/Running Job)

MEMORY RESTDENT

SYSGLOB BRSE = DB+13(X15) DST = 24(10) SIR = 13(10)

01234567891012345 Total Configured number of Jobs and Sessions ٥ Total number of free entries Bit Map relative index of word containing next free entry 3 unused free entry = 1 allocated entry = 0 Bit Map Maximum 64 words long

A JPCMT entry must be allocated before the main process can be procreated. The JPCMT Index is located in word 4, PXGLOBAL area, of the stack of a job or session. One JPCMT Index is allocated per job or session.

The job SIR (JIR) = base+JPCNT index, where base is the number of system reserved SIRs. The JIR is used to lock the Job Directory Table.


NOTE: This table is completely bit oriented with each entry consisting of one bit. Entries are taken from available pool on a "first found" basis. R "!" found in the bit map indicates a free entry. R zero (0) found in the bit map indicates an allocated entry. Word 2 of this table is the index of the word in the Bit Map where the next free entry resides. Rt system start up, this word is set to zero (0). The Bit Map can be thought of as ranging from 0-63 (64 total words - 1024 entries).

Job Cutoff Table (JCUT) 1 Entry/ CPU-limited Job


MEMORY RESIDENT

SYSGLOB BASE = DB+11(X13)
DST = 36(10);SIR = 14(10)
SYSGLOB + X117 = default
CPU time limit for jobs

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15



Job Information Table (JIT) JIT DST is word 11 (base 10) in PXGLOB



G.01.00 8- 10

Job Tables

JIT (Cont.)

1 1 1 1 1 1 0|1:2:3|4:5:6|7:8:9|0:1:2|3:4:5 JITUN user name 53 | 32 pointer to JITRIP 40 İ P - Group's hone volume is a private volume M - Private volume nounted (i.e. group bound to hone volume set), JITGIP = 57 41 PM: pointer to JITGIP 55 33 34 35 LATTR local attributes PASSF passed file pointer 36 37 44 i 45 i UCAP user capability * 38 39 Reserved for DS'II 40 50 local RIN pointer 43 53 JITJN job name 0|1:2:3|4:5:6|7:8:9|0:1:2|3:4:5 1 1 1 1 1 1

Job Tables

JIT (Cont.)

	1 1 1 1 0 1:2:3 4:5:6 7:8:9 0:1:2 3	1 1 :4:5		
60		3	48	Accounting Info
61	JITCREC - # of creations		49	
62 63			50 51	
64	not used : HIPRI		52	HIPRI - highest job priority
65 66			53 54	Account Index Pointer
67 70			55 56	Group index pointer System volume set
71 72			57 58	Group index pointer Mounted private volume set MVTABX - Mounted Volume
73		1	59	Table Index
74		0	60	
75 76 77 100 101 102	allow mask**		61 62 63 64 65	
	 0 1:2:3 4:5:6 7:8:9 0:1:2 3 1 1 1 1		Ì	

* THE FORMAT FOR UCAP (X46-47) IS AS FOLLOWS:

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 1	- 5
NORD1	SM AM AL GL DI OP CV UV LG // PS NA NM CS ND S	F
WORD2	BA IA PM MR DS P	H

Allow Mask Format

** The Allow mask for MPE V is expanded to six words. There is a mask in each user's JIT and the global allow mask in the SYSGLOB extension area. The Allow mask contains enough bits for a one-to-one correspondence to every present OPERATIOR type cohmand, or any future OPERATIOR command. When a user is ALLOWED any OPERATIOR command or RSSGCIATED to a device (which will use OPERATIOR type commands) then the corresponding bit(s) in the mask in that user's JIT for that command is set. If the ALLOW or RSSGCIATE was done on a global scale, then the bit(s) in the mask of the SYSGLOB area is/are updated.

The following EQUATEs define the mask bit for each operator command.

The first set of commands define the operator commands dealing with devices.

When adding a new command to this set of EQURTEs, be sure to add a corresponding nove statement in LOGIMAGE, even if the command will not be logged.

	Hord	<u>Bit</u> #
ABORTIO .	0	0 0
ACCEPT	0	1 1
DOLIN	0	2 2 3
GIVE HEADOFF	0	4 4
HEADON	ŏ	5 5
REFUSE	ŏ	6 6
REPLY	٥	7 7
STARTSPOOL	0	1 1 2 2 3 3 4 4 5 5 6 6 7 7 8 8 9 9
TAKE	0	
UP MPLINE	0	10 10
DSCONTROL	ŏ	11 11 12 12
UPPER LIMIT->DEV	ICE CO	MANDS
ABORTJOB	0	13 13
ABORTJOB RLLON	0	13 13 14 14
ABORTJOB RLLON ALTFILE	0	13 13 14 14 15 15
ABORTJOB ALLON ALTFILE ALTJOB	0 0 0	13 13 14 14 15 15 0 16
ABORTJOB RLLOW ALTFILE ALTJOB BREAKJOB	0	13 13 14 14 15 15 0 16 1 17
ABORTJOB RLLOW RLTFILE RLTJOB BREAKJOB DELETE DISALLOW	0 0 0 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19
ABORTJOB ALLON ALTFILE ALTJOB BREAKJOB DELETE DISALLON JOBFENCE	0 0 0 1 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19 4 20
ABORTJOB ALLON ALTFILE ALTJOB BREAKJOB DELETE DISALLON JOBFENCE LIMIT	0 0 0 1 1 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19 4 20 5 21
ABORTJOB ALLON ALTFILE ALTJOB BRENKJOB DELETE DISALLON JOBEENCE LIMIT STOPSPOOL	0 0 0 1 1 1 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19 4 20 5 21 6 22
ABORTJOB RLLOH RLTFILE RLTJOB BRERKJOB DELETE DISRLLOH JOBFENCE LINIT STOPSPOOL SUSPENOSPOOL	0 0 0 1 1 1 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19 4 20 5 21 6 22 7 23
ABORTJOB ALLON ALTFILE ALTJOB BRENKJOB DELETE DISALLON JOBEENCE LIMIT STOPSPOOL	0 0 0 1 1 1 1 1 1	13 13 14 14 15 15 0 16 1 17 2 18 3 19 4 20 5 21 6 22

G.01.00 8- 13

G.01.00 8- 14

Job Tables

Job Directory Table (JDT)

O MRX SEG SIZE(UDS) 1 POINTER TO JOSD 2 POINTER TO JIFD 3 POINTER TO JIFD 4 POINTER TO JEQ 5 POINTER TO JULEQ 6 POINTER TO JULEQ 6 POINTER TO JULEQ 1 SHORK REER 1 S WORDS JOB DATA JOB DATA JOB DATA JOB SEGNENT DIRECTORY JOB SEGNENT DIRECTORY JOB THE OIRECTORY JOB LINE EQUATION TABLE JOB CONTROL WORD TABLE (JJCH) FREE SPACE SUDNAME 1 entry per job DST # in word 10 (base 10) of PXGLOB DATA IN mord 10) FAMILY STATE IN MARE SIZE (WDS) C1 C2 CN (Z40) The name is a concatenation of up to 3 subnames. Bit O of the 1st character of each subname is 1.		1	•					
1 POINTER TO JOSO 2 POINTER TO JIFD 3 POINTER TO JIEQ 4 POINTER TO JIEQ 5 POINTER TO JIEQ 6 POINTER TO JIEQ 6 POINTER TO JIEQ 5 POINTER TO JIEQ 6 POINTER TO JIEQ 6 POINTER TO JIEQ 7 JOS DATA JOS DATA JOS DATA JOS DATA JOS DETECTORY JOS SEGRENT DIRECTORY JOS TEMPORARY ENTRY NAME SIZE (MOS) SIZE (MOS) JOS LINE EQUATION TABLE JOB LINE EQUATION TABLE JOB CONTROL MORD TABLE (JUCU) JOB CONTROL MORD TABLE (JUCU) THE NAME S CONCATABLE INFORMATION JOB CONTROL MORD TABLE INFORMATION JOB CONTROL MORD TABLE INFORMATION JOB CONTROL MORD TABLE INFORMATION	0	MRX SEG SIZE(NDS)	1 entry per job					
3 POINTER TO JEEQ 4 POINTER TO JUEQ 5 POINTER TO JUEQ 6 POINTER TO FREE SPRCE WORK REEN 15 WORKS JOS DATA JOB DATA JOB DATA JOB TEMPORRRY FILE DIRECTORY FILE DIRECTORY JOB FILE GURTION TABLE JOB LINE EQUATION TABLE JOB CONTROL WORD TABLE (JJCN) The name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	1	POINTER TO JOSO	(base 10) of PXGLOB					
4 POINTER TO JLEQ 5 POINTER TO JUEQ 6 POINTER TO FREE SPRCE 15 WORK REER 15 WORDS 17 NUM JOB DATH 17 NUM JOB DATH 18 SEGNENT DIRECTORY JOB TEMPORARY ENTRY NAME SIZE (WDS) SIZE (WDS) C1 C2 JOB FILE 100 LINE EQUATION TABLE JOB CONTROL WORD TABLE (JUCN) The name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	2	POINTER TO JTFD						
5 POINTER TO JJCW 6 POINTER TO FREE SPRCE WORK ARER 15 words JDSJNUM TY NUM job number JJSMPIN main process number JOB DATH JOB DATH JOB SEGMENT DIRECTORY FILE DIRECTORY ENTRY NAME SIZE (MDS) SIZE (MDS) C1 C2 JOB FILE JOB LINE EQUATION TABLE JOB LINE EQUATION TABLE JOB CONTROL WORD TABLE (JJCW) The name is a concatenation of up to 3 subnames. Bit O of the 1st character of each	3	POINTER TO JFEQ						
JOS TEMPORARY JIFD JOB TEMPORARY JIFD JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY JOB TEMPORARY SIZE (MOS) C1 C2 JOB FILE GUATION TABLE JOB LINE ENTRY JOB TEMPORARY SIZE (MOS) TO 1 C2 JOB FILE JOB LINE JOB LINE FILE DIRECTORY JOB LINE JOB LINE JOB CONTROL WORD TABLE (JJCH) THE name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	4	POINTER TO JLEQ						
JOSJNUM TY NUM job number JOSD DATA JOSD SEGMENT DIRECTORY JOB TEMPORARY JIFD FILE DIRECTORY ENTRY NAME SIZE (MDS) SIZE (MDS) C1 C2 JOB FILE JOB LINE ENTRY JUB CONTROL MORD TRBLE (JJCH) JOB CONTROL WORD TRBLE (JJCH) The name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	5	POINTER TO JJCH						
JDSJNUM TY NUM job number JSMPIN Hain process number JOB DATA JOB DATA JOB TEMPORARY JIFD FILE OIRECTORY ENTRY NAME SIZE (MOS) SIZE (MOS) C1 C2 JOB FILE JOB TIME ENTRY NAME SIZE (MOS) SIZE (MOS) C1 C2 JOB FILE JOB LINE ENTRY JUB LINE ENTRY JUB CONTROL MORD TABLE (JJCH) The name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	6	POINTER TO FREE SPACE						
JSMPIN Hain process number JOB DATH JOB DATH JOB SEGRENT DIRECTORY JOB TEMPORARY JIFD FILE DIRECTORY ENTRY NAME SIZE (MDS) SIZE (MDS) C1 C2 JOB FILE FUND TABLE CN (X40) JOB LINE ENTRY JUB CONTROL WORD TABLE (JJCN) The name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each								
JOB DATA SEGMENT DIRECTORY JOB TEMPORARY JIFD FILE DIRECTORY ENTRY NAME SIZE (MDS) SIZE (MDS) C1 C2 JOB FILE FUNCTION TABLE JOB LINE EQUATION TABLE JOB CONTROL MORD TABLE (JJCH) THE name is a concatenation of up to 3 subnames. Bit 0 of the 1st character of each	JDSJNUM	TY NUM	job number					
JOSD SEGMENT DIRECTORY JOB TEMPORARY JOB TEMPORARY ENTRY NAME SIZE (MOS) SIZE (MOS)		JSMPIN	main process number					
JIFD FILE OTRECTORY ENTRY NAME SIZE (WDS) SIZE (WDS) C1	JDSD							
JOB FILE JOB LINE SUBSTITUTE STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES STATES	JTFD		SIZE (MDS) SIZE (MDS)					
JEEQ EQUATION TABLE CM (240) JOB LINE ENTRY JEEQ EQUATION TABLE INFORMATION JOB CONTROL WORD TABLE (JJCW) The name is a Concatenation of up to 3 subnames. Bit 0 of the 1st character of each			C1 C2					
JUEQ EQUATION TABLE INFORMATION JOB CONTROL WORD TABLE (JJCW) The name is a	JFEQ		CH (240)					
TABLE (JJCW) The name is a	JLEQ							
Bit O of the 1st character of each								
		FREE SPACE	Bit 0 of the 1st character of each					

Job Tables

Job Data Segment Directory Entry (In JDT)

If a DST is allocated as sharable, then it will have entries in both the JDT and PMFIX. Sharable means that it can be be shared by all processes in the Command Interpreter process tree (sons, etc.). Nonsharable DSTs only have entries in the PMFIXED.

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15					
SEGMENT ID					
EXTRA DATA SEGMENT DST INDEX					
# OF PROCESSES ACCESSING					

NOTE: A return of X2004 in the INDEX value after using the GETDSEG intrinsic indicates that there is no more room in the Job Directory Table for another job sharable data segment.

Job Temporary File Entry (In JDT)

. 0	1	2	4						
		 !Y S				HAI			
j			 	 	 		 	 	 i

concatenation of up
to three subnames.
Bit 0 of the first
character of each NAME-ACTUAL FILE DESIGNATOR

VOLUME POINTER | FILE LABEL POINTER subname is 1.

Since all son processes of a CI share the same JDT, exclusive access of the JDT is controlled with the Job SIR (JIR) and is locked and unlocked by calls to LOCKJIR and UNLOCKJIR. The JIR number is found in the PKGLOBAL area (JPCOUNT index). Only job and sessions traces have JIRs, system processes do not, even though they have JDTs. The JDTs were provided for system processes for consistency, but are not meant to be increased or reduced.

File Equation Table Entry (In JDT)


NAME (FORMAL DESIGNATOR) PHASK NAME LENGTH (BYTES) | DEVICE LENGTH (BYTES)

> NAME-ACTUAL DESIGNATOR (may not be present)

DEVICE/CLASS WAME (may not be present) **FOPTIONS** AOPTIONS #BUFFERS | INIT ALLOC |D |T |S disposition BIT13 DEL BIT14 TEMP BIT15 SRVE RECORD SIZE 1////// # EXTENTS BLOCK FACTOR FILE SIZE FILE CODE OUTPRI | NUMCOPIES REF COUNT | # OF USER LABELS LANG (Native Language Support) LENGTH FORMS=/LABEL= FORMS/LABEL ARRAY

G.01.00 8- 17

Job Line Equation (JLEQ) Entry



G.01.00 8- 18

Job Tables

JLEQ Entry (Cont.)

NUMBER OF BUFFERS 26 BUFFER SIZE IN WORDS 22 27 INSPEED (2 words) 23 OUTSPEED (2 words) 31 İ 25 33 POLL REPEAT POLL DELRY 35 C TRACE INFO 36 LOCAL ID PNTR 30 N 37 REMOTE ID PNTR i 31 SUPLIST PHIR REL TO ORIG OF LEG ENTRY 32 PHONE LIST PHIR 33 42 POLITST PNTR 34 MISC ARRAY PNTR 35 /

Job Control Word Table (JJCW)

Name may be any alpha-numeric string, begin-ning with an alpha, between 1 and 255 char-acters long. NAME SIZE (BYTES) NAME TY 00 = 0K 01 = WARN 10 = FATAL 11 = SYSTEM TY | MODIFIER MODIFIER = VALUE FROM 0 TO 2377777

Job Tables

Aoptions and Foptions Word Breakdown

OPTION WORD 2 (ROPTIONS) OPTION WORD 1 (FOPTIONS) ٥ 0 0 0 0 file type сору no-wait 0 5 0 disallow files multilahelled tane |carriage inhibit buff. exclusive record format 10 dynamic locking 10 |default |designator record 12 12 13 ascii/binary access type 14 15

G.01.00 8- 20

PMASK Word Breakdown

----- PMASK HORD 2 ---- PMASK HORD 1 BLOCK FACTOR FILE TYPE LABELLED TAPE RECSIZE DISPOSITION FRMS MESSAGE USER LABELS NUMBUFFERS I ANG INHIBIT BUFFERING EXCLUSIVE VTERM POINTER ENTRY MULTI-RECORD ACCESS TYPE DYN. LOCKING MAIT, NOMAIT COPY, NOCOPY CARRIAGE CONTROL MULTI RCCESS RECORD FORMAT NUMCOP OUTPRI DEFRULT DESIGNATOR ASCII/BINARY FILECODE итаносі FILESIZE MUMEXTS DEVICE INIT ALLOC NAME


> 1->info present 0->info absent

> > G.01.00 8- 21

UCOP Request Queue (DST#9)

The UCOP Request Queue (URQ) is used to to signal UCOP that a process is requesting process deletion. The URQ is a circular queue using a FIFO algorithm to process requests. When the next available pointer is equal to the next request pointer, then the table is empty. When the next available pointer is (logically) one less than the next request pointer and the request is entered, then the table is full. A full table uill cause System failure (SF1). Thus, the last (logical) entry cannot be used. An entry is added via a call to REQUCOP.

The UCOP Request Queue (MPE IV) was previously used for many functions such as stack expansion, but those functions noved to other areas with MPE V. The only valid entry now is a type 2 entry (process deletion). The original format is retained in the event that more functions are added.



G.01.00 8- 22

Job Tables

UCOP Entry Format

Each entry is 2 words long

CHAPTER 9 RELOCATABLE OBJECT CODE

USL Files Introduction

* USL record length 128 words always. * Layout of doubleword disc addresses



- * Hash links join all entries with the same hash key regardless of type.

 * Linear lists terminate with a zero link
 * Circular lists containing only the list head point directly to thenselves.

 * Single-word disc addresses

9-811	RECORD #	WOF	RD # RECORD
0		8 9	15

Uninitialized fields are reserved for future use and should be set to zero.

Record O and Overall USL File Format

					NOTE:	
٥	LID	0	LOADER ID	S.A.	= Starting	Address
1	NE	1	NR. DIRECTORY ENTRIES			
2	DL	2	DIR. LENGTH			
3	SUMDG	3	TOTAL DIR. GARBAGE			
4	NDG	4	NR. DIR. GARB. ENTRIES			
5	SABDL	5	S.A. BLOCK DATA LIST			
6	SAIPL	6	S.A. INTERRUPT PROC. L	IST		
7	SASL	7	S.A. SEGMENT LIST			
10 11		8	FILE LENGTH			

G.01.00 9- 1

Relocatable Object Code


USL File Format (Cont.)

1	1		
12	SAAD	10	S.A. AVAIL. DIR.
13	ADL	11	RVRIL. DIR. LENGTH
14 15	SAI	12 13	S.A. INFO BLOCK
16 17	ΙL	14 15	INFO BLOCK LENGTH
20 I	SAAI		S.A. AVAIL. INFO
22 23	AIL	18 19	AVAIL. INFO LENGTH
24 25	TOTAL	20 21	TOTAL INFO GARBAGE
26	NIG	22	NR. INFO GARB. ENTRIES
27		23	
30		24	
31	j	25	
32		26	
33		27	
34		28	
35		29	
36		30	
37		31	
40		32	
41		33	HASH LINKS
		127	•
177		124	,

G.01.00 9- 2

Relocatable Object Code


USL Files General Information (Cont.)



NOTE: ALL ADDRESSES IN RECORD O ARE WORD ADDRESSES.

Relocatable Object Code

USL Files General Information (Cont.)



SECONDARY ENTRY POINT ENTRIES

Data Descriptors, Passed Parameters

		10 11 12 13 14	
- - -	- - - - - - -		
HODE	SINGLIGHE	ITPE	1

TYPE	HORDS	CODE
1172	HUNUS	CODE
NULL		0
LOGICAL INTEGER	1	0 1 2 3 4 5 6 7
BYTE	1/2	3
REAL	2	4
DOUBLE Long	1 1/2 2 2 3 4	6
COMPLEX	4	ž
LABEL (SPL) CHARACTER (STRING)	N /0	10
LABEL (FORTRAN)	N/2	11 12
UNIVERSAL (MATCHES ANY TYPE)		13
STRUCTURE		
SIMPLE VARIABLE		0
POINTER		0 1 2 3
array Procedure		2
		3
MODE		
NULL		0
VALUE Reference		1
NAME		0 1 2 3
		-

NOTE: A descriptor of O results in an automatic match.

Pascal sets the high order bit in the parameter type descriptor when it is generating hashed values. The remaining 15 bits are based on a hash of the types of the parameter. Only the Pascal compiler can compute the value, and the SEGMENTER must match the whole 16 bit value.

G.01.00 9- 5

Relocatable Object Code

Clarification Notes on Entry Types 2 and 4 With Respect to SPL and FORTRAN

*ENTRY TYPE 2 SPL 0.8.	**ENTRY TYPE 4 SPL PROC	*ENTRY TYPE 2 FORTRAN MAIN	**ENTRY TYPE 4 FORTRAN SUB.
TPD8	0	0	0
1,5 TSDB	1 TSDB	1,2,3,4 TSDB	1,2,3,4 TSD8
NUPUST	HUPUST	NUPUST	NUPUST
5 ROSUM	NUC	MUN	MUD

WHERE: TPDB = Total primary DB length in words
TSDB = Total secondary DB length in words
NMPUST = Number of words in "TRRCE" array
NMSDB = Number of words in secondary DB array
NMU = Number of words in own array
NMU = Number of words in data array

Notes: 1. Does not include the length of the STLT
2. Does not include the length of the FLUT
3. Does not include the length of any common array
4. Includes the length of any DB-allocated format array
5. Rre not necessarily equal

In general TPDB and TSDB are summations of storage allocated in the global area of the program's data segment. They are not, however, complete since the compilers are not aware of all storage actually allocated! The STLT and FLUT are examples of this since these tables are constructed by the segmenter. Common arrays also present a problem since their inclusion in TPDB and TSDB might cause their storage requirements to be counted more than once.

Relocatable Object Code

Entry Type 0

GARBAGE

0 1		10 11 15					_			
1///1	NH	1	0	Ī	MH -	Number block	of	Hords	īn	this
	GARBAG	Æ								

Entry Type 1

SEGMENT NAME

0 1	7 8	10 11	15	
1//1	NLI	1	1	NU - Numbe block
I IA 1////	H L	Chari	<u> </u>	HL - Hash entry hash
(VAR	CABLE # CHAR	. SEE NC)		A - Activ O if a 1 if a (init
CHAR.	NC 1///	///////////////////////////////////////	///I I	Note: An in po:
111	SUBL		ī	NC - Numbe

per of words in entry

h link — points to next ry having the same h code

vity bit active inactive tialize to 0)

n inactive segment uplies that all entry pints are inactive

SUBL | NC - Number of characters in name. Max is 16

CHAR. 1 - First character in variable field CHAR. NC - Last character in variable field SEGL - Segment link - points to next segment name

next segment name entry SUBL - Subprogram link - points to next entry having the same segment name L - Last entry in list O if not last 1 if last

G.01.00 9- 6

10 11 15

Relocatable Object Code

Entry Type 2

OUTER BLOCK 0 1 2 3 4 5 6 7 8

1//1	NI		I	2			
1	Н	L		ı			
I A I	C I /// NC		CHAR 1	١			
	(VARIABLE #	CHAR. SE	E NC)				
1	CHAR NC	1/////	//////	/////\			
ILI	SU	BL		1			
	SE	CL		ı			
1	SS	R		I			
	SAC RELATIVE TO SAI (SEE RECORD 0)						
F	u j nu	C		Ī			
	S	E		I			
1	TP	DB		Ī			
	TS	DB		I			
1	NUP	UST		I			
1	NUD/	NUSDB		1			
1	N	H		I			
	SA RELATIVE TO SA		RECORD C)			
	HD	1					

Entry Type 2 (Cont.)

<u>:</u>	
HDU	1
:	
T NH	1
SAH	
HDH	I
· :	
HDH	1

- NW Number of words in entry block.
- HL Hash link points to next entry with same hash code.
- A Activity bit. O if active, 1 if inactive outer block.
- C Callability bit set if entry point is uncallable.
- I Privilege mode bit set if program unit is to be executed in Privilege mode..
- NC Number of characters in name. Max is 16.
- CHAR. 1 First character in variable field.
- CHAR. NC Last character in variable field.
- L Last entry in list. O if not last 1 if last

G.01.00 9- 9

Relocatable Object Code

Entry Type 2 (Cont.)

- SUBL Subprogram link points to next entry Entry having the same segment name.
- SECL Secondary entry point list link.
- SSA Program unit starting PB address.
- SRC Starting 8FILE9 address of code module
- F Set if fatal error
- W Set if nonfatal error
- NWC Number of words in code module.
- SE Stack size estimate
- TPDB Total number of words of primary DB to be allocated
- TSDB Total number of words of secondary DB to be allocated.
- NWPUST Number of words in trace array (PUST)
- NND Number of words in data array (FORTRAN)
- (FORTRAN)
- NUSDB Mumber of words in secondary DB array (SPL) T - Terminating bit - set if last set of headers in entry
- NH Number of headers
- SRH Starting address of header (relative to SRI)
- HDW Header (pointer)

G.01.00 9- 10

Relocatable Object Code

Entry Type 3

OUTER BLOCK - SECONDARY ENTRY POINT

0	1	2	3	4	5	6	7	8	3	10	11		15
1//1					H	4					١	3	
I						н	L						<u> </u>
R	1 0	1/	/1/	71	1	NC		ı		CHA	R 1		
	(VARIABLE * CHAR.SEE NC)												
Ī	(HAR	NC	:			1/	///	//	/////	///	///	///\
L	1					SE	CL						1
l						SS	A						

Entry Type 4

PROCEDURE

			3 4567	8		10			
1//		1		NLI				4	
				HL					
ĮR	0	I	H NC		CHAR.1				
 			(VARIA	BLE # CHF	IR. SEE	NC)		
1	CHAR	. NC	I	////////	//////	///	/////	////	///
۱L	ı		S	UB L	 -				
۱L	ı		S	ECL					
,			9	30					

Relocatable Object Code

Entry Type 4 (Cont.)

	_
SAC	-
[F [W] NHC	Ī
SE	ŀ
TPDB	Ī
TSDB	Ī
NUPUST	Ī
NUD/NUO	1
P NP CN	I
] TN	I
PARM.1	1
(VARIABLE # OF PARMS. SEE CM)	
PARM. NP	Ī
T NH	I
SAH	
HDW	ı
:	
HDW	ı
:	
į ETC	

Entry Type 4 (Cont.)

MW — Mumber of words in entry block
ML — Hash link — points to next entry with same hash code
R — Rctivity bit. O if active, 1 if inactive entry point
C — Callability bit set if entry point is uncallable
I — Privilege mode bit. Set if procedure is to be executed in privilege mode.
H — Hidden entry point. Set if entry point will not be in
library directory.
MC — Number of characters in name. Hax is 16.
CHORN — First character in variable field.
CHORN — Last character in variable field.
L — Last entry in list
O if not last
1 if last
SUBL — Subprogram link. Points to next entry having the same segment
Name SUBL - Subprogram link. Points to next entry having the same segment have

SECL - Secondary entry point list link.
SSR - Unit starting PB address
SSC - Starting (file) address of code module
F - Set if fatal error
H - Set if nonfatal error
H - Set if nonfatal error
H - Set if anotes in code module
SE - Stack size estimate
TPDB - Total number of words of primary DB to be allocated.
TSDB - Total number of words of secondary DB to be allocated.
HAUD - Number of words in tode array (PUST)
HAUD - Number of words in data array (FORTRAM)
HAUD - Number of words in own array (SPL)
P - Parameter checker
On o checking. (Implies MP undefined, FN and PRRM's absent)
Of check procedure type. (Implies MP is undefined and PRRM's absent)
10 check procedure type and number of PRRM's (implies PRRM's absent)
10 check procedure type and number of PARM's (implies PARM's absent)
11 check procedure type, number of PARM's and type of each PARM.
NP - Mumber of PARM's
CN - Character count of PARM's
TN - Terminating bit. Set if last set of headers in entry.
NH - Number of headers
SRH - Starting address of header
NDW - Header (pointer)

G.01.00 9- 13

Relocatable Object Code

Entry Type 5

PROCEDURE - SECONDARY ENTRY POINT

0	1	2	3	4	5	6	7	8		10	11	l 	15
111	//I NH I							5	1				
								HL					-
Al	С	1//	H	Ī	N	C	١		c	HAR		1	-
((VARIABLE #CHAR. SEE NC)												
	C	HAR	. N	iC				1/	///	///	//	//////	7
LI	L SECL							-					
					SSI	A							-

NW - Number of words in entry block

HL - Hash link - points to next entry with same hash code

A - Activity bit. O if active, 1 if inactive entry point

C - Callability bit set if entry point is uncallable.

H - Hidden entry point set if entry point will not be in library directory

NC - number of characters in name, max is 16

CHAR 1 - First character in variable field.

L - Last entry in list O if not last 1 if last

SECL - Secondary entry point list link

SSR - Unit starting PB' address

G.01.00 9- 14

Relocatable Object Code

Entry Type 6

INTERRUPT PROCEDURE

0 1 2 3 4567 8	10 11	15
1//1 NU	6	
HL I		
A IT // NC	CHAR.1	i
(VARIABLE # CHAR.	SEE NC)	
A IT // NC	CHAR.1	l
(VARIABLE # CHAR.	SEE NC)	
! CHAR. NC /////	///////	////\
l IPL		
i DBS		ı
I SSA		I
SAC		
IF W MMC		ı
[T] NH		1
SAH		
1 HDW		Ī
:		-
l HDW		Ī

Relocatable Object Code

Entry Type 6 (Cont.)

NU - Number of words in entry block

HL - Hash link. Points to next entry with same hash code

A - Activity bit. O if active, 1 if inactive entry.

II - Interrupt procedure type number

NC - Number of characters in name (maximum is 16)

CHAR 1 - First character in variable field.

CHAR NC- Last Character in variable field

IPL - Interrupt procedure link

Number of words of DB storage required.

SSA - Unit starting PB' address

SAC -Starting (file) address of code

Set if fatal error

W - Set if nonfatal error

NWC - Number of words in code module

Terminating bit. Set if last set of headers in entry.

Number of headers

SAH - Starting address of header.

HDW - Header (pointer)

Entry Type 7

BLOCK DATA

0	1 2 3 456	7 8	10	11	15				
1///	NII	-1-			7				
		HL							
A	F W /// NC	1	C	HAR.1					
! 	CHAR.NC		///////////////////////////////////////	,,,,,,	,,,,,,,				
! !		BDL							
! i		CAL							
				 AR. 1					
1///	///////////// NC		LN:	HK.1 					
 	COMMON	ARR •	RY NAME						
1	CHAR. NC	1/	////////	//////	11/1///				
1	l	NH							
 		SAH							
1		HDN							
 	:								
 I	HON								
		:							

G.01.00 9- 17

Entry Type 7 (Cont.)

ŀ		CAL		
1////	77777777	NC	CHAR.1	
	connoi	N ARRAY	NAME	
Ī	CHAR.NC	1///	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	/////
1		NH		
		SAH		
1		HDN		
		ETC		

- Number of words in block NLI
- Hash link. Points to next entry with same hash code.
- Activity bit. O if active, 1 if inactive
- Set if fatal error.
- Set if nonfatal error.

CHAR 1- First character in variable field.

CHAR NC-Last character in variable field.

BDL - Block data link

CAL - Common array length

- Terminating bit. Set if last set of headers in entry.
- Number of headers.
- SAH Starting address of headers.
- HDW Header (pointer)

G.01.00 9- 18

Relocatable Object Code

Entry Type 8

PROCEDURE - SECONDARY ENTRY POINT

	1 ,2 ;			, 8	10	11	15
///			NU	-1			8
HL							
R	C1//I	H	NC	ı	CHR	₹. 1	
(VARIABLE #CHAR. SEE NC)							
	CHAR.	NC	ı	1111	//////	////	//////
LI			SEC	L			
			SSF	1			
P		NP			-1	CH	
			1	H			
PARM. 1							
	:						
	PARN. NP						

- NN NUMBER OF WORDS IN ENTRY BLOCK
- HL HASH LINK POINTS TO NEXT ENTRY WITH SAME HASH CODE
- A ACTIVITY BIT. O IF ACTIVE, 1 IF INACTIVE ENTRY
- C CALLABILITY BIT SET IF ENTRY POINT IS UNCALLABLE
- H HIDDEN ENTRY POINT. SET IF ENTRY POINT WILL NOT BE IN LIBRARY DIRECTORY
- NC NUMBER OF CHARACTERS IN NAME. MAX IS 16

Relocatable Object Code

Entry Type 8 (Cont.)

CHAR 1 - FIRST CHARACTER IN VARIABLE LIST

CHAR NC - LAST CHARACTER IN VARIABLE

L - LAST ENTRY IN LIST O IF NOT LAST 1 IF LAST

SECL - SECONDARY ENTRY POINT LIST LINK

SSA - UNIT STARTING PB' ADDRESS

- P PARM CHECKER
 OO NO CHECKING (IMPLIES NP UNDEFINED,
 IN OND PARMS ABSENT)
 O1 CHECK PROCEDURE TYPE (IMPLIES NP
 IS UNDEFINED AND PARMS ABSENT)
 10 CHECK PROCEDURE TYPE AND NUMBER
 OF PARMS. (IMPLIES PARMS ABSENT)
 11 CHECK PROCEDURE TYPE, NUMBER OF
 PARMS AND TYPE OF PARM.
- NP NUMBER OF PARMS
- CN CHARACTER COUNT OF PARMS
- TN PROCEDURE TYPE



EACH ENTRY (EXCEPT SECONDARY ENTRY POINT ENTRIES) MAY DESCRIBE N> 0 SETS OF HEADERS. THE HEADERS IN EACH SET INUST BE CONTINUOUS AND IN THE SAME ORDER AS THE HOW LIST DESCRIBING THE SET.

THE CODE HODULE MAY BE PLACED IN ANY POSITION IN A HEADER SET. NOTE THAT IF THE CODE MODULE IS AT THE BEGINNING OF A SET, SAC = SAH.

IF THE ENTRY HAS NO HEADER SET, THEN NH, SAH SEQUENCE IS ABSENT.

G.01.00 9- 21

Relocatable Object Code


Header Type O

GARBAGE

0 1		10	11	15
///	MM		0	
	GARBAGE			

Header Type 1

PCRLs



PBR - PB' ADDRESS OF LINKED LIST OF PCAL INSTRUCTIONS TO BE REPRIRED-LOWER 14 BITS USED AS MEGATIVE DISP. - BIT O SET MERMS THAT THE WORD IS NOT A PCAL INSTRUCTION, BUT A POINTER TO A SST LABEL OF ''EXTERNAL'' FORMAT - R LINK OF O TERMINATES THE LIST - BIT I SET MERMS THAT THE WORD IS TO BE INITIALIZED WITH THE PB ADDRESS OF THE PROCEDURE.

G.01.00 9- 22

Relocatable Object Code

Header Type 2

PB ADDRESSES

0 1		10	11	15
 	MII			2
	PBA			
!	:			
 	PBA			

PBA - PB' ADDRESS OF PB ADDRESS TO BE CORRECTED

Header Type 3

OWN/DATA VARIABLES

0	1 10	11 15
//	ñ	3
81	PBA	
	,	
1	:	
BI	PBA	

PBA - PB' ADDRESS OF OWN VARIABLE POINTER TO BE CORRECTED

Relocatable Object Code

Header Type 4

DSDB/OHN/DATA/VALUES

0 1	10	11	15
///	NU	1	4
	D		
8	IN		
	INITIAL VAI	MES	

LD - LDGICAL WORD DISPLACEMENT
IN OWN ARRAY FOR INITIAL VALUES
B - BYTE BIT-SET IMPLIES THAT LD IS
TYPE BYTE AND THAT THE FIRST
WORD OF THE INITIAL VALUE BLOCK
IS A COUNT OF THE NUMBER OF BYTES
IN THE INITIAL VALUE BLOCK
IN - INTECRATION NUMBER - AUMBER OF
TIMES THE BLOCK OF INITIAL VALUE
IS TO APPEAR IN THE SECONDARY BD 1-NO DUPLICATION,
2->DUPLICATION, ETC

Header Type 5

PUST

0 1		10	11	15
//	NU		!	5
	PBA			
	INITIAL VA	.UES		

PBR - PB' ADDRESS OF LINKED LIST OF POINTERS TO BE INITIALIZED WITH DB ADDRESS OF PUST (SAME LIST FORMAT AS FOR FORMAT STRINGS) A PBA of -1 INDICATES NO FIX-UPS.

NOTE: ALL REFERENCES TO THE PUST INCLUDE THE FOUR-HORD HEADER THAT IS APPENDED BY THE SECHENTER. THESE MORDS ARE NOT PRESENT IN THE HEADER; THEY ARE AUTOMATICALLY ALLOCATED AND INTITALIZED BY THE SEGMENTER.


Header Type 6

GLOBAL VARIABLES

0 1	7,8 10,11 15,
// NH	6
	TN
DBA	/////// NC
CHAR.1	CHAR. 2
<u> </u>	:
CHAR. NC	1//////////////////////////////////////

Header Type 7

EXTERNAL VARIABLES



- PBR-PB' address of linked lists H-PB' address of linked lists of instructions to be repaired; lower 8 bits of inst. used as neg. displacement to next instruction; a link of 0 terminates the list.
- -Monitored variable bit;set if variable is being monitored by debug.
- DA -Logical word disp. in PUST; lower 8 bits of word will be init. with prim.DB address of variable;DA is present if M=1.

NOTE:PBA of -1 implies null list

G.01.00 9- 25

Relocatable Object Code

Header Type 8

PRIMARY DB

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 - - - - - - - - - - - -
:
U U U U U ////////////////////////
INITIAL VALUES

U - ADDRESS BITS
OO IF NO ADDRESS
O1 IF NO ADDRESS
10 IF MORD ADDRESS
11 IF BORD ADDRESS IN SECONDARY DB
11 IF BYTE ADDRESS IN SECONDARY DB

N - NUPDB

NOTE: INITIAL ADDRESSES THAT ARE SECONDARY DB ADDRESSES ARE O


RELATIVE (I.E., THEY ARE LOGICAL DISPLACEMENTS IN SECONDARY DB).

G.01.00 9- 26

Relocatable Object Code

Header Type 9

COMMON VARIABLES



Relocatable Object Code

Header Type 9 (Cont.)

NUC - NUMBER OF HORDS IN COMMON ARRAY

NC - NUMBER OF CHARACTERS IN COMMON NAME- IF BLANK COMMON 4 COM'

- LOGICAL WORD DISP. IN PUST - LOWER 8 BITS OF WORD WILL BE INIT. WITH PRIM. DB ADDRESS OF VARIABLE - NOTE DA IS PRESENT IF M = 1

- BYTE BIT O IF THE PRIMARY DB POINTER TO BE RILLOCATED RAND INITIALIZED AND LD RAE OF TYPE WORD 1 IF TYPE BYTE

- MONITORED VARIABLE BIT - SET IF VARIABLE IS BEING MONITORED BY

NL - NUMBER OF ADDRESS LISTS FOR VARIABLE

LD - LOGICAL DISPLACEMENT OF VARIABLE IN COMMON ARRAY

PBR - PB' ADDRESS OF LINKED LISTS OF INSTRUCTIONS TO BE REPRIRED LOUER 8 BITS USED AS NEGATIVE DISPLACEMENT TO NEXT INSTRUCTION A LINK OF O TERMINATES THE LIST


PBR = -1 INDICATES NO FIX-UPS

LID

O LOADER ID

Header Type 10

LOGICAL UNITS



BIT MAP - BIT MAP OF LOGICAL UNITS REFERENCED; BIT 0 CORRESPONDS TO LU 0, ETC. (1 LESS THAM OR EQUAL TO LU LESS THAM OR EQUAL TO 99)

Header Type 11

FORMAT STRING

0 		10	11	15
	W		11	
	PBA			
	NC			
CHAR. 1	ı	CHAR.	2	
	•			
	:			-
CHAR. NC	1//	//////	/////	77

- PB' ADDRESS OF LIMKED LIST OF POINTERS TO BE INITIALIZED LOWER 14 BITS OF WORD USED AS NEGATIVE DISTRIBUTED TO MEXT POINTER - BIT O SET MEANS THAT THE POINTER IS TO BE TYPE BYTE - A LINK OF O TERMINATES THE LIST.

G.01.00 9- 29

HL 94 177

Relocatable Object Code Relocatable Object Code

Storage Management

FILE SPACE IS MANAGED IN TERMS OF 32 WORDS BLOCKS (4 BLOCKS PER 128 WORD RECORD).

FREE SPACE (BLOCKS) IS ACCOUNTED FOR IN A BIT MAP, WHICH IS PARTITIONED INTO RECORDS (2K BLOCKS PER SECTION). A O INDICATES THAT A BLOCK IS USED, A 1 INDICATES THAT IT IS FREE.

FILE SPACE IS ALSO PARTITIONED INTO 512 RECORD SECTIONS (64 MAX. SECTIONS, 2K BLOCKS PER SECTION, 1 MAP PER SECTION). THE NUMBER OF SECTIONS IN A FILE IS MS=(FL+51) & LSR(9). THE FIRST MS RECORDS FOLLOWING RECORD O (RECORDS 1 TO MS) MRR RESERVED FOR THE SECTION MAPS.

A COMPLETE FILE ADDRESS WOULD HAVE THE FOLLOWING CONFIGURATION:

0 1 2 3 4 5		16 26	27 31
	SECTION		DISPLEMT

FILE (WORD) ADDRESS DOUBLE WORD

FL FILE LENGTH (IN RECORDS) RECORD 0 NS 2 NR. SECTIONS SAXL S.A. EXTERNAL SET LIST FREE MAP 10 11 12 10 NS FREE MAP

RL File Format

NOTE: UNINITIALIZED FIELDS ARE RESERVED FOR FUTURE USE AND SHOULD BE ZERO. NS+1 İAVATLABLE

33 S.A. HASH LIST O

127 S.A. HASH LIST 94

G.01.00 9- 30

Entry Point Directory

LINK	>>	LINK	>>	0
USED		USED	l	USED
i				!
!				
i				
1//////////////////////////////////////		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		\//////
	USED	USED	USED USED	USED

THE DIRECTORY IS PARTITIONED INTO 95 HASH LISTS (SAME HASH FUNCTION AS USL); EACH HASH LIST IS A LINKED LIST OF RECORDS.

EACH RECORD CONTRINS A SUCCESSOR LINK (RECORD #) AND A USED SPACE COUNT. A LINK OF O TERMINATES A LIST. WHEN A RECORD IS VOID OF ENTRIES (USED=2), ITS SPACE IS RETURNED TO THE FREE STORAGE AREA.

Typical Directory Entry

0 1 2 3 4567 8 S U I /// NC CHAR. 1 CHAR. NC S.A. INFO BLOCK S.A. ENTRY F | 4 | NH CODE LC TN PARM. 1. PARM. NP

- S SECONDARY ENTRY POINT BIT SET IF THE ENTRY POINT WAS ORIGINALLY A SECONDARY ENTRY POINT.
- U UNCALLABLE BIT SET IF ENTRY POINT IS UNCALLABLE.
- I PRIVILEGED MODE BIT SET IF CODE MODULE IS TO BE RUN IN PRIVILEGE MODE.
- LC is (0:2)...Level of Checking
 0 = No checking
 1 >= Check for procedure type
 2 >= Check for # parameters
 3 >= Check for parameter type
 NP is (2:6) is # parameters

6.01.00 9- 33

NW INFO NH CODE # ENTRY POINTS CODE MODULE

Procedure Information Block

HHC EXTH LINK TPDB TSDB NUSCB NWİ HEADER HEADER HEADER -1

ALL HEADERS FOR THE PROCEDURE ARE APPENDED TO THE INFO BLOCK. THE HEADER SETS (EXTERNAL LISTS) ARE LINKED BY INCREASING FILE RODRESS; A LINK OF X1777777777D TERMINATES THE LIST.

G.01.00 9- 34

Relocatable Object Code

Headers

	2 3 -		10 11	15
/// 		NU:	 	1
FIW	1 6	IN CODE		İ
 	S.A.	INFO BLOC	к	İ
	\$.	A. ENTRY		ļ
		PBA		
SIU	I ///	NC	CHAR. 1	
		•		
	CHAR. NC	1///	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	//////
P	I NP	I	CN	
		TN		
		PARM. 1		
		;		
		PARM. NP		i

- F SET IF FATAL ERROR
 W SET IF NON-FATAL ERROR
 S SATISFIED BIT SET IF EXTERNAL IS
 SATISFIED WITHIN RL.
 U UNCALLABLE BIT
 I PRIVILEGED BIT

ALL HEADERS ARE THE SAME AS IN A USL EXCEPT FOR THE PCAL HEADER.

Prepared Object Code


CHAPTER 10 PREPARED OBJECT CODE

Program File Format

_		_	
١٥	FLAGS	0	
1	NS	1	NUMBER OF CODE SEGMENTS
2	GS	2	GLOBAL SIZE (DB TO QI) IN WORDS
3	SAG	3	GLOBAL AREA RECORD #
4	SAS		SEGMENT SET RECORD # (EACH SEG. STARTS IN NEW RECORD)
5	ISS	5	INITIAL STACK SIZE IN WORDS
6	IDLS	6	INITIAL DL SIZE IN WORDS
7	MAXD	7	MAX. DATA SEGMENT SIZE (DL TO Z) IN WORDS
10	SAE	8	ENTRY POINT LIST RECORD #
11	SSEG	9	STARTING SEGMENT #
12	SADR	10	PRIN. ENTRY PT PB RDDRESS
13	SASTLT	11	DB ADR. OF STLT (-1 IF NO STLT) (STLT=Segment Length Table)
14	SAFLUT	12	OB ADR. OF FLUT (-1 IF NO FLUT)
15	SAX	13	EXTERNAL LIST RECORD #
16	1122	14	PRIN. ENTRY PT SST #
17	SATC	15	STARTING ADDRESS OF TRAPCOM'
20	SAPMAP	16	STARTING RECORD OF PHAP INFO
21	SASI	17	STARTING RECORD OF SYMBOLIC ITEMS
22	FLAGS2	19	
23	CKSUM	19	TOTAL CHECKSUM OF ALL SEGMENTS
24		20	NOTE : ALL UNUSED WORD ARE RESERVED FOR
25		21	FUTURE USE AND SHOULD BE SET TO ZERO.
26		22	

G.01.00 10- 1

Prepared Object Code



Prepared Object Code

Flags

- F FATAL ERROR IN PROGRAM
 N NON-FATAL ERROR IN PROGRAM
 Z ZERO UNIT OL AREA
 P SET IF ANY SEG IS PRIVILEGED MODE (IF NOT SET NORMAL=
 NONPRIV MODE)

CAPABILITIES

```
BATCH ACCESS (9) [BA]
                             INTERACTIVE ACCESS (8) [IA]
                               PRIVILEGED MODE (7) [PM]
ACCESS TO
GENERAL
RESOURCES
                                    MULTIPLE RINS (4) [MR]
                               EXTRA DATA SEGMENT (2) [DS]
                                PROCESS HANDLING (1) [PH]
```

Prepared Object Code

- T PATCH AREA EXISTED IN ALL CODE SEGMENTS K CHECKSUM VALID

CST Remapping Array

CONTAINS THE LAST CST NUMBERS ASSIGNED TO THE SEGMENTS; INDEXED BY SEGMENT NUMBER. WHEN A PROGRAM FILE IS PREPARED, THE ARRAY IS INITIALIZED TO 0, 1...,N. THIS ARRAY IS USED TO RE-ESTABLISH INTRA-PROGRAM LINKAGE WHEN THE PROGRAM IS LORDED.


Segment Descriptor Array

CONTAINS THE SEGMENT LENGTH AND A FLAG INDICATING IF THE SEGMENT IS 10 BE LOADED IN PRIV. MODE. INDEXED BY SEGMENT NUMBER. ALL SEGMENTS BEGIN ON A RECORD BOUNDARY. THE NUMBER OF RECORDS FOR A GIVEN SEGMENT IS (SL + 127) & LSR(7). THE RECORD NUMBER, SAS, OF SEGMENT N IS

SAS:=0 FOR I=0 TO N-1 BEGIN SAS:=SAS + (SL(I) + 127)&LSR(7) END

Global Area Format

A SET OF RECORDS CONTRINING THE INITIAL VALUES FOR THE GLOBAL AREA OF THE DATA SEGMENT. THIS SET BEGINS AT RECORD SAG (WORD 3) AND CONSISTS OF (GS + 127) & LSR(7) RECORDS.



PMAP Records

Type O Segment PMAP Record

0123456789012345 O| NC | char1 char NC STT LEN | SEG NUM SEG LENGTH

Type 1 Procedure PMAP Record

0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 1| NC | char 1 char NC |///////////// SA OF CODE CODE LENGTH PRIMARY ENTRY POINT ADDR COBOL TOOL BOX ID TOOL BOX PROCEDURE ID

G.01.00 10- 9

SL File Format

Prepared Object Code

Type 2 Secondary Entry PMAP Record

0123456789012345 2| NC | char 1 char NC SECONDARY ENTRY POINT ADDR NUMBER OF ENTRY POINTS

H : HIDDEN ENTRY FLAG

G.01.00 10- 10

Prepared Object Code

O LID O 11 FL 11 FILE LENGTH (IN RECORDS) EL 2 EXTENT LENGTH (IN RECORDS) 4 NSEG 4 # SEGMENTS FRTL 7 S.A. OF FREE R.T. ENTRY LIST (-1 IF NONE) 11 NRT 9 # REFERENCE TABLE ENTRIES 12 10 13| NS |11 # SECTIONS 12 41 HLO 33 NOTE: HOPE AND UNINITIALIZED FIELDS ARE THE HIGH TELES ARE THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIGH THE HIG

G.01.00 10- 11

Prepared Object Code

SL File Format (Cont.)

RECORD <--- REFERENCE TABLE POINTERS FREE MAP FREE MAP NS-1 NS+2-----RVAILABLE

Storage Management


FILE SPACE IS MANAGED IN TERMS OF 128 WORD BLOCKS (1 BLOCK PER 128 WORD RECORD).

FREE SPACE (BLOCKS) IS RCCOUNTED FOR IN A BIT MAP, WHICH IS PARTITIONED INTO RECORDS (2K BLOCKS PER SECTION). A O INDICATES THAT A BLOCK IS USED; A 1 INDICATES THAT IT IS FREE.

FILE SPACE IS ALSO PARTITIONED INTO 2048 RECORD SECTIONS (16 MRX. SECTIONS, 2K BLOCKS PER SECTION 1 MRP PER SECTION). THE NUMBER OF SECTIONS IN A FILE IS MS=(FL + 2047) & LSR(7). THE FIRST MS RECORDS FOLLOWING RECORDS O, 1 (RECORDS 2 TO MS+1) ARE RESERVED FOR THE SECTION MRPS.

IF THE SECTION MAPS SPECIFY MORE SPACE THAN IS POTENTIALLY AVAILABLE, THOSE RECORDS BEYOND FLIMIT ARE MARKED AS "USED".

Entry Point Directory



THE DIRECTORY IS PARTITIONED INTO 95 HRSH LISTS (SAME HASH FUNCTION AS USL); ERCH HASH LIST IS A LIMKED LIST OF RECORDS.

EACH RECORD CONTRINS A SUCCESSOR LINK (RECORD #) AND A USED SPACE COUNT. A LINK OF O TERMINATES A LIST. WHEN A RECORD IS VOID OF ENTRIES (USED=2), ITS SPACE IS RETURNED TO THE FREE STORAGE AREA.

THE HASH LIST HEAD POINTERS (HL IN THE DIAGRAM ABOVE) ARE IN RECORD O WORDS 241 TO 2177.

G.01.00 10- 13

Prepared Object Code

Code Segment Linkage Structure



EACH CODE SECHENT OCCUPIES AN INTEGRAL MUMBER OF RECORDS. THIS BLOCK OF INFORMATION CAN BE SUBDIVIDED INTO THREE TABLES: THE CODE SEGMENT PROPER, AN STI SEGMENT MAP ARRAY, AND AN EXTERNAL LIST.

STT MAP ARRAY

A 1 BYTE X 256 BYTE ARRAY. IT IS INDEXED BY STT NUMBER AND RETURNS (IF THE STT CORRESPONDS TO AN EXTERNAL OF THE SEGMENT) THE SEGMENT WUMBER OF THE EXTERNAL HOW 255 OTHERUISE. THIS ARRAY IS USED WHENEVER THE SEGMENT IS LOADED AND IS UPDATED WHENEVER THE SL IS BOUND BY THE SEGMENTER.

A SYMBOLIC LIST OF THE EXTERNALS OF THE SEGMENT. ERCH ENTRY CONTRINS IMFORMATION ABOUT THE EXTERNAL: PARAMETER CHECKING LEVEL AND PARAMETER MATCHING IMFORMATION, AND THE SEGMENT MUMBER AND STT NUMBER IF THE EXTERNAL IS SATISFIED UITHIN THE SL.

Typical Directory Entry

٥	1		2	3	4	5	6	7	8	9	10	11	12	13	14	15
///	U	1	///	P	1	NC						CHR	1			
									•							
		(CHAF	NC.					1///	////	///	////	////	////	////	////
			STT	#					l			SEG +)			
LC	;	1			HP				i			CN				
								Ţ	N							
								PAR	1 1							
		•														

PARM NP

LC is (0:2)...Level of Checking
0 = No checking
1 >= Check for procedure type
2 >= Check for # parameters
3 >= Check for parameter type
NP is (2:6) is # parameters

- P O= Not permanently allocated 1= Permanently allocated
- Uncallable bit set if entry point is uncallable.

6.01.00 10- 14

Prepared Object Code

Code Segment Structure (Cont.)

0

0 1 2 3 4567 8 15	
- - - -	
CODE SEGMENT	
STT MAP ARRAY	
S / / / NC CHAR. 1	S - SATISFIED BIT - SET IF EXTERNAL IS SATISFIED WITHIN SL
	TO OUT TO MILITIN OF
CHAR. NC /////////	
STT # SEG. #	
P NP CN	
TN	
PARM. 1	
PARM. NP	

G.01.00

G.01.00 10- 16

EXTERNAL LIST TERMINATOR

Reference Table Structure


FOR EACH SEGMENT THERE IS A REFERENCE TABLE ENTRY OF 32 WORDS. THE REFERENCE TABLE ENTRIES ARE PRICKED FOUR TO A RECORD. THE RECORDS CONTAINING THE REFERENCE TABLE ENTRIES ARE LISTED IN RECORD 1. THE RECORD CONTAINING REFERENCE TABLE ENTRY N IS REC 1 (N.(0: 14)); THE FIRST WORD OF THE ENTRY IS REFTAB (N.(14: 2) & LSL (5)).

WHEN A SEGMENT IS DELETED, THE REFERENCE TABLE ENTRY CORRESPONDING TO THE SEGMENT IS RELEASED. THESE FREE ENTRIES ARE LINKED TOGETHER IN A LIST; THE SEGMENT # IS USED AS A LINK AND IS PLACED IN THE FIRST WORD OF THE ENTRY.

WHEN A SECHENT IS RODED IT IS ASSIGNED A SECHENT NUMBER (O LESS THAN/EQUAL TO N LESS THAN/EQUAL TO 254); THE NUMBER IS THAT OF THE FIRST FREE REFERENCE TRBLE ENTRY, OR, IF NONE ARE FREE, THE NEXT AVAILABLE REFERENCE TABLE ENTRY (CRUSING SPACE ALLOCATION FOR THE ENTRY).

Reference Table (256 Maximum Entries)

TYPICAL ENTRY



G.01.00

G.01.00 10- 17

Prepared Object Code

Code Segment With Patch Area

PATCH AREA

Patch Area

	_	
SEGMENT NAME	8-WORD	SEGMENT NAME
//	1-WORD	UNUSED
CHECKSUM	1-WORD	CHECKSUM
PREP TIME	2-WORD	PREP TIME
PRTCH TIME	2-MORD	PATCH TIME
PATCH AREA	 	
PALEN	 1-Word 	PATCH AREA LENGT
STT	 -	

Prepared Object Code

PMRP Information



PMRP Type Table

PTTL !	TYPE TABLE LENGTH
LPRO	LENGTH OF PMAP RECORD TYPE O
LPR1	LENGTH OF PMAP RECORD TYPE 1
LPRn	LENGTH OF PMAP RECORD TYPE n

NOTE : n = PTTL - 2

}	Prepared Object Code	Prepared Object Code
Type © Segment PHRP Record 0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 O NC char 1	Prepared Object Code	Type 2 Secondary Entry PMRP Record O 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5
G.01.00 10- 21		G.01.00 10- 22

CHAPTER 11 LORDER


MPE Loader

The loader is a system process which will do loads sequentially. If a process needs code to be loaded, it will get the load process' SIR, fill loader communication table, and then awake the loader. Upon completion, the loader will return its status through the loader communication table, and then activate the waiting process.

Loader Segment Table Overview

Loader Segnent Table consists of two DST's. The main one is DST X22 (LST). The other DST (XLST) has its DST number stored in SYSGLOB X226.


LST Overview



G.01.00 11- 1

Loader

XLST Overieu



The above DSI's has exactly the same primary DB area so that directory entry handling procedures can be used on both DSI'S. XLSI is the LSI extension and used to store the extension entry only. When an extension entry is needed, it is copied into the LSI to eliminate frequent EXCHANGEDD. Note that XLSI is capable for any types of entries. It is used for extension entry only for now. RISO, some of the primary DB's in the XLSI are not used. They are there just for the consistency.

G.01.00 11- 2

Loader

Loader Segment Table Primary DB

0	@DIR	16	20
1	DIR LEN	17	SP
2	@LCT	20	20
3	ENTP	21	SR
4	ENTP1	22	\$\$
5	ENTP2	23	\$T
6	ENTP3	24	HDFULINK(TYPE 0)
7	@SBUF		:
10	\$1		HDFWLINK(TYPE 8)
11	ររ		HDBKLINK(TYPE 0)
12	SK		:
13	\$L		HDBKLINK(TYPE 8)
14	SH		LCT
15	SN		";
		1	

ENTPh : POINTERS POINT TO THE CURRENT ACCESSED ENTRY.
SBUF : UTILITY BUFFER. USUALLY CONTAINS PROGRAM FILE RECORD
O INFORMATION.
SI ST : UTILITY DB RELATIVE VARIABLES.
HOFULLINKS : HEAD OF FORWARD LINK FOR EACH TYPE.
HDBKLINKS : HEAD OF BACKWARD LINK FOR EACH TYPE.

Loader

Directory Entries

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	GARBAGE(O)
BACKHARD LINK	
LENGTH	
1 0	
GARBAGE	
O 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	SL FILE(1)
BACKWARD LINK	
LENGTH	
1	
FILE DISC ADDRESS	
FILE PV INFO	
# ALLOCATED SEG # SEGLIST ENTRIES	
SEG ARRAY (16 WORDS)	
LOG SEG NUMBER A C X M	
REFERENCE COUNT	SEGLIST RRRRY > 3 WORD ENTRY
PHYSICAL CST NUMBER	PER ALLOCATED
:	′
!	!

G.01.00 11- 4

G.01.00 11-3

G.01.00 11-8

l nader

Directory Entries (Cont.)

G.01.00 11- 7

Loader

Directory Entries (Cont.)

0 1 2 3 4 F0	5 6 7 8 9 10 RHARD LINK) 11 12 13 14 15 -	LOADPROC Master(8)
BA	CKWARD LINK		
L	ENGTH		
		8	
	PIN		
# SLID ENT	RIES # AC	TIVE LOADPROCS	
EX	T IDX TABLE (16	IORDS)	
MC	ST IDX TABLE (16	NORDS)	
	SLID(1)		}
	: :		REFERENCED > SL ARRAY
	SLID(n)		}
	#mcst	LOGSEG SIZE	
LOG SEG #	l 2rī	D INDEX(1)	
	REFERENCE COUNT		
	: : :		MCST LOGSEG > ARRAY 2 HORDS PER
LOG SEG #	\$LI	D INDEX(H)	ENTRY
	REFERENCE COUNT		
			1 /

G.01.00 11- 9

Loader Cache

SYGLOB extension area + %72 contains DST number of cache BUCKETSIZE = %52

Cache Data Segment Format

		0 1	HIT COUNTER	
		2 3	MISS COUNTER	!
		4	BUCKET 0	İ
	4+ BUCKETSIZE	Ī	BUCKET1	I
			•	
			:	
94*	BUCKETSIZE	Ī	BUCKET 94	

Bucket Format

4+95* BUCKETSIZE -1

0	Length of SLDIR1 +1	
1	SLDIR 1 LENGTH OF SLDIR2 + 1	Most recently referenced system SL directory entry from this SL directory bucket
	SLDIR 2	Second most recently referenced entry
	: :	
	LENGTH OF SLDIRN + 1	
IZE-1	SLDIRN 	Hth most recently referenced entry;if not complete then indicates end of bucket

bucket All bucket words are initialized to BUCKETSIZE +1, indicating no entries.

G.01.00 11- 10

Loader

Loader Communication Table (LCT)

Form Incoming to Loader (Load/Allocate Program)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
0		
1	PIN	
2	LDEV	
3	DISC ADDRESS	CMD=loader end
4		0=load prgm 1=load proc
5		2=alloc pro 3=alloc pro
6		LIB=library search
7	UNUSED	0=SYS 1=PUB
8		2=GROUP
9		M=NONPRIV MODE
10		LD=LOAD DOMAIN L=LOAD MAP REQ.
11	HRITER PCB INDEX	
12	 BA IA PM MR DS PH -	USER CAPABILITY
13		
14	GROUP	
15	NRME	
16		
17		
18	ACCOUNT	
19	NAME	
20		
21	PV INFO	

G.01.00 11- 11

Loader

LCT (Cont.)

Form Incoming to Loader (Load/Allocate Procedure)

0	O 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	
1	 PIN	
2	EXTENSION ID	
3	# CHAR IN NAME	CMD=loader cmd
4		O=load prgm 1=load proc
5		2=alloc prog 3=alloc proc
6	PROCEDURE NAME	LIB=library search O=SYS
7		1=PUB 2=GROUP
8		
9		M=NONPRIV MODE LD=LDAD DOMAIN
10		L=LOAD MAP REQ.
11	WRITER PCB INDEX	
12		USER CAPABILITY
13	 -	
14	GROUP	
15	NAME	
16		
17		
18	RCCOUNT	
19	NAME	
20		
21	PV INFO	
		l

LCT (Cont.)

Form Returned (No Error)

0	M MF STARTING SEGMENT NUMBER
1	0
2	LOAD MAP FLAG
3	LDEA
4	DISC
5	ADDRESS
6	TRACE LABEL (IF TRACE)

Form Returned (Error Occurred)

0	FILE SYSTEM ERROR #
1	LOADER ERROR #

G.01.00 11- 13

G.01.00 11- 14

Loader

Logical Segment Transform Table (LSTT) (Cont.)

	# of Logical Segments	<u> </u>
	Length of LSTT	, !
	Physical Segment #	i
	Pointer to STT list	+ Logical seg 1
	Physical Segment #	
	Pointer to STT list	+ Logical seg 2
ı		·
- [:	l :
	Physical Segment #	• I
	Pointer to STT list	+ Logical seg n (Max 255)
	M STT # SEG #	·
	IMI STT # SEG #	STI's for logical segment 1
		(if needed)
		<u> </u>
	M STT # SEG #	•
>	Total STT's for this seg	 •
1	:	:
İ		
İ	M STT # SEG #	STT's for logical
İ	IN STT # SEG #	segment n (if needed)
į		(1) NEEGEG)
İ	IMI STT # SEG #	
	t	•
	Total STT's for this seg	

G.01.00 11- 15

Logical Segment Transform Table (LSTT)

When a process references any user SL segments, these segments are assigned logical segment numbers if the new mapping ucode is running. The LSTT provides a map mapping these logical segments into their physical segment numbers and having true STT's for the mapped segments. The LSTT is created by LDRDER during the load time. It occupies an DST and the DST number is stored in PCB(15). If no user SL segment is referenced, the LSTT will not be needed, hence it will not be created.

The new mapping microcode depends on the existence of the LSTT for getting the physical segment number for a mapped segment. So the LSTT has to be included in process' locality list if there is an LSTT. Dispatcher will then bring the LSTT in before the process can be run. Also the bank and address for the LSTT belonging to the current running process are stored in sysglob cells (X221 and X222) during the launch time by the dispatcher. These cells are used by microcode for fast accessing the LSTT.

Private Volumes/Serial Disc

CHAPTER 12 PRIVATE VOLUMES / SERIAL DISC


Mounted Volume Table (MVTAB)
DST =53 =X65
SIR =27 =X33

1 1 1 1 1 1 0|1:2:3|4:5:6|7:8:9|0:1:2|3:4:5 entry size : max entries # of mounted volume sets

ldev : DIRBASE 2 master volume of SYS VS is always 3 ldev = 1. of SYSTEM volume set 0 ٥ - entry 0 (MVTRBX = 0) 22 18 23 19 ٥ 20

Private Volumes/Serial Disc


MVTAB (Cont.)



G.01.00 12- 1

Private Volumes/Serial Disc


MVTAB (Cont.)



G.01.00 12- 3


Private Volumes/Serial Disc


Private Volume User Table (PVUSER) DST =54 =266 SIR =29 =235



G.01.00 12- 4

PVUSER (Cont.)






6.01.00 12- 5

Bind Names Data Segment


(Created and managed via PVUSER Table)



G.01.00 12- 6

Private Volumes/Serial Disc

Bind Names Data Segment (Cont.)



Private Volumes/Serial Disc


Serial Disc Tables and Data Structures

Data Record Format

The primary purpose of the Serial Disc Interface (SDISC) is to adapt the undefined length transfers characteristic of magnetic tape to the fixed-length environment of a disc or cartridge tape (CTRPE). To accomplish this, data is buffered within SDISC. The buffer is an integral number of sectors (blocks for the CTRPE) long. Files always start on a sector boundary, but data records within files may start anywhere and straddle sector boundaries. R record in the buffer is structured as follows:

+		+
record	1	record
Length	data	Length
(bytes)		(bytes)
4	L	

The record length is always a one-word positive byte count which includes only the data portion of the record, not the length words themselves. Records within a file might be stored on the disc as follows:



The reason for the trailing byte count is to implement an easy way to backspace records.

End of File Format

Since files always start on a sector boundary, it follows that they also end on one. End of files consist of a O record length and O-fill to the end the current sector as follows:



In addition, an End-of-File entry is made in the Gap Table, so that files may be skipped by scanning Gap Table entries instead of serially scanning the data area. The Gap Table is described a few pages from now.


Private Volumes/Serial Disc

Gap Table Format

The Gap Table is a four-word header followed by a series of two-word device address entries. A permanent copy lives on the device, starting in sector 4, while a working copy lives in wain memory. The copy in memory is posted to the disc only when a backspace or rewind operation occurs after writing (in other words, when the copy in wain memory has changed). The length of the Gap Table is device-dependent according to the table below:

Device	Number of sectors (or CTAPE blocks)
HP7920	44
HP7925	106
HP7933/35	219 (250 for G.00.00 and later releases.)
HP7902/9895	26
HP9110/HP9144	4 blocks ("S" cartridge)
HP9110/HP9144	15 blocks ("L" cartridge)

The Gap Table looks like this:



The type field is bits 0, 1 and 2 of the first word. The eight possible


End of File. The associated sector address contains one or more end of file fill characters (0) to fill out that sector. In the worst case (the previous record ended exactly at the end of the previous sector), the end of file sector contains all zeros.

of file sector contains all zeros. End of data. The associated sector address is the last address of valid data plus 1, in other words, the next available address. In practice, such an entry is usually preceded by an end-of-file entry, since the EOD entry is written when you stop writing, and the file system will not let you backspace or rewind after writing without sending a Write End of File. An EOD entry is also written at the beginning of the Gap Table when new (unwritten) media is inserted. This prevents erroneous reading of blank media.

Private Volumes/Serial Disc

Contiguous Block Format

A serial disc, if it can do everything a magnetic tape can do, must also be a cold-load device. This means that machine microcode must be able to read a bootstrap channel program and the resident segments of INITIRL From the disc into memory. The microcode and channel programs cannot deal with the record length words which surround standard data records, so for them we have a structure, called a CONTIGUOUS BLOCK, which has the data without the length words. Information as to the length of each contiguous block must therefore be kept elsewhere, so there are Gap Table entries which hold the beginning and ending sector addresses of each contiguous block. This implies that each block must begin and end on a sector boundary. In this way they are similar to data files. To set contiguous blocks off from normal data, and to reach a sector boundary, a record length and fill character = %177777 is used, as follows:



Hole Format

Holes on the serial disc have the same format as contiguous blocks (that is, they start and end on sector boundaries with -1 fill characters as required). Starting with TME version G.00.00, holes are obsolete and SDISC will not generate them. However, code has been left in SDISC to process any holes found on serial discs written with earlier versions of SDISC. Further details may be found in the Serial Disc IMS.

G.01.00 12- 10

Private Volumes/Serial Disc

- Beginning of Hole. The starting address of a "defective" area of the disc. Usually on a track boundary, but may be in mid-track if a contiguous block was being written when the "defect" was encountered. Obsolere, starting with MPC version G.OO.OO.
 End of Hole. The corresponding ending address of the "defective" area. Rluays at a track boundary. Obsolete, starting with MPC version G.OO.OO.
 Beginning of (contiguous) Block. The starting address of a contiguous block, exclusive of the -1 fill characters which may have been required to get us to a sector boundary. Unlike the End of File fill characters, there need not be any -1 characters if the previous record or contiguous block (with or without the trailing length word) ended exactly on a sector boundary.
- block (with or without the trailing length word) ended exactly on a sector boundary.
 End of (contiguous) Block. The address of the last sector containing contiguous block data. The sector nay also contain -1 fill characters to get us to a sector boundary, but as with the beginning of block they are not required if the contiguous block ends exactly on a sector boundary. End of Tape mark. The sector address of the simulated End of Tape reflector. This type is now written only to floppy discs for use by INITIRI's serial disc interface. When read by MPE's SDISC, it will be skipped no matter what device it is found on. This ensures compatibility with older serial discs.
 End of Gap Table. No associated sector address. If you hit this while scanning the Gap Table, you've gone too far. In practice, this type is created whenever the Gap Table is cleared, by the simple device of initializing the table to -1.

Private Volumes/Serial Disc

SDISC Extra Data Segments

With insignificant exceptions, SDISC operates entirely in split-stack mode, that is, using an extra data segment for its working storage. Starting with MPE version G.00.00, there are two additional data segments used as no-mait data buffers. For the most part, our discussion here is restricted to the original data segment, now used only for variables, the Gap Table, and data buffer management.

The working storage extra data segment (XDS) is usually acquired by the external procedure RLIDCRTE when the serial disc device is first assigned to a user as part of an FDPEN. The external procedure DERLIDCRTE makes the XDS go away as part of its processing of the final FICUSE against the device. The system program PVPROC may also acquire and release an XDS so that the tape label routines in LBRSEG may also use SDISC for their work when DEVREC processes a device on-line interrupt. SDISC allocates the two data buffer segments as they are needed, then deallocates then as part of the Device Close processing.

In addition to the Gap Table already described, the XDS contains SDISC's global storage area, including the data buffer management areas (BUFFER'INFO), and a small buffer (called WORKTRBLE). WORKTRBLE holds the contents of the Serial Disc label sector when SDISC reads it in as part of its self-configuration. It also hold the Defective Tracks Table (RRC family discs) or Defective Sector Table (CSSO discs) while reassigning suspect or deleted tracks.

The three arrays in the XDS (WORKTRBLE, BUFFER'INFO and GPI (Gap Table)) are all dynanically configured by SDISC as vanilla indirect arrays, such as might have been constructed by SPL. This is done by declaring the array manes as pointers, then inserting appropriately conputed element-O addresses in them.

The extra data segment is organized as follows:

	+
0	HORDSPERSECTR
1	SECTORSPERTRAK
2	STARTADORESS (BOT)
3	EOTSECTR (disc
4	address of simu- lated end of tape)
5	EODSECTR (last sector of disc)
6	sector or disc;
7	JUSTALLOCATED
8	HRITE RING
9	FATALERROR

These twelve words are reserved for use by RLLDCATE when the data segment is created. However, RLLDCATE only stuffs the last five of them. We fill the first seven ourselves with information we get from the label sector.

Simulates tape runoff.

Tells us to initialize SDISC parameters to BOT if true. Simulation of tape write ring.

Disables SDISC permanently when true.

10	Volume Fatal Error
11	MAX DSEG SIZE
	SDISC global vari- ables, including array pointers.
	# 0
•	B I N F F O E R,
	G P T B L E

If TRUE, disables SDISC until a new volume is mounted.

Max size of our XDS, so we can check that it's big enough.

Length is 512 words.

Length is calculated as MAX'NUM'BUFFERS (currently 2) * INFO'ENTRY'SIZE (currently 8).

Length varies with device, and is calculated by SDISC as part of its self-configuration.

G.01.00 12- 14


Private Volumes/Serial Disc

Serial Disc Organization


The disc is organized as follows:

Label sector	0 See expanded view in Chapter 3.
DTT/DSCT	1 DTT (MAC family) or DSCT (CS80).
Cold load	2 HP-IB cold load channel prog.
Soft dump	3 SOFTDUMP channel program.
Gap Table	4 to STARTADDRESS - 1.
:	
Data	STARTADDRESS
:	:
•	to
	EOTSECTR
	to
Last data sector	EODSECTR

CHAPTER 13 I/O



Device Reference Table (DRT)



SIOP - absolute address of SIO program PI - interrupt handler plabel OBI - this is the absolute address of the ILT

G.01.00 13- 2

I / 0

Driver Linkage Table (DLT)

0	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	DPROC
1	MONITOR PLABEL	DMNTR
2	INITIATOR PLABEL	DINIT
3	COMPLETOR PLABEL	DCOMP
4	INTERRUPT PLABEL	DINTP
5	DIT SIZE DEVICE TYPE	DTYPE
6	CS DRIVER EDITOR PLABEL	
7	INITIALIZATION PLABEL	

There is one DLT for each type of driver. A pointer in the DLT allows different devices on a controller to have different drivers and interrupt handlers.

DPROC.QNUMB - This field contains the I/O process request queue number for type 2 drivers. Zero for all other types.

(8:1).DRVRFRZH - Driver code Frozen. Set by MRH when then the driver code segment has been made present and frozen from a request from SIODM.

(9:1).MRMERRORCE MRH Error on Code Makepresent

(.10:1).CORERES - If set both initiator and completor code are core
(CR) resident
(.10:1).DRERIYPE- DRIVER/MONITOR TYPE

(HTVP)

UNIVEX/FOURTION TIPE

- not used

- driver can be executed on any stack

- driver can be executed in the user process or
 in the I/O process identified by IONUMB

3 - run only in process whose PCB number is in
 IDNUMB

DMNTR - I/O Monitor Plabel.
DINIT - Driver Initiator Procedure Plabel.

DCOMP - Driver Completor Procedure Plabel.

DINTP - Special interrupt handler Plabel. This procedure is called by GIP if ISPEC is set DFLMG. No other action is taken by GIP except to set the Interrupt Status in DSTMT.

DTYPE.DITSIZE - The length of the DIT in words for this driver.

I / 0

Logical-To-Physical Device Table (LPDT)

DST = 13 (= X15) SIR = 9 (= X11)

The LPDT has several fields which describe the state of a device. Some of these fields have the same meaning for all devices. Others are device depen-dent. All are described below.

dent. All are described below.

There are two types of devices represented in the LPDI: real devices and virtual devices. A real device is one which has been configured into the system and is capable of performing input and/or output. A virtual device simulates some of the properties of a real device (for example a spooled line printer or an INP), but there is no physical I/O involved. The two main uses for virtual devices are for OPEN spooled devicefiles and certain communication devices (such as INP's).

A given virtual device entry is in use only while the devicefile it represents is open. When the file is FCLOSCd, the entry becomes available for another virtual device. This is the reason for the SYSOUMP/INITIAL configurator question MRX # OF OPEN SPOOLFILES—it needs to know how many virtual device entries to allocate to the LPDI (and to the LDT). Entries in the LPDI are ordered by logical device number. The first word address of a real device entry is obtained by multiplying the LDN by the entry size. Except for the Oth entry, entries for which no logical device is configured on a given system are used for virtual device entries. Any remaining virtual device entries follow the last real device entry.

Entry 0

•1	1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
0	Mumber of entries in table
1	Entry size = 4
2	DEVREC service request count
31///	

Discussion:

Nord 2 is incremented by a device driver whenever it sets the Device Ownership State field (below) to 2 (Service Requested). DEVREC decrements the count for each interrupt it services until the count reaches 0, at which time DEVREC hibernates.

Device drivers must lock this table by DIS-BBLE/EMRBLEing, -MOT by trying to acquire the LPDT SIR.

<u>Typical Entry (Virtual Devices)</u>

0 1	2 :	3 4 !	5 6	7 8 9	10 11	12 13 14 15
0 1		Po:	inte	r to XDD (subent	ry *
1	1 1	1.1	Ιİ		İ	
						///////////////////////////////////////
3 10 //	/////	/////	////	ıinın	/////	(())(()()()()

IO -- O for input, 1 for output.

Word 0, bit 0 is 1 for a virtual device, 0 for a real device. The fields in word 1 are the same, as applicable, as for the real device represented by a given virtual device. See below.

G.01.00

T / D

Entry for Terminal-Like Devices

+	111			111	2 13 14 15 -
0 0 0 / / /	/////////	//////	////////	////////	minin
Devc 1 Duned State	J Da Ct o ta 1Y b	D I u n p t	End of File Cndition	B L r o k g	Device Subtype
2		lative	pointer	to the (
31/////	////////		///////	////////	,,,,,,,,

Discussion (unique fields only): Word 1.(4:1) -- CONTROL-Y is allowed and has been detected.

Word 1.(10:1) -- BREAK has been detected -DR- ignore BREAK if the C.I. is

Mord 1.(11:1) — The terminal is logging on. This bit is set by PROGEN and DEVREC when the logon sequence starts. If the bit is off when polled by INTIJSMP, the terminal has disconnected. For now, only IOTERNO and MIOTERN support the use of this bit. Multipoint and OS pseudo-terminals do not.

Entry for Tape Drives

0 0 0 ///////	 ////////////////	10 11 12 13 14 15
Devc J Da 1 Ouned o ta State b	B D I End of O u n File T p t Cndition	A Au: Device V to: Subtype R :
	8-relative pointer	to the DIT
3 //// AR //	///////////////////////////////////////	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,

Discussion (unique fields only):

Word 1.(4:1) -- BOT. Tape is at Load Point -OR- no tape mounted. Recording density may only be switched when this bit is true (for multiple density tape drives).

Word 1.(11:1) -- If true, DEVREC is performing Rutomatic Volume Recognition (RVR) on a tape (or PVPROC is doing the same on a serial disc), -OR-RVR is to be suppressed on job or data accepting devices.

Typical Entry (R11 Real Devices)

SYSDB-relative pointer to the DIT

Discussion:

iscussion:

Nord 1.(0:2) -- Device Ownership State:

0 -- Not owned by any process.

1 -- Owned by a process.

2 -- Service requested. Set by driver for unexpected interrupt, then wakes DEV-

2 -- Service requested. Set by driver for unexpected interrupt, then wakes DEV-REC.

3 -- Service granted. Set by DEVREC. Logon sequence is 0-2-3-1.

3 -- Device reserved (alternate use). Set during STRRISPOOL, spooler process sets to 1 when it gets started.

Word 1.(2:1) -- Device is Data Recepting if true.

Word 1.(3:1) -- Device is Data Recepting if true.

Word 1.(5:1) -- Device is Duplicative if true (all devices except discs).

Word 1.(7:3) -- End of File condition:

0 -- Mo COF detected.

1 -- Hardware EOF (e.g., tape nark).

2 -- :DATH record read.

3 -- :EOD record read.

5 -- :BYE record read.

5 -- :BYE record read.

7 -- :EOJ record read.

7 -- :EOJ record read.

7 -- :EOJ record read.

1 -- :EOJ record read.

7 -- :EOJ record read.

Word 1.(12:4) -- Device subtype. See discussion for tape entry (below) for a description of the Auto bit (12:1).

The remaining bits in Word 1 are device-dependent and are described with their corresponding entry diagram.

G.01.00

T / 0

Word 1.(12:1) -- Part of Device Subtype field. If true, device may be allocated automatically when opened. If false, operator must

Mord 3.(2:1) -- RUTO REPLY. Device may be allocated without prompting the operator for REPLY. This bit is set automatically if word 1 (12:1) is true.

Entry for Disc Drives

0 0 //	 //////		6 7 8 9 ////////	1-1-1-	<u> </u> ///////
Devc 1 Ouned State	J Da o ta b	NIMTIR Sid I DIPVI	End of File Cndition	S F Au or o To F r	Device Subtype
5			ve pointer	to the D	
3 // SD	AR ///	//////	///////////////////////////////////////	////////	////////

Discussion (unique fields only):
Word 1.(0:2) -- Device Ownership State. May not be 1 (owned) for shared device (system volume or private volume). Serial and formering discs are non-sharable and nay be owned. See the full discussion of this field under Typical Entry, above.

Word 1.(4:1) -- If true, the disc is a nonsystem domain (private volume, serial disc or foreign disc) disc drive.

Word 1.(5:1) -- If true, disc is a mounted private volume.

Word 1.(6:1) -- If true, the disc is a reserved volume used to satisfy the requirements of a multiple volume private volume set.

Word 1.(10:1) -- If true, the disc is a physically and logically mounted serial or foreign disc. Bits 5 and 6 must be false.

Word 1.(11:1) -- If bit 10 is true, then 1 ==> foreign disc, 0 ==> serial

Hord 3.(1:1) -- If true, the device is currently being used as a serial disc (that is, it is allocated to a user as a serial disc). This bit duplicates a bit in the LDTX entry so that this information can be found in a system (memory-maid-dept) table. resident) table.

Word 3.(2:1) -- AUTO REPLY. Device may be allocated without prompting the operator for REPLY. This bit is set automatically if word 1 (12:1) is true.

Logical Device Table (LDT)

Overview of Data Segment

-----DST X16 DST 14 (= X16) SIR 10 (= X12) Logical Device Table (LDT) Logical Device Table Extension (LDTX)

Ingical Device Table

Zero Entry Format

0	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	
1	Entry size = 6	ļ
2	Streams device number	į
3	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ļ
4	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	į
5	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ļ
6	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1

G.01.00 13- 9

Typical Entry Format

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 14 14 14 14 14 14 14 14 14 15 16 17 18 18 18 18 18 18 18 18 18 18 18 18 18	
Volume table index if device type = 0-7, els main process pin # or spooler process pin #	1
Record width CS FO Device type	į
Spool Sy Di Dn Tr Hd Cl S Device-dependent state st ag Rq lr r as Q info (see below)	į
////// XDD head index	į
CONTROL-Y pin	<u>.</u>
Default output device -OR- default class inde	:× 6

Discussion:

G.01.00 13- 10

I / 0

Logical Device Table Extension (LDTX)

Overview of Data Segment

DST 14 (= X16) SIR 10 (= X12) ------DST X16 Logical Device Table (LDT) Logical Device Table

I / 0

Zero Entry

0	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1	Entry size = 5
2	
3	<i>\\\\\\\\\\\\\\\\\\\\\\\\\\\</i>
4	

Typical entry

0 1 2 3 4 5 6 7 8 9 10 1 +	- +
O 2 20 Chit2in2 KesetA60 D6A70	e-specific
	į.
1 information	I
+	+
2 fields.	1
. 115100.	

3 See the following example	s I
+	+
4 of LDTX entries.	1
4 UI WIN EIII 1283.	!

Where:

S....Seek ahead enable/disable flag (system or PV disc only).

SD...This logical device is a Serial Disc or a Foreign Disc.

CP...This logical device uses the CIPER protocol.

FS...This is a system or PV disc with Disc Free Space Hanagement.

DS...This LDEV is a DS or data communications device.

Terminal Entry

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 +
0	0 0 0 0 0 Reserved TBRC
1	Terminal Descriptor Table Offset
2	CHRHNEL ID
4	<i>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</i>

TBRC..Terminal's baud rate code (CPS = characters per second).

Speed (CPS) ADCC/ATP (HPIB) TBRC

0
16 (ATP only)
8
ġ
7
11
6
13
14
15

WS.... This terminal is connected to a Workstation Configurator port.

TDT offset...Offset from the base of the Terminal Descriptor
Table (TDT) to the TDT entry for this terminal. A
-1 indicates no TDT entry exists for this termi-

G.01.00 13- 13

I / 0

Device Class Table (DCT)

Overview of Data Segment

DST 40 (= X50) SIR 40 (= X50) Device Class Table (DCT) Terminal Descriptor Table (TDT)

Header Entry Format

Entry size (variable, this word set to 1) Number of device class entries Pointer to first device class entry (segment relative) Number of terminal descriptor entries 5 Pointer to first terminal descriptor entry (segment relative)

Serial or Foreign Disc Entry

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 0 0 0 0 1 1 0 0 0 Reserved SDISC: XDS# for variables, Gap Table FDISC: 1 SDISC: 1 ==> data buffer XDS's acquired FDISC: not used. SDISC: PCB index when WAITing, else O FDISC: not used. 1

CIPER Entry

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 +	15
0	0 0 1 0 0 Reserved DB //////////////	///
1	CIPER Device Control Data Segment # (CDCDS	
2	DN CTM Index for this device (CTMI)	į
3		///
4		///

DB....If set to 1, then debugging is in effect.
DN....If 1, the CIPER facility has been de-activated for this device because of error.
CTMI...Control Table May Index (an index into the Control Table May Index).

System or Private Volume Disc Entry


	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
0	
1	<i></i>
2	Disc Free Space DST number (DFSDST)
3	Disc Free Space error status (DFSERR)

S.....Seek ahead enable/disable flag.

G.01.00 13- 14

I / 0

Device Class Table Typical Entry Format



Discussion:

The Device Class Table (DCT) contains a varying number of variable length entries. This is because you nay configure an arbitrary number of device classes on a system, and each device class may be comprised of an arbitrary number of logical devices. There is one DCT entry per device class, and each DCT entry contains a list of logical devices in the class. There is no established order of entries in the DCT, nor is there an order of LDEVs within an entry.

Due to the haphazard nature of the DCT, its overall properties are kept in the header entry. These include the segment-relative starting address of the DCT (in case the header entry should be expanded later) and the number of entries in the table. A segment-relative pointer to the Terminal Descriptor Table (which follows the DCT) may also be used to calculate the size of the DCT. Also note the "Entry size" word. It is meaningless for this table, but is included for compatibility with other fixed-length entry MPE tables. Since the DCT entries are of variable length, when you want a particular entry you must always start at the beginning of the DCT and link through each entry until you find the one you're interested in.

A few of the fields in the DCT require further description:

Word 4.(1:7) --Cyclical pointer. Currently used only for system and private volume disc devices. The pointer varies from 1 to N (number


of entries in the class) and indicates the LDEVM in the class list on which the last extent was allocated. The disc space allocation routines will try to satisfy the next request on the next disc drive indicated by the cyclical pointer (with wraparound to 1 if the pointer > M). If that fails, the pointer is incremented until space is found or all devices in the class have been tried.

Word 4.(8:1) -- If set, spooling has been enabled (spool queues opened) for this device class.

Word 4.(9:1) -- If set, the class is a terminal type class.

Word 4.(10:6) --Usually the same as the device type represented by the class (0-7 for disc, 24 for tape, 32 for printer, etc.). Serial disc classes are disc devices accessed as tape drives, so their true device types are kept in the LDT, while this field holds a special type (31, or X37), indicating a serial I/O (non-concurrent) device. Similarly, a foreign disc is a nonsharable disc drive, so that fact is reflected by a special type 7 in this field, even though the true hardware type is kept in the LDT, as for serial discs.

Terminal Descriptor Table Typical Entry Format



The Terminal Descriptor Table contains a varying number of variable length entries, because each Terminal Descriptor entry may have an arbitrary number of logical devices. However, you can only configure a fixed number of valid terminal entry files. These are the ITnn or TTPCLnn files which reside in

G.01.00 13- 17

G.01.00 13- 18

I / 0

Interrupt Linkage Table (ILT) for HP-IB Systems

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
0 1 2 3	Channel Program Variable Area (ICPVA) For terminals with ATP drivers, this area is zero.	ICPVAO (O forATP) ICPVAO1 (O forATP) ICPVAO2 (O for ATP) ICPVAO3 (O for ATP)
4 5	DMA Abort Address	ICPVRO4 ICPVRO5
6	0	ISRQL/ICPGM
7	M CHRNQUE CHRN DEV	ICNTRL
X10	SYSDB relative pointer to channel program area.	
X11	SYSDB relative pointer to status return area.	ISTAP
	single instruction that is executed to extract the device unit number from the status pointed to by ISTAP.	IUNIT
	SYSDB relative DIT pointer of the device currently using the channel to perform a data apperation.	ICOP
714	•	IQUEUE
X15	RU UP IG SC SQ HCUNIT	IFLAG
	SYSDB relative DIT pointer for unit 0	IDITPO
	· :	
	SYSDB relative DIT pointer for unit n	IDITPN
	Program status return area pointed to by ISTAP	
	Seekmask (Disc only)	
	I/O Program Area	

I / 0

ILT (Cont.)

ILT (Cont.)

IPCVA - These four words comprise the channel program variable area where information is stored concerning a channel program Interrupt instruction or abort.

ICPVAO should be used only for channel program aborts.

ICPVAO + Words 4 and 5 contain DMR address, when channel program aborts during DMR transfer.

ISRQL - Serial poll request queue length. HP-IB Systems do not support any serial poll devices. This should always be zero.

ICPCAD - This is the SYSDB relative address of the channel program to be started for this device after receiving a HIDP interrupt in GIP. GIP will call STARTIO when the flags word indicates "ignore halt interrupt" and "start channel program" bits are set.

ICNTRL - Contains controller information.

If set, the controller is sharing a software channel resource number.

CHNQ The software channel resource number.

ORTN The DRI number for a Series 33 device is equivalent to:

CHNA - channel number (4 nost significant bits of DRIN)

DEV - device number (3 least significant bits of DRIN)

IFLAG - Used for controller flags.

RIV Runmait flag. An idle channel program should be started then there are no active requests to process.

JP Waitprog flag. An idle channel program has been started for this controller. This bit is reset by an interrupt.

IG Ignorehi flag. An HIOP instruction has been issued against this controller, but the channel program halts.

SC Start channel program flag. When set along with the IG flag, GIP will start a previously attempted SIOP on this device.

SQ Start channel program "queued" flag. When bit SC is set, this bit will determine if the call to START'HPIB will have logical parameter QUEUED true or false.

HCUNIT Highest configured unit number for this controller.

Davice Information Table (DIT)

There is one DIT per physical device. If a physical device represents nore than one logical device, the logical device number is obtained from the I/O queue element. Although details of DIT's vary with device, the following structure is common to all:

DIT for HP-18 Systems

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
٥	T D AC RQ SI MU O IO IA MO ST MS STATE	DFLAG
1	SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
5	SYSDB relative pointer to the first IOQ in request list for this device	DIOQP
3	Logical device number	DLDEV
4	SYSDB relative pointer to Device Linkage Table	DOLTP
5	SYSDB relative pntr to Interrupt Linkage Table	DILTP
6	Controller Hardware Status	DSTAT
7	Hardware error status. Set when the driver detects an error. Whenever <>0, the driver monitor logs an I/O error and clears this word	DSERR
8	Device Dependent Area	(DTIME)
9	Device Dependent Area	(DTRQX)
10	IOT ////////// Phys. unit #	DUNIT

DTROX Used by some device drivers, it denotes timer request index.

G.01.00 13- 21

DIT Terminology for HP-IB Systems

```
DFLAG - DEVICE RELATIVE FLAGS
T SET IF DEVICE IS A TERMINAL,
D SET IF DEVICE IS A DISC.
ACT THE DEVICE IS A DISC.
HIS DEVICE.
RQ REQUEST BIT 1 IMPLIES A HONITOR CURRENTLY SERVICING
THIS DEVICE.
RQ REQUEST BIT 1 IMPLIES SERVICE REQUESTED WHILE
```

Device Information Table (DIT) for CIPER

There is one DIT per physical device. If a physical device represents more than one logical device, the logical device number is obtained from the IOQ element (houever, this driver only supports one device per controller.) The following diagram shows the DIT used for the HP-IB CIPER physical driver.

1/0

1/0

DATA CHT TO CHT PRTY CHT

```
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 MMEMONIC
  OI OI OIACIRGI OI OI OIIDIIAINOISTI OI STATE
                                                                    DFLAG
      SYSDB relative pointer to the DIT for the next device requesting this resource or service
                                                                    DLINK
     IOQ table index to the first IOQ in request list for this device
                                                                    DIOGP
               Phys. unit # | Logical device number |
                                                                    DLDEV
  4| SYSDB relative pointer to Device Linkage Table|
                                                                    DOL TO
  5| SYSDB relative pointer to Intrp Linkage Table |
                                                                    DILTP
   6|VS|AB|RE|TP|NR| NR CHT |
                                        DEVICE STATUS
  7| Hardware error status. Set when the driver detects an error. Whenever <>0, the driver nonitor logs an I/O error and clears this word
                                                                    DSERR
X10| Bit O is set at completion of timer
                                                                    DTIME
X11 Holds the time out request entry index while a timer is active.
                                                                    DROST
X12[RF|UE|DE|TO|UNIT CHT|DATA CHT| TO CHT |PRTY CHT|
                                                                  DCOUNTS
X131
                 Error logging location #1
                                                                 DLOGERROR
                  Error logging location #2
DFLAG - Flags and request state

AC ACTIVE - A monitor is currently servicing this device.

RQ REQUEST - A service request is pending while the monitor is
    IA IAK -
NO HOTRDY -
ST STWAIT -
  STRIF
```

```
X10 - wait for interrupt (operator intervention)
restart at state 0
X11 - wait for data segment freeze, then state 2
X12 - wait for data segment freeze, then state 2
X13 - wait for driver initiator to be frozen, then
allocate controller (state 2)
X14 - wait for I/O completion interrupt, then state 3
X14 - wait for controller, then call driver initiator
X15 - not used
X16 - wait for initiator make present, then state 2
X17 - wait for completor make present, then state 3
     DLDEV - I/O system type, unit and logical device number
O - HP3000 Series iII/III
1 - HP 3000 HH-IB
2 - Unused
3 - Unused
DSRVE - Device processing flags
VS - VRLID STATUS - Set to indicate Device Status has been updated.
RB - DVRABFLAG - Sequence Abort in progress due to ABORT request.
RE - RETRYLAG - Sequence Abort in progress due to an error.
TP - IIMERPOPPED - Current error is due to software timer popping.
RR - NOTROYFLAG - Not Ready Wait in progress.
RC LAY - Nourber of Not Ready Waits during this request.
DEVICE STATUS - Device status returned during a Sequence Abort.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERVED.
RESERV
     DSERR - Pointer to status to be logged.
Bits(0:8) - Mumber of words to be logged.
Bits(8:8) - Offset relative to DITP(0).
                                                                                                                                                                                                      - Error flags and error counts (4).
- An error has forced this request to be aborted.
- The current error is a Data Error.
- The current error is a Data Error.
- The current error is a CDI line Out Error.
- Number of Unit Errors during this request.
- Number of Data Errors during this request.
- Number of GIC line Outs during this request.
- Number of GIC line Outs during this request.
        DCDUNTS
                                   OUNTS

RF - REQ FAILED

UE - UNIT ERROR

DE - DATA ERROR

TO - TIME OUT

UNIT CNT
```

I / 0

DLTNK

DIT for Channel Devices

5 6 7 8 9 10 11 12 13 14 15 ٥ 1 2 3 4 | M | SIO | IO |IAK| M |NT| |UNIT| PREMP|PROG| |HEAD|RY| DFLAG O TERMIDISCIACT RED NEXT DITP DLINK IOOP DIOQP DLDEV LOGICAL DEVICE NUMBER DLTP DLTP ILTP DILTP Controller Hardware Status DSTAT DSERR Hardware Error Status NTTHE DTRQX PHYS. UNIT # DUNTT

DRIVER DEPENDENT DIT AREA

DFLAG.TERNINAL - Device is a terminal
DISC Device is a Disc (Bit 0 = 0)
RCTIVE - A monitor is currently servicing this device
REQUEST - Service requested while monitor was active

.RUNIT - device controller servicing multiple units
.SIOPREMPT- If set then a request has been queued for
this device. Preempt code is set in IOQ.
.IOPROG - I/O program in progress. Decrement SIOCOUNT and
check for multi-channel when complete
.TRK - Interrupt or Response has occurred.
.THEAD - Hoving head disc
.NT RDY - Not ready for SIO. SIODM holds off next SIO until
ALLOWPOLL is done.

Used by some device drivers, it denotes timer request index.

G.01.00 13- 25

DIT for Channel Devices (Cont.)

DFLAG.STATE - this quantity specifies the next action to be taken in servicing the request.

O-new - start request.

O-new - start request.
1-not used.
2-call Driver Initiator Procedure
3-call Driver Completor Procedure
5-complete request
6-device recognition
7-start operator intervention wait (X10)
X10-restart request on interrupt
X11-wait for data to be frozen then state 2
X12-wait for driver code to be frozen then state 2
X13-call completor on interrupt
X14-wait for device controller
X15-not used
X16-wait for initiator make present then state 2
X17-wait for completor make present then state 3

DIDOP

DLDEV.LDEVN .UNIT .IOT

DDLTP DILTP DSTAT

DSERR

DITHE

X17-wait for completor make present then state 3

- SYSDB relative pointer to the DIT for the next device requesting this resource or service.

- SYSDB relative pointer to the first IOQ in the request list for this device |
- Logical Device Number |
- unit number of the physical device.

- IO type 0=> Series III I/O, 1=> HPIB I/O |
- SYSDB relative pointer to the DIT.
- SYSDB relative pointer to the DIT.
- SYSDB relative pointer to the III.
- SYSDB relative pointer to the III.
- Hardware Device Controller Status. Set when the driver detects an error. Whenever not zero, SIODB logs an I/O error and clears this word.
- time out completed flags. If a timeout occurs in response to a timer request type XZO (I/O request), the sign bit is set in this word.
- The ID bit in DFIBG is also set, and the monitor for this device is awakened. (Only used if timer services are requested. Must be word #8 if timer services are requested. Must be word #8 if timer services are requested.

G.01.00 13- 26

I / 0


DIT For 7905/7906/7920/7925

DTRQX

	0 1 2 3 4 5 6 7 8 9 10 11 12 15		
	O 1 1 ACT REQ CD M O I/O IRK 1 O O STATE		DFLAG
1	NEXT DITP	1	DLINK
2	CURRENT (RCTIVE) DISC REQUEST	į	DIOQP
3	LOGICAL DEVICE NUMBER	3	DLDEV
4	DLTP	4	DDLTP
5		5	DILTP
6		6	DRQST
7	# OF ERROR WORDS TO LOG DIT REL ADDR TO LOG	7	DSERR
8	INDEX OF FIRST REQUEST IN QUEUE	10	DMANQ
9		11	TOMANO
10		12	DUNIT
11	SIO PROGRAM-RELATIVE ABORT ADDRESS	13	DLOGSIOP
12 13	CURRENT PHYSICAL	14 15	CPDA
14		16	CDBA
15		17	HCR
16			CMC
17		21	SYSBUFA
18		22	STAT1
19	I	23	STRT2
20	_	24	CEDA
21	HEAD SECTOR	25	
22	1		Ì
23	CYL		

I / 0

DIT for 7905/7906/7920/7925 (Cont.)



DMISC (15:1) L'STAT'ERR - 1 Last transfer ended in error.

IOT - I/O Devices O - non-HP-IB 1 - HP-IB Systems 2 - unused 3 - unused

Error and Retry Information

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 OMISC OF TOO

retry determination

D - retry determination
S - request syndrone
E - request error information
H - update track map
U - writing track map
C - issued a recalibration

CL- driver issuing channel clear T - timeout wait

MOTE: Integrated Cartridge Tape's DIT has the same format.

G.01.00

T / n

```
X34 REIDCIDRIEN
                           |LOCAL STATE| RPSWORD1
   X35
                           T2 | RPSHORD2
```

DFLAG - Flags and request state

TM TERM - Set if device is a terminal.

DS DISC - If TM = 0 and this bit is set then the device is a disc, otherwise device dependent.

RC RCTIVE - R monitor is currently servicing this device.

RQ REQUEST - R service request is pending while the monitor is

RV RCUUEST - R service request is pending while the nonitor is active.

IO IOPROG - Rn I/O Channel Program is rumning for this device.
Rn interrupt or response has occurred for this device.
NO HOTROY - Go to state X10 after Idle Channel Program is started.
ST STURIT - The device nonitor is starting an Idle Channel Program for this device. There is no IOQ associated with this type of request.

STRTE - State of the device monitor. Specifies the next action to be taken in SIODM in servicing the request:

0 - start new request 1 - not used

1 - not used
2 - call driver initiator procedure
3 - call driver completor procedure

- not used

4 - not used
5 - process request completed
6 - initiate device recognition sequence
7 - start operator intervention wait
110 - wait for interrupt (operator intervention)
restart at state 0
211 - wait for data segment freeze, then state 2
212 - wait for driver initiator to be frozen, then
allocate controller (state 2)
213 - wait for I/O completion interrupt, then state 3
214 - wait for I/O completion interrupt, then state 3
215 - not used
216 - wait for initiator make present, then state 2
217 - wait for completor make present, then state 3

DLINK - A SYSDB relative pointer to the next DIT requesting this resource or service.

DCURREQP - A current request sysbase index.

DUNIT. (0:2) - I/O system type

0 - non-HP-IB 1 - HP3000 HP-IB Systems 2 - Unused 3 - Unused

G.01.00 13- 31

CS 80 Disc Device Information Table (DIT)

There is one DIT per physical device. If a physical device represents more than one logical device, the logical device number is obtained from the IOQ element. For the CS'80 disc controller, there will only be one device. The following diagram shows the DIT used by the CS'80 disc driver.

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	NNEMONIC
0	THIDSIACIRGICDI OI OITOITAINOISTI OI STATE	DFLAG
1	SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
2	Current request index	DCURREQP
3]	Logical device number	DLDEV
4	SYSDB relative pointer to Device Linkage Table	DDLTP
5	SYSDB relative pointer to Intrp Linkage Table	DILTP
6	DSTAT is -1 when a system powerfail occurred	DSTAT
7	Hardware error status. Set when the driver detects an error. Whenever <>0, the driver monitor logs an I/O error and clears this word	DSERR
X10	index of first request in queue	DQHEAD *
X11]	index of last request in queue	DQTRIL *
X12	IOT Physical Unit #	DUNIT
X13	Table relative index to system buffer element	DSBUFADDR
X14	High order logical sector address of bad blk	DBADB LK1
X15	Low order logical sector address of bad blk	DBADBLK2
X16	Byte transfer left when bad block occurred	DBADXFER
X17	Hardware logged error status - CPVA (0)	DLOGERROR
X20	Channel program aborted relative offset	DSIOPSTOP
X21	Disc status (20 bytes)-Logged on status error	DSTATUS
· [•
٠Ĭ		•
X33	LK IF HD SUBSTATE	DMISC

G.01.00

T / n

DLDEV - Logical device number of this device.

DSTAT - Set to a -1 when a system powerfail has occurred.

DSERR - Pointer to status to be logged.

Bits(0:7) - Number of words to be logged. Bits(8:15) - Offset relative to DITP(0).

DMISC - Device dependent processing flags

LOCK'FLG - Lock flag denoting unload status of the disc volume.

0 - Allow operator unload to the volume. 1 - Deny operator unload to the volume.

IGNORE'INT'FLG - Ignore unexpected interrupt flag.

SUBSTATE - Indicates state of the idle channel program:

0 - Normal idle channel program наіт 1 - Idle request being serviced наіт

DSBUFADDR - SYSDB relative pointer to the system buffer element used to read the DSCT. Zero, if no element gotten.

DBADBLK1 - High order logical sector address of the bad block for the Defective Sector Table (DSCT) entry.

 $\ensuremath{\mathsf{DBADBLK2}}$ – Low order logical sector address of the bad block for the DSCT entry.

DBADXFER - Byte transfer left when bad block occurred.

DLOGERROR - CPVA(0) logged on hardware error status.

<code>OSIOPSTOP</code> - Stopped channel program relative offset location due to an error in $\mbox{CPVR}(0)$.

DSTATUS - 20 bytes disc status logged on status error. (See CS'80 Disc Drive Status).

RPSWORD1 - Flags and local state

RE - Read revision code done.
Set if read revision code level is done.
DC - RPS revision code.
Set if controller is "PEP"ed.
DR - RPS desirable.
Set if RPS is desirable.
EN - RPS enabled.
Set if default value for RPS is enabled.
NR - Driver is processing a narginal data error

from the drive. Do not return hard error. Local State - State of the local request made by driver

No local request is being processed
 Reading rev code

1 - Reading rev code 2 - Setting default RPS

RPSWORD2 - Default value for RPS

11 - Time to target in hundreds of microseconds 12 - Window size in hundreds of microseconds

DIT For 7970 Magnetic Tape

DELAG NEXT DITE DLTNK TOOP DIOQP LOGICAL DEVICE NUMBER DLDEV DLT PTR DOI TP ILT PTR DILTP HARDWARE STATUS DSTAT 6 RH RU SHICE DC ERROR STATUS DSERR TIMEOUT FLAGS DTIME TIMER REQUEST INDEX NTROX PHYSICAL UNIT # DUNIT 13|RB4| RW DOFLAGS

IOT - I/O Devices O - non-HP-IB 1 - HP-IB Systems 3 - unused 4 - unused

DSRVE - Device processing flags.

RU RUBIT - Indicates tape has been геноинд.

RU RUBIT - Indicates that a rewind/unload was performed to allow a write-ring mount.

SH SHORT - R short read is in progress. After completion of read, EOF is checked for and if not present, the requested bytes are transferred from the short-read buffer to the user's buffer.

CE CESTAT - Channel parity error processing is in progress.

DC DSFLRG - Transfer used data chaining - used for computing the transmission log.

RU - (DDFLRGS, bit 15) if set, tape is rewound.

RB4 - (bit 14) if set, need to rewind tape before next write.

I / 0

G.01.00 13- 34

G.01.00 13- 33

QMISC

Where
R - retry in progress
B - backspace in progress
F - foruard space in progress
G - gap in progress
E - backspace on data end-of-file

S - short read in progress
U - unload tape for write ring installation

I / 0

DIT for 7976 Magnetic Tape

There is one DIT per physical device. If a physical device represents more than one logical device, the logical device number is obtained from the IOQ element. The following diagram shows the DIT used for the mag tape driver.

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	O O O I RC RO O TO TO O O O STATE	DF LAG
1	SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
2	SYSDB relative pointer to the first IOQ in request list for this device	DIOQP
3	Logical device number	DLDEV
4	SYSDB relative pointer to Device Linkage Table	DOLTP
5	SYSDB relative pntr to Interrupt Linkage Table	DILTP
6	RW RU SH DC PF	DSRVE
7	Hardware error status. Set when the driver detects an error. Whenever <>0, the driver nonitor logs an I/O error and clears this word	DSERR
	Bit 0 is set at completion of timer	DTIME
X11	Interrupt status for this unit. Set by the driver each time it processes an interrupt.	DSTAT
X12	IOT //////////// Physical unit #	
X13	Holds the time out request entry index while a timer is active.	DRQST
×14	Error log. Contains 5 valid bytes of status	DLOGERROR

DFLAG - Flags and request state

AC ACTIVE - A monitor is currently servicing this device.

RQ REQUEST - A service request is pending while the monitor is

RQ REQUEST - R service request is pending while the monitor is active.

NU MUNIT - This device is on a multi-unit controller.

10 IDPROG - Rn I/O Channel Program is running for this device.

NO MOTRDY - Go to state XIO after Idle Channel Program is started.

ST STWAIT - The device monitor is starting an Idle Channel Program for this device.

The device monitor is starting an Idle Channel Program for this device. There is no IOQ associated with this type of request.

OITS ٥

2

10 11 12

DSTAT - Mag tape controller status

END OF FILE (EOF)

UNIT ONLINE GCR (6250 BPI DENSITY) UNIT NUMBER (MSB)

UNIT NUMBER (LSB) TIMING ERROR TAPE RUMANAY

BEGINNING OF TAPE (BOT) / LORD POINT (LP) END OF TAPE (EOT) SINGLE TRACK ERROR (NOT LOGGED FOR READS)

COMMAND REJECT (REJECT)
FILE PROTECT (NOT WRITE EMBBLED; NO WRITE RING)
MULTIPLE TRACK ERROR (MTE)

REWINDING * (REPORTED AS UNIT NOT READY) INTERFACE BUSY *

- State of the device monitor. Specifies the next action to be taken in SIODM in servicing the request:

0 - start new request
1 - not used
2 - call driver initiator procedure
3 - call driver completor procedure
4 - not used STRIF 3 - call driver completor procedure
4 - not used
5 - process request completed
6 - initiate device recognition sequence
7 - start operator intervention mait
X10 - mait for interrupt (operator intervention)
restart at state 0
X11 - mait for data segment freeze, then state 2
X12 - mait for driver initiator to be frozen, then
allocate controller (state 2)
X13 - mait for I/O completion interrupt, then state 3
X14 - mait for controller, then call driver initiator
X15 - not used
X16 - mait for initiator make present, then state 2
X17 - mait for completor make present, then state 3

DSRVE - Device processing flags
RW RWBIT - Indicates tape has been rewound.
RW RWBND - Indicates that a rewind/unload was performed to allow a write-ring mount.
SH SHORT - A short read is in progress. After completion of read,
EOF is checked for and if not present, the requested bytes are transferred from the short-read buffer to the user's buffer.

DC DSFLAG - Transfer used data chaining - used for computing the transmission log.
PF POWER - Device power up indication.

I / 0

Card Reader DIT

	0 1 2 3 4 5 6 7 8 9 10 11 12 15	
	O O ACT REQ O O I 1/0 IAK READ NR INSTATE	DFLAG
1	DIYP LINK TO NEXT DIT	DLĮNK
2	IOQP POINTER TO 1st REQUEST	DIOQP
3	LOGICAL DEVICE NUMBER	DLDEV
4	DRIVER LINKAGE TABLE POINTER	DDLTP
5	INTERRUPT LINKAGE TABLE POINTER	DILTP
6	(SEE BELOW)	DSTAT
7	ERROR STATUS IF NOT O	DSERR
X10	REQUESTED HORD COUNT	DTIME
X11	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	DTRQX
X 12	IOT //////// PHYSICAL UNIT #	DUNIT

G.01.00

DSTAT bits:

BIT7=COMPARE ERROR
BIT8=OF DETECTED
BITS 9-10 = OO NORMAL
O1 HOPPER EMPTY
10 UNUSED
11 STACKER FULL BIT11=INVALID HOLLERITH
BIT12=PICK FAIL OR MOTOR CHECK
BIT13=TEST
BIT14=TROUBLE
BIT15=NOT READY

Card Reader DIT Field Definitions

DFLAG - Flags and device state

ACTIVE Monitor is currently active servicing this device.

REQUEST Service for this device was requested while the monitor was active.

G.01.00

IOPROG SIO program in progress.

TOK Interrupt occurred or request aborted or preempted.

READDONE Previous read resulted in an EOF with a backup save requested. The data has been saved in an auxiliary buffer and will be passed back on the next read reque

Set when a not ready message has been issued, and cleared when the reader is found ready. Used to prevent multiple Not Ready messages when power is turned on. NRMESSAGE

MSTRIF Monitor State. See SIODM specifications for details.

DLINK - SYSDB relative pointer to the DIT for the next device requesting service for this resource.

DIOQP - SYSDB relative pointer to the first IOQ element in the request list for this device.

DLDEV - Logical device number and unit number.

UNIT Unit number of device.

LDEVN Logical device number.

DDLTP - SYSDB relative pointer to driver linkage table (DLT).

DSTAT - Device interrupt status. Contains the device interrupt status at the last interrupt. See hardware ERS for details.

DSERR - Device interrupt error status. If not zero, then holds the device interrupt status from an operation with an erroneous completion status. Causes SIODM to log an error.

DWCNT - Holds the requested transfer count in words.

G.01.00 13- 39

STATE

Device Information Table for HP-IB Card Reader

There is one DIT per physical device. If a physical device represents nore than one logical device, the logical device number is obtained from the IOQ element. The following diagram shows the DIT used for the card reader

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	O O O O O O O O O O O O O O O O O O O	DFLAG
1	SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
2	IOQ table relative index to the first IOQ in request list for this device	DIOQP
3	Logical device number	DLDEV
4	SYSDB relative pointer to Device Linkage Table	DDLTP
5	SYSDB relative pntr to Interrupt Linkage Table	DILTP
6	RD AF	DSAVE
	Hardware error status. Set when the driver detects an error. Whenever <>0, the driver nonitor logs an I/O error and clears this word	DSERR
210	Not Used	DTIME
X11]		DHENT
X12	IOT ////////// Physical unit #	DUNIT
X13	Device Status. Read from device during each execution of the channel program.	DSTRT
X14 !	Logging will be done from here.	DLOGERRO
DELO	C	•

DFLRG - Flags and request state
RC RCTIVE - A monitor is currently servicing this device.
RQ RCDUEST - A service request is pending while the monitor is active.
NU NUMIT - This device is on a multi-unit controller.
IO IDPROG - An I/O Channel Program is running for this device.
NO NOTRDY - Go to state X10 after Idle Channel Program is started.
ST STWAIT - The device monitor is starting an Idle Channel Program for this device.
The device nonitor is starting an Idle Channel Program for this device.
There is no IOQ associated with this type of request.

G.01.00 13- 41

I / 0

2608 Line Printer DIT (HP-IB Systems)

There is one DIT per physical device. If a physical device represents nore than one logical device, the logical device number is obtained from the IOQ element (however, there is only one device per 260% controller.) The following diagram shows the DIT used for the 260% line printer driver.

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
O O O O O O O O O O O O O O O O O O O	DFLAG
1 SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
2 IOQ table relative index to the first IOQ in request list for this device	DIOQP
3 Logical device number	DLDEV
4 SYSDB relative pointer to Device Linkage Table	DDLTP
5 SYSDB relative pntr to Interrupt Linkage Table	DILTP
GIVMI TAB PS FL TP	DSRVE
7 Hardware error pointer. Set when the driver detects an error. Whenever <>O, the driver моліtor logs an I/O error and clears this word	DSERR
X10 Bit 0 is set at completion of timer	DTIME
X11 Holds the time out request entry index while a timer is active.	DRQST
%12 IOT ////////// Physical Unit #	DUNIT
X13 Hardware logged error status	DLOGERROR
*	•

DFLAG - Flags and request state

AC ACTIVE - A monitor is currently servicing this device.

RQ REUUEST - A service request is pending while the monitor is

TOPROG - An I/O Channel Program is running for this device.

10PROG - An I/O Channel Program is running for this device.

10RTOY - Go to state XIO after Idle Channel Program is started.

STURIT - The device monitor is starting an Idle Channel Program for this device. There is no IOQ associated with this type of request.

G.01.00 13- 43

I / 0

STATE

- State of the device monitor. Specifies the next action to be taken in SIODM in servicing the request:
0 - start new request
1 - not used
2 - call driver initiator procedure
3 - call driver completor procedure
4 - not used

G.01.00 13- 42

- State of the device monitor. Specifies the next action to be taken in SIODM in servicing the request:

0 - start new request
1 - not used
2 - call driver initiator procedure
3 - call driver completor procedure
4 - not used

2 - Call Grayer Instacts.
3 - Call drayer completor procedure
4 - not used
5 - process request completed
6 - initiate device recognition sequence
7 - start operator intervention wait
X10 - wait for interrupt (operator intervention)
restart at state 0
X11 - wait for data segment freeze, then state 2
X12 - wait for driver initiator to be frozen, then
allocate controller (state 2)
X13 - wait for I/O completion interrupt, then state 3
X14 - wait for controller, then call driver initiator
X15 - not used
X16 - wait for initiator make present, then state 2
X17 - wait for completor make present, then state 3

DLDEV - Device logical device number

IOT I/O TYPE - I/O System type
O Series II / III I/O system
1 = HP-IB Systems

DSRVE - Device processing flags RD READDONE - R card has already been read. RF ABORTFLAG - R device clear has already been sent for this series of aborted IOQs.

4 - not used
5 - process request completed
6 - initiate device recognition sequence
7 - start operator intervention usit
X10 - wait for intervention restart at state 0
X11 - wait for data segment freeze, then state 2
X12 - wait for driver initiator to be frozen, then allocate controller (state 2)
X13 - wait for I/O completion interrupt, then state 3
X14 - wait for controller, then call driver initiator
X15 - not used
X16 - wait for initiator make present, then state 2
X17 - wait for completor make present, then state 3

DLDEV - I/O system type, unit and logical device number IOT I/O TYPE- Type of I/O system O - H93000 Series II/III 1 - HP3000 HP-IB Systems 2 - unused 3 - unused

DSAVE - Device processing flags
VM VFCMOD - VFC has been modified.
TAB TABPFAULT - System tab default.
PS PRESPACE - Last request used prespacing.
FL FULL - Line printer buffer is full.
TP TOP - Printer is at top of form

2608 Line Printer Status

STATE

BYTE 1 & BYTE 2: BITS USE ON LINE NOT READY VFC CHRNNEL 9 (BOTTOM OF FORM)
VFC CHRNNEL 12 (TOP OF FORM) VFC INITIALIZED 6/8 LINES PER INCH (NOT USED) POWER RESTORED/UNIT RESET ON LINE PRINT MECH ERROR SELF TEST FAILURE PAPER ERROR SELF TEST MODE 10 11 12 13 14 15 6/8 LPI PLATEN/RIBBON ERROR (NOT USED)

G.01.00 13- 45

I / 0

```
DLDEV - I/O system type, unit and logical device number IOT I/O TYPE - Type of I/O system 0 - HP3000 Series 2/3 1 - HP3000 HP-IB Systems 2 - Unused 3 - Unused
DSRVE - Device processing flags
BJ BETJOB - Between jobs flag. If set, suppress
Powerfail nessage.

AB ABORT - Abort (caused by Powerfail or Operator)
has occurred.

PS PRESPACE - Last request used prespacing.
FL FULL - Line printer buffer is full.
TP TOP - Printer is at top of form
```

HP 2619R or 2613 Line Printer DIT (HP-IB Systems)

There is one DIT per physical device. If a physical device represents more than one logical device, the logical device number is obtained from the IDQ element (however, there is only one device per 2631 controller.) The following diagram shows the DIT used for the 2631 line printer driver.

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEHONIC
0	O O O O O O O O O O O O O O O O O O O	DFLAG
1	SYSDB relative pointer to the DIT for the next device requesting this resource or service	DLINK
2	IOQ table relative index to the first IOQ in request list for this device	DIOQP
3	Logical device number	DLDEV
4	SYSDB relative pointer to Device Linkage Table	DDLTP
5	SYSOB relative pntr to Interrupt Linkage Table	DILTP
6	BJ AB PS FL TP	DSRVE
7	Hardware error status. Set when the driver detects an error. Whenever ⟨>0, the driver monitor logs an I/O error and clears this word	DSERR
210	Bit 0 is set at completion of timer	DTIME
X 11	Holds the time out request entry index while a timer is active.	DRQST
X12	IOT ///////// Physical unit #	DUNIT
213	Hardware logged error status	DLOGERROR

DFLAG - Flags and request state

AC ACTIVE - A monitor is currently servicing this device.

RQ REQUEST - A service request is pending while the monitor is

ID IDPROG - Rn I/O Channel Program is running for this device.

NO NOTRDY - Go to state 210 ofter Idle Channel Program is started.

ST STMRIT - The device nonitor is starting an Idle Channel Program for this device.

The device nonitor is starting an Idle Channel Program for this device. There is no IOQ associated with this type of request.

G.01.00 13- 46

I / 0

HP

2680A	/2688R DIT		
	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15		
DITO	10 10 INCIRGIO 10 ISPICPITAINRISMI ! STATE		DFLAG
1		ļ	DLINK
2		ļ	DIOQP
3	! LOGICAL DEVICE NUMBER		DLDEV
4	! DRIVER LINKAGE TABLE POINTER		DOLTP
5	! INTERRUPT LINKAGE TABLE POINTER	!	DILTP
6	! SPECIAL ERROR CONDITIONS TO BE LOGGED		DSTAT
7	! ERROR LOGGING INFORMATION	!	DSERR
8		ļ	DTIME
9	! TIMER REQUEST INDEX (TRL) OR ZERO	į	DTRLX
10	! IOT !//////// PHYSICAL UNIT #	Ī	DUNIT
11	CURRENT DATA WRITE BYTE COUNT	!	DCBCNT
12		•	DCHCNT
13		!	DRCNT
14	! BUFFER OFFSET FOR NEXT # OF WORDS TO XFER.	ļ	DOFFSET
15			DDEBUG
16	! I/O STATUS BLOCK WORD 1 GETS LOGGED FROM HERE		DLOGBUFFER
17	! I/O STATUS BLOCK WORD 3 GETS LOGGED FROM HERE		
18/33	! I/O STATUS AREA (16 HORDS, SEE DEFINITION)		DIOSTAT
	***************	+	
DFLAG	- DEVICE RELATIVE FLAGS. AC ACTIVE BIT. 1 IMPLIES A MONITOR CURRE	NTI	LY
	SERVICING THIS DEVICE. RQ REQUEST BIT. 1 IMPLIES SERVICE REQUES	TEI)
	WHILE MONITOR IS ACTIVE. SP SIO PREEMPTION. IF SET THEM A PREEMP?		
	REQUEST HAS BEEN QUEUED FOR THIS DEVI PREEMPT CODE IS SET IN IOQ ELEMENT.		
	CP CHANNEL PROGRAM IN PROGRESS. IF SET, H CHANNEL PROGRAM IS CURRENTLY EXECUT	IN	i.
	IA IF SET, AN INTERRUPT OR RESPONSE HAS	OC	URRED.

IF SET, DEVICE IS IN A NOT READY OR OPERATOR WAIT. IF SET, AN IDLE CHANNEL PROGRAM SHOULD BE STARTED FOR THIS DEVICE. CURRENT DRIVER STATE AS DEFINED BY THE MONITOR. FOR THIS DEVICE.

CURRENT DRIVER STATE AS DEFINED BY THE MONITOR.

RLLQUABLE STATES ARE:

0 - START REQUEST

1 - NOT USED(BUT RESERVED)

2 - CALL DRIVER INITIATIOR

3 - CALL DRIVER COMPLETOR

4 - UNUSED(BUT RESERVED)

5 - COMPLETE REQUEST. PERMAPS RETURN TO USER.

6 - UNEXPECTED INTERRUPT OCCURRED.

7 - START OPERATIOR INTERVENTION MAIT.

10 - MAITING (ON DEPARTOR). RESTART AT O.

11 - MAITING (ON DEPARTOR). RESTART AT O.

11 - MAITING (TANTATOR).

12 - MAITING (TANTATOR CODE MEKEPRESENT/FREEZE)

13 - WAITING (FOR COMPLETION INTERRUPT)

14 - MAITING (FOR COMPLETION INTERRUPT)

15 - UNUSCOUNT RESERVED)

16 - MAITING (TANTATOR CODE MEKEPRESENT)

17 - MAITING (TANTATOR CODE MEKEPRESENT)

17 - MAITING (TANTATOR CODE MEKEPRESENT) MSTATE DLDEV - I/O SYSTEM TYPE, UNIT AND LOGICAL DEVICE MUMBER.
I/O SYSTEM TYPE.
O - HP3000 SERIES II/III (SIO/DIO)
1 - MP-IB Systems
2 - RESERVED
3 - RESERVED DCBCNT - CURRENT BYTE COUNT TO BE TRANSFERRED. DOUGHT - CURRENT WORD COUNT TO BE TRANSFERRED. DRONT - REMOTATING HORD COUNT TO TRANSFER. DOFFSET - OFFSET IN BUFFER OF NEXT # WORDS TO TRANSFER. DDEBUG - IF BIT 15=1 THEN DEBUGGING INFO WILL BE SENT TO CONSOLE DLOGBUFFER - STATUS WORDS 1 & 3 ARE MOVED HERE TO BE LOGGED IF THEY WERE LOGGED FROM THE I/O STATUS BLOCK THEIR CONTENTS MIGHT BE CHANGED BEFORE THEY WERE LOGGED. DIOSTAT - I/O STATUS AREA 16 WORDS, SEE I/O STATUS BLOCK DEFINITION. G.01.00 13- 49 I / 0 IS NO MCS FAULT. SEE DCS ERS FOR A DESCRIPTION OF THE MCS FAULT NUMBERS.

WORD 4 - BIT= 0 - (CL) NO ROOM FOR ATTEMPTED CHARACTER SET LOAD.

1 - (FL) NO ROOM FOR ATTEMPTED FOR LOAD.

2 - (VL) NO ROOM FOR ATTEMPTED FOR LOAD.

3 - (CU) ATTEMPT TO PRINT DATA AND THERE IS NO CURRENTLY SELECTED CHARACTER SET.

4 - (FU) ATTEMPT TO PRINT DATA AND THERE IS NO CURRENTLY SELECTED CHARACTER SET.

5 - (VU) ATTEMPT TO PRINT DATA AND THERE IS NO CURRENTLY SELECTED VFC SET.

6 - (IL) ATTEMPT TO PRINT DATA AND THERE IS NO CURRENTLY SELECTED LOGICAL PAGE TABLE (LPT) ENTRY.

7 - (IP) ATTEMPT TO HOVE PEN OF THE LOGICAL PAGE.

8 - (ST) THE 2680A-2688A COULD NOT PROCESS ALL OF THE DATA BEFORE IT WAS SUPPOSED TO BE TRANSFERRED TO THE DATA BEFORE IT WAS SUPPOSED TO BE TRANSFERRED TO THE DATA BEFORE IT WAS SUPPOSED TO BE TRANSFERRED TO THE DATA BEFORE IT WAS LOCK CONTRINS FORMAT ERROR.

10 - (IR) INVALID RECOVERY BLOCK RECEIVED FROM SPOOLER.

11 - (PP) HAXIMUN MUMBER OF COPIES PER PHYSICAL PAGE HAS BEEN EXCEEDED. THIS IS A RESULT OF THE SPOOLER PROCESS SETTING THE MAXIMUNI COPIES PER PAGE WITH FUNCTION CODE 132.

12 - (NJ) A COMMAND OR FUNCTION CODE WAS RECEIVED WHEN NO "JOB" WAS IN PROCESS. THE COMMAND OR FUNCTION WAS INDURED BY THE DCS.

13 - (NI) NO HEIDRY 2680R/2688B DYNAMIC MEMORY BLLOCATION BY CHORGE BY THE DCS. THE CUMPHAD OR FORCITOR WHS
IN PROBRESS. THE CUMPHAD OR FORCITOR WHS
INDIRECTED THE THEORY ALLOCATION HAS
DETECTED THAT HAIN HERORY IS COMPLETELY OCCUPIED WITH
CHARACTER SETS, VFC'S, FORMS AND DATA SUCH THAT THE
2680A/2688A CANNOT PROCESS THE CURRENT INPUT DATA. DATA
WILL BE LOST! MILL BE LOST!

14 - (TL) ATTEMPT TO PRINT DATA AND THERE ARE MORE THAN
THE MAXIMUM ALLOWABLE LOGICAL PAGE TABLE (LPT)
ENTRIES SELECTED.

15 - (NC) R NOM-EXISTENT VFC CHANNEL WAS SKIPPED TO. WORD 5 - BIT= 0 - (LP) LOGICAL PAGE TRUNCATED TO FIT PHYSICAL PAGE.

1 - (PF) PAGE SIZE REQUIRED BY PROGRAMMER DID NOT MATCH PAGE SIZE SET BY OPERATOR. OPERATOR PAGE SIZE PREVAILS. 2 - (NC) NO CHBRACTER SET SELECTED. WORDS 6/11 NOT USED BUT RESERVED FOR FUTURE USE. WORDS 12/13 - THE RECORD MUNBER WHICH CONTAINS THE OFFENDING ERROR
AS DEFINED BY WORD FOUR. IF A POWER FAIL OCCURS DURING
A "JOB". THE POWER FAIL BIT IS SET RAND A SHEET MUNBER IS
HADE RVAILABLE IN WORDS FOUNTEEN HAW FIFTEEN. HOWEVER,
THE RECORD NUMBER IS LOST AND CHANOT BE REPORTED. THESE
WORDS OCCUR IN A "JOB" ONLY.

I/O Status Block 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 10 !--THE "OR" DF HORDS 1/15 IS LOCATED HERE----! DIT 17 18 19 2 MCS FAULT NUMBER 3 20 ICLIFLIVLICUIFUIVUIILIIPISTISBIIRIMPINJIMMITLINCI 21 !LP!PF!NC! ! ! (RESERVED) ! ! ! ! ! ! ! 22 (RESERVED) ! ! ! ! ! 23 !!!!! (RESERVED) !!!!! 7 24 8 25 26 (RESERVED) ! ! ! ! ! 10 ! 27 | | | | (RESERVED) | | | | | 11 28 RECORD NUMBER OF ERROR 12 29 IF WORD 4 IS 13 ! NON-ZERO 30 14 ! SHEET NUMBER OF ERROR IF WORD 4 IS NON-ZERO ! 31 15 ! LAST SHEET TRANSFERRED IF "JOB" & POWER-ON 32 WORD O - EACH BIT IS THE 'OR' OF ONE WORD IN THE TRBLE (EXCEPT BIT O WHICH IS NOT USED). THEREFORE, BIT .(1:1) IS SET IF WORD 1 IN THE TABLE IS NOW-ZERO. WORD 1 - BIT= 0 - (OF) ONLINE/OFFLINE BIT.

1 - (NS) MESSAGE BEING DISPLAYED ON THE 2680A/2688A CONSOLE.

2 - (PW) POWER UP COMPLETED SINCE LAST I/O STATUS READ.

3 - (PE) PARTITY ERROR DETECTED ON PHI COMMAND.

4 - (TE) TRANSMISSION ERROR DETECTED IN THE PRINTER.

5/15 - RESERVED. UNUSEO.

HORD 2 - NOT USED, RESERVED.

MORD 3 - NCS FAULT NUMBER. CONTAINS AN INTEGER DESCRIBING THE LAST FAULT TO OCCUR SINCE THE LAST TIME THE I/O STATUS WAS READ OR THE HP 2680A/2688A WAS POWERED DOWN. IF THE WORD IS ZERO THERE

I / 0

IN ADDITION, WHEN A POWER FAIL OCCURS DURING A "JOB", THE POWER ON BIT IS SET IN WORD ONE AND THE SHEET NUMBER OF THE LAST SUCCESSFULLY TRANSFERRED PAGE IS PLACED HERE. THIS IMFORMATION IS FOR USE BY THE SPOOLER SHOULD A RECOVERY OF A "JOB" BE DETERMINED. THESE WORDS OCCUR IN "JOB" ONLY.

ALL HORDS OF THE I/O STATUS ARE CLEARED WHENEVER THE STATUS BLOCK IS RETURNED TO THE HOST. IT IS UP TO THE HOST CPU TO RETAIN ANY ONGOING STATUS BITS REQUIRED.

OMISC -

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 |MB|RB|RB|IO|TO| | XFER | PARITY | QMISC T003 !M8!R8!AB!IO!TO!

WHERE:

USER REQUESTED TRANSFER IN EXCESS OF 4096
MORDS. THE DRIVER CAN WRITE UP TO 4096 MORDS
TO THE 26800/26589. IN ORDER TO HAPOLE UP TO 32K
MORDS, MULTIPLE WRITES ARE USED WITHOUT A
RETURN TO THE USER WHO CRILED THE DRIVER.
THIS BIT INDICATES THAT MULTIPLE WRITES ARE .(0:1) ~ MB

.(1:1) - RB THE CURRENT WRITE BLOCK MUST BE RETRIED.

.(2:1) - AB USER REQUESTED ABORT IN PROGRESS FLAG.

I/O STATUS HAS BEEN READ AND IS AVAILABLE. .(3:1) - I0

.(4:1) - TO GENERAL I/O CONTROLLER TIMED OUT.

.(5:4) - RESERVED NOT CURRENTLY USED.

.(9:3) - XFER 2680A/2688A TRANSFER ERROR COUNTER.

.(12:3)- PARITY CHANNEL PROGRAM COMMAND PARITY ERROR COUNTER.

.(15:1)- RESERVED NOT CURRENTLY USED.


NOTE IN THE ABOVE, SINGLE BIT FIELDS ARE AS DEFINED WHEN THE BIT IS A LOGIC "1".

WORDS 14/15 - THE SHEET NUMBER ON WHICH THE ERROR OCCURRED AS DEFINED BY WORD FOUR. IF AN ERROR OCCURS IN THE ENVIRONMENT FILL AT THE START OF A "JOB", THEN THIS MUMBER WILL BE ZERO.

Disc Request Table and Disc Requests

Requests for disc transfers are effected by acquiring an entry from the Disc Request Table (DISCREGIAR), filling the proper information, and calling the DISCOMPANAGER to link the request into the device's doubly linked request qu

The head and tail of a device's request queue are contained in the devices' DIT.




G.01.00 13- 53

Disc Request Table

DISCREQTAB DST ENTRY# = 56 (270) DISCREQTAB PRT = 21017

Disc Request Table Entry O Format



G.01.00

I / 0

Disc Request Element Format

INLOCAL Word 01 REQUEST URGENCY CLASS URGCLASS Hard 02 LOGICAL DEVICE MINNER I DEVN MISCELLANEOUS DST (IF PROCESS DISC I/O) DSTN Hord O4 SI S=STACK BANK (IF SEGMENT TRANSFER) Hord O5 OFFSET INTO DATA SEG (IF PROCESS DISC I/O) ADDR ADDRESS IN BANK (IF SEGMENT TRANSFER) Nord 06 1 COUNT/XLOG/CONTROL RETURNS Hord 07 XFERCNT Mord 08 P1 (HODR IF SEGMENT TRANSFER PAR1 Word 09 P2 (LODA IF SEGMENT TRANSFER PAR2 Word 10 /////// QUALIFIER | STATUS STAT Word 11 FREE! PCB NUMBER PCBN INDEX OF PREV REQUEST IN QUEUE PREVREOP Word 121 Hord 13 INDEX OF NEXT REQUEST IN QUEUE NEXTREOP Hord 14 SEGIDENTIFIER (IF SEG TRANSFER) SEGIDENT Hord 15 Word 16 DISPLACEMENT OF READ OR WRITE FROM SEG BASE(MM) SEGDISP

Note: Upon return to free list, word (#1) becomes index of next $\mbox{\it EE}$ free entry.

I / 0

- QFLAG - Request dependent flags
.ABORT Request has been aborted externally. Hord O Bit O . NMREO Request is for a segment transfer. . DIAG Bit 2 Diagnostic request (not used). System Buffer. Target is a system buffer whose index is relative to the start of the SBUF table. Bit 3 . SBUF Bit 4 . TOURKE Wake caller on completion of request. Bit 5 . BLOCKED Blocked I/O. Caller is waited in ATTACHIO until request is completed. Request has been completed and caller woken if he had specified. Bit 6 COMPLETED .DATAFRZN Bit 7 Data segment has been made present and is Bit 8 . MAMERRORD MAN error on data segment make present. Bit 9 .PREQQUEUED Request is queued into disc's reg queue Bit 10 .SFAIL Start SIO failure in GIP. Bit 11 .PFATI The I/O has been aborted because of a powerfail. Bi+ 12 CHRRED Request is device's current request. .DISABLED Bit 13 Request is disabled. Bit 14 . LDR Request in local DRO. Bit 15 .INLOCAL Buffer DST is in process locality. Word 2 - QLDEV.QLDEVN - Logical Device Number Word 3 - QMISC - Device dependent. MODSTN - If SYSBUFRs is clear then this is the DST number of the target data segment. If bit 0 is set then buffer address is a DB offset value instead of segment relative offset (implemented for MODENT IO and MOBUFF). Word 5 QRODR - Offset in data segment or sys buff table to target data buffer. Word 6 QFUNC.FUNC - Function code and qualifiers as specified by driver.

G.01.00

Word 7
QXFERCNT-On initiation specifies the word count if positive or byte count if negative. At completion of the request this location contains the actual transmission count in the same units as the call. Certain control requests return data through this location.


call. Lerian commend of the commend of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the call of the

NOTE: See I/O System Status Returns.

Word 11 - bit 0=1 Q element is on free list.

G.01.00 13- 57

IOQ Table Layout



G.01.00 13- 58

I / 0

I / 0

I/O Queue Element (IOQ)

IOQ (Cont.)				
ENTRY 3				
Indeterminate				
ENTRY 4 (IN USE)				
	<			
INDEX OF 2	ļ			
ENTRY 5				

ļ	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	
٥	REGUEST DEFENDENT LENGS	QFLRG
1	IOQ POINTER	QLINK
2	QLDEVN	QLDEV
3	MISCELLANEOUS	QMISC
4	S DATA SEGMENT DST NUMBER	QDSTN S(Nord 4(0:1) Stackflag If set QADDR is DB rel.
5	ADDRESS	QADDR
6	UNIT # FUNCTION	QFUNC
7	COUNT/XLOG/CONTROL RETURNS	QUBCT
8	P1	QPRR1
9	P2	QPAR2
10	//////////////// QUALIFIER STATUS	QSTAT
11	FR] PCBN	QPCBN

•		•
FLRG - lit 0	Request depend .ABORT	ent flags Request has been aborted externally.
Bit 1	.SPECIAL	Special handling is to be applied to this request. For disc, indicates a memory management request.
Bit 2	.DIRG	Diagnostic request (not used).
Bit 3	. SBUF	System Buffer. Target is a system buffer whose index is relative to the start of the SBUF table.
it 4	. IONAKE	Wake caller on completion of request.
Bit 5	.BLOCKED	Blocked I/O. Caller is waited in ATTACHIO until request is completed.
Bit 6	.COMPLETED	Request has been completed and caller woken if he had specified.

I/O Queue Element (Cont.)

Bit 7	. DATAFRZN	Data segment has been made present and is frozen.
Bit 8	. MAMERRORD	MAM error on data segment make present.
Bit 9	.PREQ	This request has been started but was preempted by a MRM request.
Bit 10	.SFRIL	Start SIO failure in GIP.
Bit 11	.PFAIL	The I/O has been aborted because of a powerfail.
8its12-13	. PREEMPT	Preemptive type code: 1-soft, 2-hard.
QLINK - T	.MSGDONE able relative ord of elemen ogical Device evice depender	Number
d	ata segment. 🕽	clear then this is the DST number of the target (f bit O is set then buffer address is a DB offset of segment relative offset (implemented for OMBUFF).
QADDR - 0 QFUNC.FUN QUBCT - 0 C	ffset in data C - Function on initiation of ount if negation ontains the ac	segment or sys buff table to target data buffer. code and qualifiers as specified by driver. pecifies the word count if positive or byte twe. At completion of the request this location trust transmission count in the same units as the control requests return data through this
QPRR1 - P	arameter one,	defined by driver defined by driver
QMISC - M QPCBN - P	iscellaneous : CB Number of :	oerined by Griver. request dependent storage available to driver. process which made this request. Zero if with any process and IOQ is to be returned
	LIFIER - A cod	te which further defies or qualifies the
.STA	TUS - General the requ 0 - not 1 - suc 2 - enc 3 - uni	ral status. Defined by driver. Status. Indicates current and result state of seat according to the following codes. • started or awaiting completion. cessful completion. of file detected. swal condition.
	4 - irr	recoverable error.

Mord 11 bit 0- Queue element is on free list.

G.01.00 13- 61

I/O System Status Returns

	X SUTATE
O - PENDING	
1 - WAITING FOR COMPLETION	10
2 - DOING ERROR RECOVERY	20
3 - NOT RERDY WAIT	30
4 - NO WRITE RING WAIT 5 - NEW PAPER TAPE WAIT	40
2 - MEN LALEK LALE MATI	50
1 - SUCCESSFUL	
O - HORNAL	1
1 - READ TERMINATED WITH SPECIAL CHARACTER	11
2 - TAPE RETRY FOR SUCCESS REQUIRED	21
3 - LOW TAPE OR END OF TAPE AFTER WRITE	31
2 - END OF FILE	
1 - PHYSICAL END OF FILE 2 - DRTR	12
2 - DHIM 3 - END OF DATA	22 32
4 - HELLO	42
5 - BYE	52
6 - JOB	62
7 - END OF JOB	72
3 - UNUSUAL CONDITION	
1 - TERMINAL PARITY ERROR	13
2 - TERMINAL READ TIMED OUT	23
3 - I/O ABORTED EXTERNALLY	33
4 - DATA LOST	43
5 - DATA SET NOT RERDY OR DISCONNECT OR UNIT NOT ON LINE	53
6 - ABORTED BECRUSE OF POWER FAIL	63
7 - BOT AND BSR. BSF REQUEST	73
10 - TAPE RUNAWAY	103
11 - EOT AND WRITE REQUEST	113
12 - NO WRITE RING RFTER REQUEST TO OPERATOR	123
13 - END OF TAPE (PAPER TAPE LOW)	133
14 - PLOTTER LIMIT SWITCH REACHED 15 - ENABLE SUBSYSTEM BREAK AND NO CONTROL Y PIN	143 153
16 - READ TIME RETURNED OVERFLOW	163
17 - BREAK STOPPED READ	173
20 - WRITE AND NO CARD IN WAIT STATION	203
21 - DEVICE POWERED ON - OPERATING ENVIRONMENT LO	
27 - VFC HAS BEEN RESET	273

G.01.00 13- 62

I / 0

I/O System Status Returns (Cont.)

4 - IRRECOVERABLE ERROR

A TINIA TA AFAIRAT	_
O - INVALID REQUEST	4
1 - TRANSMISSION ERROR	14
2 - I/O TIME OUT	24
3 - TIMING ERROR	34
4 - SIO FAILURE	44
5 - UNIT FAILURE	54
6 - INVALID DISC ADDRESS	64
7 - TAPE PARITY ERROR	74
11 - PAPER TAPE TAPE ERROR	114
12 - SYSTEM ERROR	124
13 - INVALID SBUF INDEX	134
14 - CHANNEL FAILURE, TIMEOUT OR NO RESPONSE FROM	144
	144
CONTROLLER	
15 - UNINITIALIZED MEDIA (LINUS)	154
16 - NO SPARE BLOCKS AVAILABLE	164
17 - DELETED RECORD DETECTED ON IBM FLOPPY DISC	174
20 - LABELED DEVICE UNAVAILABLE AFTER REELSHITCH	204
21 - PARITY ERROR DETECTED ON PHI COMMAND (EPOC)	214

5 - ERROR IN DATA CONTROL INFORMATION

EKKÜK TI	A DAIH CONIKOE THEORUHIION		
			XLOG
0 - 1	WRLID ITEM NUMBER	5	
1 - I	WALID ACCESS FOR ITEM	15	VALID ACCESS
2 - FF	RILURE IN FOPEN OR FREAD	25	FS ERROR NUMBER
3 - PF	RRITY CHANGE IN 8 BIT MODE	35	
4 - I	WALID INFO. FILE FORMAT	45	
5 - CI	HECKSUM ERROR IN INFO FILE	55	
6 - PF	ASSED VALUE LESS THAN HIN.	65	MIN. VALUE ALLOWED
7 - PF	ASSED VALUE GREATER THAN MAX.	75	MAX. VALUE ALLOWED
	ASSED VALUE IS UNSUPPORTED	105	
11 - CC	OUNT LESS THAN REQUIRED TO	115	MIN.SPACE NEEDED
RE	TURN ALL INFO.		
12 - CC	OUNT GREATER THAN AVAILABLE	125	MAX.SPACE AVAIL
TO	STORE INFO.		
13 - PF	ASSED VALUES NOT IN ASCENDING	135	OFFSET OF ELEMENT
	RDER		
14 - PF	ISSED CHARACTER HAS OTHER	145	OTHER FUNCTION
	FINED FUNCTION		

I / 0

I/O Queue Element for 7976A Magnetic Tape

	0 1 2 3 4 5 6 7	8 9 10 11 12 13 14 15	MNEMONIC
٥	Request dependent	flags (see below)	QF LAG
	SYSDO relative pointer Points to first word o	to next IOQ element.	QLINK
2	logical devi	ce number	QLDEV
3	R B F G BO TOUT F	SCNTR BSCNTR RTCNTR	QMISC
4	S If QFLAG.(3:1) is c. DST number of the t. S is set, QADDR is	arget data segment. If	QOSTN
5	Offset in the data seg table to the target da		QADDR
6	į	Function code for this request. (See next section.)	QFUNC
7	On initiation, specific or byte count (<0). A request this location of transmission count in or words) as in the rec	t completion of the contains the actual the same units (bytes	QUBCT
X10	Parameter 1. Used only the EOF specification	y for reads. Contains in bits (13:3).	QPRR1
X11	Parameter 2. Used only (13:1) is set, writing	y for writes. If bit past EOT is allowed.	QPAR2
X12	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	QUALIFIER STATUS	QSTRT
X13	PC8 NUI	1BER	

QFLAG - Request dependent flags

Bit 0 ABORT - Abort this request and return an error indication to the caller.

```
until the request is completed. Implies IOWARE.

Bit 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IOWARE).

Bit 7 DRTAFRZN - Set by the nenory management routines (RMR) when a MAKEPRESENT request is successfully completed and indicates the data segment is frozen in memory.

Bit 8 MAMERRORD - An error has occurred while MRM was trying to make the target data segment present and freeze it in memory.
                                                           it in memory
                                                        it in memory. (Not used) (Not used) Delayed failure of SIO instruction. If a call to START MPIB resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected
      Bit 9 PREQ
Bit 10 SFAIL
                                                          instruction failed when the request was selected
for execution.
The request was aborted because of a system power
failure.
      Bit 11 PFAIL
\operatorname{QMISC} – Driver request dependent flags and counters. Used mostly for error retries.

    Indicates an error retry is in progress.
    Backspace record processing for an error retry is in progress.
    Forward space record processing for an error retry is

      RETRY
      FORMARD
                            in progress.

- Gap processing for an error retry is in progress.

- Backspace record due to a data EOF processing is in
      BUDEUE
     BODEOF - Backspace record use to 5 55.
TOUTCHIR - GIC timed-out counter.
FSCHTR - Forward space record counter.
BSCHTR - Backspace record counter.
FTCHTR - Error retry counter.
QSTAT - PCB number and request completion status.
                         - The Process Control Block (PCB) number of the process which made this request. If zero, the request is not associated with any process and the IOQ element is to be returned by the system when the request has completed. General status indicating the final state of the request. The following codes are used:

0 - Not started or awaiting completion.

1 - Successful completion.

2 - End-of-file detected.

3 - New York of the processing of the process.
     PCBN
      STATUS
     3 - Unusual, but recoverable, condition detected.
4 - Irrecoverable error has occurred.

QUALIFIER - A code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)
                                                                                               G.01.00
13- 65
                                                                                                                                                                                                    I / 0
                                                         MAKEPRESENT request is successfully completed and indicates the data segment is frozen in memory. 
An error has occurred while MRM was trying to make the target data segment present and freeze it in memory.
      Bit 8 MAMERRORD -
                                                   it in memory.

(Not used)

Delayed failure of SIO instruction. If a call to STRRIO resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected
      Bit 9 PREQ
Bit 10 SFRIL
                                                    for execution.

The request was aborted because of a system power failure.
     Bit 11 PFRIL
QSTAT - PCB number and request completion status.

    The Process Control Block (PCB) number of the process
which made this request. If zero, the request is not
associated with any process and the IOQ element is to
be returned by the system when the request has completed.
    General status indicating the final state of the request.
The following codes are used:

     RSTATUS
                                          O - Not started or awaiting completion.
1 - Successful completion.
2 - End-of-file detected.
3 - Unusual, but recoverable, condition detected.
4 - Irrecoverable error has occurred.
     QUALIFIER - A code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)
HP-IB CIPER Physical Driver Request Codes
                         OPERATION FUNCTION PARAMETERS
                           READ
                                                                                  None
                           WRITE
                           FILE OPEN
                                                                   2
                                                                                  None
                           FILE CLOSE
                                                                   3
                           DEVICE CLOSE 4
                           CIPER INIT 184
                                                                                  None
CIPER Driver Return Status Codes
   General Status (13:3)
                                                                               Qualifying Status (8:5)
                                                                                                                                                              Overall (8:8)
```

I/O Queue Element (IOQ) for CIPER							
	0	1 2 3 4	5 6	7 8 9 10 11 1	2 13 14 15	MNEMONIC	
0		Request	ttt- dependen	t flags (see be	lou)	QFLAG	
11	IOO	table ind	ex to th	e next IOQ elem of element.	ent. I	GLINK	
2				Logical devi	ce number	QLDEV	
3					i	QMISC	
	S	If QFLAG.(3:1) is of the QADDR is	clear then this target data seg DB relative.	is the	QDSTN	
5	Off tab	set in the le to the	data se target d	gment or system ata buffer.	I	QADDR	
6				Function cod this request next section	e for	QFUNC	
7	7 On initiation, specifies the word count (>0) QWBCT or byte count (<0). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.						
710	Dan	amotor 1			i	QPAR1	
				-+		QPAR2	
212				QUALIFIER	IRSTATUS	QSTRT	
X 13					DCDN 1	QPCB	
QFLF	QFLAG - Request dependent flags						
Bi	t O	RBORT		this request a e caller.	nd return a	n error indication	
	t 1		- Apply	special handli	ng to this	request. (Not used)	
	t 2		- Targe	t is an index r	om the diag elative to	nostic subsystem. the SBUF Table of	
р.	it 4	IONAKE	the d	ata buffer. caller on compl	ation of no	auget	
		BLOCKED	- Black	ed T/O. The ca	ller is wai	ted in STIRCHIO	
Bi	it 5 BIOCKED - Blocked I/O. The caller is waited in ATTACHIO until the request is completed. Implies IDWARE. it 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IDWARE).						
Bi	t 7	DATAFRZN	- Set b	y the memory ma	nagement ro	utines (MAM) when a	
					_		

G.01.00 13- 66

I / 0

0 - Pending	1 - Waiting For Completion 3 - Mot Ready Wait	X10 X30
1 - Successful	0 - No Errors	X1
2 - End of File	(Not Used)	
3 - Unusual Condition	3 - Request Aborted 6 - Powerfail Abort X21 - Device Powered Up	733 763 7213
4 - Irrecoverable Error	O - Invalid Request 1 - Transfer Error 2 - I/O Timed Out Before Complet 4 - SIO Failure 5 - Unit Failure X12 - System Error X14 - Channel Failure X21 - Parity Error	24 214 224 244 254 2124 2124 2144 2214

2608 Line Printer I/O Queue Element (HP-IB Systems)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
o	Request dependent flags (see below)	QFLAG
1		QLINK
2	Logical device number	QLDEV
3	PP PE MC TOUTCNTR WAITCODE	QMISC
4	S If QFLRG.(3:1) is clear then this is the DST number of the target data segment. If S is set, QRDDR is DB relative.	QDSTN
5	Offset in the data segment or system buffer table to the target data buffer.	QADDR
6	Function code for this request. (See next section.)	QFUNC
7	On initiation, specifies the word count (%) or byte count (<0). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.	QUBCT
1 10	Parameter 1. Vertical Format specification. (See next section for detail.)	QPRR1

1/0

X11 Parameter 2. Space Mode Flage. (See next section for details.)	QPRR2
X12 /////// QUALIFIER STATUS	QSTAT
213 PCB NUMBER	QPCBN

QFLRG - Request dependent flags

Bit O RBORT - Abort this request and return an error indication to the caller.

Bit 1 SPECIAL - Rpply special handling to this request. (Not used)

Bit 2 DIRG - This is a request from the diagnostic subsystem. (Not used)

Bit 3 SYSBUFF - Target is an index relative to the SBUF Table of the data buffer.

Bit 4 IOUAKE - Wake caller on completion of request.

Bit 5 BLOCKED - Blocked I/O. The caller is waited in RTTACHIO until the request is completed. Implies IOWAKE.

Bit 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IOWAKE).

Bit 7 DATAFRZN - Set by the memory management routines (MRM) when a MRKCPRESENT request is successfully completed and indicates the data segment is frozen in memory.

Bit 8 MRMERRORD - Re meror has occurred while MRM was trying to make the target data segment present and freeze it in memory.

Bit 9 PREQ : (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used) - (Not used)

Bit 9 PREQ Bit 10 SFRIL

- (not used)
 - Delayed failure of SIO instruction. If a call to STARTIO resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected

for execution.

The request was aborted because of a system power failure. Rit 11 PERTI

QMISC - Driver request dependent flags and counters.

PRE'TO'POST - Pre to post spacing change flag.
PEJECT - Last operation was a page eject.
MMSTERCLR - Haster clear done to clear powerfail bit in status.
Haster clear done to clear powerfail bit in status.
Haster clear needs to be done from not ready condition.
- Channel time-out retry counter.
- Undicate type of wait:
- O - new request
- 1 - completion wait
- 2 - not ready wait

QSTRT - PCB number and request completion status.

PCBN - The Process Control Block (PCB) number of the process which made this request. If zero, the request is not associated with any process and the IOQ element is to be returned by the system when the request has completed.

STATUS - General status indicating the final state of the request. The following codes are used:

0 - Not started or awaiting completion.

1 - Successful completion.

2 - End-of-file detected.

3 - Unusual, but recoverable, condition detected.

4 - Irrecoverable error has occurred.

QUALIFIER - R code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)

G.01.00 13- 69

2608 Line Printer Request Codes

G.01.00 13- 70

I / D

Operation	Function	Parameters
WRITE	1	P1 - Vertical Format Specification 1 - use 1st data char as format spec
		X53 - "+", print and suppress spacing X55 - "-", print and triple space X60 - "0", print and double space X61 - "1", print and top of form
		X200-X277, print and space M-X200 lines X300-X377, print with channel M-X277
		All others, print and single space.
		P2 - Space Mode Flags (15:1) - Prespace flag if set, print then fill buffer if clear, fill buffer then print (14:1) - Mo page stepover flag if set, single and double space uithout etepover (66 lines/page) if clear, single and double space uith stepover (60 lines/page)
FILE OPEN	2	Page eject if not at top of form
FILE CLOSE	3	Page eject if not at top of form
DEVICE CLOSE	4	Page eject if not at top of form
READ STATUS	X17	Read I/O status Count - buffer must be at least 2 bytes
VFC SET	X100	Load VFC RRM Count - form length in words (O loads RRM form internal ROM) P1 - 6 for 6 UPI or 8 for 8 UPI any other value defaults to 6 UPI
TAB SET	Z101	Sets logical column definition P1 - 0 to 15, any other value defaults to 15

I / 0

2619A & 2631 Line Printer IOG Element (HP-IB Systems)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	Request dependent flags (see below)	QF LAG
1	SYSDB relative pointer to next IOQ element. Points to first word of element.	GLINK
2	Logical device number	QLDEV
3	PP PE PF TOUTCHTR HAITCODE	QMISC
4	S If OFLAG.(3:1) is clear then this is the DST number of the target data segment. If S is set, QADDR is DB relative.	QDSTN
5	Offset in the data segment or system buffer table to the target data buffer.	QADDR
6	Function code for this request. (See next section.)	QFUNC
7	On initiation, specifies the word count (20) or byte count (40). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.	QUBCT
X 10	Parameter 1. Vertical Format specification. (See next section for detail.)	QPRR1
X11	Parameter 2. Space Mode Flags. (See next section for details.)	QPRR2
X12	/////////////////// QUALIFIER STATUS	QSTAT
X13	PCB NUMBER	QPC8N

QFLAG - Request dependent flags

Bit O ABORT - Abort this request and return an error indication

Bit 0 RBURT - Abort this request and return an error indication to the caller.

Bit 1 SPECIAL - Apply special handling to this request. (Not used)

Bit 2 DIRG - This is a request from the diagnostic subsystem. (Not used)

Bit 3 SYSBUFF - Larget is an index relative to the SBUF Table of the data buffer.

Bit 4 TOWAKE - Hake caller on completion of request.

Bit 5 BLOCKED - Blocked I/O. The caller is waited in ATTACHIO

```
until the request is completed. Implies IOWAKE.

Bit 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IOWAKE).
                                                                    Set by the memory management routines (MRM) when a MRKEPRESENT request is successfully completed and indicates the data segment is frozen in memory. An error has occurred while MRM was trying to make the target data segment present and freeze it in memory.

(Not used)

Delayed failure of SIO instruction. If a call to STARTIO resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected for execution.

The request was aborted because of a system power failure.
 Bit 7 DATAFRZN -
 Bit 8 MAMERRORD
 Bit 9 PREQ
Bit 10 SFRIL
 Bit 11 PERIL
                                                                             failure.
```

QMISC - Driver request dependent flags and counters for 2631.

Format for 2619A

0 1 2 3 4 [PP | PE | PF | TO | BF | | WAITCODE |

TOUT - Channel timed out flag BUF'FILL - Buffer fill operation in progress

QSTAT - PCB number and request completion status.

PCBN - The Process Control Block (PCB) number of the process which nade this request. If zero, the request is not associated with any process and the IOQ element is to be returned by the system when the request has completed.

STATUS - General status indicating the final state of the request. The following codes are used:

0 - Not started or awaiting completion.

1 - Successful completion.

2 - End-of-file detected.

3 - Unusual, but recoverable, condition detected.

4 - Irrecoverable error has occurred.

QUALIFIER - R code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)

G.01.00 13- 74

G.01.00 13- 73

I / 0

2619 Line Printer Request Codes

Operation F	unction	Parameters
WRITÉ	1	P1 - Vertical Format Specification 1 - Use 1st data char as format specification.
		X53 - "+", print and suppress spacing X55 - "-", print and triple space X60 - "0", print and double space X61 - "1", print and top of form
		%200-%277, print and space N-%200 lines %300-%312, print with channel N-%277
		%320 - Fill Line Printer Buffer Only
		All others, print and single space.
		P2 - Space Mode Flags (15:1) - Prespace flag if set, print then fill buffer if clear, fill buffer then print (14:1) - No page stepover flag if set, single and double space uithout stepover (66 lines/page) if clear, single and double space uith stepover (60 lines/page)
FILE OPEN	2	Page eject if not at top of form
FILE CLOSE	3	Page eject if not at top of form
DEVICE CLOSE	4	Page eject if not at top of form
READ STATUS	2 17	Read I/O status Count - buffer size
*IDENTIFY	X110	Return ID value in Bank & Buffaddr
*SELF TEST: INITIATE	X 111	Subtest number to execute in Bank and Buffaddr (subtest number ranges from 0 to 7)
STATUS	X112	Subtest result returned in Bank & Buffaddr
*LOOPBACK TE: WRT DATA READ DATA	X113	Data to LP in Bank & Buffaddr [PING] Data from LP read into Bank & Buffaddr [PONG] Count - Buffer Size (256 bytes мах)

I / 0

2631 Line Printer Request Codes (HP-IB)

Operation	Function	Parameters
WRITE	1	P1 - Vertical Format Specification 1 - Use 1st data char as format specification.
		X53 - "+", print and suppress spacing X55 - "-", print and triple space X60 - "0", print and double space X61 - "1", print and top of form
		%200-%277, print and space N-%200 lines %300-%307, print with channel N-%277
		%320 - Fill Line Printer Buffer Only
		All others, print and single space.
		P2 - Space Mode Flags (15:1) - Prespace flag if set, print then fill buffer if clear, fill buffer then print (14:1) - No page stepover flag if set, single and double space uithout stepover (66 lines/page) if clear, single and double space with stepover (60 lines/page)
FILE OPEN	2	Page eject if not at top of form
FILE CLOSE	3	Page eject if not at top of form
DEVICE CLOS	E 4	Page eject if not at top of form
READ STATUS	X17	Read I/O status Count – 1 byte minimum required
VFC SET	X100	LORDS VFC RRM P1 - 1 - 1 LPI (lines per inch) 2 - 2 LPI 3 - 3 LPI 4 - 4 LPI 5 - 5 LPI 6 - 6 LPI 8 - 8 LPI 12 - 12 LPI Rny other value defaults to 6 LPI.

G.01.00 13- 76

I/O Queue Element For HP-IB Card Reader

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	Request dependent flags (see below)	QFLRG
1	SYSDB relative pointer to next IOQ element. Points to first word of element.	GLINK
2	Logical device number	QLDEV
3	Ruxiliary buffer flag.	QMISC
4	S If QFLAG.(3:1) is clear then this is the DST number of the target data segment. If S is set, QADDR is DB relative.	QDSTN
5	Offset in the data segment or system buffer table to the target data buffer.	QADDR
6	Function code for this request. (See next section.)	QFUNC
7	On initiation, specifies the word count (*0) or byte count (*0). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.	QUBCT
X10	Parameter 1. Contains the EOF specification	QPAR1
X 11	Parameter 2. Contains the data mode specification in bits (11:2). (See below card reader request codes for detail information)	QPAR2
X12	/////////////////// QUALIFIER STATUS	QSTAT
X13	PCB NUMBER	QPCBN

QFLRG - Request dependent flags

Bit 0	RBORT	- Abort this request and return an error indication
		to the caller.
Bit 1	SPECIAL	- Apply special handling to this request. (Not used)
Bit 2	DIAG	- This is a request from the diagnostic subsystem.
Bit 3	SYSBUFF	- Target is an index relative to the SBUF Table of the data buffer.
Bit 4	IOWAKE	- Wake caller on completion of request.
Bit 5	BLOCKED	- Blocked I/O. The caller is waited in ATTACHIO until the request is completed. Implies IOWAKE.

Bit 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IOMAKE).

Set by the nemony management routines (RRM) when a RHKEPRESENT request is successfully completed and indicates the data segment is frozen in memory.

Bit 8 MRHERRORD - Rh error has occurred while MRH was trying to make the target data segment present and freeze it in memory.

Bit 9 PREQ - (Not used)

Bit 9 PREQ Bit 10 SFAIL (Not used)
 Delayed failure of SIO instruction. If a call to STRRIO resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected for execution.
 The request was aborted because of a system power failure.

Bit 11 PFRIL

QMISC - Ruxiliary buffer flag used to indicated a read into the driver's buffer and not the user's buffer.

QSTAT - PCB number and request completion status.

PCBN - The Process Control Block (PCB) number of the process which made this request. If zero, the request is not associated with any process and the IOO element is to be returned by the system when the request has completed.

STATUS - General status indicating the final state of the request. The following codes are used:

O - Not started or awaiting completion.

1 - Successful completion.

2 - End-of-file detected.

3 - Unusual, but recoverable, condition detected.

4 - Irrecoverable error has occurred.

QUALIFIER - R code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)

G.01.00

I / 0

CS 80 Disc Request Queue Element (IOQ)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	Request dependent flags (see below)	QFLAG
1	Request urgency class	QURGCLASS
2	Logical device number	QLDEV
3	CHANFIRS OP IM SR RTRAN LF SP WAITCODE	QMISC
4	S DST (If process disc I/D)	QDSCTN
į	DST (If segment transfer) [S=Stack]	<u> </u>
5	Offset in the data seg (If process disc I/O)	QADDR
į	Address in Bank (If segment transfer)	
6	Unit # Function code for this request.	QFUNC
7	On initiation, specifies the word count (>0) or byte count (<0). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.	QUBCT
x 8	P1 - Parameter 1 (Usually High Order of Current Logical Disc Address [CLDA1])	QPRR1
	P2 - Parameter 2 (Usually Low Order of Current Logical Disc Address (CLDR2))	QPAR2
X10	//////////////////// QUALIFIER STATUS	QSTAT
211	PCB	QPBC
X 12	Sysbase relative indx of previous req in queue	QPREVREQP
X13	Symbase relative indx of next req in queue	QNEXTREOP
214 215	- Segidentifier (If seg transfer)	QSEGIDENT
X16	DISPLACEMENT OF READ OR WRITE FROM SEG BASE(HM)	OSEGDISP

QFLAG - Request dependent flags

I / 0

Bit 0 RBORT - Request has been aborted externally.

Bit 1 MMREQ - Request is for a segment transfer.

Bit 2 DIG6 - This is a request from the diagnostic subsystem.

Bit 3 SBUF - Target is an index relative to the SBUF Table of the data buffer.

Bit 4 IOWARKE - Make caller on completion of request.

Bit 5 BLOCKED - Blocked I/O. The caller is waited in ATTACHIO until the request is completed. Implies IOWARKE.

Bit 6 COMPLETED - The request has been completed and the caller askened if he had requested (with IOWARKE).

Bit 7 DATIAFRZN - Data segment has been present and is frozen.

Bit 8 MRMERRORD - Request has been present and is frozen.

Bit 10 SFRIL - Delayed failure of SIO instruction. If a call to STARILO resulted in the request uses the SIO instruction failed when the request the SIO instruction failed when the request the SIO instruction failed when the request the SIO instruction failed when the request uses selected for execution.

Bit 11 PFRIL - The request was aborted because of a system power failure.

Bit 12 CURREQ - Request is device's current request.

Bit 13 DISRBLED - Request is device's current request.

Bit 14 DISRIPT - Rttempt to disable this request.

Bit 18 DISRIPT - Rttempt to disable this request.

BIT 18 MRMEQ - Request is device's current pagest. QLDEV.QLDEVN - Logical Device Number

QMISC - Driver request dependent flags and counters.

CHAN'ERR'FLG - Channel error retry flag.
RSTAT'FRIL'FLG - Request status failed flag.
OPER'REO'FLG - Operator requested release flag.
IN'FRUL'FLG - Status error single retry flag.
STAT'RTRY'FLG - Status error single retry flag.
CHAO'FLG - Retransmit required flag.
SYS'PFRIL'FLG - System powerfail flag. WAITCODE - Indicates type of wait: 0 - new request 1 - completion wait

2 - not ready wait
3 - release/release deny wait
4 - 100 defer wait
5 - DSCT read wait
6 - DSCT write wait
7 - synchronization wait

QDSTN - If system buffer is clear then this is the DST number of the target data regisent If hit O to set then buffer address is a DB offset value

instead of segment relative offset (implemented for MOWAIT 1/0 and NOBUFF).

QADDR - Offset in data segment or system buffer table to target data buffer.

QFUNC - Function code and qualifiers as specified by

QSTAT - PCB number and request completion status.

 The Process Control Block (PCB) number of the process which made this request. If zero, the request is not associated with any process and the IOQ element is to be returned by the system when the request has completed. DCRN

STATUS - General status indicating the final state of the request.

0 - Not started or auaiting completion. 1 - Successful completion. 2 - End-of-file detected. 3 - Unusual, but recoverable, condition detected. 4 - Irrecoverable error has occurred.

QUALIFIER - A code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)

G.01.00 13- 81

CS 80 Integrated Cartridge Tape Request

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0	Request dependent flags (see below)	QFLAG
1	Request urgency class	QURGCLASS
2	Logical device number	QLDEV
3	CHANFIRS OP IM RETRY LF SP WAITCODE	QMISC
4	S DST (If process disc I/O)	QOSCTN
	DST (If segment transfer) [S=Stack]	
5	Offset in the data seg (If process disc I/O)	QADDR
	Address in Bank (If segment transfer)	
6	Unit # Function code for this request.	QFUNC
7	On initiation, specifies the word count (>0) or byte count (<0). At completion of the request this location contains the actual transmission count in the same units (bytes or words) as in the request.	QUBCT
Z10	P1 - Parameter 1 (Usually High Order of Current Logical Disc Address [CLDA1])	QPAR1
X 11	P2 - Parameter 2 (Usually Low Order of Current Logical Disc Address [CLDA2])	QPAR2
X12	PCBN QUALIFIER STATUS	QSTAT
X13	Sysbase relative indx of previous req in queue	QPREVREQP
X14	Sysbase relative indx of next req in queue	QNEXTREQP
X 15	Segidentifier (If segment transfer	QSEGIDENT
X16	Displacement of read or urt from seg base (MM)	QSEGDISP
	S ///////////////////////////////////	

QFLAG - Request dependent flags

G.01.00 13- 82

I / 0

Bit 0 RBORT - Request has been aborted externally.

Bit 1 MMREO - Request is for a segment transfer.

Bit 2 DIAG - This is a request fron the diagnostic subsystem.

Bit 3 SBUF - Target is an index relative to the SBUF Table of the data buffer.

Bit 4 IONAKE - Nake caller on completion of request.

Bit 5 BLOCKED - Blocked I/O. The caller is waited in ATTACHIO until the request is completed. Implies IOMAKE.

Bit 6 COMPLETED - The request has been completed and the caller awakened if he had requested (with IOMAKE).

Bit 7 DATAFRZN - Data segment has been present and is frozen.

Bit 8 MRMERRORD - An error has occurred while MRM was trying to nake the target data segment present and freeze it in memory.

make the target data segment present and freeze it in memory.

Bit 9 PREQUEUED - Request is queued into disc's request queue

Bit 10 SFRIL - Delayed failure of SIO instruction. If a call to STRRIIO resulted in the request being added to the channel queue, this bit indicates that the SIO instruction failed when the request was selected for execution.

Bit 11 PFRIL - The request was aborted because of a system power failure.

Bit 12 CURREQ - Request is device's current request.

Bit 13 DISRBLED - Request is disable this request.

Bit 14 DISRIMPT - Ritterpt to disable this request.

Bit 15 DISGOONE - Respect of the request of the request of the request is disable this request.

QLDEV.QLDEVN - Logical Device Number

QMISC - Driver request dependent flags and counters.

CHAN'ERR'FLG - Channel error retry flag.
RSTRT'FRIL'FLG - Request status failed flag.
OPER'REQ'FLG - Operator requested release flag.
In'FRUIT'FLG - Internal naintenance fault flag.
RETRY'COUNT area.
- Media load flag.
SYS'PFRIL'FLG - Systen powerfail flag.

WAITCODE - Indicates type of wait:

0 - new request

0 - new request
1 - completion наit
2 - not ready наit
3 - release/release deny наit
4 - IOQ defer наit
5 - DSCI read маit
6 - DSCI write наit
7 - synchronization наit

QDSTN - If system buffer is clear then this is the DST number of the target data segment. If bit 0 is set then buffer address is a DB offset value

I / 0

instead of segment relative offset (implemented for MOWAIT $1/\tilde{\rm O}$ and MOBUFF).

QADDR - Offset in data segment or system buffer table to target data buffer.

QFUNC - Function code and qualifiers as specified by

QSTRT - PCB number and request completion status.

- The Process Control Block (PCB) number of the process which made this request. If zero, the request is not associated with any process and the 10Q element is to be returned by the system when the request has completed. PCBN


STATUS - General status indicating the final state of the request.

0 - Not started or availing completion.

To state to detected.
 Successful completion.
 End-of-file detected.
 To Unusual, but recoverable, condition detected.
 Irrecoverable error has occurred.

QUALIFIER - A code which further defines or qualifies the general status. (See the section Driver Return Status Codes.)

SBUF Table Layout



3 - 1 - 5 - 4 - 2

G.01.00 13- 85

Table Element Allocation (SBUF)

The allocation of the elements in the IOO terminal buffer (TBUF) and system buffer (SBUF) tables is of concern to the I/O system.

FREE LIST OF TABLE ELEMENTS

These tables are in the form of a free-linked list of the free elements. For the SBUF's the -1 word of entry is the link to the next element. For the TBUF's, word zero is the link and word 1 is the link for the IDQ elements.

Each word has an 11-word header beginning at the base of the table . The first six words of the header are for managing the table and the second five are for monitoring table activity.

The entries follow the header at word eleven.

ELEMENT ALLOCATION

Elements are obtained from the beginning of the free list, pointed to by the head and returned to the end of the free list pointed by the tail.

When the free list is empty, the head index is zero and the tail index is set to point at the head index.

The tables are divided into two areas: a primary and a secondary area. Most requeste are obtained from the primary area. The secondary area is used only for critical requirements when the primary area is exhausted. These areas are logical areas determined by parameters in the header.

The utility of the core resident tables is seriously reduced if their use is not restricted to dynamic situations.

One of three responses must be specified to the routines which allocate elements from the ${\rm I}/{\rm O}$ system tables.

- 1. Impede caller if primary is empty.
- 2. Get from primary area only.
- 3. Get from secondary area if primary area is empty.

G.01.00 13- 86

I / 0

Table Element Allocation (Cont.)

Request types 2 and 3 return an indication to the caller if the request could not be satisfied. The following table specifies the types of calls for element allocation and the action if an element is not activated.

BUFFER USER	CALL TYPE	FINAL ACTION		
SBUF's				
file system Ptape Bad track	Inpede Inpede Prinary	 Forget request		
100's				
ATTACHIO (not impedable) ATTACHIO (impedable) SIOOM (memory management) IOMESSAGE	Prinary Inpede Secondary Secondary	Return IOQX-0 Sudden death I/O error		

HEADER DEFINITION

Primary W	- Number of elements in the primary area,
Total #	- Total number of elements in the table.
Size	- Size in words of each element.
Impeded PCB	 If not zero then contains the PCB number of the first process waiting for an element in this table.
Head index	- Index of first free element.
Tail index	- Index of last free element.
In use	- Current number not in free list.
Overflows	- Number of requests made for an element.
Total requests	- Total number of elements requested.

I / 0

ICS Global

QI -	leeseesses 1
63 50	RESERVED
49	
48	LAST WEIGHT
47 46	PAUSETIME
45	LISTSTATE
44	CUREFILTER
43	
42 41	
40	CURCFILTER
39	MAXCFILTER
38	
37 36	
35	
34	WORSTEPRI
33	NORSTOPRI
32	MORSTCPRI
31 i	MISC. BOUNDS FLAGS
29	XDS UPPER BOUND
28	DL INITIAL

ICS Global (Cont.)

- 1		
27		
26	XDS SEGMENT BANK	Series 64 only
25	XDS SEGMENT BRSE	Series 64 only
24	XDS SEGMENT LIMIT	Series 64 only
23	PRIV BNDS STAT HD	Series 64 only
22	i	
:	RESERVED .	
19		
18	DISAP	PSEN, PSDB counter
17	Reserved	
16	SDST	process' stack DST#
15	PSTR	pseudo-interrupt status
14	PADDR	pseudo-interrupt address
13	TRACE FLAG	flag set non-zero on IXIT away from ICS
12	PFRIL	PTR to powerfail PCB
11	JCUT	absolute JCUT address
10	ХP	pointer to executing process PCB
9	PCBX	absolute stack address
8	Z	stack DB relative Z
7	DL	stack DB relative DL
6	S	stack DB relative S
5	SBRNK	stack bank

G.01.00 13- 89

ICS Global (Cont.)

STDB absolute stack DB 0 DISPATCH stack marker STRTUS OIP I DB BRNK RETURN > FOR DISPATCH DB RETURN D | PARM

P=PSEUDO-DISABLED AND DISP INSTRUCTION EXECUTED. D=DISPATCHER INTERRUPTED.

ICS Global Cells With Initial Values

STDB - absolute address of the currently running process's stack.

SBRNK - bank address for process' stack.

- stack DB relative DL

- stack DB relative DL

Z - absolute stack address

KP - PCB table relative pointer to word 0 of the running process'

PCB.

The above cells are to be initialized for the PROGENITOR.

CPCB - absolute 4, is an absolute version of XP. If CPCB is zero, then the above cells are invalid. This will never be the case in a process. CPCB should also be set by INITIAL.

SDST - DST# for running process' stack.

JCUI - the bank zero absolute address of the JCUI table.

PRDDR - PB relative address for the procedure PSEUDOINT.

PSTR - status value for PSEUDOINT, X140000+CST#.

DISRP - PSDB counter, initially 0.

INITIAL sets the above as described.

G.01.00 13- 90

1/0

CS 80 Disc Interrupt Linkage Table (ILT)

There is one ILT for each device controller configured on the system. R controller may support more than one unit, however the CS'80 disc driver will only concern itself with the single unit controller.

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	MNEMONIC
0 1 2 3	Channel Program Variable	ICPVRO ICPVR1 ICPVR2 ICPVR3
4		ICPVR4 ICPVR5
6	0	ISRQL
7	LI CHANQUE ! CHAN DEV	ICHTRL
X10	SYSDB relative pointer to channel program area	ISIOP
X 11	SYSDB relative pointer to idle status area	ISTAP
X12	single instruction that is executed to extract the device unit number from the status pointed to by ISIRP. [Since only Unit O exists on the CS'80 discs, RMDI O is used to return Unit O]	
X13	SYSDB relative DIT pointer of the device currently using the channel to perform a data operation.	ICDP
X14	SIOPSIZE CQUEN	IQUEUE
X15	RU UP IG HCUNIT	IFLAG
%16	SYSDB relative DIT pointer for unit 0	IDITPO
X17	20 bytes status area for idle channel program	ISTAT
		į
		į
X31	CS'80 Discs Channel Program	

ICPVAO - Channel Program Variable Area

T / 0

The first word is used by the channel program processor to store status information after 1/0 channel aborts. The next word is used by the driver to indicate if status should be examined for special conditions or errors. The other two words are not used.

ICPVR4 - DMR abort address

If a DMA abort occurs, the absolute address where the abort occurred is stored in this area. $\label{eq:decomposition} % \begin{array}{ll} & & & & \\ & & & \\ & & & \\ & & & \\ & & & \\ \end{array}$

TCMTRL - Contains controller information

-If this bit is set, the controller is sharing a software channel resource in order to limit bandwidth.

CHANGUE -The software channel resource number.

-Channel number (four most significant bits of DRTM).

-Device number (three least significant bits of DRTN). DEV

IQUEUE - The channel program contains:

SIOPSIZE - (number of words + 1)/2 in the channel program area.

 $\ensuremath{\mathsf{CQUEN}}$ - or a multi-unit controller this field contains the software controller resource number.

IFLAG - Controller and Channel Program state flags

RUNWRIT - An Idle Channel Program should be started when there are no active

WRITCROG - An Idle Channel Program has been started for this controller.

This bit is reset by an interrupt.

 $\begin{tabular}{ll} $\sf IGMOREHI-An MIOP instruction has been issued against this controller but the channel program was not in a wait statement. Therefore ignore the interrupt generated by $$\sf Improvement of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of the interrupt of$

HCUNIT the channel code when this program halts. - Highest configured unit number for this controller.

ISTAT - 20 bytes of status from the idle channel program.


CHAPTER 14 SPOOLING

Input Device Directory/Output Device Directory

IDD/ODD (Common attributes referred to as XDD)

ODD: DST = 46 (= X56) SIR = 4 IDD: DST = 45 (= 255) SIR = 3

Overview of Table Structure



G.01.00 14- 1

Spooling

Typical Head Entry (4 words)

٥ اا	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
į,		vic													
į					ŀ	lead	d po	oin1	ter						
į					1	ai	l p	oin	ter		•••				į
					L	gio	cal	de	ic	2					

There are two types of head entry, a class entry and a logical device entry. There is only one class entry, and it is the first head entry in the ODD. The IDD does not have a class entry, and its position is filled with zeros. All spoolfiles opened by class (e.g., LP, SLOWLP, EPOC, PP, etc.) are linked to this entry. There is one logical device entry for each real (physical, as opposed to virtual) device on the system. Output devices appear in the ODD, input devices in the IDD. RC/DC devices such as terminals appear in both directories.

Each head entry is linked to 0 or more subentries (a typical subentry is shown in the next table). A null chain (0 subentries) consists of head pointer = 0 and tail pointer = segment-relative address of the associated head pointer. If one or more subentries exists, the pointers are segment-relative addresses of the first word of the first and last subentries of the chain. Rny intermediate subentries are linked through the subentries. The tail subentry always contains a 0-link.

The Device Outfence and LDEVM fields are meaningless for the class entry. For logical device entries (non-0 Logical Device field), a non-0 Device Outfence means that this outfence overrides the system-wide outfence in word 4 of entry 0, but only for this device.

Spooling

Entry O (Overall Table Definitions)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 1	
٥	+	0 (sectors)
1	Head entry size = 4 Subentry size = %40	1 (words)
2	Subentry area pointer (segment relative)	12
3	DD Next avail device file ID (DFID)	j 3
4	///////// Fence	4
5		// 5
6		// 6
7		// 7

0 ==> This is the IDD, 1 ==> This is the ODD. DD:

Fence: For spooled output devices (DDD), the system-wide out-fence. For spooled input devices (IDD), the jobfence.

G.01.00

Spooling

Typical Subentry (X40 words)

I Y D 1	cal Subsutty (x40 Holds)	
20	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 	0
	Type Job number	1
22 23 24 25	User name	2 3 4
26 27 210 210	Account name	6 7 8
12 213 214 215	Job name	110 11 12 13
216 217 220 220 221	File name	14 115 116 117
222		18
Z23	FS DR // XDD head index (see explanation)	19
(24		20
	Virtual LDEV number of open spoolfile	21
226	•	22
227		23
x30		24
X31	•	25
232	SQ // RS FD SO AB // Number of copies	26
233	Segment-relative link to next subentry, this device or class. O ==> last subentry.	27
	Number of records in spoolfile (doubleword)	28 29
236	Year MOD 100 Julian Day of Year/2	Ĭ30
	DY Hour (24 hr) Minute Seconds/4	31

Mote: Mords 0-X24 are used in all subentries. Mords X25-X37, although present in all subentries, are zero unless the subentry is for a spooled file (spoolfile).

Hord 0: State -- State of subentry: 0 ==> Active 1 ==> Ready 2 ==> Open 3 ==> Locked

3 ==> Locked

CL -- 1 ==> Word X24 is a class index into the Device Class Table.

0 ==> Word X24 is the LDEV associated with this subentry.

Hord 1: Type -- Describes which environment created the subentry:

0 ==> Session
2 ==> Job (SPOOK)

1 ==> Session
2 ==> Job (SPOOK)

| See | Job | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See | See

-- Spaced Out bit. File System could not acquire a new extent when creating spoofile.

-- This is the \$SIDLIST of an aborted job.

-- Time stamp when spoofile was made RERDY, or OD if not closed properly. Julian day is 9 bits starting with Word X36, bit 8. 50

A8 Words X36-37:

G.01.00

SPOOK Tape Format

The overall format of output tapes produced by the SPOOK "OUTPUT" command is shown below. The various components of the tape are then described in datail. The format described here is subject to change as RPE evolves. Also, there way be errors in SPOOK which would cause the actual tape format to differ from the one described here in sone cases. All numeric information is in integer format unless otherwise specified.

EOF

Label Record

File Directory Records

Device and Class Directory Record

EOF Spoolfile

Spoolfile

EOF

Mechanisms for End-of-tape and tape suitching are the same as for ${\sf STORE/RESTORE}$ tapes.

Label Record

Words 0-13: "SPOOLFILETRPE LRBEL-HP3000."

Hord 23: reel number (first reel is number 1)

Word 24: date (from CRLENDAR intrinsic)

Words 25826: time (from CLOCK intrinsic)

"MPEV" if an MPE V SPOOK tape

G.01.00

Spooling

All other words are zero.

File Directory

The File Directory has one entry for each spoolfile on the tape. Each entry is 12 words, and entries are packed into as many 1020 word records as needed. The last record will be padded with zeros if necessary. The entry format is:

Device file id number (bit 0 is on to indicate that the file is an output spoolfile)

Hords 1-3: zero

Hords 4-7: User name

Mords 8-11: Account Name

Device and Class Directory

The Device and Class Directory is contained in one 1024-word record. There is no EOF separating this record from the File Directory. This directory contains one entry for each logical device or device class linked to the spoolfiles on the tape. Also, there is an entry for each logical device in each class in the directory, whether or not that logical device was directly referenced by a spoolfile. The entries are packed into the tape record one after another in no particular order. The entry formats are shown below.

Logical Device Entry

Word O: logical device number

Bits 0:8 : device subtype Bits 8:8 : 3 (=length of this entry in words) Word 1:

Word 2: device type

Spooling

Device Class Entry

O: Device class number (negated). This is the number of the entry of this device class in the system's Device Class Table. Mord

1: Total number of words in this entry.

Words 2 on: The entire contents of the Device Class Table entry for this device class.

Spoolfile Format

ODD entry (32-word tape record)

Spoolfile block ---> Two spoolfile blocks packed into one 1024-word tape record.

Two spoolfile blocks

Two spoolfile blocks

The first few spoolfile blocks have been modified to contain user label information from the spoolfile. This is explained later.

Spoolfile Block Format

A spoolfile block is a 512-word block that contains variable length records in spooler format. Spoolfile records start at the first word of the block. The last record is followed by a -1 to indicate that no more records follow. The last two words of the block contain a doubleword which is the record number of the first record in the block.

Spoolfile Record Format

Word 0: Byte count of record - 2

Byte count of data portion of record. Not that this count includes trailing blanks. However, trailing blanks are truncated in Ward 1.

G.01.00

Spooling

the actual record, so this count may be more than the number of bytes actually present in the data portion.

Word 2:

Function Code: 1=Furite 2=Fcontrol 3=Fopen 4=Fclose X100 and beyond=FDEVICECONTROL

P1 -- RTTACHIO parameter Word 3:

Word 4: P2 -- ATTACHIO parameter

Morde 5 on: Data Portion of Record

User Labels Information

1. Master: user label 0.

2. FOPEN entry catalog: user labels 1-10.

3. Circular queue for restart checkpointing: user labels 11-27.

Since older versions of MPE did not use user labels, a way was needed to incorporate them into the SPOOK tape format without losing forward and backward compatibility. The method used is to add several special spoolfile blocks the beginning of the spoolfile on tape. Each of these blocks has exactly one FOPEN record at its beginning. This record is followed by a -1. Thus old versions of MPE will assume that the rest of the block is garbage. However, the rest of the block is actually used to contain user label information. The first two spoolfile blocks (i.e. the first tape record of the spoolfile proper) contain only the FOPEN records. The next 5 tape records actually contain user labels in addition to the FOPEN records. The user labels are packed 3 to a spoolfile block, 6 to a tape record. Each spoolfile block of 512 words has the following format:

Unrds 0-4: FOPEN record

-1 (to "terminate" the block) 5:

Words %200-%377:

user label

Hords \$400-\$577:

user label

Wards %600-%777:

user label

G.01.00 14- 9


Following this special group of blocks, the spoolfile resumes a normal format. The special FOPEN records all have the number of user labels in P2.

It is often the case that some of the 27 user labels have not been initialized before the tape is written. In that case, their places will be filled with garbage. There is no easy way of detecting this except by careful inspection.

G.01.00 14- 10

CHAPTER 15 UNIFIED COMMAND LANGUAGE (UNCL)

Reply Information Table (RIT) DST X34; SIR X25



NOTE: Process Number = 0 means entry is empty
Reply Type = 0 for number (num)
= 1 for yes or no (y/n)
= 2 for string (sxx)
= 3 for yes, no, or STRING

G.01.00 15- 1

Unified Command Language

.flaq=2 = 4 for string TABLE SIZE = 2046 words .flag=2 MAX # OF ACTIVE ENTRIES = 39 MAX # OF QUEUED ENTRIES = 52

Message System General Description

- The message system consists of the following parts:

 Callable intrinsic GEMMESSAGE.

 Uncallable procedure GEMMSG which is used by MPE.

 System message catalog (CATALOG.PUB.SYS) and any number of

 - System Message catalog (LMTMLUG.PUB.STS) and a user catalogs. Program MRKECAT which builds message catalogs. MESSAGE SIR Z24 MESSAGE SYSCLOB CELLS X371-373 MESSAGE DATA SEGMENT

The message system is used by calling GENMESSAGE (or GENMSG) with a message number. The message system fetches the message from a message catalog, inserts parameters, then routes the message to a file or returns the message in a buffer to the caller.

A message catalog is a numbered editor-type file containing sets of messages. The sets serve to break a catalog into manageable portions. A message system user may call GENMESSAGE using either his own message catalog or using MPE's catalog (CRTRLOG.PUB.SYS).

Rfter creating a message file, run the program MAKECRT in order to build a catalog that is readable by the message system. This file is still readable by the editor (it can be "texted") but it contains a directory (uritten as a userlabel).

In order to use the message catalog, the program must first open the message catalog, then call GENMESSAGE with the file number, set number and message number. (MPE users don't need to open the catalog, GENMSG automatically uses CATALOG.PUB.SYS.) The file must be opened with the aoptions "NOBUF" and "MULTI" -record access.

G.01.00 15- 2

Unified Command Language

Message Catalog

Messages in the catalog can be of any length and can contain up to five parameters. Continuation of a message is indicated by "Y" or "\\\^{\text{T}} at the end of a line. The "\text{T}" symbol indicates that the message is continued and that a carriage return, line feed be issued the terminal. The "\\\^{\text{T}}" symbol indicates that the message is continued on the same line with no carriage return, line feed.

Parameters may be inserted into the message fetched from the catalog. The parameters are passed in the GEMMESSRGE (or GEMMSG) call and inserted wherever a "!" is found. For the system message catalog, the back slash () is also a parameter, reflecting a logical device number. The message is routed to the user associated with that logical device through the :RSSOCIATE command. Message sets are indicated by "SSEI" in 'starting in column 1 (the rest of the line is treated as a comment). Maximum value for n is 63. Comments can be inserted in the catalog by placing "\$" in column 1. Message numbers are positive integers, need not be contiguous, but must be in ascending order. After processing by the program MRKECAT, the catalog file contains records of 80 bytes, blocked 16, in 32 extents. (The system message catalog is only one extent, however). The format of the message catalog is as follows:

```
$SET 1 SYSTEM MESSAGES
1 LDEV #! IN USE BY FILE SYSTEM
2 LDEV #! IN USE BY DIRHORSTICS
3 LDEV IN USE, DOWN PENDING
5 IS "!" ON LDEV#! (Y/M)?
* nessage 35 is two lines long, a parameter starts the $ first line and the second line is "HP32002" 35 !2
 HP320028.00.
 276 LDEV # FOR "!" ON ! (NUM)!
**SET 2 CIERROR MESSAGES
82 STREAM FACILITY NOT ENABLED: SEE OPERATOR. (CIERR 82)
200 MORE THAN 30 PARAMETERS TO BUILD COMMAND. (CIERR 200)
```

204 FILE COMMAND REQUIRES AT LEAST THO PARAMETERS. INCLUDING

Unified Command Language

FORMAL NAME OF THE FILE (CIERR 204)

MAKECAT Program

The program MAKECAT.PUB.SYS is used to build message catalogs (and also HELP catalogs). The program's input file has the formaldesignator IMPUT, which must be used for all entry points. The program has the following entry points:

(no entry point)

- Reads from input file and builds a temporary file (formaldesignator CATALOG). Also renames any old temporary CATALOG, CATnn, using an archival numbering scheme (i.e., CAT1, CAT2, etc.).


BUILD - (Must log on under MRNRGER.SYS.) Reads from input file, build the system message catalog (formaldesignator CRTALOG), and installs the message system. Existing catalog is remaned CRTANNA according to the same scheme as for no entry point (above). Installation of the message system means moving the directory contained in the userlabel of the catalog into a data segment. The DST number and the disc address of CRTALOG are placed in system global area. The message system may be installed while the system is running.

- (Must have PM or OP capability.) Installs the system message catalog (does not build a neu one). Opens input file, moves the directory in the CRTRLOG into a data segment, and places the DST number and disc address of CRTRLOG in system global area. This may be done when the message system seems to be "broken", but the catalog is intact. (MPE is issuing "MISSIM MISS. SET=mm. MSG=mm" at terminals and at the console.) This may be done while the system is running. DTR

 Used to build the HELP catalog. Reads input file and builds a HELP catalog (formaldesignator HELPCRT). HELP

HELP Subsystem


KEPT AS USER LABEL READ ONTO USER'S STACK USES SEARCH INTRINSIC FORMAT VARIABLE ENTRY SIZE



Unified Command Language

UDC Directory

*EXTRA DATA SEGMENT - DST # IN D8+X255 OF UMAIN STACK *BUILT BY INITUDE



G.01.00 15- 7

G.01.00 15-8

UDC's COMMAND. PUB. SYS

*RECORD SIZE = 20(10) WORDS, 6 RECORDS/BLOCK *KEEPS TRACK OF WHO IS USING WHAT UDC CATALOG *CAN BE PURGED TO DISABLE UDC'S *CON BE REBUTLT TO RE-ENGBLE HDC'S

RECORD O FREE ENTRY 0 1st FREE ENTRY # |0 O NEXT FREE ENTRY # O not used ENTRY TYPE=0 MAX IN USE # IN USE not used not used 23 119 23

G.01.00 15- 9

Unified Command Language

COMMAND. PUB. SYS (Cont.)

x	USER ENTRY	#	z	FILE ENTRY	
0	CATALOG ENTRY #	o	0	NEXT CAT. ENTRY #	0
1	ENTRY TYPE=1	1	1	ENTRY TYPE = 2	1
2		2	2	 FILE NAME	2
3		3	3		3
4		4	4		4
5		5	5		5
6		6	6	FILE	6
7	ACCOUNT*	7	7	[/LOCKWORD]	7
10		8	10	GROUP	8
11		9	11	ACCOUNT	9
12		10	12	۰	10
13	not used	11	13		11
14		12	14		12
15		13	15	(UP TO 36 BYTES)	13
16		14	16		14
17		15	17		15
20		16	20		16
21		17	21		17
22		18	22		18
23		19	23		19
		I			i

* IF THE USER FIELD AND THE ACCOUNT FIELD CONTAIN "@____THIS INDICATES SYSTEM LEVEL UDC'S.


IF ONLY THE USER FIELD CONTAINS @ AND 7 SPACES, THIS INDICATES ACCOUNT LEVEL UDC'S.

G.01.00 15- 10

Unified Command Language

CI Stack Definition

G.01.00 15- 11



Unified Command Language

Field Definitions

BCOMINAGE: Byte pointer to COMINAGE (sometimes called MCOMINAGE) in the CI stack.

COMMAND IMAGE: Command character string currently being executed.

LINELENSTACK: A CI command can span up to 30 input lines. This stack holds the length of each input line.

NEXTMSG: Used to be used to link messages together. No longer being used.

THIS IS SPARE: Not used.

UDCO: Holds the DST number of the UDC definitions.

UDC1: Holds the old S register value for UDC's.

UDC2: (0:1)--FLUSHUDC, used by :SETCATALOG

UDC3:

(0:1)--OPTION LIST = 1 (1:1)--OPTION LOGON = 1 (2:1)--OPTION NOHELP = 1 (3:1)--OPTION NOBREAK = 1

UDC4: (0:1)--UDC Fatal Ci Error (1:1)--UDC EXITBREAK (2:1)--UDC BREAKDETECTED (3:1)--UDC HOPRINT (4:1)--UDC INFDERDJUST (10:6)--UDC NESTLEVEL

IFNESTING: Level of nesting of :IF commands.

IFSKIP: Whether the current commands are being skipped as the false part of a :IF command.

ELSESEEN: Level of the :ELSE commands.

CIFLAGS: (13:1)--Sequenced: line numbers at rear. (15:1)--Not REDOable (last command).


CONTINUE STATE STACK: History of the :CONTINUE commands. = 0--no::CONTINUE = 1--just seen = 2--in effect.

PEMDINGCOMLEN: If \leftrightarrow 0, command is already in stack and this word is the command string length.

BLASTCOMINAGE: Byte pointer to last command image.

LAST COMMAND IMAGE: When a command completes execution, the command string is copied here for use by the :REDO command.

Resociation DST Lavout



G.01.00 15- 13

Application Message Facility


The Replication Message Facility consists of two parts: GENCAT, the catalog maintenance facility, and the "CAT" intrinsics, through which the message catalogs are accessed. The "compiled" catalog, which GENCAT creates, contains an extensive directory at the front of the file which describes where every message in the catalog is located. When a message catalog is opened (via CATOPEN) part of this directory is read into an extra data segment which is created specifically for that purpose. This "caching" of the directory provides nearly direct access to the desired message.

These messages include message set number, message numbers, and record numbers placed or "cached" into 324 word message caches. The first set number and message number of each message cache is placed into a cache directory (set and message number be ascending). A message is found by scanning first the cache directory, then the message cache searching for the desired set and message number. The retrieved message directory entry contains the record number in the catalog file of that message. Now, the catalog file can be read directly using the record number.

Internally, the two layer directory format is used by both the formatted application message catalog, and the message extra data segment created by the intrinsic CRTOPEN (and used by CRTREAD).

The catalog files created for MRKECRT and GENCRT may be used with the Roplication Message Facility. In most cases, applications will increase their performance in message routing and decrease the file space with formatted catalogs.

NLS Message Catalog/DST Overview




The maximum catalog size is 65536 sectors long. The largest set number is 255. The largest message number is 64766, while the smallest set and message number is 1.

G.01.00 15- 14

Unified Command Language

Formatted Catalog File Structure




where MC = 2 + (2 * #message caches)/128 D = MC + (384 * #message caches)/128

Each physical record is one sector long (128 words). Each structure starts on a sector boundary.

Unified Command Language


Cache Directory

Each entry in the cache directory is a two word entry. There exists one cache directory entry for each 384-word message cache. The first word of the cache directory entry is the set number of the first entry in the associated message cache. The second word of the cache directory entry is the message number of the first entry in the associated message cache.



Message Cache Format

Each message cache is 384 words long (3 records). A message cache entry is 3 words long, 128 entries per message cache. Each entry contains the message number and set number of the message. The byte offset is the offset to the start of the message in the record specified by the record number. Entry 127 is a duplicate of the first entry in the next cache. This is to allow the total number of bytes of the message to be computed without reading the next message cache.



G.01.00 15- 17

Unified Command Language

Message DST Overhead

0	"M" "D"	MDST'ID
1	"5" "7"	
2	Size of MDST (in words)	MDST'SIZE
3	Catalog File Mumber	MDST'CRT'FNUM
4	Offset to Resident Cache	MOST'RESIDENT'CACHE
5	Offset to Cache Directory	MDST'CACHE'DIR
6	Offset to Msg directories	MDST'MSG'DIR
7	Cache Directory Size (wds)	MDST'CDIR'SIZE
8	fisg directory size (µds)	MDST'DIR'SIZE
9	Max num of resident cache	MDST'CACHE'MAX
10	Recnum of first msg dir.	MDST'FIRSTDIR'RECHUM
11	Reserved	
12	Reserved	
		l l

Unified Command Language


Data Format

The format of the messages is straight foreword. It contains only the text of the message. It contains no comment records, message numbers or set numbers. All leading and trailing blanks are stripped from the message.

Message DST (MDST) Structure

An message extra data segment is allocated during a CATOPEN. The data segment number is kept by the application on the return from CATOPEN. The format of the data segment is similar of that of the formatted message catalog. The main difference is the addition of a table to track resident caches in the DST, and the catalog data in not kept in the DST.

Message DST Overview




NOTE: A resident cache is a message cache copied from the formatted catalog. Resident caches are suapped in and out of the MDST and are used to determine the record number of the desired set and message.

G.01.00 15- 18

Unified Command Language


Message DST Resident Cache Area

The Resident Cache Area is a table of the message directory blocks currently stored in the MDST, together with their index. They are held in order from the most recently accessed at the top to the and the oldest on the bottom. The maximum number of caches held in the MDST at any one time is MDST'CRCHE'MRX.




MOST Cache Directory

Each entry in the cache directory is a two word entry. There exists one cache directory entry for each 384 word message cache. The first word of the cache directory entry is the set number of the first entry in the associated message cache. The second word of the cache directory entry is the message number of the first entry in the associated message cache.



MDST Message Cache Format

Each message cache is 384 words long (3 records). A message cache entry is 3 words long, 128 entries per message cache. Each entry contains the message number and set number of the message. The byte offset is the offset to the start of the message in the record specified by the record number. Entry 127 is a duplicate of the first entry in the next cache. This is to allow the total number of bytes of the message to be computed without reading the next message cache.



G.01.00 15- 21 G.01.00 15- 22

Sysdump/Initial/Store

CHAPTER 16 SYSDUMP/INITIAL


CONFORTR File

Record O of CONFDATA File (CTABO)

0		0
1	CURRENT VERSION OF CTAB	1
2	STANDARD STACK SIZE	2
3	CORESIZE IN K WORDS	3
4	TERMINAL BOUND PRIORITY	4
5	NORMAL PRIORITY	5
6	CPU BOUND PRIORITY	6
7	# OF SECONDS TO LOG-ON	7
10	LOG FILE RECORD SIZE (SECTORS)	8
11	LOG FILE SIZE (RECORDS)	9
12	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	10
13	LOG BITS (ONLY 11 USED)	11
14 15 16		12 13 14
17		15
20	DEFRULT JOB/SESSION CPU TIME LIMIT	16
:		·
34	MAXIMUM OPEN SPOOL FILES	28
35	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	29
36		30
37		31
40	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	32
41	# SECTORS PER SPOOL EXTENT	33

Sysdump/Initial/Store

Record 1 of CONFDATA File (CTAB)




G.01.00 16- 2

Sysdump/Initial/Store

CONFDATA (Cont.)

G.01.00 16- 1




Sysdump/Initial/Store

INITIAL/PROGEN Communication DST

The INITIAL/PROGEN Communication data segment is used by Initial to pass information to PROGEN. This segment is only temporary and not memory resident.

COMMOSTN = SYSGLOBEXT (%122)

DST (SYSGLOBEXT (X122))



DESCRIPTIONS

OPT = Start-up option 0 = Warmstart 1 = Coolstart 2 = Coldstart 3 = Update 4 = Reload

Recovery = 1 If Recover Lost Disc Space = 0 If Not Recover Lost Disc Space

CTRB & CTRBO -See the descriptions of CONFORTA file in this chapter.

The microcode will store the CMTRL B command into (QI-11) equivalent to (ABS(5)-11) for the Series 37.

CNTRL B 0 = Start
1 = Harnstart
2 = Coolstart
210 = Load
211 = Update
212 = Coldstart
213 = Reload
214 = Neu
220 = Dunp

Starttype = ABS (ABS (5)-11)


Defdata Table Lookup File

This file contains the default information for MP-supported devices. This file, DEFDRIR.PUB.SYS, is available to Sysdump and Initial and eliminates the necessity for looking up default information every time a device is added to the system. Despite its name, DEFDRIR.PUB.SYS in not only a file, but a table in the Coldicad Information Table. It is not easily modified. Therefore, it is recommended that the file be left alone; if any user is unhappy that the defaults, they can be overridden during the Sysdump or Initial dialogues.

Defdata Table Lookup File Header Format

0	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15
1	VERSION
2	TOTAL TABLE SIZE IN HORDS
3	ENTRY SIZE (SET TO 1)
4	# OF TABLE ENTRIES


Defdata Table Lookup File Entry Format



6.01.00 16- 5

Sysdump/Initial/Store


Defdata Table Lookup File Entry Format (Cont.)



6.01.00 16- 6

Sysdump/Initial/Store

Defdata Table Lookup File Entry Format (Cont.)



Sysdump/Initial/Store

DEVDATA. PUB. SYS

Overview

1
PARAMETER RECORD
DRIVER TABLE
LPDT
LDT
LDTX
CLASS/TERM HEADER
CLASS
TERM DEF
ADD'L DWR TABLE
CS DEF
CS TABLE
,

Parameter Record

	l
0	CHECKSUM
1	VERSION
2	MEXT RECORD
3	HIGHEST LDEV
4	HIGHEST DRT
5	NR. ADD'L DRIVERS

Sysdump/Initial/Store

Parameter Record (Cont.)

64	REC #	DVR TABLE
	LENGTH	i
66	REC #	LPDT
	LENGTH	
68	REC #	ומו
	LENGTH	<u>.</u> i
70	REC #	LDTX
	LENGTH	_[
72	REC #	DCTH
	LENGTH	i
74	REC #	CLASS
	LENGTH	
76	REC #	TERM DEF
	LENGTH	
78	REC #	ADD'L DVR
	LENGTH	
80	REC #	CS DEF
	LENGTH	i
82	REC #	CS TABLE
	LENGTH	
	j-	·i
128	- UNUSED -	:
	1	•

Driver Table

		DR1		
CR CHAN #		DS		TURTOR CHIEN
	MASTER LDEV			TYPICAL ENTRY FORMAT
)		R	
]	<u> </u>		٧	
N	ı		A	
	1		E	

DS DS DEVICE (if set DRT is zero)
CR CORE RESIDENT
CHAN # CHANNEL #
MASTER LDEV DEV of device which this DS device is linked to.

Sysdump/Initial/Store

Words 3-7 contain the driver name.

G.01.00 16- 9

G.01.00 16- 10

Sysdump/Initial/Store

SYSDUMP Format

	CHECKSUM ANIGO CHANNEL PROGRAM MCS TABLE PRT ANIGO MCS TABLE MCS #1 MCS #2 MCS #n	<entry #1="" (rom="" 127="" 64="" 68="" 68.="" 95="" below.<="" brsed="" for="" machines)="" mcs="" o="" only="" point="" refer="" table="" th="" the="" to=""></entry>
	CHECKSUM Anigo	<pre><entry #2="" (mcs="" 0="" 127<="" based="" hachines)="" point="" pre=""></entry></pre>
	AMIGO	127
į	ICS	
	LOW CORE	
į	Initial CST	
Ì	CS TABLE	
į	DEVICE CLASS TABLE HEADER	
į	DEVICE CLASS TABLE	
į	TERMINAL DESCRIPTOR TABLE	
į	TABLE LOOKUP BUFFER	
ı	VTAB	
į	OLDVTAB	*
į	DISC COLD LOAD INFORMATION TABLE	*
	CTAB	
ļ	CTABO	
	COMMUNICATION RECORD	
į	CSDVR	
ľ	CSDEF	

Sysdump/Initial/Store

SYSDUMP Format (Cont.)

INITIAL'S DO AREA	
STACK MARKER	
DRIVER TABLE	
LPDT	
TOI	
ХТОЛ	
INITIAL'S SEGMENTS	
RIN TABLE	*
LOGGING IDENTIFIER TABLE	*
DIRECTORY HEADER	*
DIRECTORY	
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	
SYSTEM PROGRAMS, SL, NON-STD. DRIVERS	
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	
STORE/RESTORE HEADER	
XXXXXXXXXXXXXXXXXX EOF XXXXXXXXXXXXXXX	
STORE/RESTORE DIRECTORY	*
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	
USER FILES (SEPARATED BY "EOF's"	*
STORE/RESTORE TRAILER	
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	
XXXXXXXXXXXXXXXXXX EOF XXXXXXXXXXXXXXX	
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	

* NOT DUMPED IF DATE = CARRIAGE RETURN

NOTE: ON DISC, READ-SIO-PROGRAM KEPT IN DISC LABEL.

Sysdump/Initial/Store

End of Volume

		١.
<files> (separated by "EOF's)</files>		 FILES
 	İ	,
"STORE/RESTORE LABEL-HP/3000."	io 113	}
	14	į Į
	20	!
FLAG: PRECEDING EOF MARKS FILE ENDED	21	TRAILER
FLAG: PRECEDING EOF MARKS TAPESET ENDED	22	40 HDS.
VOLUME NO.	23	ļ
DATE	24	į
TIME	25 26	<u> </u>
	27	
	39	<i>)</i>
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	İ	
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX		
XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	İ	

G.01.00 16- 17

Labeled Tape Subsystem

CHAPTER 17 MISCELLANEOUS

Labeled Tape Subsystem

The NPE labeled tape subsystem permits convenient access to tapes labeled to either RNSI or IBM standards. It operates as a set of subprocedures to the file system. A labeled tape consists of one or more logical files. Each logical file consists of three physical files, i. e. tape areas delimited by tapemarks. The first physical file contains header labels, the second contains the data, and the third contains trailer labels which are (except for minor differences) copies of the header labels. The tape mark following trailer labels will be followed either by header labels for the next file, or by another tapemark if there is no next file. Labels are 80 bytes long, and conventionally are identified by their first four characters (three letters and a digit) and contain information as follows (CP := character position; L:= length):

VOL1: Present only on the first file of a volume, the volume label contains the volume identifier, which is usually the number on the tape strap, and is thus not expected to be changed.

k			×
CP	Field Name	L	Content
1/3	Label identifier	3	"VOL"
4	Label Number	1	"1"
5/10	Volume Identifier	6	Vol ID
11	Accessibility	1	"O" if IBM, else " "
12/79	Not used	62	Blanks
80	Label-Standard Version	1	"1" if HP ANSI else " "

 ${\tt IVLn:}$ User volume labels. May be present on tapes from foreign shops, but are not written by MPE. If encountered, they are ignored.

Labeled Tape Subsystem

HDR1: First header label, Required for each file. Specifies:

k			
CP	Field Name	L	Content
1/3	Label identifier	3	"HDR"
4	Label Number	1	"1"
5/21	File Identifier	17	File name, if tape was not written by MPE, only the first eight are significant.
22/27	Volume Set Identifier	6	Names the volume on which the set of files begins
28/31	Reel Number	4	Counts the reels that contain this file (1 starts)
32/35	File sequence number	4	Counts the files in the set of files (1 starts)
36/41	Not Used	6	MPE writes blanks
42/47	Creation Date	6	Year and day within year when the file was written.
48/53	Expiration Date	6	Year and day within year when the file may be over- uritten without permission.
54	Accessibility	1	%230 if Lockword, "O" if IBM
55/60	Block count	6	Number of blocks if IBM.
61/73	Systen Code	13	"HP MPE 3000 "
74/80	Not Used	7	Blanks
61/73	Systen Code	13	"HP MPE 3000 "

G.01.00

Labeled Tape Subsystem

HDR2: Second header label. Although defined by the standard, may be missing on foreign tapes. Contains:

CP	Field Name	L	Content
1/3	Label identifier	3	"HDR"
4	Label Number	1	"2"
5	Record Format	1	"F" = Fixed "Y" = Variable "U" = Undefined Others treated as Undefined
6/10	Block Length	5	Block length (in character format).
11/15	Record Length	5	Record length (adhering to to MPE rules) in characters.
16/23	Lockword	8	MPE File Lockword.
24/36	Not Used	13	MPE writes blanks
37	Record Type	1	"A" = ASCII "B" = Binary.
38	Carriage Control	1	"C" = control " " = no control.
39/80	Not Used	42	Blanks

G.01.00 17- 2

Labeled Tape Subsystem

IBM has a slightly different format. It is:

t			
CP	Field Name	L	Content
1/3	Label identifier	3	"HDR"
4	Label Number	1	"2"
5	Record Format	1	"F" = Fixed "Y" = Variable "U" = Undefined Others treated as Undefined
6/10	Block Length	5	Block length (in character format).
11/15	Record Length	5	Record length (adhering to to MPE rules) in characters.
16	Not Used	1	Blank.
17	IBM Position	1	"O" = no volume switch "1" = a switch has occurred.
18/38	Not Used	11	Blanks.
39	IBM Block Attribute.	1 1	"B" = Blocked records. "S" = Spanned records. "R" = Blocked and Spanned. "" = No blocked or spanned.
40/80	Not Used	41	Blanks

Labeled Tame Subsystem

User header labels: optional. Standard prescribes UHLn in the first four characters, but MPE doesn't care.

EOV1: End of Volume; used as first trailer label. Required if the logical file is continued onto another reel. Identical to HDR1, except contains the number of physical blocks of data in the data area.

CP	Field Name		Content
1/3	Label identifier	3	"EOV"
4	Label Number	1	*1*
5/54	Same as HDR1	50	
55/60	Block Count	6	Number of data blocks since last beginning of file section label group.
61/80	Same as HDR1	20	

EOV2: Defined by the standard, but may be missing on foreign tapes. Follows EOV1; format same as $\mbox{HDR2}.$

EOF1: End of File; used as first trailer label. Required if this is the end of the logical file. Format same as EOV1.

EOF2: Same as EOV2 except used after EOF1.

User trailer labels: optional. Standard prescribes UTLn in the first four characters, but MPE again doesn't care.

Labeled Tape Subsystem

Tape Label Table

The tape label table is the private playground of the tape label subsystem. It consists of two parts: LDEV Control Blocks (LEBs) and Volume Control Blocks (VEBs). The LDEV area is set up at system initialization and contains one entry for each magnetic tape LDEV and serial disc device in the system. As is common in MPE, the first entry is a dummy which tells where the other things in the table are. The volume area contains one entry for each labeled tape volume requested or active on the system.

Rithough table entries are stored in an extra data segment, they are generally manipulated via local copies on the stack. The procedures GETLDEV and GETFMUM look for LDEV and volume entries as specified; they copy them to stack buffers and return the DSI address for use in copying them back. POSTVTENT copies the entries back, and in the case of a new volume entry, allocates space for it in the volume section of the tape label table.

Initial will build the "uninitialized" TLT as follows:

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
•					1)	. >	нау	(a)	uorde	in	ble,	e ta	f the	ze o	Si	
1							X	e =	tabl	the	S in	LDEV	of I	nber	Nu	
! ! 2	I IT								/#	LDE					j=1	flag
İ	i				bove	of a	es c	ntri	(X) e	EV\$	FLDI	el o	Tota			
 X+										. DE						
									APES	ea JP' Ti			Expar dur			
	 T 													·		

T: 1 if Tape drive 0 if not Tape drive (i.e. serial disc)

6.01.00 17- 6

G.01.00 17- 5

Labeled Tape Subsystem

During PROGEN, SETUP'TAPES is called to initialize the table. The overall structure of the initialized TLT is:

TLTDST -- X32,826

TLTSIR -- 247,839

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

Table initialization word (=1 when initialized)	
Entry size (ESIZE) = %32,826	1
Table relative pointer to base of LCB entries (LTBRSE) (1)	2
Table relative pointer to base of VCB entries (VTBRSE) (2)	3
Table relative pointer to top of Volume table (VTTOP) (3)	4
Size of Tape Label Table, in words (YTMRX)	5
	6
	7
	10
not used	l
	!
	30
	31
	32 <-(1)
LDEV Control Block area one entry/mag tape drive	
	<-(2)
Volume Control Block table contains VCB entries	
and free entries	1
 	i
	<-(3)
Area available for expansion of VCB table	

Labeled Tage Subsystem

LCB Entry Format

The LCB entries have the following structure:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

	_					
	0					
Logical device number VCB address						
File sequence number	4					
Creation date	5					
Expiration date	6					
	7					
File name	10					
'	ļ					
	16					
+						
 	17					
	20					
(not used)	21					
	22					
	23					
	24					
Voluне set identifier	25					
	26					
	27					
Volume identifier	30					
	31					

Labeled Tape Subsystem

Type: CO = no tape wounted C1 = unlabelled 10 = RNSI 11 = IBM L: 1 if file has lockword.

L: 1 if file has lockword.
T: 1 if device is a tape drive.
B: 1 if tape is from Burroughs, which has incorrect block/record size in the HDR2 label. Code can be patched to correct the size.
HP: 1 if tape is Hewlett-Packard RHSI format.

VCB address: Pointer to VCB entry describing volume mounted on tape drive, only if linked. Otherwise, O.

Labeled Tape Subsystem

VCB Entry Format

The VCB format is:

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

A F D Position W SeqTyp LblTyp L M R B	0
LDEV #	1
PIN	2
File number (AFT index)	3
File sequence number	4
S R D C Density V Reel number	5
Expiration date	6
	7
File name	10
'	
	16
† 	17
·	

20 21 Lockword 22 24 Volume set identifier 25

G.01.00 17- 9

G.01.00

Labeled Tape Subsystem

VCB (Cont.)

26 27 30 Volume name 31

R: ASCII FOPTION
F: Flush bit - operator did REPLY <pin>,0.
D: DEVREC Wait (used with reelswitching).
Position: Gives head position within logical file.
0 = at load point (UPPNT)
1 = HOR1 label next (HHXX)
3 = after HDR2 label (AH2)
4 = after user header labels (RHU)
6 = data next (DNX)
7 = after data (RD)
8 = EDF1/EDV1 label next (THXX)
10 = after EDF2/EDV2 label (AT2)
11 = after user trailer labels (ATU)
W: Write access specified.
SedTyp: File open sequencing type.
0 = natch filename
1 = NEXT
2 = RDDF

1 = NEXT
2 = RDDF
3 = use file sequence number
LblTyp: Rs in LCB entry.
L: Linkwait - mark left by CREATETLTENT for LINKLABEL.

R: Nount wait - waiting for operator to mount tape on FOPEN.
R: Reelswitch wait - waiting for next reel.

B: Busy bit - this entry is in use.

LDEV #: Logical device number of tape drive with this volume, only if linked. Otherwise, O.

S: STORE tape.
R: REELSWITCH has been done. Used by STORE/RESTORE to handle STORE
label and directory file.
D: Next file is directory. Used by STORE.
C: VOII label is to be created (written).
Density: volume set density. During a volume set open, contains the
density requested by the user in FOPEN. Once the volume set is
open, contains the actual density of the volume set. Only
valid for tapes on variable density tape drives.
0 = default density for volume set open
1 = 1600 BPI
2 = 6250 BPI
V: 1 if volume set is being opened. Reset after completion of FOPEN

V: 1 if volume set is being opened. Reset after completion of FOPEN.

Labeled Tape Subsystem

Volume Recognition

Volume recognition is the responsibility of DEVREC, which reads the first record of a newly-mounted tape on an unouned drive and passes the record to RVREC. RVREC may see: VOLI in the first 4 bytes, in RSCII, in which case the tape is RRS; VOLI in the first 4 bytes, in EBCDIC, in which case the tape is IBR; Anything else, in which case the tape is considered unlabelled.

If the tape is unlabelled, RVREC reports to DEVREC that no further action is required. If the tape is labelled, RVREC wants to see the first HDR1 label, so asks DEVREC to read another record. (Unfortunately, DEVREC cannot be stopped long enough for RVREC to do its own read.) When the HDR1 record is found, the volume entries can be searched to see if there is a pending request for this volume. If so, the waiting process is restarted.

If the system has been restarted with tapes mounted, there will not be interrupts to alert DEVREC. The procedure RECOGNIZE is called when needed to see if any such tapes exist.

Opening a File

FOPEN gets into the tape label code in three different places. The first is to call CREATETLIENT, which parses the string passed in the FORMSTNSG parameter to identify the labeled tape file required. If there is no existing corresponding entry in the volume area, this is a volume set open, and a new volume entry is created. There may be an existing entry (if the tape was FOPENed and FCLOSEd with disposition 2 or 3), in which case there is an associated LDEV entry for the drive on which the tape was left nounted by the prior operation; in this case, the new information is stuffed into the existing volume entry. A bit (LINKUARIT) is left set to mark the entry for LINKLABEL.

The second entry is through LINKLRBEL, which is called from ALLOCATE. At this time, it is necessary to identify the LDEV to be used for the tape. If no LDEV is associated, the LDEV entries are searched to see if the operator has already nounted the required tape; if so, the volume and LDEV entries are cross-tied and LINKLRBEL is done. If the search turns up nothing suitable, the operator is requested to nount the appropriate tape, and the procedure waits for either a REPLY or for RYREC to discover the appearance of a suitable tape and restart the process. If the operator enters a reply, it is validated.

The third entry is through POSITION, which is responsible for positioning the tape to the requested file. At the file, the HDR1 and HDR2 label are examined as required to determine the file characteristics.

Reading and Writing Files

All procedures which move tape go through the catchall procedure CHECKUL, which takes care of necessary labeled tape doings. The code insures that the sequence: header labels (including user labels), data, trailer labels

If an EOT reflective mark or an EOF in data is found, REELSHITCH is called (principally from the file system procedure IDMOVE) to call for the next reel, if any. If another reel is needed, the tape drive is set Unoumed so that APVREC will be called to recognize the new tape when it is mounted. REELSHITCH returns to its caller when it is satisfied that an appropriate tape is mounted.

Closing Files

FCLOSE calls CHECKUL to handle uriting EDF1 and EDF2 if needed and resolving the tape position. If the disposition is 3, the tape is left positioned at the next file. If the disposition is 2, the tape is supposed to be left at the beginning of the current file, but the code does not presently provide for reelsuitching if the present file began on a prior reel.

At present, ensuing volumes of a multi-volume set must be mounted on the same drive as the first, mostly because neither the file system nor STORE-RESTORE was capable of dealing with LDEV changes in the middle of a file. REELSWITCH reports the LDEV being used, however, so that the capability of using a different LDEV can be added in the future.

Store-Restore

Complications ensue on labeled STORE-RESTORE tapes because there needs to be a file directory at or near the beginning of each tape of a multi-volume set; RESTORE uses this directory to determine whether the specified file(s) can exist on this tape. Because the reel suitching process would otherwise be invisible to STORE-RESTORE, special bits (VCD*RSMODME and VCD*WRIDDIR) are kept to enable special intrinsics callable by STORE-RESTORE to report whether a directory needs to be written or is about to be encountered.

The special procedure MEXTTRPEFILE is used by STORE-RESTORE in lieu of doing a FCLOSE(,3) followed by an FOPEN to get to the next file. This permits cleaner handling of both REPLY 0 and Forward Space (logical) File over a Reelswitch, as well as saving the time needed to tear down and reconstruct all the control blocks.

Miscellaneous

PVOLID is used by the SHOWDEV command processor (in SPOOLEOMS) to obtain the name of the volume on the specified drive uithout having to know the structure of the tape label table. For the same reason, IGETINFO is used by the FFILEINFO intrinsic (in FILEIO) to get labeled tape information.

System failure 86 in MPE is defined as a major problem in LMBSEG. Generally speaking it is a problem with the TLT setup, for example if LMBSEG cannot find an LDEV in the table.


G.01.00 17- 13

Breakpoint Table

PCB Breakpoint Extension Table

ı	# ENTRIES	I	ENTRY SIZE =	1
Ī	HEAD SYSTEM LIST	Ī	FREE ENTRY =	0
] 	W USED USER ENTRIES USER ENTRIES	1	ACTIVE ENTRY =	Index 1st Entry in breakpoint chain
		!		

Breakpoint Entry Table



The breakpoint entry table consists of variable length entries The minimum entry size is 7.

Breakpoint Table


Breakpoint Table

DST = 30(10) = X36

The break point table is divided into 2 sections:

- PCB BREAKPOINT EXTENSION TABLE (PCB'BKPT'EXT)
 This table contains the heads of the breakpoint chains
- 2) BREAKPOINT ENTRY TABLE (BKPT'ENTRY'TAB)
 This table contains the actual entries

General Layout



G.01.00 17- 14

Breakpoint Table

Active Entry

01	1 2 3 4 5 6 7 8 9 0 1 2	3 4 5
101	PILIVIDIFITIUIPICIUI SIZ	E
[11]	UNUSED	1
	BLOCKLABEL	
Ī	PLOC	i
Ī	INSTRUCTION	Ī
Ī	LINK	1
Ī	USERLABEL	ī.
	CONDITION/COUNT	variable
ı		ı .:
1	COND DESCRIPTOR	<u>-</u>

Breakpoint Table

```
FREE ENTRY

1 = FREE

0 = USED

PRIVILEGED HODE BREAKPOINT
ENTRY(0).(0:1) = FR:
ENTRY(0).(1:1) = P:
                                                                              PRIVILEGED MODE BREAKPOINT

1 = PRIV.

0 = NON-PRIV
PROCESS-LOCAL
PRIVE BREAKPOINT
1 = PROCESS-LOCAL
0 = SYSTEN
VALIDATION BIT
1 = INSTRUCTION IN ENTRY(3)
0 = INSTRUCTION NOT IN TAB.
DOUBLE TRAP
1 = DREAKFOINT OSCILLATES BETHEEN
P/PAI
ENTRY(0).(2:1) = L:
ENTRY(0).(3:1) = V:
ENTRY(0).(4:1) = D:
                                                                             DOUBLE TRAP

1 = BRERKPOINT OSCILLATES BETWEEN
P/P+1

0 = NOT DOUBLE TRAP
FRIKE 'DUMINY' TRAP
1 = BRERKPOINT AT P+1
0 = BRERKPOINT AT P (ORIG. LOC)
THO HORD INSTRUCTION
1 = THO HORD INSTRUCTION
USER LABEL PRESENT
1 = TRAP TO USER SUPPLIED LABEL
0 = TRAP TO DEBUG
PERHANENT BRERKPOINT
1 = PERM
0 = TERPORTY
CONDITION/COUNT
1 = CHOONITION/COUNT
1 = CHOONITION/COUNT
1 = CHOONITION/COUNT
1 = CHOONITION/COUNT
1 = CHOONITION/COUNT
0 = NO COND/COUNT
UPDRIING
1 = ENTRY IN PROCESS OF BEING
UPDRIED/REMOVED
USER PLABEL MODE
LINK
0 = END OF CHAIN
>O = END OF CHAIN
>O = IND EX NEXT ENTRY
ENTRY(0).(5:1) = F:
ENTRY(0).(6:1) = T:
ENTRY(0).(7:1) = U:
ENTRY(0).(8:1) = PM:
ENTRY(0).(9:1) = C:
ENTRY(0).(10:1) = UP:
ENTRY(1).(0:1) = M
ENTRY(6) = LINK:
```

Breakpoint Table

Breakpoint Entry Table (Cont.)

COUNT	CONDITION		
1) ORIGINAL CNT.	i	2) OPERAND1	Ī
# OF HITS	1	OPERAND2	١
	1	OPT1 OPt2 RELOP	١

RELOP -> (8:8) RELOP NUMBER: 3 = LT 9 = LTE 4 = GT 10 = GTE 5 = EQ 11 = NEQ

OPT1 -> (0:2) OPERAND1'S TYPE
OPT2 -> (2:2) OPERAND2'S TYPE

OPERAND TYPES:

17FES:
0 -> CONSTANT (SINGLE HORD)
1 -> ADDRESS (DOUBLE HORD)
3 -> INDIRECT ADDRESS (TRIPLE HORD)

OPERAND FORMS: CONSTANT ->

CONST

ADDRESS ->

| REG | BASE| | OFFSET |

[IND. OFFSET] (TYPE 3 ONLY)

REG

3 = A 4 = SY 7 = DA 8 = DX 9 = DB

BASE -> (6:10) SEG #/BANK #


G.01.00 17- 17

G.01.00 17- 18

Breakpoint Table

Timer Request List (TRL)

The system clock interrupts every 100 ms, with the CR being automatically cleared. An exception is the Shared Clock Interface measurement service which allows rates as fast as 5 ms. The interrupt handler is the procedure TICK. On entry, DB is pointing to the base of timer request list. Besides timeout requests, the clock also controls time slicing.



Timer Request List

TRL (Cont.)

CODE	& REQ	indicate the type of	request.
	CODE:	REQ:	` TYPE:
	0	DITP	Hangup
	1	DITP	Carrier failure
	2	DITP	202 turnaround
	3	DITP	Read
	4	DITP	Logon
	5	PCB8 index	Delay
		to process	·
	6	DITP	LP not ready
	7	DITP	2640
	X10	Port nask	Msg port timeout
	X11	DITP	Block mode read
			tineout (30 secs)
	X12	PCBB index	Watchdog timer for
		to process	process

The list of pending requests is kept ordered by time with later entries at the tail.

220-237 DITP SIO device timeout: DIT8. (code_1 on expiration, cleared on Timereq.

25/26 *DTIME For Series 30/33, DTIME is # of TICS (0.091457 ms) since last midnight.

MPE User Logging

MPE USER LOGGING enables users and subsystems to log changes to data sets on disc or serial files. This "change" file can later be used to recover data lost due to a system or program failure. The log file can itself be used for auditing purposes.

General Design Overview

Marduare Environment

No special hardware is required to operate the system. Mowever, if logging to a tape file is desired, the hardware configuration must include a tape drive. If there is no tape drive, then may log to a serial disc class device.

Software Environment

MPE User Logging is an integral part of MPE. No other special software is

Design Narrative

User Logging enables users and subsystems to journalise additions and modifications to MPE and subsystem files. The journal can reside on either disc or serial logfiles.

User Logging consists of a logging process, a memory buffer, a disc resident logging buffer (for serial logging) and a user defined destination log file on disc or serial media.

The logging process has two functions depending on whether the destination file resides on disc or serial media. If the destination file is serial, the logging process performs all output to the destination file. If the destination file is on disc, the logging process allocates additional space (extents) as it is required by the user.

The logging buffer is divided into communication and buffer areas. The communication area is used to pass information among the users and the logging process. This information includes status of the logging process and logging file, space remaining in the logging file and error information inportant to users or the logging process. The buffer portion of the logging data segment blocks inputs into the logging file before the data is actually posted. The buffer is flushed any time a user requests to close a log file or when a logging process is terminated. (The buffer is also flushed by the begin/end transaction or buffer flush requests).

G.01.00 17- 21

User Logging Table

Design Structures

User Logging Table

ENTRY SIZE = #38 words

Table containing an entry for each activated user logging process. Each entry is created when the process is started, and deleted when the process terminates. (Via :100 command). The information is extracted from the Logging Identifier Table (LIDTAB).

ENTRY O							
*		X					
ο .	NUMBER OF ENTRIES	0					
1	FREE ENTRY HEAD PT.	1					
2	INUSE ENTRY HEAD PT.	2					
3	NEXT BUFFER NUMBER	3					
4	MAX # PROCESSES	4					
5	MAX W USERS/PROCESS	5					
6		6					
7	ENTRY SIZE	7					
37	:	45					

MGRD ENTRIES

NUMENTRIES		LOGTAB
FREE	=	LOGTAB(1
INUSE	=	LOGTAB(2
BUFNUM	=	LOGTAB(3
MAXLOGPROC	=	LDGTAB(4
MAX'USR'PROC	=	LOGTAB(5
LOGTAR' ESTZE	=	LOGTAR(2

Timer Request List

Error Recovery Description

The error recovery mechanisms provided by User Logging are: power fail recovery and recovery from system failure.

Power failure recovery applies only to tape log files since MPE provides adequate recovery for disc files during power fail. When a power failure is detected, a nessage will be printed on the console asking the operator to place the tape drive back on-line. (If the operator places the tape on-line before the nessage valid data may be overwritten). (To reset the tape drive the operator must hit the load button until the tension returns to the drive. Then hit the reset button followed by placing the tape drive back on-line). At this time the log process will recover the file by rewinding to the load point and then forward spacing to the point where the power fail occurred. Writing to the log file will continue at that point.

In the event of a system failure, the warm start load option initiates recovery of User Logging files. In the case of a serial file, the file is read and compared to the disc logging buffer. All records found in the disc buffer that are not on the serial log file are posted and a proper end of file written. If the destination file is a disc file, all records are read and verified and an end of file posted to the file. In order to continue logging to a User Logging file that has been recovered in this manner, the logging process for the file must be restarted using the console command: LUGG.

Any records in the buffer area of the logging buffer will be lost.

User logging has been enhanced to work with labeled serial discs. Internally the log process handles serial disc (or cartridge tape) log files the same as for tape files.

G.01.00 17- 22

User Logging Table

NUMENTRIES
The number of entries in the logging table.

FREE

A table relative pointer to the first free entry in the logging table. (-1 = table full).

IMUSE R table relative pointer to the first entry in the logging table that is being used (-1 = no entries in use).

The number of the buffer associated with this logging process. Used to create the name of buffer file if serial logfile. (i.e. ULDGxxxx.PUB.SYS).

MAXLOGPROC
The maximum number of user logging processes allowed.


MAX'USR'PROC

The maximum number of users per logging process.

LOGTAB'ESIZE
The size (in words) of each entry in the table.

Typical Entry # O LOGGING IDENTIFIER 4 BUFFER NAME 10 8 FILE NAME 12 14 LOCK MORD 16 20 GROUP 20 24 ACCT 24 NUMBER OF USERS 30

User Logging Table



BTRBINDEX	=	BYTE INDEX TO CURRENT ENTRY
		DOUBLE INDEX TO CURRENT ENTRY
DTABINDEX	=	DOORSE TADEX TO CORRENT ENTRY
LGNAME	=	BTABINDEX
BNAME	=	BTABINDEX+8
LENAME	-	BTRBINDEX+16
	-	BTABINDEX+24
LFLOCKW		
LFGROUP	=	BTABINDEX+32
LFACCT	=	BTABINDEX+40
NUMUSERS	=	TABINDEX+24
DST	-	TABINDEX+25
	-	
STATUS		
LGAUTO	=	TABINDEX+27. (0:8)
LGTYPE	Ξ	
LGDEV	=	TABINDEX+28
PIN	=	TABINDEX+29
LGSWITCH	=	TABINDEX+30
LGNEWAUTO	=	TRBINDEX+31.(0:8)
LGNEUTYPE	=	TRBINDEX+31.(8:8)
LGADDR	=	DTABINDEX+16
BSIZE	=	DTABINDEX+17
NEXT	=	TABINDEX+36
	-	TRBINDEX+37
PREV	-	INDINUENTS!

WORD INDEX TO CURRENT ENTRY

G.01.00 17- 26

User Logging Table

User Logging Table

25

26

The name of the logging process (logging identifier).

BUFFER DST NO

LOG STATUS

BNAME
The name of the disc buffer used if the logging process destination file is a serial file. This is a file that resides in PUB.SYS. The format of the name is ULOGXXXX where XXXX is the buffer number padded on the left with zeros.

31

32

G.01.00 17- 25

If the suitch flag is true, the following will be the fully qualified file name of the new log file.

LFNAME
The name of the logging file.

LFLOCKH

The lockword of the disc logging file.

 $\overline{\mbox{D}}$ owner. The group that the destination logging file resides in if the file is a disc file.

The account that the destination logging file resides in if the file is a disc file.

NUMUSERS

The number of users currently accessing the logging file.

 $\ensuremath{\mathsf{DST}}$ The dst number of the logging data segment (LOGBUFF). (-1 = LOGBUFF not created yet)

STATUS
The status of the logging process.
INITIALIZING = -1
INACT = 0
RCT = 1
RECOVERING = 2

 $\ensuremath{\mathsf{LGRUTO}}$ True if the automatic changelog facility was enabled. (Not used – for future use).

LGTYPE

LGTYPE
The type of destination file of the logging process.
DISC = 0
TAPE = 1
SDISC = 2
CTAPE = 3

The logical device number of the disc logging file or the disc logging buffer.

PIN

User Logging Table

TARTNDEX

The PCB number for the logging process (PIN * PCBSIZE).

Flag indicating a CHRNGELOG is pending (if true). (Not used - for future use).

Lumcumulu True if the automatic changelog facility was requested for the new log file. (Not used – for future use).

LCHEUTYPE If a switch is pending, this will be the type of the new log process. (-1 = no switch pending). (Not used – for future use).

I GADDR

Sector number of the current extent in the disc logging file or the disc buffer file. (Disc buffer file has only 1 extent)

The number of records in the current extent (for disc logging) or the number available in the disc logging buffer.

 $\overline{n}_{\rm tot}$. A table relative pointer to the next entry in the logging table. (-1 = this is last entry)

A table relative pointer to the previous entry in the logging table. (-1 = this is first entry)


User Logging Buffer

There will be one of these tables around for the life of any active user log-ging process. The table consists of three parts:


COMMUNICATIONS RREA - Information about status of the process, etc. that is common to all users of the process. Also the cells for messages to/from the process.

USER ENTRIES - Information for a specific user of the process. One of these for every user of a process (Setup by OPENLOG, released by CLOSELOG).

 $\mbox{BUFFER AREA} \mbox{ - Buffer used to hold logging records from all users before writing to the log file.}$




G.01.00 17- 29



6.01.00 17- 30

User Logging Buffer



User Logging Buffer

LOGID		BLOGBUFF(0)
SHITCH'		LOGBUFF(4)
NEURUTO	=	LOGBUFF(5).(0:8)
NEUTYPE		LOGBUFF(5).(8:8)
AUTO	=	LOGBUFF(6).(0:8)
LOGTYPE	=	LOGBUFF(6).(8:8)
BOST	_	LOGBUFF(7)
LOGPIN	=	LDGBUFF(8)
MUMUSER	=	LOGBUFF(9)
MAXUSER'	=	LOGBUFF (10)
USERNO	_	LOGBUFF(11)
SLPCT	=	LOGBUFF(12)
STATE	-	LOGBUFF(13)
MSG	-	LOGBUFF (14)
LOGHSG	:	LOGBUFF (15)
USERMSG	-	LOGBUFF(16)
LOGERR	-	LOGBUFF (17)
LOGDEV	-	LOGBUFF(17)
BSPRCE		LOGBUFF (19)
BUFUSED	-	LUGBUFF (19)
VSETNO	:	LOGBUFF (21)
VOLINO	-	COODUFF(21)
LOGADOR		DLOGBUFF(11)
INBUFREC	-	DLOGBUFF(11)
FSIZE	:	DLOGBUFF(12)
FSPACE'	:	DLOGBUFF(14)
TRECS	:	DLOGBUFF(15)
MAXESPACE	•	DLOG8UFF(16)
HUNLOLUCE	•	DEDUCOUPT (16)
LASTEXT		LOGBUFF (34)
EXTENT	-	LOGBUFF (35)
ENIENI	•	LUGBUFF (35)
RESOURCE		DLOGBUFF (18)
UHEAD		LOGBUFF (48)
FHERD	=	LOGBUFF (49)

LOGID

The name of the logging process.

SHITCH

True if log file switch is pending. (Not used - for future use).

True if the automatic changelog option has been specified for the new log file. (Not used - for future use).

MEUTYPE If a switch was requested, this will be the type of the new logging file. (-1 = no switch pending) (Not used - for future use).

True if the automatic changelog option was specified for the current log file. (Not used - for future use).

INCTYPE

The type of destination file for the logging process.
DISC = 0
TAPE = 1
SDISC = 2

BDST The data segment number of this table.

LOGPIN This is the PCB number for the logging process (PIN*PCBSIZE).

NUMUSER
The number of users currently accessing the logging file.

MAXUSER'
The maximum number of users allowed to access the logging file.

The next sequential number to be assigned users accessing the system. It will get incremented for every unique OPENLOG – used as the log # in the log-ging record format.

The number of users currently waiting for activation by the logging process.

The state of the user logging process.
INACTIVE = 0
ACTIVE = 1

NSV
Rn internal message word used to indicate an error or operator request.
6 - Continue processing, all is fine.
2 - Suspend - error reading buffer file or writing to serial file
3 - Stop - set when issue: LOG logid, STOP or when an EOF condition is found on the disc log file.

G.01.00

User Logging Buffer

The current extent size of the logging destination file or disc logging buffer file for serial destination files. (on the last extent this will be the last extent size minus 1).

The space in records that remains in the current extent of the disc logging destination file or disc buffer for tape destination files. (On the last extent of the disc log file, this is the amount of space minus 1).

TRECS

The total number of records written to the logging destination file (including those records currently in the buffer).

The total file size, in records, minus 1. (Need that last record to post close information).

The extent number of the final extent in the disc logging file or disc buffer file.

EXTENT

The current extent number of the disc logging file or disc logging buffer.

RESOURCE

MESUURLE
Used for resource management (i.e. locking the LOGBUFF). Format is:

RESOURCE + 0 = Duner PCB number

RESOURCE + 1 = Head of inpeded queue PCB number

RESOURCE + 2 = Tail of inpeded queue PCB number

RESOURCE + 3 = Queue length

A table relative pointer to the first entry into the logging data segment. (-1 = no entries currently in use)

FHEAD Relative pointer to the first free entry in the logging data segment. (-1 = no free entries)

User Logging Buffer

LDGMSG
A messages from the logging process.
6 - Continue processing, all is fine.
15 - EDF - if there are no more extents available to be

15 - EUr - IT there are no more extents available to be allocated.

12 - Disc space - could not allocate the new extent because no space left in the group.

9 - Write error - error occurred while writing to log file

HEEDMEC

USEKINGO

A messages from the user process.

6 - Continue processing, all is fine.

12 - Disc space - user process needs another extent allocated

for disc logging.

LUGERM
Last error found. After changelog:

AN - File System error number encountered

O - No error

-1 - New disc log file was not empty
-2 - New disc log file did not have file code LOG
-3 - New disc file is too small
(Not used - for future use).

LOGDEV

The logical device number of the current extent of the disc log file or the disc buffer file (buffer file has only 1 extent).

BSPHLC
The amount of space, in records, that are currently available to the users.
On the last block of the last extent, one record will be saved by the logging process so that the proper close information can be posted to the file - either the trailer record (if the log logging process is stopped) or the change to neuron because of an EOF condition (and the AUTO option had been specified).

BUFUSED

DO OSD.

The number of records currently in the buffer. On all extents, except the last extent BUFSPACE+BUFUSED = 32 (number of records in a complete block). However, on the last block of the last extent this will NOT be true since one record is always held in reserve by the logging process.

This shows the order in the log file "set" of the currently opened log file. (Not used - for future use).

The disc address of the current extent of the disc log file. If it's a serial file, this is the disc address of the disc buffer for the file.

The record number of the next block to be written to the logging destination file or the disc logging buffer for serial files. (Used as an offset into the current extent for the writes - since each record is one sector in length).

User Logging Buffer

*	TYPICAL LOGBUFF ENTRY	X
0	- USER -	0
	- NAME -	
	- RAILE	
4		4
	GROUP	
	NRME	
8		10
	_ ACCOUNT _	
	_ NAME _	
12	USER PCB #	14
13	OPENLOG COUNT	15
14	WAIT STATE	16
15	ERROR CODE	17
16	LOG NUMBER	20
17	SUBSYSTEM CODE	21
18	TOTAL	22
	RECORDS -	
23	FRUD ENTRY PTR	27
24	BKURD ENTRY PTR	30
	'	

User Logging Buffer

SYTE INDEX TO CURRENT ENTRY HORD INDEX TO CURRENT ENTRY DOUBLE INDEX TO CURRENT ENTRY BINDEX INDEX DINDEX USER GROUP ACCT BINDEX BINDEX+8 BINDEX+16 UPIN OPENCHT HISTATE ERROR LGNUM SCODE INDEX+12 INDEX+13 INDEX+14 INDEX+15 INDEX+16 INDEX+17 RECS DINDEX+9 INDEX+23 INDEX+24 MENTRY PENTRY

USER The name of the user who opened the logging file through this entry.

GROUP
The group of the user who opened the logging file.

 $\ensuremath{\mathsf{RCCT}}$ The account of the user who opened the logging file.

UPIN
The PCB number of the user process (PIN * PCBSIZE).

OPENCNT
Counter of how many times this user called OPENLOG. (Incremented for every OPENLOG, decremented for every CLOSELOG). (Not used - for future use).

NSTATE
The mait status of the users process.
INACTIVE = 0
ACTIVE = 1

Used to hold error information for this user.

-1 = No room in disc (or disc buffer) and MOWRIT.

0 = 0.K.

 \mbox{LGNUM} The logging number assigned to the user. (From USERMO in global area to be used as log $\mbox{\tt W}$ in the log record).

 $\ensuremath{\mathsf{SCOOE}}$ The subsystem code for the caller. This applies only to privileged callers.

RECS The number of records written by this user.

User Logging Buffer

MENTRY R table relative pointer to the next entry in the logging data segment. (-1 = this is the last entry)

PENTRY
A table relative pointer to the previous entry in the logging data segment.
(-1 = this is the first entry)


G.01.00 17- 38

Logging Identifier Table

User Logging Identifier Table

ENTRY SIZE = #33 words DST X41

Table containing an entry for each potential logging process. Entries are added via : GETLOG and released via : RELLOG.



ENTRIES


MENTRIES ENTRYSIZE LIDTAB(1) LIDTAB(4)


The maximum number of entries in the table. (i.e. maximum number of user log-ging processes. 1 entry for every process - activated or not).

ENTRYSIZE
The size of each entry in the table.

Logging Identifier Table

Typical Entry





User Logging Record Formate

DATA FIELDS OF LOG RECORDS

OOUBLE INTEGER
INTEGER
INTEGER
DOUBLE (from intrinsic CALEMDAR)
RSCII
INTEGER (From intrinsic CALEMDAR)
RSCII
INTEGER
RSCII
INTEGER
RSCII
INTEGER

RECH CKSUM CODE TIME DATE LOGID LOGW LEM USERAREA CREATOR PCB

- 1. The checksum algorithm uses the exclusive or (XOR) function against a base of negative one. $\,$
- 2. Null record is used for filler.
- 3. The code word of the logging record can contain a subsystem code defined by the user in the first half of the word (0:8). User logging allows privileged users to pass this code in the index parameter of the Openlog intrinsic.
- 4. The "len" field will contain the entire length of the data in the transaction (i.e. the length passed to MRITELOG, BEGINLOG, ENDLOG). If a continuation record is part of the transaction, it will also contain the entire length of the data. For example, a length of 140 was passed to the intrinsic. The "len" field of the first record will be 140, the "len" field of its continuation record will also be 140 even though the actual amount of data found in the first record will be 119 and the data found in the continuation record will be 21. (Positive length = # words, negative length = # bytes)

G.01.00 17- 45

DST = 59 (X 73) MERSINFOTAB

Measurement Information Table

•••	0	LDEV # OF MERSIO	MERSLDEV
	1		MERSPLAB
	2		MERSOSTN
Reserved for MERS	3		i
control	4		
	5		
	6		
	7		_
	10		<u> </u>
	11		<u> </u>
Reserved	12		
for performa	13		
tuning paramete	1	4	. 1
,	15		<u> </u>
	16		<u>.</u>
	17		<u>.</u>
	20	GLOBAL STATISTICS XOS NUMBER	MERSSTRTX- DSNUM
	21	PROCESS STATISTICS XDS BANK 	MERSPROC- XDSBANK
	22	PROCESS STATISTICS XDS BASE	MEASPROC- XDSBASE
	23		MEASPROC-
	24	CLRSS 14 STRTISTICS XDS BANK	Ī
	25	CLASS 14 STATISTICS XDS BASE	Ī

G.01.00 17- 46

Measurement Information Table

MERSINFOTAB (Cont.)

26	CLRSS 14 STRTISTICS XDS NUM.	ı
27	CLASS 13 STATISTICS XDS BANK	ı
30	CLASS 13 STATISTICS XDS BASE	ı
31	CLASS 13 STATISTICS KDS NUM.	ı
32	CLASS 12 STATISTICS XDS BANK	Ī
33	CLASS 12 STATISTICS XDS BASE	
34	CLASS 12 STATISTICS XDS NUM.	1
35	CLASS 11 STATISTICS XDS BANK	I
36	CLASS 11 STATISTICS XDS BASE	١
37	CLASS 11 STATISTICS XDS MUM.	1
40	CLASS 10 STATISTICS XDS BANK	ļ
41	CLASS 10 STATISTICS XDS BASE	I
42	CLASS 10 STATISTICS XDS NUM.	ı
43	CLASS O9 STATISTICS XDS BANK	ĺ
44	CLASS O9 STATISTICS XDS BASE	
45	CLASS O9 STATISTICS XDS NUM.	1

Measurement Information Table

MERSINFOTAB (Cont.)

reserve		1
fo measureme interfac	nt .	1
11161130	•	1
	50	CLASS O ENABLED CLASS 1 ENABLED COUNT
	51	CLASS 2 EN.CHT. CLASS 3 EN.CHT.
	52	CLRSS 4 EN.CHT. CLRSS 5 EN.CHT.
	53	CLASS 6 EN.CHT. CLASS 7 EN.CHT.
	54	CLASS 8 EN.CHT. CLASS 9 EN.CHT.
	55	CLASS 10 EN.CHT. CLASS 11 EN.CHT.
l	56	CLASS 12 EN.CHT. CLASS 13 EN.CHT.
1	57	CLASS 14 EN.CHT. CLASS 15 EN.CHT.
	60	
reserve	61	
for shared	-	
clock	63	
interfa user	64	
	65	
	66	
1	67	

MERSINFOTAB (Cont.)

	70		FLAG	A	
share	d 71		XDSI	1	
clock	72		XDS2	1	
interfac	e 73		DEGUNT	1	
cells	74		DLIMIT	1	
1	75	i	TCOUNT	i	
	76	1	TLIMIT	1	
l	77	l	DLABEL		
	100	MONIT	OR BUFFER INDEX	1	SMONIDX
	101	MERS	BUFFER		MERSBUFO
	102	MERS	BUFFER INDEX		MERSIDX
reserved for	103	MEAS	ENRBLED FLAGS	!	MERSMSKO
event		MERS	ENABLED FLAGS		MERSMSK1
logging	105	MEAS	BUFFER BANK		MEASBUFBANK
	106			 	
		1			
ļ	•	1			
	116			ı	
	117	1		I	

M: Interrupt has missed due to last interrupt handling.

A: Current interrupt handling active.

CHAPTER 18 MESSAGE FILES

Message File Data Structures

This chapter contains the data structures necessary to support message files. The first section details the message file's version of the familiar file system data structure; ie, the file label, file control block, etc.

The second section shows the tables used by the basic IPC mechanism which is a set of internal, MPE procedures designed to support the "boundary conditions" of IPC files. For example, signaling a no wait reader that its record has arrived. See the section's introduction for a detailed description.

File Structure

File Label/FCB Extent Map

	End of file block	Start of file block
Disc addr of extent 0	•	
		•
Disc addr of extent 1	٧	•
	-	•
Disc addr of extent 2		•
		•
Disc addr of extent 3		•
		•
)	i	•
		•
Disc addr of extent n-1		٧
		-
Disc addr of extent n		

The EOF and SOF are examples only, meant to show:

1) The start of file moves into the extent map as records are read 2) The file can wrap around and, hence, cause the SOF to be greater than the EOF.

When a file becomes empty the SOF and EOF are reset to the first block of extent zero.

Each extent is composed of a number of blocks. Extents all have the same number of blocks. Extent zero also contains space for the file label and user labels in the exact same format as standard files. Starting with block zero, sufficient blocks are allocated to the file label/user labels to satisfy their space requirements.

Extents outside of the SOF/EOF range may not exist. They are deleted at close time when there are no more writers accessing the file.

G.01.00

Message Files

Block Structure

First data record	*********
Second data record	Exact same format as standard variable length blocks.
Last data record	
Record delimiter (-1)	*******
Empty space (next record would not fit)	
Header delimiter (%77)	
Last header record	
Second header record	
First header record	

Separating the data portion of the records from their header enables the standard file system access procedures to read the records with no knowledge that they are msg file records.

Record Format

Number of bytes in record
First data word of record
Last data word of record

Length word's value does not include itself.

G.01.00 18- 2

Message Files

Header Format

CILCI	i	Header	Type	0
Writer's	ID			-

C (0:1) - Set on if this was the last record written before the system crashed. This bit is set on by the first open on the file after the crash.

LC (1:1)- Valid only for close headers. Set to one if this is the last writer to close the file.

Type(8:8)- O data 1 open 2 close

Message Access Control Block

Notes:
1. Words/fields that do not pertain to message files are left blank.

2. This diagram shows the "combined" ACB as it appears to the message access procedures (the procedures in IPC). Thus it is a combination of the LACB and the PACB.

-5	DST number of the PACB	-5	
-4	PACB control block vector table address	-4	
-3	DST number of the LACB	-3	
-2		-2	
-1			
0	Size of the ACB including buffers (words)	٥	
1	File Mumber	1	*
2	File name	2	*
	\	\	*
6	Foptions	6	*
7	Roptions	7	*

Message Files

Message Access Control Block (Cont.)

8	Record size (bytes)	10 *
9	Block size (words)	11 *
10		12
11	Carriage control code (uriters)	13 *
12	No нait I/O target	14 *
13	No wait I/O count	15
14	Error code	16 *
15	Transmission log (units same as last read/write)	17 *
16	Total number of unread records (includes opens	20
17	and closes)	21
18	Block number of the file's tail (relative to the	22
19	start of file block)	23
20	Logical record transfer count	24
21		25
22	Physical block transfer count	26
23		27
24	DST REL ADDR of Read Header	30
25	DST REL RDDR of Write header	31
26	FCB DST	32
27	FCB vector table offset	33
28	Share count (number of LACBs)	34
29	Access class, status, etc.	35
30	Logical device number	36
31	 	37
32	DST relative address of next read record	40
33	Size of the buffer (Hords)	41
		ı

G.01.00 18- 4

G.01.00 18- 3

Message Files

Message Access Control Block (Cont.)

34	Spare	42
35	FMAVT index	43
36	Number of read LRCBs	44
37	Type and disposition	45
38	Accese nask Records per block	46
39	Ol# rd buf # ut buf er qu n c d e f	47
40	Misc. meg file flags	50
41	Number of free word in the current free record	51
42	Number of free récords	52
43		53
44	Number of mondata records in the file	54
45		55
46	Spare	56
47	#open records # read requests	57
48	last read error last write error	60
49	DST relative address of the next write record	61
50	Spare	62
51	Spare	63
52	DST rel address of the PACB	64
53	DST rel address of the LRCB	65
54	DST relative address of the stack ACB	66
55	Stack DST relative address of DB	67
56	Target area's DST number	70
57	Reserved for calling parameters	71
58		72
59		73

Message Files

Message Access Control Block (Cont.)

		1
60	Reserved for the stack marker from file system	74
61	intrinsics	75
		,
64	User's soft interrupt plabel	100*
65	Number of seconds to wait on boundary condition	101*
66	D Ex Nd Vr Bt Cls C Carriage control	102*
67	Reply Port (basic IPC port)	103*
68	Writer ID	104*
69	Control block index for nowait writer record buf	105*
70	DST relative addr of nowait writer record buffer	106*
71		107*
72	No wait I/O resultant error code	110*
73	No wait I/O resultant transmission log	111
74	urite wait queue (basic IPC port)	112
75	Read wait queue (basic IPC port)	113
76	Length of record in bytes	114
77	Head record's record type (same values as header)	115

G.01.00 18- 6

Message Files

Message Access Control Block (Cont.)

	1	
78	Head record's writer ID	111
79	Misc. flags Record type	117
80	Size of record + count + header words	120
81	Completor ID Waiter ID	121
82	Local flags	122
83	Target DST number	123
84	DST relative address of target area	124
85	Length of target area	125
86	Waiter's reply port, O if using ACB compltm area	126
87	Waiting process's PIN	127
88	Waiting process's pin	130
89	Waiter's soft interrupt plabel	131
90	Resultant error code	132
91	Resultant transmission log	133
92	DST rel address of first buffer	134
	DST rel address of buffer two	

* Value is private to a particular accessor.

Message Files

Hord	Field	Description
66		Accessor's local flags.
	(0:1)	
	(1:1)	
	(2:1)	nd 1 - do not destroy the next record read.
	(3:1)	vr 1 - uriter has not yet uritten his first record (ie., he is a virgin).
	(4:1)	bt 0 - transmission log should be expressed in words.
	(5:1)	cls - Not currently used (reserved for group IPC standard).
	(6:1)	C - No wait completion message is in LACB area.
	(8:8)	ar ctl- carriage control character to be used for
		the writer's record (a value of one indicates carriage control character).
40		File's global flags.
	(1:4)	- number of read buffers
	(5:4)	- number of write buffers
		er 1 - extended read
	(10:1)	qu 1 - one or more writers has been queued on the
		wait queue.
	(11:1)	n 1 – wait msg is located in the ACB
	(12:1)	c 1 - completion msg is located in the ACB
	(13:1)	d 1 - the current write buffer has dirty bit set
	(14:1)	s 1 - the start of file is block zero
	(15:1)	f 0 - the ACB buffers have not been filled

MMSTAT Definitions

Octal Value	Event Type	Parameter 1	Parameter 2
72/0	Read init	# free rec	
72/1	Read compl	(0:8) error, (8:8) ID	Number of records
72/2	Write init	(0:8) # rec, (8:8) ID	Number of free records
72/3	Write compl	(0:8) error, (8:8) ID	Number of free records
72/4	Control	(0:8) error, (8:8) ID	(0:4) func, (4:12) parm
72/5	EOF	(0:8) error, (8:8) ID	Number of records
72/6	Open	(0:8) error, (8:8) ID	Number of records
72/7	Close	(8:8) #free, (8:8) ID	Number of records
72/10	Initiation	0	(0:8) fix, (8:8) update
73/0	Put record	(0:8) error, (8:8) ID	(0:3) rec type,
73/1	Delete rec	(0:8) error, (8:8) ID	(3:13) number of records (0:3) rec type
73/2	Delete blk	Start of file block #	(3:13) number of records End of file block #

Notes:

- 1. The aa/bb notation in the "octal value" column denotes type/subtype. Type is the actual MMSTAT event number. Subtype is (0|4) of parameter 0.
- Several items can possibly exceed their fields, in that case the bits beyond the field are lost. These items are number of records, number of free records, start of file, and end of file.

G.01.00 18- 9

Message Files

Reader and writer wait queues

When an empty message file is accessed by more than one reader (share), then there must be a way of having the readers' FRERDs satisfied in the same order that they were issued. That is, there must be queue of waiting readers. The ipc access procedures accomplish this by dedicating a basic ipc port as a "read wait queue." Whenever a reader's request is stalled because the file senty, a message is sent to the read wait queue. Subsequent FRERDs by other processes will queue up behind the first reader in a FIFO manner. Rn FIRITE will take the first entry from the wait queue and send a "read may be done" message to the reader's reply port.

G.01.00 18- 10

In a like manner multiple writers will queue on the write wait queue when the file is full.

Completion notification for nowait I/O

The IOWAIT intrinsic waits for a message to be sent to the reply port (s) of the specified user files.

Tineouts

When an accessor encounters a boundary condition (ex, a reader accesses an enpty file), it nay specify that the condition must be satisfied in x seconds (FCDNTROL 4). To this end the ipc access procedures merely issue the FCPORTSEND to the wait queue with the user's timeout value specified. The timeout will tear the message from the wait queue and place it on the accessor's reply port.

G.01.00 18- 12

Message Files

File System Basic IPC Definitions

The objective of this set of uncallable procedures is to provide a simple ipc mechanism to support the ipc file access procedures. It enables one process to send short, control messages to another process.

General Behavior

FCPORTOPEN Procedure

The heart of this mechanism is the port. A process desiring to receive messages would first open (create) a port. This process is termed the "port manager." When the port is created, a port number is returned to the opener. Since the port number value cannot be known in advance, potential senders need some method of obtaining the port number from the port manager.

Both the ports and the messages are contained in a single disc resident data segment. There can be a total of over thiry-five hundred open ports and outstanding messages. Thus neither ports nor message blocks are scarce resources.

FCPORTSEND Procedure

This procedure sends a 0 to 5 word message to a port. Optionally a timeout value may be specified which will limit the duration the message will remain attached to the port. Expiration of the timeout causes the message to be deleted from the target port's gueue and placed on the sender's reply port (specified by the sender in the FCPORTSENO procedure call).

FCPORTRECEIVE

Reads and deletes the head message from a port. The sender's return port number is also given to the receiver, enabling him to send a reply message.

FCPORTCLOSE

Demolishes the port.

IPC file's use of this mechanism

All open message files have two ports open for the file (read wait queue and write wait queue), plus one port per accessor (reply port). Their use is described in the following.

G.01.00 18- 11

Message Files

3. Parameter word zero has a common format for all the MMSTAT events.

LISTO	Description
(0:4)	Event's subtype.
(4:2)	File's state 0 - empty 1 - partially full 2 - only a fraction of a free record is left 3 - completely full
(6:1)	Nonzero indicates that there is one or more waiting readers.
(7:1)	Monzero indicates that there is one or more waiting writers.
(11:1)	Monzero indicates that the write has a carriage control character.
(12:4)	Flags local to the accessor. (12:1) - the accessor has done no FREADs/FURITEs (13:1) - extended wait (14:1) - nondestructive read (15:1) - writer has not written any records
	(0:4) (4:2) (6:1) (7:1) (11:1)

Port Data Structures

Port Data Segment

Port data segment Global area

Remainder is composed of "block size" chunks. The chunks are a combination of free entries, ports, message queue entries, and timer list entries.

Port With Two Outstanding Messages



G.01.00 18- 13

Message Files

Port Number

Port DST Number Array

Located in System DB Extension Area.

64 Port,data segment number	64
65 Reserved for a second port segment	65

G.01.00 18- 14

Message Files

Port Data Segment Global Area

	_		
0	1	Data segment number of this port data segment	0
1	Ī	Block size in words	1
2	Ī	Total number of blocks	2
3	Ī	Maximum number of blocks	3
4	Ī	Current number of free blocks	4
5	Ī	Number of open ports	5
6	ī	Head of free list	6
7	Ī	Tail of free list	7
10	ī	Head of impeded process list	8
11	ī	Tail of impeded process list	9
12	ī	Head of timeout thread (TQE address)	10
13	Ī	TRLX of timeout	11
14	Ī	Value returned by TIMER intrinsic when	12
15	Ī	Timeout was initiated.	13
16	Ī	Head of port list (in units of port numbers).	14
17	ī	Not used.	15

Message Files

Port

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	
0 Head MQE address	0
1 Tail MQE address	1
2 E W Next port number in port list thread!	2
3 I Subtype Port Pin number	3
4 Soft interrupt parameter one	4
5 Number of MQEs in the port's queue	5
6 Number of sends to this port	6
7 Soft interrupt plabel	7
8 PIN of port's owner	10
0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	

Enable wake up bit 0 - Do not awaken the process 1 - Awaken the process E

W type Rction to be taken on an enabled port when a message is received.

- 0 Awaken the process on a message wait bit.
- 1 Generate user software interrupt
- 2 Generate system software interrupt
- Interrupt mode.

Subtype Soft interrupt subtype

Message Queue Entry (MQE)

٥	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	-
	Port number of return port	1
2	Time List Entry (TLE),0=no timeout,-1=timed out	2
3	Parameter zero	1 3
4	Parameter one	1 4
5	Parameter two	5
6	Parameter three	6
7	Parameter four	7
	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	Ī

Timer entry definitions - 0 - no timeout
1 - timeout expired
2 - TLE address for a pending timeout

File System Message Files

Wait Message

parm#

0 - WRITER ID

1 - LOCAL FLRGS (differ with each accessor)
(0:1) - accessor just opened file
(1:1) - will wait on boundary condition if no symbiotic process
(3:1) - writer has not written a record
(4:1) - transmission log in bytes
(8:1) - carriage control code

2 - DSTH of data buffer

3 - Rddress of data buffer (DST relative)

4 - Length of data buffer in bytes

0 - Resultant error code 1 - Resultant transmission log in bytes

G.01.00 18- 17

Timer List Entry (TLE)

	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	_
0	Next TLE (sorted in incr time val), 0 if last	
1	Preceding TLE entry (0 if first entry)	1
2	Number of milliseconds the timeout value	2
3	of this TLE is beyond the previous TLE.	3
4	Address of the affected MQE	1 4
5	Address of the MQE's port	5
6	Value of TIMER when this timeout expires	5
7	[(Milliseconds)	7
	0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	Ī

MMSTRT Definitions

Octal Value	Event Type	Parameter 0	Parameter 1	Parameter 2
62	Open	Port number	Port DST num	Flags parameter
63	Receive completion	Port number	MQE address 15:1 Waitspc	Return port
64	Send	Port number	MQE address 15:1 Q type	Return port
65	Change status	Port number	0 = enable 1 = disable	Head MQE address
66	Abort	Port number	Parameter zero	Return port
67	Close	Port number	Port DST	# open ports left
70	Expand	Port DST num	# expand blks	Total # blocks
71	Timeout expired	Port num	MQE address	Return port

G.01.00 18- 18

CHAPTER 19 MPE MEMORY RESIDENT MESSAGE FACILITY

Overview of Facility

The memory resident message facility of MPE V addresses the need for an efficient, simple, and uniform method for system code to send short status-type messages to processes.

Each process is created with a "port" in the message harbor table (DST X71) which supports a set of message subqueues which are private to that process. There is a maximum of four subqueues per port in the initial implementation. This limit can be easily extended when new subqueues are required.

Rny system code, even code running on the ICS, can send a message to any sub-queue of any process. The destination process' PIN must be known, any a priori conventions on subqueue number and message formats must be es-tablished. The caller of SEMDNSC hay optionally specify that the destination process be анаkended from a message wait.

Message can be any length up to the configured maximum. Message length is specified in the call to SENDMSG and RECETVENSG. In the initial implementation, messages are limited to 6 words in length with 4 words available for data. This maximum can easily be increased if the need arises.

By calling PORTSTATUS, a process may at any time determine whether a specified subqueue is non-empty or obtain the subqueue number of the most urgent non-empty subqueue (lowest numbered one).

By calling RECEIVEMSG, a process may receive the message at the head of the specified subqueue. This receive is optionally non-destructive.

 $\boldsymbol{\mathsf{R}}$ process can wait on a message wait, or on a combination of message wait and other wait types.

Message Intrinsics

SENDMSG

Procedure SENDMSG(Destpin, Subqueue, MsgLength, Flags); Value Destpin, Subqueue, MsgLength, Flags; Integer Destpin, Subqueue, MsgLength; Flags; Option Privileged, Uncallable;

Destpin, Subqueue, and MsgLength have to be within range or a System Failure 622 $\ensuremath{\mathrm{Hill}}$ occur.

The caller of SENDNSG stacks the message contents before calling the procedure. SENDNSG expects the first mag word to be at Q-7-RsgLength, and the last mag word at Q-8. The message contents at Q-8 to Q-2-RsgLength are deleted from the top of stack by the exit from SENDNSG to the caller.

G.01.00 19- 1

Memory Resident Message Facility

Flags.(1:1) = 1 ==> Wake-up destination process from a message wait.

Return CC = CCG if process was already awake else CC = CCE.

PORTSTATUS

Logical Procedure PORTSTATUS(Subqueue); Value Subqueue; Integer Subqueue; Value Su Integer Su Option Privileged, Uncallable;

When supplied a valid subqueue number, PORTSTATUS returns a true value if the subqueue is non-empty and a false value if the subqueue is empty.

When passed a $^{-1}$ a subqueue parameter, PORTSTATUS returns the subqueue number of the process' most urgent non-empty subqueue (the smaller the number, the more urgent the subqueue).

If all subqueues are empty, PORTSTATUS returns CC – CCE. If at least one subqueue is non-empty, PORTSTATUS returns CC = CCG.

RECEIVEMSG

Procedure RECEIVEMSG(Subqueue, Msglength, Flags); Value Subqueue, Msglength, Flags; Integer Subqueue, Msglength; Flags; Logical Option Privileged, Uncallable;

Subqueue and MsgLength has better be within range or a System Failure 622 will occur.

The caller of RECEIVENSG does an RSSEMBLE(RDDS MsgLength) to make space for the message contents. RECEIVENSG stores the message contents into Q-8, Q-9,...,Q-7-MsgLength. Q-7-MsgLength contains the first word of the message.

Flags.(0:1) ==> do not release message from head of subqueue (non destructive read).

Return CC = CCG if all subqueues were empty, else CC = CCE.

| 0| 1| 2| 3| 4| 5| 6|

G.01.00

Memory Resident Message Facility

Supporting Data Structures

Message Harbor Table [DST #57 (X71)]

0	DST Index Number (%71)
1	Data Segment Size
2	Reserved
3	Maximum number of PINS + 1
4	Maximum Msg Size (6)
5	Reserved
6	Message Pool Head Pointer
7	Message Pool Tail Pointer
8	Rvailable Msg Frames Count
9	Head of impeded queue
10	Tail of impeded queue
11	Reserved
13	Ports (16 words each) (8 for header + 2 link words for each of 5 subqueues)
	Messages (б ноrds each) (2 for header + 4 for data)

4----

CHAPTER 20 MMSTATS EVENTS

MMSTRTS Catalog Index

				EVENT NAME		
ALCSTBLK	20	024 (-)	×	FREAD FREADDIR FREADLABEL FREADLABEL FREADSEEK FREMANIE FSETHODE FSPACE FUNLOCK FUPDATE FWATITE FWATITE FWATITE FWATITE FURTITE FURTITE FURTITE FURTITE FURTITE FURTITATE TOWATI TOWATI HOWOFF FROCESS COMPLETE QUE FURTITATE FURTITATE TOWATI HOWOFF FROCESS COMPLETE FROM FORESS FORE FURTINE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITATE FURTITA	62	076 (-)
ALLOCMEM	12	014	×	FREADDIR	64	100 (-)
BINREAD	233	351 (-)	*	FREADLABEL	76	114 (-)
BREAK	237	355 (-)	*	FREADSEEK	68	104 (-)
C_ABSENT	139	213	*			()
CABORTIO	142	216	Χ.	FRENHITE	80	120 (-)
CACHENOV	14	016	ž	COLIMODE	70	110 ()
CCLUSE	146	222	î	L OF ILLIANE	- 12	105 (-)
CCONTROL	154	232	î	LOUNCE	70	117 (-)
CONTRUL	102	126	*	TURLUCK	13	117 (-)
CCORROCE	7	007	*	FIRPORTE	66	102 (-)
CONFIG-THEO	221	335 (-)	×	FURTIE	63	077 (-)
CONFIG-INFO	222	336 (-)	×	FURITEDIR	65	101 (-)
CONFIG-INFO	223	337 (-)	×	FURITELABEL	77	115 (-)
COPEN	140	214	*	GIPINTERRUPT	192	300
			*	GET_CDT	15	017
COPENTRACEFILE	153	231	*	IOBUFTRAP	125	175
CPOLLIST	155	233	*	I/O COMPLETION	111	157 (-)
	443	000		TUTTITHE	64	124
CKEHU	14/	223	÷	TOMMT!	90	103 (-)
CDEOD4	147	240		MONEUL TIME VEG	1	001
CAERDI	177	270	×	MAD DOM	87	127
CSDRTVER	150	226	*	MONTNIT	228	344 (-)
CSTOWALT	144	220	×	MONOFF	229	345 (-)
CWRITE	149	225	*	PROCESS COMPLETE	211	323 (-)
DC1DC2RCK	231	347 (-)	*	QONSEG	. 0	000
			*	QUE_LDR	16	020
DEALLOCM	13	015	*	QUIESCE	40	050
DEALCSTBLK	21	025 (-)	*	RELRESOURCES	23	027 (-)
			Ž	REQUIENT	90	132
DIZKROGCHICHEK	200	310	î	SEPTOTAT:	104	202
NTOVOLICCOTCUED	201	211	÷	STOOM-ENIKT	105	302
DISKEDBUD	100	144 (-)	*	STODII	193	006
DISKLANDA	100	144 (-)	×	SOFT'DERTH	120	170
DISKERROR DISKERROR DISKINTRPT DQUE_LDR	101	145 (-)	*	QUE_LDR QUIESCE RELAESOURCES REGCACHE SEGIOINIT SIODN-ENTRY SIODNE SOFI'DERTH SPECCHAR SPECIALRQ	236	354 (-)
DISKINTRPT	191	277	*	SPECIALRO	2	002
DQUE LDR	17	021	*			
			*	SPECREAD START I/O STRATEGY	238	356 (~)
			*	START I/O	193	301
			*	STRATEGY	83	123

MMSTATS Events

DISK TRAFFIC	98	142 (-)	*	SWAPIN	8	010
FCHECK	74	112 (-)	×	SYSPINS	224	340 (-)
FCLOSE	81	121 (-)	×	SYSPINS	225	341 (-)
FCONTROL	71	107 (-)	×	SYSPINS	226	342 (-)
FETCHSEG	4	004	*	SYSPINS	227	343 (-)
FGETINFO	75	113 (-)	×	TERMLOGOFF	235	353 (-)
FIND DE	18	022	×			
FLOCK	78	116 (-)	×	TERMLOGON	234	352 (-)
FOPEN/(DA)	60	074 (-)	*	TERMREAD	230	346 (-)
FOPEN/(DA)	61	075 (-)	×	TERMURITE	232	350 (-)
FPOINT	70	106 (-)	×	UN MAP_RG	88	130

G.01.00 20- 2

MMSTATS Events

MMSTAT CATALOG INDEX

G.01.00 20- 1

EVENT GROUP	DESCRIPTION OF GROUP	PAGE NO.
0	MEMORY MANAGER	20-1
1	MEMORY MANAGER/CACHING	20-9
2	MEMORY MANAGER	20-10
4	SCHEDULING	20-13
6	FILESYS	20-16
7	FILESYS	20-25
8	FILESYS/CACHING	20-30
9	DISC I/O TRANSFER/CACHING	20-31
10	DISC ERRORS	20-32
11	210	20-33
12	DISC SPACE	20-34
13	DISC CACHING	20-51
14	CS/3000	20-36
15	CS/3000	20-40
16	CS/3000	20-43
19	DISC CONTROLLER INTRPT	20-44
20	PRIVATE VOLUMES	20-47
21	PROCESS CREATION AND TERMINATION	20-48
22	MONITOR CONFIG INFORMATION	20-49
23	TERMINAL I/O	20-53

G.01.00 20-3

MMSTATS Events

MMSTAT Event Group O (Memory Management Events)

Even	ţ	0

EVENT NAME: QONSEG DESCRIPTION: ABSENCE TRAP ON CODE/DATA SEGMENT

CALLING MODULE: KERNELC CALLING PROCEDURE(S): QUEUEONSEGMENT

PARAMETER DESCRIPTION

P1,P2 = Segment Identifier

P1.(0:4) = Segment type field 0 => Data Segment 1 => SL Segment 2 => Program Segment 3 => Cache Domain

P1.(4:12) = Program index into CSTBLK (type 2 only)

= Segnent Mumber

P3 = \$LL Pointer (\$LL table relative)

P4 = STRTUS (in stack marker) of calling (trapping) segment

P5,P6 - Unused.

PARAMETER DESCRIPTION

EVENT NAME: SPECIALRQ
DESCRIPTION: REQUEST OF SEGMENT EXPANSION/CONTRACTION, UNLOCK,
UNFREEZE, IOUMFREEZE, LOCK, IOFREEZE, FREEZE

CALLING MODULE: KERNELC, KERNELD, ININ
CALLING PROCEDURES: UNLOCKSEG*, IOFREEZE*, FETCHSEGHENT-(KERNELC)
DISIZE, ZSIZE, GETPKSEG, RLTDSEGSIZE,
ALTPKFILESIZE
STACKOVERFLOW - (ININ)

P1.(0:4) = Segment type field 0 => Data Segment 1 => SL Segment 2 => Program Segment 3 => Cache Domain

= Segment Number

P4 = For types (P3.(12:4))
= 0,2,3,5 => P4.(8:8) = LOCK OR IOFREEZE COUNT
= 1,4 => P4.(0:8) = FREEZE COUNT
= 6-15 => REQUESTED SIZE OF AREA IN WORDS

G.01.00 20- 6

P1.(4:12) = Program index into CSTBLK (type 2 only)

Event 2

```
Event 1
```

EVENT NAME: MAKEOC
DESCRIPTION: MAKE SEGMENT AN OVERLAY CANDIDATE - RELEASE SEGMENT
TO THE POOL OF AVAILABLE SPACE

CALLING MODULE: KERNELC CALLING PROCEDURE: MAKEOC

PARAMETER DESCRIPTION

P1, P2 = Segment Identifier

P1.(0:4) = Segment type field 0 => Data Segment 1 => SL Segment 2 => Program Segment 3 => Cache Domain

P1.(4:12) = Program index into CSTBLK (type 2 only)

= Segment Number

P3 = Bank of region P4 = Address of region

P5, P6 - Unused.

G.01.00 20- 5

P1,P2 = Segment Identifier P2 = Segment Number

=> Request is through FETCHSEGHENT
(types 0,1,2)
Type of request
0 > JORREEZE
= 1=> RREEZE
= 2=> LOCK
= 3=> TOUNFREEZE
= 4=> UNFREEZE
= 5=> UNLOCK
= 6=> DISIZE EXPRNSION
= 7=> DISIZE EXPRNSION
= 7=> DISIZE EXPRNSION
= 9=> PWFILE EXPRNSION
= 10=> PWFILE CONTRACTION
= 11=> XDS EXPRNSION
= 12=> XDS CONTRACTION
= 13=> SZIZE EXPRNSION
= 14=> SZIZE EXPRNSION
= 15=> SZIZE EXPRNSION
= 15=> SZIZE EXPRNSION
= 15=> SZIZE EXPRNSION
= 15=> SZIZE EXPRNSION
= 15=> SZIZE EXPRNSION
= 15=> STICKEVERION

MMSTATS Evente

P5,P6 - Unused.

Event 5

EVENT NAME: SEGIO
DESCRIPTION: MEMORY MANAGEMENT READ/WRITE OF SEGMENT FROM/TO
DISC QUEUED

CALLING MODULE: KERNELC CALLING PROCEDURES: PROCESSINITMSG, STARTSEGURITE

PARAMETER DESCRIPTION P1,P2 = Segment Identifier

P1.(0:4) = Segment type field 0 => Data Segment 1 => SL Segment 2 => Program Segment 3 => Cache Domain

P1.(4:12) = Program index into CSTBLK (type 2 only)

= Segnent Number

P3 = Disc Request Index - (DRQ Table relative)

P4 = .(0:1) = 1 => WRITE START = 0 => READ START .(1:15)= Ldev #

P5.P6 - Unused.

MMSTATS Events

Event 4

EVENT NAME: FETCHSEG DESCRIPTION: SEGMENT REQUEST (FOR I/O SYSTEM OR PROCESS)

CALLING MODULE: KERNELC CALLING PROCEDURE: FETCHSEGNENT

PARAMETER DESCRIPTION

P1,P2 = Segment Identifier

P1.(0:4) = Segment type field
0 => Data Segment
1 => St. Segment
2 => Program Segment
3 => Cache Domain
P1.(4:12) = Program index into CSTBLK (type 2 only)

P2 = Segment Number

P3 = Requester ID
.(0:1) = 1 => I/O System request
.(1:15) = Ldev #
.(0:1) = 0 => Process request
.(1:15) = Pan # of requesting process

.(1:1) = 1 => IOFREEZE REQUEST .(2:1) = 1 => BLOCKED LOCK REQUEST .(3:1) = 1 => LOCK REQUEST .(4:1) = 1 => FREEZE REQUEST

P4= .(13:3)= 0 => Segment already present = 1 => Segment is Recover Overlay Candidate = 2 => Segment already on its way in for someone (Segment In Motion In) = 3 => Segment not present -- must fetch (Full fetch)

P5,P6 - Unused.

G.01.00 20- 7

G.01.00 20-8

Event 6

EVENT NAME: SIODONE
DESCRIPTION: MEMORY MANAGEMENT SEGMENT READ/WRITE FROM/TO DISC
COMPLETE

CALLING MODULE: KERNELC CALLING PROCEDURES: SEGREADCOMPLETOR, SEGMRITECOMPLETOR

PARAMETER DESCRIPTION

P1,P2 = Segment Identifier

P1.(0:4) = Segment type field 0 => Data Segment 1 => St. Segment 2 => Program Segment 3 => Cache Domain

P1.(4:12) = Program index into CSTBLK (type 2 only)

= Segment Number

P3 = Disc Request Index (DRQ Table relative) P4 = .(0:1) = 1 => Write complete = 0 => Read complete

P5,P6 - Unused.

Event 7 (27)

EVENT NAME: CGARBAGE EVENT DESCRIPTION: GARBAGE COLLECTION HAS JUST TAKEN PLACE

CALLING MODULE: KERNELC
CALLING PROCEDURE: COLLECTGARBAGE

PARAMETER DESCRIPTION

P1 = BRNK OF SOURCE JUST MOVED FROM
P2 = BODR OF SOURCE JUST MOVED FROM
P3 = MOVEPBECNT, NUMBER OF PRGES JUST MOVED FROM
P4,P5,P6 - Unused.

G.01.00 20- 9

MMSTATS Events

MMSTAT Event Group 1 (Memory Manager)

Event 12 (214)

EVENT NAME: ALLOCHEM
DESCRIPTION: FOUND A HOLE FOR A SEGMENT REPLACEMENT REQUEST

CALLING MODULE: KERNELC CALLING PROCEDURE: RESERVEREGION

PARAMETER DESCRIPTION

P1 = REQUESTED SIZE IN PAGES
P2 = BANK OF SELECTED REGION
P3 = RODRESS OF SELECTED REGION
P4,P5,P6 - Unused.

Event 13 (%15)

EVENT NAME: DEALLOCH DESCRIPTION: RELEASE REGION OF MEMORY TO AVAILABLE STATUS

CALLING MODULE: KERNELC
CALLING PROCEDURE: RELEASEREGION

PARAMETER DESCRIPTION

P1 = SIZE RELEASED IN PAGES
P2 = BANK OF RELEASED REGION BASE
P3 = ADDRESS OF RELEASED REGION BASE
P4,P5,P6 - Unused.

MMSTRTS Fuents

Event 8 (%10)

EVENT NAME: SWAPIN
DESCRIPTION: SWAP IN A PROCESS

CALLING MODULE: KERNELC CALLING PROCEDURE: SHAPIN

PARAMETER DESCRIPTION

P1 = PIN OF PROCESS BEING SUAPPED IN
P2 = .(0:1) = 0 => BEING SUAP
= 1 => END SUAP
.(1:1) = 0 => NORINGL (PARTIEL SUAP OK)
= 1 => SUAP REQUIRED
.(12:4) = 0 => PROCESS SUAPIN COMPLETE
2 => NO ROOM, HARD REQ MAY SUCCEED
3 => NO ROOM, HARD REQ FILED
4 => SUAPIN STOPPED - MORE URGENT ACTIVITY
8 => NO LOCK SPACE
P3 = HARDREQUEST = TRUE => HARD REQUEST ON SUAPIN FALSE=> NORMAL

P4,P5,P6 - Unused.

G.01.00 20- 10

MMSTATS Events

Event 14 (%16)

Event Name: CRCHEMOV
Description: A cache move (i.e. logical disc request) has
just completed.
Calling Module: CRCHESEG
Calling Procedure: ProcessCDTLogReqQue

Parameter Description

P1,P2 = Segment identifier of target DST (LDR'BUFDST)
P2.(0:1) = 1 then this is a stack.
P3 = Happed Donain CDT entry number
P4 = Transfer count
P5,P6 = Unused

Event 15 (X17)

Event Name: GET_CDT
Description: Called when an entry in the CDT table is obtained or released.
Calling Nodule: CRCHESEG
Calling Procedures: Get'CDT'Entry, CDT'Free'Entry, CDT'Get'MD'Entry, CDT'Rel'MD'Entry

Parameter Description

= CDT entry number = Type of call 0 = Free entry 1 = Get entry 2 = Get Mapped Domain entry 3 = Release Mapped Domain entry = If P2=3 then Ldev Entry number DO Not week

P3 = If P2=3 the P4,P5,P6 Not used.

Event 16 (X20)

Event Name: QUE_LDR
Description: Called when an LDR is queued onto the CDT
Calling flouls: CACHESEG
Calling Procedure: CDT'Queue'LDR

Parameter Description

= Mapped Domain CDT entry number = LDR entry index to be queued = Queue type X12 - CDT impeded queue X13 - CDT active queue P4. P5. P6

Event 17 (X21)

Event Name: DQUE_LDR
Description: Called when an LDR is removed from the CDT queue.
Calling Module: CRCMESSEG
Calling Procedure: CDT Dequeue'LDR

Parameter Description

 Mapped Domain CDT entry number
 LDR entry index being removed from the queue
 Queue type
 X12 - CDT impeded queue
 X13 - CDT active gueue P4.P5.P6 Not used.

Event 18 (X22)

Event Name: FIMD_DE
Description: Called when need to find an assigned CDT
Device entry.
Calling hodule: CACHESEG
Calling Procedure: CDT'Find'DE

Parameter Description

P1 = Ldev number of the CDT Device entry to be found.
P2 = CDT Device entry
P3,P4,P5,P6 Not used.

G.01.00 20- 13

MMSTAT Event Group 2

Event -20 (-X24)

EVENT MAME: ALCSTBLK
DESCRIPTION: REQUEST TO RESERVE A BLOCK OF ENTRIES IN THE CSTX

CALLING MODULE: KERNELD CALLING PROCEDURE: RLCSTBLDCK

PARAMETER DESCRIPTION

P1=EIX P2=CSTX CST BLOCK INDEX RSSIGNED DST RELATIVE INDEX OF NORD O OF THE FIRST RESERVED CSTK ENTRY P4,P5,P6 - Unused.

Event -21 (X25)

EVENT NAME: DERLCSTBLK
DESCRIPTION: INDICATES THAT A CST EXTENSION BLOCK HAS BEEN
DERLLOCATED

CALLING HODULE: KERNELD CALLING PROCEDURE: DEALCSTBLOCK

PARAMETERS PARAMETER DESCRIPTION CST BLOCK INDEX ASSIGNED TO THE BLOCK OF CST ENTRIES DST RELATIVE INDEX OF WORD O OF THE FIRST CST ENTRY TO BE RELERSED P1=FIX P2=CSTX RELEASED =(#ALLOCATED CSTX ENTRIES-#ENTRIES BEING RELEASED)*4 PR=MCNT

G.01.00 20- 14

MMSTRTS Events

Event -23 (-X27)

EVENT NAME:RELRESOURCES
DESCRIPTION: RESOURCES (VDS, MAIN MEMORY, ST ENTRY) RESERVED FOR THE
FOR THE SEGMENT HAVE BEEN RELEASED

CALLING MODULE: KERNELD

CALLING PROCEDURE: RELDATASEG

PARAMETERS PARAMETER DESCRIPTION

P1=NEW DB DST NUMBER
P2=DELTA P AT EXCHANGED8 CALL P3=STATUS AT EXCHANGEDO CALL P4,P5,P6 - Unused.

MMMSTAT Event Group 3

(NOT CURRENTLY ASSIGNED)

MMSTATS Events

MMSTRT Event Group 4 (Scheduling)

Event 40 (X50)

EVENT NAME: QUIESCE
DESCRIPTION: PROCESS SWITCH - STATE OF PROCESS SAVED

CALLING MODULE: KERNELC CALLING PROCEDURE: DSP

PARAMETER DESCRIPTION

= PCBOO(CPCB)
.(0:1) = 1 => SAR - SCHEDULING ATTENTION REQUIRED
.(2:1) = 1 => CRIT - PROCESS IS CRITICAL
.(3:1) = 1 => HSIR - PROCESS HS SIR
.(4:1) = 1 => PTOVR - PENDING PI, PROCESS CRITICAL
.(5:1) = 1 => HSPRI - HOLD SIR PRORBITY
.(5:1) = 1 => TPEXP - INCORE PROTECT EXPIRED
.(7:1) = 1 => PEXP - INCORE PROTECT EXPIRED
.(3:1) = 1 => PR - HUST PREEMPT
.(9:1) = 1 => LH - LONG MAIT
.(10:1) = 1 => SAR - SCHOOL HAIT
.(11:1) = 1 => TRH - TERTHARL READ MAIT
.(12:1) = 1 => USEQD - USED R QUANTUM SINCE TRANSACTION
BEGAN
.(13:1) = 1 => HILDI - HOLD IMPEDED PRIORITY
.(14:1) = 1 => RITPRI - HOLD IMPEDED PRIORITY
.(14:1) = 1 => RITBK - PROCESS IN RIT BREAK P1 = PCBOO(CPCB) - MOURNING URIT

.(15:1)= 1 => RITBK

P2 = PCBO4(CPCB)
.(0:1) = 1 => M
.(1:1) = 1 => RG
.(2:1) = 1 => RL
.(3:1) = 1 => RB
.(4:1) = 1 => BIO
.(5:1) = 1 => BIO
.(5:1) = 1 => UCP
.(7:1) = 1 => UCP
.(7:1) = 1 => INT
.(10:1) = 1 => INT
.(10:1) = 1 => INT
.(10:1) = 1 => FR
.(12:1) = 1 => IPP
.(13:1) = 1 => IPP
.(13:1) = 1 => IPR
.(14:1) = 1 => IPR
.(14:1) = 1 => IPR
.(15:1) = 1 => IPR
.(15:1) = 1 => IPR
.(15:1) = 1 => IPR
.(15:1) = 1 => IPR
.(15:1) = 1 => IPR - MOUNTING WAIT
- GLOBAL RIN WAIT
- LOCAL RIN WAIT
- HAIL WAIT
- BLOCKED IO WAIT
- IO WAIT
- UCOP WAIT, RIT WAIT
- JUNK WAIT
- TIMER WAIT
- INTERRUPT WAIT
- SOW WAIT
- SOW WAIT - SON WAIT - FATHER WAIT - PROCESS WAITING TO UNIMPEDED
- PROCESS WAITING FOR SIR
- PROCESS WAITING FOR TIME OUT
- PROCESS WAITING FOR MEMORY

G.01.00 20- 15

G.01.00

P3 = PCB13(CPCB)
.(0:1) = 1 => DISPQ - PROCESS ON DISPRTCHING QUEUE .(1:1) = 1 => L SCHEDULING CLASS .(2:1) = 1 => C SCHEDULING CLASS .(3:1) = 1 => D SCHEDULING CLASS .(4:1) = 1 => D SCHEDULING CLASS .(5:1) = 1 => INTER-PROCESS IS INTERRCTIVE .(6:1) = 1 => CORER-PROCESS IS CORE-RESIDENT .(8:8) = PROCESS' SCHEDULING PRIORITY

P4,P5,P6 - Unused.

(SEE CHAPTER 18 FOR THESE EVENTS)

MMMSTAT Event Group 5

MMSTATS Events

Event -61(%75)

EVENT NAME: FOPEN' DESCRIPTION: DLD FILE OPEN (CONTINUATION OF EVENT -60)

CALLING MODULE: FILEACC

CALLING PROCEDURE: FOPENDA

PARAMETER DESCRIPTION PARAMETERS

> P1= FILE LABEL FILE LIMIT MSN

G.01.00 20- 17

P2= FILE LABEL FILE LIMIT LSU

P3= FILE LABEL # OF EXTENTS

P4-P6 unused

Event -60(%74)

EVENT NAME: FOPEN
DESCRIPTION: NEW DISC FILE OPEN

CALLING MODULE: FILEACC

CALLING PROCEDURE: FOPEN

PARAMETERS PARAMETER DESCRIPTION

P1= FILE # (0:2)=2 -> MON-SPOOLER ACCESS (0:2).NE.2 -> P2= ROPTIONS SEE INTRINSICS MANUAL

P3= FOPTIONS SEE INTRINSICS MANUAL

P4= RECORD SIZE

PS= BLOCK SIZE

P6= # OF BUFFERS

MMSTAT Event Group 6 (FILESYS)

THESE EVENTS ARE FOR DEVELOPMENT USE ONLY AND ARE NOT NORMALLY ENABLED

Event -60(274)

EVENT NAME: FOPEN
DESCRIPTION: OLD FILE OPEN CALLING MODULE: FILEACC CALLING PROCEDURE: FOPENDA

PARAMETERS

PARAMETER DESCRIPTION

(0:2)=2 -> NON-SPOOLER RCCESS (0:2).NE.2 -> P1= FILE #

P2= AOPTIONS SEE INTRINSICS MANUAL
P3= FILE LABEL FOPTIONS SEE INTRINSICS MANUAL
P4= RECORD SIZE
P5= FILE LABEL BLOCK SIZE
P6= # OF BUFFERS

G.01.00 20- 18

MMSTATS Events

Event -61(275)

EVENT NAME: FOPEN' DESCRIPTION: NEW DISC FILE OPEN (CONTINUATION OF EVENT -60)

CALLING MODULE: FILEACC CALLING PROCEDURE: FOPEN

> PARAMETERS PARAMETER DESCRIPTION

> > P1= FCB FILE LIMIT

P2= FCB MRX # EXTENTS

P3= (0:8)= INITIAL ALLOCATION EXTENTS

P4-P6 unused

G.01.00 20- 20

Event -62(276)

EVENT NAME: FREAD DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FREAD

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2= ACBTLOG

TRANSFER COUNT

P3- FLAGS

(15:1) Buffer hit flag

Event -63(X77)

EVENT NAME: FURITE DESCRIPTION:

CALLING MODULE: FILEIO CALLING PROCEDURE: FURITE

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= TCOUNT

SEE INTRINSIC MANUAL

P3≈ FLAGS

(15:1) Buffer hit flag

G.01.00 20- 21

6.01.00 20- 22

MMSTRTS Evente

Event -65(X101)

EVENT NAME: FURITEDIR DESCRIPTION:

CALLING MODULE: FILEIO

CALLING MODULE: FWRITEDIR

PARAMETERS

PARAMETER DESCRIPTION

MSH

LSW

P1= FILENUM

P2= TCOUNT

See Intrinsic manual

P3≠ FLAGS

(15:1) Buffer hit flag

P4= REC #

P5= REC #

P6= NOT USED

MMSTATS Events

Event -66(X102)

MMSTATS Events

Event -64(X100)

EVENT NAME: FREADDIR DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FREADDIR

PARAMETERS

P1= FILE #

P2= ACBTLOG

P3= FLAGS

P4= RFC #

PS= REC #

P6= NOT USED

PARAMETER DESCRIPTION

TRANSFER COUNT

LSH

(15:1) Buffer hit flag

EVENT NAME: FUPDATE DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FUPDATE

PARAMETERS

P1= FILE #

See Intrinsic manual

PARAMETER DESCRIPTION

P2= TCOUNT P3= FLAGS

(15:1) Buffer hit flag

P4-P6 not used

Event -67(X103)

EVENT NAME: IONALT DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: IONAIT

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= ACBTLOG

TRANSFER COUNT

P3= FLAGS

(15:1) buffer hit flag

G.01.00 20-23

Event -68(%104)

EVENT NAME: FREADSEEK DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FREADSEEK

PARAMETER DESCRIPTION PARAMETERS

P1= FILE #

P2= FLAGS

(15:1) buffer hit flag

MSH P3= RFC #

P4= REC # LSH

P5-P6 not used

Event -69 (%105)

EVENT NAME: FSPACE DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FSPACE

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= DISPLACEMENT SEE INTRINSIC MANUAL

P3-P6

not used

G.01.00 20- 25

MMSTATS Events

Event -72 (X110)

EVENT NAME: FSETMODE DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FSETMODE

PARAMETERS

PARAMETER DESCRIPTION P1= FILE #

P2= MODEFLAGS SEE INTRINSIC MANUAL

not used

P3-P6

Event -74 (X112)

EVENT NAME: FCHECK DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FCHECK

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2= ERRORCODE

SEE INTRINSIC MANUAL

P3-P6

not used

MMSTAT Event Group 7 (FILESYS)

THESE EVENTS ARE FOR DEVELOPMENT USE ONLY AND ARE NOT NORMALLY ENABLED

Event -70 (X106)

EVENT NAME: FPOINT DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FPOINT

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2= RFC # MSU

P3= LSW LSH

P4-P6 not used

Event -71 (%107)

EVENT NAME: FCONTROL DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FCONTROL

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2= CODE

See Intrinsics manual

P3-P6

not used

G.01.00 20- 26

MMSTATS Events

Event -75 (X113)

EVENT NAME: FGETINFO DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FGETINFO

PARAMETERS P1= FILE #

> P2= FOPTIONS SEE INTRINSIC MANUAL

P3= AOPTIONS

SEE THIRTHSTC MANUAL

PARAMETER DESCRIPTION

P4-P6

not used

Event -76 (2114)

EVENT NAME: FREADLABEL DESCRIPTION:

CALLING MODULE: FILEIO CALLING PROCEDURE:

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= TCOUNT SEE INTRINSIC MANUAL

P3-P6

unused

Event -77 (2115)

EVENT NAME: FURITELABEL DESCRIPTION:

CALLING MODULE: FILETO

CALLING PROCEDURE: FHRITELABEL

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2= TCOUNT

SEE INTRINSIC MANUAL

P3-P6

unused

Event -78 (X116)

EVENT NAME: FLOCK DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FLOCK

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= LOCKCOND See Intrinsics manual

P3= COND CODE " " "

G.01.00 20- 29

MMSTRTS Events

MMSTAT Event Group &

Event -80 (X120)

EVENT MANE: FRENAME DESCRIPTION:

CALLING MODULE: FILEACC

CALLING PROCEDURE: FRENAME

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2-P6 unused

Event -81 (X121)

EVENT NAME: FCLOSE DESCRIPTION:

CALLING MODULE: FILEACC

CALLING PROCEDURE: FCLOSE

PARAMETERS

PARAMETER DESCRIPTION

P1= FILE #

P2= DISP

See Intrinsic manual

P3= SECCODE

P4-P6

unused

MMSTRTS Events

Event -79 (2117)

EVENT NAME: FUNLOCK DESCRIPTION:

CALLING MODULE: FILEIO

CALLING PROCEDURE: FUNLOCK

PARAMETERS PARAMETER DESCRIPTION

P1= FILE #

P2-P6 unused

G.01.00 20- 30

MISTRIS Events Event 83 (X123)

Event Name: STRATEGY
Description: Called to determine the type of strategy used
based on who the caller of CDT'ATTACHIO is.
Calling Module: CACLESEG
Calling Procedure: CDT'STRATEGY

Parameter Description

= CDT Mapped Domain entry

= LDR entry index

= Strategy

0 - Unknown caller

1 - Unknown fron File System

2 - Spooler

3 - Directory

4-7 - Unknown

8 - Gennessage

9 - File System, Quiesce I/O

10 - File System, Sequential, MOBUF

11 - File System, direct, MOBUF

12 - File System, direct, MOBUF

13 - File System, direct, BUF

14 - File System, KSRM

15 - File System, KSRM

15 - File System, KSRM

P4,P5,P6 Not used.

Event 84 (2124)

Event Name: INITIATE
Description: Called when starting/completing logical disc
request.
Calling Module: CACHESEG
Calling Procedures: CDT'Initiator, CDT'Completor

Parameter Description

P1 = CDT Mapped Donain entry number
P2 = LDR entry index
P3 type
0 = Initiator
1 - Completor
P4,P5,P6 hot used.

Event 86 (2126)

Event Name: CDT ATT Description: Called from CDT'ATTRCHIO. Calling Module: CACHESEG Calling Procedure: CDT'Attachio

Parameter Description

P1 = Ldev P2 = Function P3 = Flags P4,P5 = Parm1, Parm2 P6 = Count

Event 87 (%127)

Event Name: MRP_DOM
Description: Called when need to "map" a disc domain.
Calling Module: CACHESEG
Calling Procedure: CDT'MRP'CACHED'DOMRIN

Parameter Description

P1 = New CDT entry number P2 = Returned CDT entry P3, P4, P5, P6 Not used.

G.01.00 20~ 33

MMSTATS Events Event 88 (X130)

Event Name: UN_MAP_RG
Description: Called when disc domain no longer mapped. (i.e. both
the logical and physical I/O is complete).
Calling Module: CRCHESGG
Calling Procedure: CDT*MAP*CACHED*REGION

Parameter Description

P1 = CDT Ldev entry number P2 = Region CDT entry number P3,P4,P5,P6 Not used.

Event 89 (X131)

Event Name: LINK REG
Description: Called when a disc domain gets linked into the
linked list of domains for an ldev.
Calling Module: CRCMESEG
Calling Procedure: LINK'CRCHED'REGION,UNLINK'CACHED'REGION

Parameter Description

P1 = Type 0 = Link 1 = Unlink P2,P3 = Address of region base P4 = CDT entry number found in the header P5 = # of pages P6 Not used.

G.01.00 20- 34

MMSTATS Events

MMSTAT Event Group 9 (Disc I/O Requests)

Event 90 (%132)

Event Name: REQCRCHE
Description: Called to see if caching will accept this
I/O request.
Calling Module: CRCHESEG
Calling Procedure: REQUEST'CRCHE

Parameter Description

P1 = LDR entry index P2,P3,P4,P5,P6 Not used.

Event -98 (Z142)

EVENT NAME: DISK TRAFFIC DESCRIPTION: DISC 1/0 REQUEST HAS BEEN QUEUED

CALLING MODULE: HARDRES

CALLING PROCEDURE: ATTACHIO

PARAMETERS

PARAMETER DESCRIPTION

DATA TRANSFER COUNT: WORDS IF >O; BYTES IF <O

P2=FLRGS.(0:4)
P3=FNCT =0 ==>READ
=1 ==>NRITE
=2 ==>OPEN FILE
=3 ==>CLOSE FILE
=4 ==>CLOSE DEVICE

MMSTATS Events

MMSTAT Event Group 10

Event 100 (X144)

EVENT NAME: DISK ERROR
DESCRIPTION: RECORD DISC ERROR

CALLING MODULE: IOFDISC1

CALLING PROCEDURE: FHDDVR

PARAMETER DESCRIPTION PARAMETERS

P1=DIPT(DSTAT) HARDWARE STATUS
P2=SO QNISC
P3=IODP(QLDEV).QLDEVM LOR STOCOUNT&LSL(8))
=LDEV/SIO PROGRAM COUNTER

Event 101 (X145)

EVENT NAME: DISK ERROR DESCRIPTION: RECORD DISC ERROR

CALLING MODULE: IOMOISCO

CALLING PROCEDURE: MHDDVR

PARAMETERS PARAMETER DESCRIPTION

P1=DIPT(DSTRT) HARDWARE STATUS
P2=SO QMISC
P3=IOQP(QLDEV).QLDEVN LOR STOCOUNT&LSL(8))
=LDEV/SIO PROGRAH COUNTER

G.01.00 20- 36

MMSTAT Event Group 11

Event -110 (2156)

EVENT MAME: START I/O DESCRIPTION:DRIVER IMITIATOR FOR SIO DEVICE HAS BEEN CALLED

CALLING MODULE: HARDRES

CALLING PROCEDURE: SIODM

PARAMETERS

PARAMETER DESCRIPTION

P1=IOQPL(QSTAT) LOR IOQPL(QLDEY), LDEWN
=(0:8) PCB ENTRY N OF PROCESS HAKING REQUEST
(3:8) LOGICAL DEVICE MUMBER OF DEVICE FOR I/O
P2=IOQP(OMBCT)=HODR COUNT IF-0; PTP COUNT IF-0
P3=(0:2) = FUNCTION CODE SPECIFIED BY DRIVER

= 0 => READ = 1 => WRITE = 2 => CONTROL

(6:10) DSTN OF TARGET DATA SEG

Event -111 (%157)

EVENT NAME: I/O COMPLETION DESCRIPTION: SIO COMPLETION

CALLING MODULE: HARDRES

CALLING PROCEDURE: SIOOM

PARAMETERS

PARAMETER DESCRIPTION

P1=IOQP(QLDEV).LDEVN=LOGICAL DEVICE NUMBER OF DISC INVOLVED IN TRANSFER P2=IOQP(QPAR1) (DEFINED BY DRIVER) P3=IOQP(QPAR2) (DEFINED BY DRIVER)

G.01.00 20- 37

MMSTATS Events

MMSTAT Event Group 13

Event 139 (2213)

Event Name: C ROSENT
Description: Either the mapped disc domain or the target
DST was absent when a cache move was attempted.
Calling Module: CRCHESEG
Calling Procedure: PROCESSEDTLOGREGQUEUE

Parameter Description

P1 = O Mapped Domain absent P2 = Pin P3,P4 = Segment identifier of Mapped Domain P5,P6 Not used.

P1 = LDR entry index (DST not present)
P2 = Pin
P3,P4 = Segment identifier of DST (P4.(0:1) = 1 stack)
P5,P6 Not used.

MMSTRT Event Group 12

Event 120 (X170)

EVENT NAME: SOFT'DEATH DESCRIPTION: BUG CATCHER

CALLING MODULE: HARDRES

CALLING PROCEDURE: SOFT'DEATH

PARAMETERS

PARAMETER DESCRIPTION

SOFT'DEATH I.D. NUMBER CALLERS STATUS REGISTER CALLERS DELTA P

Event 125 (X175)

EVENT MAME: IOBUFTRP EVENT DESCRIPTION: IOSYSTEM BUFFER TRAP

CALLING MODULE: HARDRES CALLING PROCEDURE: SIODH

PARAMETER DESCRIPTION

P1 = IOQP P2 = IOQP(QDSTN).DSTN = DST NUMBER OF BUFFER P3 = 0

G.01.00 20- 38

MMSTATS Events

MMSTAT Event Group 14 (CS/3000)

Event 140 (X214)

EVENT NAME: COPEN DESCRIPTION:

CALLING MODULE: COMSYS2

CALLING PROCEDURE: COPEN

PARAMETERS PARAMETER DESCRIPTION

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 PMRP1

P3 PMAP2

Event 142 (%216)

EVENT NAME: CABORTIO DESCRIPTION:

CALLING MODULE: COMSYS1

CALLING PROCEDURE: CABORTIO

PARAMETERS

PARAMETER DESCRIPTION

P1 LOGICAL DEVICE

P2 IOQINDEX

P3 0

MMSTRTS Events

Event 144 (Z220)

EVENT NAME: CSIONAIT DESCRIPTION:

CALLING MODULE: COMSYS1

CALLING PROCEDURE: CSIGNAIT

PARAMETER DESCRIPTION PARAMETERS

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 TRANSMISSION LOG

Р3

Event 146 (X222)

EVENT NAME: CCLOSE DESCRIPTION:

CALLING MODULE: COMSYS3 CALLING PROCEDURE: CCLOSE

> PARAMETERS PARAMETER DESCRIPTION

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 LINE NUMBER

P3 0

G.01.00 20- 41

G.01.00 20- 42

MMSTATS Events

Event 147 (X223)

EVENT NAME: CREAD DESCRIPTION:

CALLING MODULE: COMSYS4 CALLING PROCEDURE: CREAD

PARAMETERS

PARAMETER DESCRIPTION

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 INCOUNT

P3 STRITION

Event 149 (%225)

EVENT NAME: CHRITE DESCRIPTION:

CALLING MODULE: COMSYS4

CALLING PROCEDURE: CHRITE

PARAMETER DESCRIPTION

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 OUTCOUNT

P3 INCOUNT

MMSTATS Events

MMSTRT Event Group 15 (CS/3000)

Event 150 (%226)

EVENT NAME: CSDRIVER DESCRIPTION:

CALLING MODULE: BSCLCM

CALLING PROCEDURE: CSDRIVER

PARAMETERS PARAMETER DESCRIPTION

> P1 TIMER LSM

P2 CURRENTSTATE

P3 CURRENTEVENT

WHERE THE DRIVER IS IN THE STATE TRANSITION TABLE (0:8) = CURRENT EVENT (8:8) = LOGICAL DEVICE WHEN CRUSED THE DRIVER TO BECOME ACTIVE

Event 152 (%230)

EVENT NRME: CCONTROL DESCRIPTION

CALLING MODULE: COMSYSS

CALLING PROCEDURE: CCONTROL

PARAMETER DESCRIPTION PARAMETERS

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 CONTROL CODE

P3 PARAMETER

Event 153 (X231)

CALLING MODULE:

EVENT NAME: COPENTRACEFILE DESCRIPTION:

CRLLING PROCEDURE: COPENTRACEFILE

PARAMETERS PARAMETER DESCRIPTION

(0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE HUMBER

P2 CTRACEINFO

P3 0

Event 154 (X232)

EVENT NAME: CCLOSETRACEFILE DESCRIPTION:

CALLING MODULE:

CALLING PROCEDURE: CCLOSETRACEFILE

PARAMETERS PARAMETER DESCRIPTION

P1 (0:8) = CS ERROR CODE (8:8) = LOGICAL DEVICE NUMBER

P2 0

P3 0

G.01.00 20- 45

IMISTATS Events

MMSTAT Event Group 16

Event 160 (X240)

EVENT NAME: CREAD DESCRIPTION:

CALLING MODULE: DSMON

CALLING PROCEDURE:

PARAMETERS PARAMETER DESCRIPTION

P1= TIME STAMP

P3= DEPENDS ON THE SUB EVENT NUMBER AND
IF IT IS AN INITIALIZATION OR COMPLETION EVENT.
NSG: (0:4) STRITYPX
(4:6) MSG CLS
(10:16) STRITYP

SUB EVENT NO. SUB EVENT . NAME INIT PARM CREAD
CURITE
IOMAIT
CCHECK
DSHITH
DSMC
CHNGEWAIT
HONREQ
CABORT
CRESET
CSDATA
CSREREAD LEN LEN LEN ERRCOD O R MSG O O T/F X MSG O O O X MSG PARM REQ O O R MSG 2 3 4 5 6 7 10 11 12 13

Event 155 (2233)

EVENT NAME: CPOLLIST DESCRIPTION:

CRLLING MODULE:

CALLING PROCEDURE: CPOLLIST

PARAMETERS PARAMETER DESCRIPTION

P1 LOGICAL DEVICE

P2 CS ERROR CODE

P3 PMRP

G.01.00 20- 46

MMSTAT Event Group 19

Event 191 (X277)

MISTRIS Evente

EVENT MANGE: DISKINTRPT
DESCRIPTION: A 7905/7920 CONTROLLER IS PROCESSING AN ATTENTION INTERRUPT
(ONLINE/OFFLIME)
CALLING MODULE: MARGAES

CALLING PROCEDURE: SIGON

P3= DITP

PRRAMETERS P1= @DITP PARAMETER DESCRIPTION
(US)--i.e. WHO GOT THE INTERRUPT

P2= @DITP (THEN) -- i.e. WHO RAN THE POLL PROGRAM "OUR" DIT FLAGS WORD

THERE SHOULD BE AT LEAST AN X300 AND AN X303 FOR EACH SID PAGH. A SINGLE ISOLATED (IN TITE) REQUEST WILL GENERATE AT LEAST A X303, X300, X303. IF THE QUEUE OF IOQ'S ON A DIT MEVER EMPILES, THERE MOULD BE ONE X300 AND ONE X303 PER SID PAGH.

Event 192 (2300)

EVENT NAME: GIPINTERRUPT DESCRIPTION: INTERRUPT JUST PROCESSED

CALLING MODULE: HARDRES CALLING PROCEDURE: GIP

> PARAMETERS PARAMETER DESCRIPTION

> > P1

P2 QUEUE ELEMENT WORD ENTRY INDEX

CONTENTS OF DIT WORD O: THE FLAGS WORD р3

CHANNEL PROGRAM INSTRUCTION POINTER

CONTROLLER STATUS

LSW of a Return from TIMER

MMSTRTS Events

Event 193 (X301)

EVENT NAME: STARTIO DESCRIPTION: Issuing SIOP machine instruction.

CALLING MODULE: HARDRES

CALLING PROCEDURE: START'HPIB, STARTIO

PARAMETERS PARAMETER DESCRIPTION

Absolute address of SIO program to start.

P2 LDEV number

РЗ DRT number

Q'ENTRY'INDEX FROM DITP(DIOQP)

P5 DIT WORD O: THE DIT FLAGS WORD

LSH of A RETURN FROM A CALL TO TIMER

G.01.00 20- 49

MMSTATS Events

THESE EVENTS ARE FOR DEVELOPMENT USE ONLY AND ARE NOT NORMALLY ENABLED

G.01.00 20- 50

MMSTRT Event Group 20

Event 200 (X310)

EVENT NAME: DISKBUGGATCHER
DESCRIPTION: A HOUNTED VOLUME TABLE CHANGE IS BEING MADE.

CALLING MODULE: PVSYS

CALLING PROCEDURE: MYTABLE

PARAMETERS PARAMETER DESCRIPTION

P1= FUNCT 0 = DELETE ENTRY 1 = ADD ENTRY 2 = PRESERVE ENTRY

P2= MVTR8X (MOUNTED VOLUME TABLE INDEX)

P3= DELTAP (VALUE OF Q-2)

Event 201 (X311)

EVENT NAME: DISKBUGGATCHER DESCRIPTION: A PRIVATE VOLUME USER TABLE CHANGE IS BEING MADE.

CALLING MODULE: PVSYS

CALLING PROCEDURE: USERTABLE

PARAMETER DESCRIPTION PARAMETERS

P1= FUNCT

FUNCT

= REMARIE USER ENTRY

= REMARIE USER ENTRY

= RETURN ALL MYTABX INDICES USED BY A
SPECIFIC PCB

= RETURN ALL PCB POINTERS USING A SPECIFIC
MYTABX

4 = GET USER ENTRY

P2= MYTABX (MOUNTED VOLUME TABLE INDEX)

P3= DELTAP (VALUE OF Q-2)

MMSTATS Events

Event 194 (X302)

EVENT NAME: SIODM-ENTRY DESCRIPTION: Entering SIODM

CALLING MODILE: HARDRES

CALLING PROCEDURE: SIODM

PARAMETERS

PARAMETER DESCRIPTION

P1 = LDEV

P2 = IOQ OR DRQ table relative index

РЗ = DIT WORD O (DIT FLAGS)

CURRENT STATE OF THE VARIABLE STATE

UNUSED AT THIS TIME

P6 = LSW RETURNED BY CALL TO TIMER

Event 195 (%303)

EVENT WAME: SIODM-EXIT DESCRIPTION: Leaving SIODM main loop.

CALLING PROCEDURE: SIODM

PARAMETERS PARAMETER DESCRIPTION

SAME AS EVENT 194 (%302) EXCEPT THAT EVENT IS 195 (%303)

MISTRIS Fuente

MISTAT Event Group 21 Process Creations and Terminations Logical Process Table

Event -211 (X323)

EVENT NAME: PROCESS COMPLETION DESCRIPTION: PROCESS HAS TERMINATED

CALLING MODULE: MORGUE

CALLING PROCEDURE: TERMINATE

PARAMETERS

PARAMETER DESCRIPTION

G.01.00 20- 53

MMSTATS Events

Event 222 (X336)

EVENT NAME: CONFIGURATION INFORMATION DESCRIPTION: MPE VERSION FIX UPDATE

CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CXHON

PARAMETERS PARAMETER DESCRIPTION

P1 = VERSION

P2= FTXI

P3= UPDATEL

Event -223 (-2337)

EVENT NAME: CONFIGURATION INFORMATION DESCRIPTION: SYSTEM TRBLE LICCATIONS AND AVAILABLE LINKED MEMORY INFORMATION CALLING MODULE: OPCOMMEND

CALLING PROCEDURE: CXMON

PARAMETERS

PARAMETER DESCRIPTION

P1=F (X1032)=@CST(0)-@DST(0)
=DISPLACEMENT TO CODE
P2=F(X1033)=@CST(LMST)-@DST(0)
=DISPLACEMENT TO SHARRBLE
P3=LOGICAL(TOTAL&DLSK(4))=LIMKED MEMORY SIZE

Event 221 (X335)

EVENT NAME: CONFIGURATION INFORMATION DESCRIPTION: EVENT GROUP MASK

CALLING MODULE: CRIO

CALLING PROCEDURE: CONSMON

PARAMETERS PARAMETER DESCRIPTION

MMSTRT Event Group 22

Time Stamp of Event Trace Enable and Disable

P1= MEASMSKO

P2= MERSHSK1

P3=Reserved

G.01.00 20- 54

MISTRES Events

Event -224 -(X340)

EVENT NAME: SYSPINS DESCRIPTION: LOGICAL PROCESS TABLE

CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CKMON

PARAMETERS PARAMETER DESCRIPTION

P1=ABSOLUTE(X1141)=PROGEM'S PCBENTRY NUMBER
P2=ABSOLUTE(X1142)=HAN'S PCB ENTRY NUMBER
P3=ABSOLUTE(X1143)=UCOP'S PCB ENTRY NUMBER

Event -225 (-X341)

EVENT NAME: SYSPINS(CNTD.)
DESCRIPTION: LOGICAL PROCESS TABLE

CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CXMON

PARAMETERS PARAMETER DESCRIPTION

P1=ABSOLUTE(X1144)=PFAIL'S PCB ENTRY NUMBER P2=ABSOLUTE(X1145)=DEVREC'S PCB ENTRY # P3=ABSOLUTE(X1146)=PRNSG'S PCB ENTRY #

Event -226 (-2342)

EVENT NAME: SYSPINS(CNTD.)
DESCRIPTION: LOGICAL PROCESS TABLE

CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CXMON

PARAMETERS PARAMETER DESCRIPTION

P1=ABSOLUTE(X1147)=STMSG'S PCB ENTRY # P2=ABSOLUTE(X1150)=LOG'S PCB ENTRY # P3=ABSOLUTE(X1151)=LORD'S PCB ENTRY W

G.01.00 20- 55

G.01.00 20- 56

Event -227 (-%343)

EVENT NAME: SYSPINS(CNTD.)
DESCRIPTION: LOGICAL PROCESS TABLE

CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CXMON

PARAMETERS PARAMETER DESCRIPTION

P1=ABSOLUTE(X1152)=IOMESSPROC'S PCB ENTRY #
P2=ABSOLUTE(X1153)=SYSIOPROC'S PCB ENTRY #
P3=ABSOLUTE(X1154)=MEMLOGP'S PCB ENTRY #

Event -228 (%344)

EVENT NAME: TIMESTAMP DESCRIPTION: TIMESTAMP CALLING MODULE: OPCOMMAND

CALLING PROCEDURE: CXMON PARAMETERS

PARAMETER DESCRIPTION

P1=CRLENDAR (0:7)=YEAR OF CENTURY (7:9)=DRY OF YEAR P2=CLOCK(HORD1). (0:7)=HOUR OF DAY (8:8)=HINUTE OF HOUR P3=CLOCK(HORD2). (0:7)=SECONOS INTO MINUTE (8:8)=TENTHS OF SECONOS

Event -229 (-2345)

EVENT NAME: MONOFF
DESCRIPTION: END EVENT TRACING CALLING MODULE: OPCOMMAND CALLING PROCEDURE: CXMON

PARAMETERS

PARAMETER DESCRIPTION

G.01.00 20- 57

MMSTRTS Events

MMSTAT Event Group 23 (Terminal I/O)

Event 230 (X346)

EVENT NAME: TERMREAD
DESCRIPTION: TERMINAL READ COMPLETION

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS

PARAMETER DESCRIPTION

P1 = LDEV P2 = READ DURATION P3 = BYTES READ

Event 231 (X347)

EVENT NAME: DC1DC2ACK
DESCRIPTION: DC1/DC2 HAS BEEN SATISFIED

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS

PARAMETER DESCRIPTION

P1 = LDEV P2 = DURATION (BETWEEN START AND DC2) P3 = BYTES READ (EXCLUDING DC2)

G.01.00 20- 58

MMSTATS Events

Event 232 (%350)

EVENT NAME: TERMURITE
DESCRIPTION: WRITE COMPLETION

CALLING MODULE: IOTERMO
CALLING PROCEDURE: TERMIOM

PARAMETERS

PARAMETER DESCRIPTION

P1 = LDEV

P3 = BYTE COUNT OF TRANSFER

Event 233 (%351)

EVENT NAME: BINREAD
DESCRIPTION: BINARY READ COMPLETED

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS P1 = LDEV P2 = DURATION P3 = BYTES READ PARAMETER DESCRIPTION

MMSTATS Events

Event 234 (%352)

EVENT NAME: TERMLOGON
DESCRIPTION: TERMINAL JUST LOGGING ON

CALLING MODULE: IOTERMO
CALLING PROCEDURE: TERMIOM

PARAMETER DESCRIPTION

PARAMETERS P1 = LDEV P2 = 0 P3 = 0

Event 235 (%353)

EVENT NAME: TERMLOGOFF
DESCRIPTION: TERMINAL JUST LOGGED OFF

CALLING MODULE: ISTERMO CALLING PROCEDURE: TERMION

PARAMETERS

PARAMETER DESCRIPTION

Event 236 (X354)

EVENT NAME: SPECCHAR
DESCRIPTION: PROCESSED SPECIAL CHARACTER

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS PARAMETER DES P1 = LDEV P2 = SPECIAL CHARACTER PROCESSED P3 = 0 PARAMETER DESCRIPTION

Event 237 (X355)

EVENT NAME: BREAK
DESCRIPTION: PROCESSED BREAK

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS P1 = LDEV P2 = DSTATE P3 = 0

PARAMETER DESCRIPTION

Event 238 (X356)

EVENT NAME: SPECREAD DESCRIPTION: SPECIAL READ TERMINATION CHARACTER DETECTED

CALLING MODULE: HARDRES CALLING PROCEDURE: TIP

PARAMETERS

PARAMETER DESCRIPTION

P1 = LDEV P2 = DURRTION P3 = BCNT

G.01.00 20- 61

MMSTAT Event Group 24 (Power Fail)

Event 240 (%360)

Event Name: PFAIL
Description: Power fail detected.
Calling Module: INIM, PFAIL
Calling Procedures: Powerup (INIM), Powerup (PFAIL)

Parameter Description

P1 = 0 Called from Powerup in ININ
1 Called from entry in Powerup in PFAIL
2 Called from end of Powerup in PFAIL

P2 = For P1=0 this is 0 For P1=1,2: TRUE = Multiple powerfail FALSE= First powerfail

P3 = PF
0 = Mo powerfail or PFRIL processing complete
1 = Set by the power down trap in INIM
2 = Set by the power up trap in INIM
3 = Set when awake the PFRIL process
4 = Set by PFRIL after message appears on console


P4 = SYSUP 0 = System not back up after powerfail 1 = System back up after powerfail

P5,P6 not used.

G.01.00 20- 62

CHAPTER 21 ROOTFILE LAYOUT

General Rootfile Layout



RECORD 0 | DATABASE GLOBAL INFO ITEM TABLE (variable size) SET TABLE (variable size) DATA SET CONTROL BLOCKS (DSCB) (variable size)

The data base ROOT FILE is an MPE file with filecode equal to -400. The record size is 128 words, fixed, binary format with a blocking factor of 1. The size of the file depends on the number of data items and data sets defined in the data base.

G.01.00

Root File Label O

		z
WORD O	RL'CONDITION (rootfile condition)	٥
1 [RL'DATE(creation_date)	1
2	RL'TIME (creation time)	2
3 [·	3
4	RL'EVEROPEN	4
5 [RL'COLDLOADID (cold load id)	5
6	RL'USERCOUNT	1 2 3 4 5 6 7
7	RL'DBCBDSTNUM (DST number of DBCB)	7
8	RL'LOGID (log id for	10
. 1	transaction logging)	
.		
11		13
12	RL'LOGPASS (log id password)	14
.		
. 1	l i	
15		17
16	_RL'FLAGS(database_flags)	20
17	RL'STORDATE (DBSTORE date)	21
18	RL'STORTIME (DBSTORE time)	22
19		23
20	_RL'BUFSPECCOUNT_(buffer_spec_count)	24
21	RL'ILRCREATEDATE (date ILR log created)	25
22	RL'ILRCREATETIME (time ILR log created)	26
23		27
24	RL'ILRLASTDATE (last_log_access_date)	30
25	RL'ILRLASTTIME (last log access time)	31
26		32
27	RESERVED	33
	. FOR .	
	. FUTURE .	
63	USE_	77
64	RL'MAINTHORD (database maintenance	100
. 1	uord)	
	l	
67		103
68	RL'BUFFERSPECS (buffer specifications)	104
1	l ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '	
to		
	i	
127		177

RL'CONDITION (IN ASCII):

JB - Virgin. The database has not been created yet.
FU - OK. The database is OK.
RM - Modified deferred. The database is being modified.
MC - Haintenance create. The database is being created.
ME - Haintenance erase. The database is being erased.
IL - ILR recovery in progress.

G.01.00 21- 2

General Rootfile Layout

Root File Label O (cont.)

RL'DATE: Root file creation date*. Its format is:

_0:_1:_2:_3:_4:_5:_6:_7:_8:_9:10:11:12:13:14:15 |year_____|day_of_year____

RL'TIME: Root file creation time*. Its format is:

_0:_1:_2:_3:_4:_5:_6:_7:_8:_9:10:11:12:13:14:15 |hour | | |ninutes | | |seconds | | | | |tenth_of_seconds |

RL'EVEROPEN: This field is no longer used under IMAGE B

RL'FLAGS:

(0:1) - RECOVERY Default is NO (0)
(1:1) - LOGGING Default is NO (0)
(2:1) - ACCESS Default is YES (1)
(2:1) - DUMPING Default is YES (1)
(3:1) - DUMPING Default is NO (0)
(4:1) - RESERVED-FOR-FUTURE-USE
(5:2) - SUBSYSTEM RACCESS Default is R/W (00)
(7:1) - ILR Default is NO (0)
(8:2) - RESERVED-FOR-FUTURE-USE
(10:1) - DIRTY FLAG Default is YES (1).

This indicates the database has been modified but not DBSTOREd.
(11:5) - RESERVED-FOR-FUTURE-USE

RL'STORDATE: Same format as RL'DATE*.

RL'STORTIME: Same format as RL'TIME*.

RL'BUFSPECCOUNT: Maximum number of buffer specifications allowed.

RL'ILRCREATEDATE: Same format as RL'DATE*.

RL'ILRCREATETIME: Same format as RL'TIME*.

RL'ILRLASTDATE: Same format as RL'DATE*.

RL'ILRLASTTIME: Same format as RL'IIME*.

RL'MAINTWORD: For data bases with no maintenance word this field has 2 semicolons (';;') and trailing blanks.


General Rootfile Layout

RL'BUFFSPECS:

BIT/	_0:_1:_2:_3:_4:_5:_6:_7:_8:_9:10:11:12:13:14:15	X
ND 68	buffers_for_1 user buffers_for_2 users	104
69	buffers_for_3 users buffers_for_4 users	105
	etc	
	ll	
127	buffers for 119 users buffers for 120 users	177

* The DATE and TIME fields can be formatted (for display purposes) individually by calling the FNTCMLENDAR and FNTCLOCK Intrinsics respectively. Or both fields can be formatted at once with FNTDATE Intrinsic.

Root File Labels 1 & 2



The PRSSMORD TRBLE occupies user labels number 1 and 2. There are four words (8 characters) reserved for each password. The relative position of a password corresponds to the user class number defined in the schema. For user class numbers not defined in the SCHEMA, the four word field is filled with blanks.

G.01.00 21~ 5

General Rootfile Layout

Root File- Next Label



The SET RERD/WRITE TABLE starts on a user label boundary after the ITEM RERD/WRITE TABLE.

There are eight words for each SET RERD/WRITE bit map.

For databases with more than 16 data sets, the read/write table continues in the next user labels.

The specific format of this table is shown in the next page.

The number of user labels occupied by the SET READ/URITE TABLE depends in the number of data sets defined in the schema, and is obtained by rounding upwards (ceiling) the result of:


Nun-of-labels = [(Nun-of-sets)*8]/128

Since there can only be a maximum of 99 data sets defined in the schema the maximum size for this table in user labels is:

 $\text{Max-size} = [(99) \times 8]/128 = 6.18 => 7 \text{ labels}$

General Rootfile Layout

Root File Label 3



The ITEM READ/WRITE TABLE starts in user label #3
There are eight words for each ITEM READ/WRITE bit map.
For databases with more than 16 items, the read/write table continues
in the next user labels. The specific format of this table is explained
after the SET READ/WRITE TABLE since it is defined the same way.
The number of user labels occupied by the ITEM READ/WRITE TABLE depends
on the number of data items defined in the schema and can be obtained
by rounding upwards (ceiling)the result of:

Num-of-labels = [(Num-of-items)*8]/128

Since there can only be a maximum of 255 data items in the schema, the maximum size for this table in user labels would be:

Max-size = [(255)*8]/128 = 15.93 => 16 labels.


6.01.00 21- 6

General Rootfile Layout

Item/Set Read/Write Table Format

There are eight words per item/set read/write table definition and up to 15 items/sets per record (user label). Within each 8 words, the first 4 words are the flags for the user classes which have read access to the item/set. The second 4 words are the flags for the user classes which have write access to the item/set. The detail format for an eight word field is shown below.

R. Four words for read access:




4 words represent 64 bits. Bit n represents read access for user class n to the item/set. If bit n is set to 1 then user class n has read access to the item/set.

For example, if the word settings are:

ного 1 ного 2 ного 3 ного 4 2000016 2020000 2000410 2001300

This means that user classes 12, 13, 14, 18, 39, 44, 54, 56 and 57 have read access to the item/set. If no read/urite security is defined at all for the item/set, then all of the read security bits are set to 1.

B. Four words for write access:




Write access flags have the same format as the read access flags. Bit n represents write access for user class n to the iten/set. If bit n is set to 1, then user class n has write access to the iten/set for example, if the word settings are:

могд 1 могд 2 могд 3 могд 4 2000010 2020000 2000000 2001100

This means that the user classes 12, 18, 54 and 57 have write access to the item/set. If no read/urite security is defined at all for the item/set, then all of the write security bits are set to 0.

Root File Record 0



ROOT'DBSTRTUS

(0:8) - IMAGE version ('B' in ASCII) (8:8) - Binary 1 (filler)

ROOT'DBNAME - DATABASE name left justified (last 2 chars are blank).


NOWOPEN - Number of data sets opened. This field is not used in IMAGE B

MRXOPEN - Maximum number of data sets that can be opened. This field is not used in IMRGE B.

ROOT'ITEMPTR and ROOT'DSETPTR is a word offset from record 0 (beginning of the file, not including the space taken by the user labels) and can span several records. These pointers point to the Oth entry of the table and since the Oth entry in the item table or the set table does not really exist, they actually point to 11 words before the beginning of the table. To get to the first entry in the table, this pointer should be incremented by the length of the entry (which is currently 11 words).

General Rootfile Layout

Root File Record 1



The ITEM TABLE starts in record #1.
Each entry is 11 words long and the length of the table depends on the number of data items defined in the schema. The relative position of an item definition depends on its relative position in the schema.

Item-name: is a data item name, left-justified and with trailing blanks

Iten-number-of-synonym: is the number of the item whose mame has the same hashed result as this one (this is utilized for quick item name searches).

Item-type: is one of the following: I, J, K, R, X, U, Z, or P

item-type VALUES, 2012; ||subiten-length |subiten-count


The maximum size for this table is $11*255 = 2805 \mu ds$

The reserved-1 and reserved-2 fields are the 'old' level numbers for read and write security. Now, the values are always zero.

G.01.00 21- 10

General Rootfile Lavout

Root File- Next Record



Set table follows the Item table.

Each entry is 11 words long. The length of the table depends on the number of data sets defined in the schema. The relative position of a set definition depends on its relative position in the schema.

Set-name: is a data set name. left-justified and with trailing blanks.

Set-number-of-synonym: is the number of a data set whose name has the same hashed result as this one (this is utilized for quick set name searches).

Data-set-type is one of the following: A, M or D.

DSCB-pointer: is a pointer to the Data Set Control Block. This pointer is word offset from record #0. The DSCB is described ahead.


The maximum size for this table is 11*99 = 1089 uds.

NOTES: The reserved-1 and reserved-2 fields are the 'old' level numbers for the read and write access respectively. Since this concept no longer applies, the values are set to zero.

G.01.00 21- 11


General Rootfile Layout

Data Set Control Blocks (DSCB)- General Layout



The DSCBs follow the SET TABLE in the Root File. There is one DSCB for each data set defined. The function of the DSCB is to define each data set within the data base.

Data Set Control Block (Global Area)



DSCOP

- data set capacity as reported by the SCHEMA processor.

DSBLOCKLGTH - data set block length including the bit map overhead.

DSMEDIALGTM - data set media record length (remember that this length includes the pointer overhead)

DSENTRYLGTH - data set entry length.

DSBLOCKFAC - data set blocking factor.

DSFIELDCT - data set field count. This is the number of fields specified for the data set.

 data set path count. This is the number of paths that are specified for the data set. DSPATHCT

N-DSKEYTYPE - data set key type. If DSKEYTYPE = TRUE then the key is hashed.

OSPRIMEY

- data set primary path or key.

For master data sets, this is the field number of the search item.

For detail data sets, this is the field number of the

primary path.

DSPATHPTR - data set path table pointer. Word offset to the data set path table which contains an entry for each path defined. It points to path Oth entry in the table, so to get to the first entry the pointer should be incremented by the length of the entry (which is currently 2 words).

G.01.00 21- 13


General Rootfile Layout

Data Set Control Block (Item Numbers)

	0: 1: 2: 3: 4: 5: 6:	7:_8:_9:10:11:12:13:14:1 iitem_num_of_2nd_field ietc
Hord 0	_iten_num_of_1st_field	item_num_of_2nd_field
1	_item_num_of_3rd_field	
	i etc.	binary O
	binary 0	binary 0

The Item Numbers Table follows the Global Area of the DSCB. The size of this table (in words) is equal to the number of items in the given data set plus 1. The first n bytes are used to carry the item numbers of the fields within the data set. The remaining n+2 bytes are set to binary zeros.

Data Set Control Block (Record Definition Item Displacement)



This table immediately follows the Item Numbers Table.


The word offset points to the starting location of the field within the nedia record. Remember that the nedia record includes the pointer overhead so this offset varies for master and detail data sets: if a master data set has only one path, the word offset for the first field is 10, since there are 10 words of overhead--5 words for the synonym chain pointers and 5 words for the data set chain head that it would be pointing to. On a detail data set with one path, the overhead is only 4 words.

The 'length-of-entry' field is the same as the media record length.

G.01.00

General Rootfile Layout

Data Set Control Block (Path Table)



There are 2 words (4 bytes) for each path definition.
The PATH TRBLE for master data sets has a different layout from the PATH TRBLE for detail data sets.

Master sets:

Byte Description

1 - item number of the search item in the related detail set.

- detail set.

 2 iten number of the sort iten in the related detail set.

 3 set number of the related detail data set 4 path number of the corresponding path in the related detail data set.


Detail sets:

- Detail sets:
 Byte Description
 1 field number of the search item.
 2 field number of the sort item.
 3 set number of the related master data set
 4 path number of the corresponding path in
 the related master data set.

General Data Set Layout

Hord	0-1	USER_LRBEL_O Hasters=capacity details=highwater Hark
Hord	2-3	number of unused records
lio rd	4-5	masters= not used details= delete chain head

General Rootfile Layout



Data Set User Label O

Word 0-1: Record name of the highest readable record. For flasters, this is the highest record in the set (i.e. Capacity). For Details, this is the greatest number of records that have been written to the set thus far. For example, if there is room in the Detail data set for 100 records and 75 were written last week when the data set was loaded with DBLURD, and yesterday 15 records were deleted from the data set, the "High Water Mark" is equal to a value of '75'.

Word 2-3: Mumber of unused records in the data set. This field is incremented when a record is deleted and decremented when a record is added. To determine the current number of entries used in the set subtract Word 1-2 (unused count) from Word 0-1 (capacity).

Word 4-5: The delete chain head for Details. This points to the record most recently deleted or contains a value of zero if no records have been deleted. This field is not used in Master data sets.

Data Set Records

The data in the data set records is arranged according to the Media records. These are formatted by the Schema Processor (DBSCHEMR).

G.01.00 21- 15

G.01.00 21- 16

CHAPTER 22 DISC FREE SPACE MAP

Disc Resident Data Structures

There are two disc resident free space data structures, the bit map and the descriptor table, for each disc volume that has a free space map, i.e. system discs and private volumes. The addresses of these data structures are kept in the disc label. The symbols that define the descriptor table and bit map are in the include file IMCLDFS2.

Bit Map

The bit map is divided up into pages, which is the physical block of the map that is read or unitten. At the moment, a page is defined to be one sector (128 words) long, this may be changed by changing a compile time constant. The last word of the page is a checksum for that page, all other words are data. There is a one to one correspondence between bits in the map and sectors of the disc. A one bit represents a free sector and a zero bit represents an allocated sector. The bit map is a contiguous set of pages, enough to represent the entire disc, excluding spare tracks and spare sectors.

Descriptor Table (DT)

The descriptor table is an array of three word entries, one entry for each page of the bit map. Each entry looks like this:

******* word 0 = largest space = word 1 = starting space = -Hord 2 = ending space =

G.01.00 22- 1

Disc Free Space

All symbols that define these data segments are in the include file INCLDFS1, and they are prefixed with "da'". The structure of the data segment is as follows:

0 (20)	= ds'ldev =
1 (%1)	= ds'dst =
2 (%2)	=
3 (23)	= ds'disc'size= = -
4 (24)	= ds'last'page'of'map =
5 (25)	= ds'last'buffer'index =
6 (26)	=
7 (27)	= ds'nap'address= = = =
8 (210)	= ds'lock =
9 (211)	= ds'lock'count =
10 (212)	= ds'queue'head =
11 (%13)	= ds'queve'tail =
12 (%14)	= ds'descriptor'table =
13 (%15)	= ds'buffer'page'number =
14 (216)	= ds'buffer'dirty =
15 (%17)	= ds'buffer'area =
16 (%18)	= ds'first'threshold'page =
	= = = = = = = = = = = = = = = = = = =
	I

Disc Free Space

Thus the descriptor table looks like this.

= entry for page 0 = entry for page 1 = entry for page 2 = entry for page 3 = entry for last page

Each entry describes the free space on the corresponding page of the bit map. The largest space word is the size of the largest contiguous block of free space on the page, which is not at the very beginning or very end of the page. That is, the first bit physically representing the space is not the first bit of data on the page or the last bit representing the space is not the last bit of data on the page. Starting space is the number sectors of contiguous space represented by the set of bits whose first bit is the first bit of data on the page. Ending space is the number of sectors of contiguous space represented by the set of bits whose last bit is the last bit of data on the page. Ending space is the number of sectors of contiguous space represented by the set of bits whose last bit is the last bit of data on the page. The starting space and ending space fields allow looking across page boundaries, thus preventing fragmentation on page boundaries. Thus, if all sectors represented on a page are free, then starting and ending space will be the same and have the total number of free sectors represented on the page. Largest space will be zero, as there is no block of space that is not at the beginning or end of the page. R value of -1 for all the fields in an entry indicates the corresponding page is bad, either from a checksum or I/O error.

Virtual Memory Resident Data Structures

For each system disc or physically mounted private volume there is a data segment which has information about the disc free space map, the current copy of the descriptor table, some work space for the procedures while in split stack mode and buffers for pages of the bitmap. The DST number of the data segment for a given disc is found in the LDTX entry for that disc.

Disc Free Space Data Segment

For each system disc or physically mounted private volume in the up and running system there is a DST which contains information about the disc free space map for that disc, some work area, a copy of the descriptor table and buffers for the pages of the bit map.

G.01.00 22- 2

Disc Free Space

	Z
19 (%23)	= ds'last'page'allocated'froн =
20 (224)	= ds'next'buffer'index =
21 (%25)	= ds'page'number =
22 (%26)	= ds'word'number =
23 (%27)	= ds'bit'number =
24 (%30)	= ds'page'pointer =
25 (%31)	= ds'starting'word'number =
26 (%32)	= ds'starting'bit'number =
27 (%33)	= = = = = = = = = = = = = = = = = = =
28 (%34)	= = = = = = = = = = = = = = = = = = =
29 (%35)	= ds'bit'count =
30 (%36)	= ds'entry'type =
31 (%37)	= ds'buffer'index =
32 (%40)	2 - 4-14:1-44
33 (%41)	= ds'disc'address=
34 (%42)	= ds'error'status =

The rest of the data segment contains tables whose size and location is dependent on the size of the disc and or the number of buffers in the data segment. They are shown below just to demonstrate there relation to one another, for there actual location, the pointers should be examined. The symbol "ds'array' area" defines the start of the area. The first table is the descriptor table, it is in the same format as the disc copy, but a dumny entry of all zeros is added before and after the table, these are needed by procedures "Find"Page" and "Build'Descriptor'Entry". The pointer to this table is "ds'descriptor'table", it points to the entry for page zero, not the dumny entry.

= largest space = entry for starting space ending space =

.

dunny ٥

The next table is ds'buffer'page'number table, it has a one word entry for each buffer in the data segment. Each entry contains the page number of the page currently in the corresponding buffer or -1 if the buffer is empty. This is pointed to by "ds'buffer'page'number".

buffer 0 entry = buffer 1 entry = = last buffer entry =

G.01.00 22- 5

Disc Free Space

The next table is the de'buffer'dirty table, which has a one word entry for each buffer. A TRUE indicates the page in the corresponding buffer is dirty, i.e. the disc copy is not up-to-date. A FRLSE indicates that the buffer is clean. If DFS was compiled with dirty buffer management turned off, this table is not present and the ds'buffer'dirty pointer is zero.

***************************** buffer 0 entry = = last buffer entry =

The remainder of the data segment contains the buffers, each buffer is the size of one page of the bit nap, which is currently one sector(128 words). The beginning of the buffer area is pointed to by "ds'buffer'area" and the number of buffers is the value in "ds'last'buffer'index" plus one.

buffer 0 ************************************* buffer 1

G.01.00 22- 6

Disc Free Space

. last buffer

Each of the fields of the data segment is described in the include file INCLDFS1, where they are defined. It should be noted that the following fields are just workspace, used to pass information between procedures while in split stack mode and have no meaning between calls to the disc free space management subsystem:

ds'page'number ds'bit'number ds'starting'nurd'number ds'number'of'sectors ds'bit'count ds'disc'address

ds'uord'number ds'page'ptr ds'starting'bit'number ds'entry'type ds'buffer'index

The field ds'error'status normally has no meaning between calls unless the error'type field has a value greater than "fatal'dfs'error", in which case it means that disc space may no longer be allocated on this disc.

CHAPTER 23 MPE DISC CACHING

Disc Caching Overview

Disc Caching is an optional feature of MPE that utilizes excess main memory and excess CPU horsepower to keep portions of frequently referenced disc "domains" in memory. (A disc "domain" is a copy of a portion of disc residing in main memory. These disc domains are considered "cached" when they are in memory and are considered "mapped" when there is I/O pending against them.) Disc Caching manages the bi-directional transfer of these disc domains between main memory and disc storage. No main memory is permanently dedicated to cached disc domains. Cached disc domains share main memory with all other types of MPE segments and are not treated differently by the memory manager. By keeping cached disc domains in memory, a significant portion of the references to disc storage can be resolved without actually having to physically access the disc. Disc Caching policies are integrated into the MPE Kernel, File System, and I/O System which allows the system performance to be tuned based on the current workload and resource availability.

Disc Caching uses the MPE kernel resource management mechanisms and strategies. These mechanisms are extended to handle cached disc domains in the same manner as segments. Thus, cached disc domains can be of variable size, fetched in parallel with other segments or cached domains, garbage collected, and replaced in the same manner as stacks, data and code segments. The relative use of main memory between stacks, data and code segments, and cached disc domains is dynamic. This partitioning is based on the workload's current requirements and current memory availability.

Disc Caching can be enabled/disabled on a disc by disc basis. When caching is enabled for the first disc, the code segment containing the Disc Caching code will be locked into memory. Also at this time the Cache Directory Table (CDT) will be built and locked into memory. When caching is disabled for the last disc, the code segment will be unlocked from memory and the CDT will be released. Thus if caching is not enabled no memory will be wasted.

The CDT is used to keep track of the following information:

- The disc ldevs currently enabled for caching. There will be a Device Entry in the table for each cached disc.
- A linked list of cached domains for each disc with caching en-abled. The head and tail of this linked list will be contained in the Device Entry. (I.e. there is a separate linked list of cached domains for each cached disc ldev.)
- 3) The cached domains that currently have user I/O pending (i.e. FRERDS/FURITES) or have memory management I/O pending (i.e. fetching the disc domain into memory, or posting the disc domain back out to disc). There will be a Mapped Domain Entry in the table for each disc domain has that I/O pending and is thus "mapped".

G.01.00 23- 1

Disc Caching

Disc Caching Tables Overview

Cache Directory Table (CDT) Header (Info for table mgt) Device entry # 1 Device entry # 2 Device entry # N =========> to 1st Logical Mapped Domain # A Disc Request Entry (LDR) Mapped Domain # 8 Mapped Domain # C for Dev # 1

Disc Caching

ordered writes include things like updating disc free space maps for a new file extent before updating the file extent map in the file label.

There are two disc request entries used for disc caching requests. The first entry is a Logical Disc Request (LDR) entry and is used to manage the data moves to/from the user's data area and the disc domain (i.e. the Logical I/O). The second entry is a regular Disc Request (DRQ) entry and is used to perform the physical I/O necessary to map a disc domain (for a read "miss") or to perform the physical post (on write requests). The disc domain will remain mapped until both the logical and physical I/O completes. If a request is not completely described by one disc domain already in memory or a Mapped Domain CDT entry (i.e. the requested disc area falls into more than one disc domain) then the overlapping disc domain(s) will be flushed to disc and the new complete disc domain will be fetched (if read) and mapped - no partial mappings are allowed.

The DST number of the Cache Directory Table (CDT) is at %1273 and the bank and offset are kept in %1274-%1275. The Caching Sir (2) is used when starting and stopping caching (via :STRRTGCHE/:STDPGHE) and by the LDRGE when loading a program file (this sir is only used when updating the STI at load

When caching is enabled for a disc, a bit in the flags word of the DII is set. Also, the Global Serial Write queue can be found by examining the header entry of the Disc Request Table. See Chapter 13 for a more detailed explanation of both the DII and the Disc Request Table header. See Chapter 2 for a description of the Memory Region Header for a disc domain (cached

4) R linked list of all user I/O pending against the mapped disc domains. There will be a logical Disc Request (LDR) queued to the Mapped Domain entries that will describe the user I/O to take place. This is analogous to a Disc Request queued to a specific DIT maiting for service.


When a request is made to access disc information, Disc Caching must first determine if the requested disc domain is present in memory. Disc Caching will first determine if the requested area of disc is already mapped into memory by scanning through the Napped Domain entries of the CDI. If the requested transfer can be satisfied with a currently mapped disc domain, then the I/O request will be queued (FIFO) behind the other I/Os pending against that mapped domain. If the requested area is not already mapped, then a search is made through the linked list of cached disc domains for the specified disc ldev. (The region header contains the disc address and size that a disc domain represents.) If the requested domain is found in this list (i.e. present in memory), then this region will be mapped. A domain is then considered mapped when there is an entry for it in the Mapped Domain portion of the CDI. Napping the domain allows Disc Caching to manage the I/O pending and/or currently active for a particular disc domain. Once the disc domain is mapped and present, the data can be moved between the process' data area and the mapped disc domain. The process can then continue executing without interruption or a process switch. The user/subsystem process for which the nove is done will be charged with the CPU overhead.

When a request is made to read data that is not currently cached in memory (i.e. a read "miss"), the fetch strategy uses the File System's knowledge of the type of access (sequential or random), the extent size of the file, along uith the current memory load to select the optimal size of the disc domain to be fetched and mapped into memory. The fetch of the disc domain is then initiated on the user's stack without a process switch. After the fetch is initiated, it completes in an unblocked manner so that this process (if no-wait I/O) or another process can proceed in parallel with the cache fetch.

In general, when writing, a process will not wait for completion of the physical I/O. Instead, the process will be awakened as soon as the transfer has completed between the process's data area and the mapped disc domain (i.e. no-wait-for-post). The physical I/O will then be posted at background priority while the process continues. (Users can specify wait-for-post on a file by file basis in place of the default no-wait-for-post with the FSETMODE intrinsic. This can be done on a global basis via :CHCHECONTROL.) If the access request is a write and there is a current write pending against the specified mapped disc domain, the process request is queued until the pending write is posted to disc. If the disc domain to be written is not currently cached in memory, a free piece of memory will be obtained to map the corresponding disc image and then the "write" takes place from the process' data area to the mapped disc domain. This prevents data from having to be read before being written. After that, a post to disc is initiated (on any write only the portion of a mapped disc domain that is modified will be posted to disc. After the move to the mapped disc domain is complete and the post to disc is nitiated, the process performing the "write" is allowed to continue to run without having to wait for the post to complete. Writes that must be posted to disc in a certain order use the Global Serial Write Queue. These

G.01.00 23- 2

Menory Regions



Cache Directory Table

The Cache Directory Table (CDT) is the bookkeeping structure for managing cached disc domains. This table is divided into 3 parts:

<u>CDT Header Entry</u>
This entry contains all information necessary to manage the entire table and also contains global caching related information.

<u>CDT Device Entry</u>
There will be one of these entries for every disc ldev that currently has caching enabled. These entries keep track of all cached disc domains in memory for this device. In addition, these entries contain statistics regarding the number of I/Os performed to the ldev.

CDI Mapped Domain Entry
These entries describe disc domains that are currently "mapped" into memory.
This means that there is logical I/O (cache move) and/or physical I/O (fatch or post) pending. These antries keep track of the state of the cached disc domain (INI, ROC, etc.) just as the DST Table keeps track of data segments.

The following low core cells contain the address of the CDT:

X1273 contains the DST Mumber of the CDT
X1274 contains the Bank Mumber of the CDT
X1275 contains the Offset within the bank of the CDT

G.01.00 23- 5

Disc Caching

Header Entry

		-
0	# Entries	CDT'ENTRIES
1	Entry Size (%30)	CDT'SIZE
2	# Free Entries	CDT'FREE'COUNT
3	1st Free Entry (table offset)	CDT'FREE'HEAD
4	Last Free Entry (table offset)	CDT'FREE'TAIL
5	Max # Entries Used	CDT'MAX'USED
6	# Ldevs cached	CDT'NUM'LDEVS
7	1st Cache device entry (entry number)	CDT'DISC'HEAD
Z 10	# Words this DST	CDT'DST'WORDS
X11	TRUE if stopcache pending	CDT'STOP'PND
X12	# Sectors sequential fetch	CDT'SEQ'MINFTCH
X13	# Sectors random fetch	CDT'RND'MINFTCH
X14	TRUE if wait for physical post	CDT'FORCE'POST
X15	Head of impeded queue (PIN)	CDT'STOP'QUEUE
X 16		
	:	
X27	· 	

Disc Caching

CDT'ENTRIES
The total number of CDT entries configured in this table (i.e. includes all three types of entries). The number of entries in the table will be:

1 entry for the header
+ 1 entry for each disc ldev configured.
(CDT Device entries)
+ 1 entry for each DRQ configured.
(CDT Mapped Domain entries)

G.01.00 23- 6

CDT'SIZE Size of each entry in the table.

CDT'FREE'COUNT Total number of entries currently unassigned.

CDT'FREE'HEAD

Table relative offset (i.e. Entry number * entry size) of the first available entry.

CDT'FREE'TAIL
Table relative offset of the last available entry.

CDT'MAX'USED

The maximum number of entries in use at one time.

CDT'NUM'LDEVS
The number of ldevs currently cached.

CDT'DISC'HEAD
The entry number of the first Device Entry.

CDT'DST'WORDS
The total number of words in this data segment.

CDT'STOP'PND
This value will be TRUE if there is a pending :STOPCACHE.

CDT'SEQ'MINFTCH

CDI'SEO'RIMFICH
If there is a prefetch for a sequential read ("niss"), the size of the prefetch is delinited by the extent size of the file. Within this limitation, the prefetch is equal to the greater of two sizes:

1) Requested size.

2) The largest integer multiple of the request size that is smaller than the value found in this cell.

The default value is 96 sectors. (This value may be changed via :CRCHECONTROL).

CDT'RND'HINFTCH

This is the same as CDT'SEQ'MINFTCH except that it's for random access. The default value is 16 sectors. (This value may be changed via :CACHECONTROL).

G.01.00 23- 7

G.01.00 23- 8

CDT'FORCE'POST

When this value is TRUE, all Hrites Hill "block" until the physical update on disc completes. The system default is FALSE. (Can be altered via :CRCHECONTROL).

CDI'STOP'QUEUE If CDI'STOP'PENDING is TRUE this will be the PIN number of the head pin of the processes impeded until the :STOPCRCNE completes.

Device Entry

0	Next ldev entry (entry number)	CDT'DE'NEXT'LDEV
1	Prev ldev entry (entry number)	CDT'DE'PREV'LDEV
2	Ldev for this disc	CD1,DE, FDEA
3	# Pages in device's domain	CDT'DE'MAPD'PAGES
4	# Disc domains currently mapped	CDT'DE'MAPD'CNT
5	Head of mapped domain (entry number)	CDT'DE'MAPD'HEAD
6	Tail of mapped domain (entry number)	CDT'DE'MAPD'TAIL
7	# Disc domain regions for this device	CDT'DE'REGIONS
%10	Menory address of head	CDT'DE'REG'HD
	cached disc domain	
%12	Memory address of tail	CDT'DE'REG'TL
	cached disc domain	
X14	- # Read hits -	CDT'DE'RHIT
X16	- # Write hits -	CDT'DE'NHIT
220	 -	COT'DE'RMISS
x22		CDT'DE'WMISS
224	 -	CDT'DE'STOP
226	Memory address of last	CDT'DE'SCANPT
	referenced donain	
		-

G.01.00 23- 10

Disc Caching

CDT'DE'NEXT'LDEV
The entry number of the next Device Entry.

CDT'DE'PREV'LDEV

The entry number of the previous Device Entry.

The Ldev number for this cached device.

CDT'DE'MAPD'PAGES

torior name Pauls.

Total number of main memory pages allocated to disc domains for this cached device. This includes mapped and unmapped regions. (1 main memory page = 128 words).

CDT'DE'MAPD'CNT
The total number of Mapped Domain entries associated with this Device Entry.

CDT'DE'MAPD'HEAD

The entry number of the first Mapped Domain entry for this device.

CDT'DE'MAPD'TAIL
The entry number of the last Mapped Domain entry for this device.

CDT'DE'REGIONS

The total number of disc domain regions for this ldev (includes mapped and unmapped regions).

CDT'DE'REG'HD

Henory address to the head region of the disc domain linked list. Disc domain regions are linked in order based on the disc address they represent (i.e. small disc address at head, large disc address at tail). This address uill not point to the region base (R8), but to the next domain (ND) field of the region header. (This is to facilitate the use of the LLSH instruction).

CDT'DE'REG'TL

Remory address of the tail region of the disc domain linked list. This address will be of the previous domain (PD) field of the region header.

Total number of times that a read was requested and the requested disc domain was present in memory - i.e. a read "hit". This means that the read completed without performing any I/O (to fetch the domain). Thus this is actually the number of read I/Os eliminated. This value will reset to zero on overflow.

COTOCHMII
Total number of times that a write was requested and the requested disc domain was present in memory — i.e. a write "hit". If there was no other write pending to the "hit" domain, then the process would continue as soon as the cache nove completes — thus eliminating a block for I/O. Otherwise, the process would block waiting for the first write to complete. This value will reset to zero on overflow.

Disc Caching

CDI'DE'RMISS
Total number of times that a read was requested and the requested disc domain was not in memory - i.e. a read "miss". This means that the requested disc domain had to be fetched into memory before the read could complete - thus potentially blocking the process. This value will reset to zero on overflow.

CDT'DE'UMISS
Total number of times that a write was requested and the requested disc domain was not in memory - i.e. a write "miss". This does not mean that the process would block until the disc domain is fetched as is the case for reads. Rather, a free memory region would be obtained to be the destination of the cache nove. This disc domain would then be posted in the background (unless overridden via :CRCHECONTROL or FSETNODE) allowing the process to continue without blocking. This value will reset to zero on overflow.

Total number of times that a process had to block on a cache transfer. Will reset to zero on overflow.

CDT'DE'SCAMPT

The memory address of the last region looked at on a search. This address will be of the next domain (ND) field of the region header. This value will be used along with CDT'DE'REG'HD to determine where to start the next search for a cached disc domain Rt times it will be more efficient to start with this address since the disc domain requested may be of a higher disc address than found in this region header, rather than always starting the search with CDT'DE'REG'HD.

٥	Prev mapped domain entry (entry number)	CDT'MD'PREV
1	Next mapped domain entry (entry number)	CDT'HD'NEXT
2	Start sector	CDT'MO'SECTOR
	address	
4	Last sector	COT'MD'END'SECTOR
	address	
6	A	CDT'MO'FLAGS
	S I O S C I C R P Q / A	
	N E I S / E T	
7	# Reads pending	CDT'MO'READ'CHT
X10	# Writes pending	CDT'MD'HRITE'CNT
X 11	Lock waiting	CD1,W0,TKD,CD1
X12	Head of impeded LDR	CDT'MD'IMPED'HO
X13	Head of active LDR	CDT'MD'LDR'HEAD
X14	Menory address	CDT'HO'HEN'ADR

G.01.00 23- 13

Disc Caching

1 - READ. Only read LDR(s) are attached. 2 - WRITE. Write LDR(s) and possibly read LDR(s) are

COTINOINTSCREO

COTINGILKICHT

COT'NO'LDEV

CULLANIA

CDT'MD'IMPEDED

attached.

3 - FLUSH. CDT is being flushed out.

4 - LOCK. Unused.

if present

DRQ for this mapped domain

Ldev for this mapped domain

Device entry (entry number)

Head impeded queue (PIN)

Flushing CDTs

CDT'MD'READ'CHT

X16

217

X20

Z21

122

X23

%27

The number of LDRs attached that are for reads (move not complete).

COT'MO'WRITE'CHT

The number of LDRs attached that are for unites. NOTE: This count will not be decremented until both the cache nove and the physical write completes. Monever, as soon as the cache nove completes, the LDR will be dequeued from the CDT.

CDT'MD'LKD'CDT Mot used.

CDT'ND'IMPED'HD
The first LDR that is impeded. (I.e. the CDT is in a write state already and another write is attached. The second write will be placed in this queue until the first write completes.)

CDT'MD'LDR'HERD
The first LDR that is on the active list for this CDT.

CDT'MD'MEM'ADDR
The memory address (region base) for this mapped disc domain, if present.

CDT'MD'DISCREO

The disc request table index associated with this mapped disc domain. This will be used to fetch this region in, or to post this region after any logical I/Os (writes) have completed. (I.e. this DRQ is used for the physical I/O.)

CDT'MD'LK'CHT

CDT'MD'LDEV
The ldev number for this mapped domain.

CDT'ND'IMPEDED
The PIM for the first process impeded on this mapped disc domain. Processes get impeded here when they do WAITFORIO when their LDR is on the CDT impeded queue and the Mapped Domain is currently being written out. (This will also happen upon a :SIOPCRCHE to force all LDRs to complete.) As soon as the physical post of the Mapped Domain is complete, all processes impeded here will be awakened.

The entry number for the Device entry that this Mapped Domain entry is as-

Disc Caching

CDT'MD'PREV

Entry number of the previous mapped domain entry for this device.

CDT'MD'NEXT Entry number of the next mapped domain entry for this device.

COT'NO'SECTOR

The starting disc sector address representing this mapped domain entry.

CDT'MD'END'SECTOR
The ending disc sector address representing this mapped domain entry.

CULLACENS

Flags describing the state of this mapped domain entry and the region associated with it:

(0:1) - Absent.
Region is not present in memory.
(1:1) - Ini.
Region is already In-Motion-In. (Set when the fetch for this cached region is initiated).

Region is already in-motion-in. (set when the recon for this cached region is initiated).

Region is In-Motion-Out. (Set by STARTOBJURITE when performing the background post of a cached region).

(3:1) - HISS.
This disc domain was not present and had to be prefetched.

(4:1) - LOCK. Not used.

(5:1) - FUIP.
Forced Write In Progress. Region was forced out of memory to make room for another object.

(6:1) - ROC.
Recover Overlay Candidate. Region may be forced out of memory to make room for another object. However, if this region is referenced again it can be recovered.

(7:1) - VIRGIM.

Clean region in the write state. Cleared as soon as a move completes inmediately. Otherwise the write will have to wait until the current write completes the physical post).

(8:1) - NOPOST.

until the current write completes the physical post.

Set when the CDT is being posted out as a result of a write request that did not want to wait for the physical post to complete. This will be cleared by the cache completor when the physical post completes. (This is used to insure that a cache move for any subsequent write request will not be serviced until the physical post completes.)

(9:1) - SEQ.

Hill not be services until the provided of the SEQ.

Set if doing sequential I/O. When the request for the last area of this disc domain is complete, this domain will be nade a ROC.

(10:3) - Not used.

(13:3) - STRIE

O - RVAIL. CDT is an available entry.

G.01.00 23- 14

Disc Caching

Logical Disc Request Table

21017 Pointer to Logical Disc Request Table

This table is really part of the DRQ (Chapter 13). Any entry with the logical request bit set in the flags will conform to this format and not the format of the standard DRQ.

Logical disc requests entries are used to manage requests between the requesting process and a mapped disc domain. They are the counterpart of disc requests entries used to manage physical I/O requests between a process and a disc. These entries are kept as part of the DRQ Table, but will never be queued to the disc's DIT, instead they will be queued to the mapped disc domain CDT entry. LDR entries may only be placed onto the following queues:

1) The CDT active list.
2) The CDT impeded LDR list.
3) The Disabled Disc Request. (This will only happen if the buffer segment is absent when the logical 1/0 (cache move) is attempted.)

LDRs are singly linked onto the CDT queues and doubly linked onto the disabled disc request queue.

Logical Disc Request Entry

	3 4 5	6 7	8	9	0 1	2	3	4	5	
0	/ S I B / B O L / U W O / F A C / K K / E E / O	0 0 N E P 0 S	SI EI RI II AI	C L D L T L Q L U L E L	M / 0 / V / D / D / N / E /	C U R R E Q	DI SI BI LI DI	RIE	I N C C	LDR'FLAGS
1	HODA	of ext	ent	li	mit					LDR'L'HODR
2		Lde	٧						_	LDR' LDEV
3	Mapped Do	omain C	DT e	nt	ry nu	nbe	r		_	LDR'CDT
4	SI D	ST nunt	er						_	LDR' BUFDST
5	Off	set int	o DS	ST						LDR'BUFADR
6	Strategy			F	uncti	on			_	LDR'STRAT'FUNC
7	Count/X	log/Cor	tro	l r	eturn	8			_	LDR' COUNT
Z10		P1								LDR'PARM1
X11		P2								LDR' PARM2
%12			Qua	lif	ier	St	atu	8	_ i	LDR'STATQ
X13		PIN r	nup	er					_	FDK, bCB
X14	Prev. LDR	in que	ue	(ta	ble r	ela	tiv	e)		LDR'PREVQ
Z15	Next LDR	in que	eue	(ta	ble r	ela	tiv	e)		LDR'NEXTQ
X 16	HODR	of exte	ent l	bas	e				_	FDK, B, HODU
X17	LODA	of ext	ent l	bas	е				_	LDR'B'LODA
X20	LODA	of ext	ent .	lin	it					LDR'L'LODA

G.01.00 23- 17

Disc Caching

```
LDR'STRAT'FUNC
(0:8) - Strategy
0 - Unknown caller
1 - Unknown File System
                         ! - Uhknoun File System
2 - Spooler
3 - Directory
4-7- Uhknoun caller
8 - Gennessage
9 - File System, Quiesce I/O
10 - File System, Sequential, No Buf
11 - File System, Direct, No Buf
12 - File System, Direct, No Buf
13 - File System, Direct, Buffered
14 - File System, KSMI
15 - File System, ISMB
```

(8:8) - Function O - Read 1 - Write

On initiation, this specifies the requested transfer count (+words, -bytes). At completion of the request, this contains the actual transmission count (+words, -bytes).

This is the High Order Disc Address of the requested disc sector.

LDR'PARM2
This is the Low Order Disc Address of the requested disc sector.

LDR'STATO

Uniform status returns.

LDR'PCB PIN of the requesting process.

DIM INCOME 17 Table relative index of the previous LDR in the queue. (NOTE: LDRs are singly linked on the CDT queues, and doubly linked on the disabled disc request queue).

LOR'NEXTO

Table relative index of the next LDR in the queue.

The High Order Disc Address of the extent base. (Used when the logical disc request is through the file system. Caching uses this information when searching memory for a "hit" on a cached domain).

LDR'B'LODA
The Low Order Disc Address of the extent base. (See note above).

LDR'L'LODA
The Low Order Disc Address of the extent limit. (See note above).

LDR'FLAGS Flags

FLRGS

(0:3) - Not used.

(3:1) - SBUF.
Set if request is to/from a System Buffer.

(4:1) - IOWAKE.
Set if system should wake up the process when the logical I/O completes.

(5:1) - BUCKED.
Set if the process wants to wait for the logical disc request to complete.

(6:1) - DONE.
Set when the logical disc request is complete and the process will be awakened (if IOWAKE is set)

(7:1) - DO'POST.
Set if the caller wants to be waited until the physical post to disc completes. Only valid for write requests.

(8:1) - SETRIL'POST.
Set when the physical post should be through the Global Serial Write queue.

(9:1) - CDI'OWEWED.

Serial Mrite queue.

(9:1) - CDI'QUEUED.

This request has been queued - either onto the CDT active queue (see CDT Happed Domain entries) or onto the disabled disc request list.

(10:1) - MOVE'DDME.

The move has been completed, but the process won't be awakened until the DDNE bit is set.

(11:1) - Not used.

(12:1) - CUR'REQ.

Set if this request is the current/active request.

(13:1) - DISABLE.

(13:1) - $\frac{\text{Set i}}{\text{DISABLE}}$. Set if the request is disabled.

Set If the request a Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the Control of the

LDR'L'HODA
The High Order Disc Address of the extent limit. (See note with LDR'B'HODA).

LDR'LDEV
The ldev for this request.

LDR'CDT
The CDT number for the Mapped Domain entry associated with this request.

Data Segment number for the target of the logical I/O request. If bit zero is set, then this is the process's stack.

I DR' BUEBOR

Offset within the DST (above) for the target address. If the DST is the process's stack, then this address will be DB relative.


G.01.00 23- 18

CHAPTER 24 NATIVE LANGUAGE SUPPORT

NL/3000 Internal Table Structure

NLS FILE CODES LANGDEF.PUB.SYS CHRDEFXX.PUB.SYS NLSDEF.PUB.SYS

Native Language Support (NLS) Table Overview



Native Language Support

Native Language Table (NLT)

This table is created by INITNLS (called by PROGEN). The DST number is contained in SYSGLOB extension X12. The Native Language Table (NLT) contains the description of all the character sets needed to support the installed languages, and additional information needed to support the configured languages (DST numbers of the languages associated DSTs, character sets, etc.).

Every installed language has had an associated Language DST, set up by $\ensuremath{\mathsf{INITNLS}}$.




G.01.00 24- 1

G.01.00 24- 2

Native Language Support

NLT Overhead Table


The NLT overhead table is 8 words long.



Native Language Support

NLT Installed Language Table Format

For each of the supported non-NRTIVE3000 languages there is a 12-word language entry.



NLT Installed Character Set Jable Format


For each character set installed on the system there is an 11 word character set table. It has the following format:



Native Language Support

NLT Character Attributes Table

The NLT Character Attributes Table is comprised of a table for each configured character set. At this time, only two character sets are configurable: Class Four Languages (KANJI-based) and Nonclass Four Languages.



The type = 1 attribute table is a 256 byte table. Each byte corresponds to a character with that octal value.

- numeric character - special character (e.g. "!", "?", "." etc.) - alphabetic uppercase character - alphabetic lowercase character Attribute 0 - control code - invalid character (unused code)

G.01.00 24- 5

G.01.00 24- 6

Native Language Support

Language DST

For each language installed on a target system (with the exception of NATIVE-3000) INTINLS will build one language DST with the following structure:

1
LDST OVERHEAD TABLE
LDST TRANSLATION TABLES (5 subtables)
LOST CUSTOM DATA TRBLES
: LDST NATIONAL SPECIAL : TABLE : (an optional table)

Native Language Support

LDST Overhead table

The overhead region has the following format:



The national special table is optional. If it does not exist, the pointer to it is zero.

LDST Translation Tables

For each language a number of translation tables are stored:

LDST UPSHIFT TABLE (128 WORDS)
LDST DOWNSHIFT TABLE (128 WORDS)
LDST ASCII -> EBCDIC CONVERSION TABLE (128 WORDS)
LDST EBCDIC -> ASCII CONVERSION TABLE (128 WORDS)
LDST COLLATING SEQUENCE TABLE (class dependent)

Native Language Support

LDST Collating Sequence Table

Overview

Class One Some languages, namely American English and Katakana, can be be Languages: collated by using the numerical representation of the RSCII encoding as the sequence number for any given character. These languages can use the Compare Bytes machine instruction.

Class Tuo
Languages:
Some languages may be able to use the COBOLII machine instruction, Compare-Translated-Strings. These languages need to have a one-to-one mapping of character encoding to sequence number. Any algorithm for this class of language must take into account the fact that not all MP 3000s have the COBOLII firmware.

Class Three Many languages will not be able to use either of the tactics Languages: described above. There are a number of language-dependent algorithms that need to be supported.

Class Four Some languages require 16-bit character string encoding. Languages: Collating these languages is not supported. The collating sequence table for this class of language is reserved.

Class One Languages


Since class one languages will use the compare bytes machine instruction (CDPB), the whole collating sequence table for this class is $3\ \text{mords}$.

	1
0	3
1	language ID
2	language class

G.01.00 24- 9

Native Language Support


Class Three Languages



Native Language Support

Class Two Languages

This sequence table has a 13-word over head table and a 128-word sequence table.




Note: Word X11 of the overhead contains in the left byte the the character value, which has the lowest sequence number and in the right byte the character value, which has the highest sequence number.

The byte value of the character is used as a byte pointer collating entries.

G.01.00 24- 10


Native Language Support

Class Three Languages (Cont.)



The byte value of the character is used as an index to the sequence entries.

2:1 Character Happing Table



Entry has same format as mode options in the LDST Collating Sequence Table Format for Class Three Languages.

G.01.00 24- 13


Native Language Support

priority (bits 10:6)

mode type (0,1,or (bits 8:2)


Class Four Languages


Class four languages require 16-bit character encoding. Sorting in class four languages is not implemented in this release of NLS. A preliminary collating sequence table is planned to be 8 words in length.



Mative Language Support

1:2 Character Mapping Table





Entry has same format as one above.

G.01.00 24- 14

Mative Language Support

LDST Custom Data Table Format

This table is 196 words long. The formats and information in this table are language dependent, and may be modified with LRMGINST.PUB.SYS.

0	LDST CALENDAR SKELETON (9 Hords)
9	LOST CUSTOM DATE SKELETOM (13 bytes)
16	LDST TIME SKELETON (4 words)
20	LDST ABBREVIATED MONTH NAMES (24 Hords)
44	LDST FULL MONTH NAMES (122 words)
116	LDST ABBREVIATED WEEKDAY MAMES (21 bytes)
127	LDST FULL WEEKDRY NAMES (42 words)
169	LDST YES/NO CHARACTER STRINGS (6 words)
175	LDST THOUSANDS INDICATORS (1 word)
176	LDST CURRENCY SYMBOL (5 bytes)
179	LDST RESERVED

LDST National Special Table

This table is optional and its existence is signaled by a nonzero pointer in the LDST overhead region. It is used to store data unique to a given language -- e.g. the Emperor data the for the Japanese calendar.

Length national dependent data

Date Formats for Japan and Taiwan

For a given language, there is only one date format possible. The format of the year stored in the date format of the LDST can either be yyyy or yy for the Julian dates or Myy for either the Japanese date (Emperor Era) or the Taiwanese date foundation of republic date).

If the format of the year stored as the date format in the LDST is Nyy then either the Japanese emperor dates or the Taiwanese foundation date has to be stored in the national dependent table.

G.01.00 24- 17

Native Language Support

Japanese Date Format

There are three entries which do not change. The user can add new entries. These entries have to be stored in ascending order sorted by word 1.

The values of the entries are:


	starting date (MDY)	octal value	starting year	emperor symbol
×	1/ 1/1873	X 1	241	Ħ
	7/30/1912	X14324	X1	ī
	12/25/1926	X32547	X1	S

* since this starting time is in the 19 th century and we are not able to handle dates before 1900 easily, we store I1 as starting time.

For new date entries created by the customer the starting year $\mbox{\tt will}$ always be 1.

Native Language Support

National Dependent Table Formats



The period entries are two word entries of the following format:

,	7 15	
year of century	day of the year	word 1 (starting date)
0	78 15	
starting year	емрегог symbol	Hord 2

The ID for Japanese and Taiwanese date formats is always set to 1.

G.01.00 24- 18

Native Language Support

Taiwanese Date Format

There are two entries for the Taiwanese national dependent table.

The values of the entries are:

Starting date (MDY)	Octal value	Starting Year	Emperor symbol	
1/ 1/1900	X1	20	240	
1/ 1/1912	X14001	21	240	

The user does not need to add new entries.

READER COMMENT SHEET

MPE V Tables Manual for MPE V/E, Version G.01.00

32033-90040

Is this manual technically accurate?

Are the concepts and wording easy to

January 1985

(If no, explain under Comments, below.)

(If no, explain under Comments, below.)

We welcome your evaluation of this manual. It is one of several that serve as a reference source for HP 3000 Computer Systems. Your comments and suggestions help us to improve our publications and will be reviewed by appropriate technical personnel. HP may make any use of the submitted suggestions and comments without obligation.

Yes [] No []

Yes [] No []

understand?						
	is manual convenient nt and readability?	Yes [] No []	(If no, explain or suggest improvements under Comments, below.)			
Comments:						
We appreciate your comments and suggestions. This form requires no postage stamp if mailed in the U.S. For locations outside the U.S., your local HP representative will ensure that your comments are forwarded.						
		Date:				
FROM:						
Name						
Company						
Address						

FOLD



NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 1070 CUPERTINO, CALIFORNIA

POSTAGE WILL BE PAID BY ADDRESSEE

Documentation Manager/47US Hewlett-Packard Company Computer Systems Division 19447 Pruneridge Avenue Cupertino, California 95014

FOLD