





Series/1 Model 5
4955 Processor
and Processor Features
Description

First Edition (November 1976)

Changes are periodically made to the information herein; any such changes will be reported in subsequent revisions or Technical Newsletters.

Text for this manual has been prepared with the IBM Magnetic Tape Selectric® Composer.

Some illustrations in this manual have a code number in the lower corner. This is a publishing control number and is not related to the subject matter.

Requests for copies of IBM publications should be made to your IBM representative or the IBM branch office serving your locality.

A form for readers' comments is provided at the back of this publication. If the form has been removed, send your comments to IBM Corporation, Systems Publications, Department 27T, P. O. Box 1328, Boca Raton, Florida 33432. Comments become the property of IBM.

©Copyright International Business Machines Corporation 1976

Contents

Preface ix	
Summary of Publication ix	Processor Status Word 3-5
Related Publications x	Program Check Conditions 3-5
A A A A A A A A A A A A A A A A A A A	Program Check or Soft Exception Trap Condition 3-5
Chapter 1. Introduction 1-1	Soft Exception Trap Condition 3-5
IBM 4955 Processor 1-1	Machine Check Conditions 3-6
D 0 11 1 m	Status Flags 3-6
Processor Optional Features 1-1 Processor Description 1-1	Power/Thermal Warning Condition 3-6
T	Class Interrupts 3-6
Communications Features 1-4	Priority of Class Interrupts 3-7
	Execution of Class Interrupts 3-7
Sensor Input/Output Options 1-5 Packaging and Power Options 1-5	Recovery from Error Conditions 3-9
Other Options 1-5	Program Check 3-10
other Options 1-5	Storage Parity Check 3-10
Chapter 2. Processing Unit Description 2-1	CPU Control Check 3-10
Main Storage 2-1	I/O Check 3-10
Addressing Main Storage 2-1	Soft Exception Trap 3-10
Registers 2-3	Program Controlled Level Switching 3-10
Console Address Key Register 2-3	Selected Level Lower Than Current Level and In-process
Console Data Buffer 2-3	Flag On 3-11
Current-Instruction Address Register (CIAR) 2-3	Selected Level Equal to Current Level and In-process
Mask Register 2-3	Flag On 3-11
Processor Status Word (PSW) 2-4	Selected Level Higher Than Current Level and In-process
Storage Address Register (SAR) 2-4	Flag On 3-12
Address Key Register (AKR) 2-4	Selected Level Lower Than Current Level and In-process
General Registers 2-4	Flag Off 3-12
Instruction Address Register (IAR) 2-4	Selected Level Equal to Current Level and In-process
Level Status Register (LSR) 2-5	Flag Off 3-12
Arithmetic and Logic Unit (ALU) 2-5	Selected Level Higher Than Current Level and In-process
Numbering Representation 2-5	Flag Off 3-13
Indicators 2-7	Interrupt Masking Facilities 3-13
Even, Negative, and Zero Result Indicators 2-8	Summary Mask 3-13
Even, Carry, and Overflow Indicators—Condition	Interrupt Level Mask Register 3-14
Code for Input/Output Operations 2-8	Device Mask (1-bit) 3-14
Carry and Overflow Indicators—Add and Subtract	Chamber 4 C
Operations 2-8	Chapter 4. Console 4-1
Carry and Overflow Indicator - Shift Operations 2-13	Basic Console 4-2
Testing Indicators with Conditional Branch and Jump	Keys and Switches 4-2
Instructions 2-13	Indicators 4-2
Indicators Affected by Compare Operations 2-14	Programmer Console 4-2
Indicators—Multiple Word Operands 2-14	Console Display 4-3
Program Execution 2-15	Indicators 4-4
Instruction Formats 2-15	Combination Keys/Indicators 4-5
Effective Address Generation 2-17	Keys and Switches 4-7
Processor State Control 2-24	Displaying Main Storage Locations 4-10
Initial Program Load (IPL) 2-26	Storing Into Main Storage 4-10
Sequential Instruction Execution 2-27	Displaying Registers 4-11 Storing Into Registers 4-11
Jumping and Branching 2-27	Storing Into Registers 4-11
Level Switching and Interrupts 2-27	Chapter 5. Instructions 5-1
Stack Operations 2-28	Exception Conditions 5-1
	D
Chapter 3. Interrupts and Level Switching 3-1	C. C. T
Introduction 3-1	Soft Exception Trap Conditions 5-1 Instruction Termination or Suppression 5-2
Interrupt Scheme 3-1	
Automatic Interrupt Branching 3-2	Instruction Descriptions 5-2
I/O Interrupts 3-3	Add Byte (AB) 5-2
Prepare I/O Device for Interrupt 3-3	Add Grant Product (ASI) 5-3
Present and Accent Interrupt 2.2	Add Carry Register (ACY) 5-3

Add Doubleword (AD) 5-4	Jump On Count (JCT) 5-42
Register/Storage Format 5-4	Jump On Not Condition (JNC) 5-43
Storage/Storage Format 5-4	Level Exit (LEX) 5-44
Add Word (AW) 5-5	Load Multiple and Branch (LMB) 5-44
Register/Register Format 5-5	Multiply Byte (MB) 5-45
Register/Register Format 5-5 Register/Storage Format 5-5	Multiply Doubleword (MD) 5-46
Storage to Register Long Format 5-6	Move Address (MVA) 5-47
Storage to Register Long Pormat 5-6	Storage Address to Register Format 5-47
Dtoruge over-the	Storage Immediate Format 5-47
Add Wold With Cally (Move Byte (MVB) 5-48
Add Word Immediate (Fig. 1)	Register/Storage Format 5-48
Register Intinediate Zerig	Storage/Storage Format 5-48
Storage Immediate Format 5-8	Move Byte Immediate (MVBI) 5-49
Branch Unconditional (B) 5-9	Move Byte and Zero (MVBZ) 5-49
Branch and Link (BAL) 5-10	Move Doubleword (MVD) 5-50
Branch and Link Short (BALS) 5-10	Register/Storage Format 5-50
Branch On Condition (BC) 5-11	Storage/Storage Format 5-50
Branch On Condition Code (BCC) 5-12	Move Doubleword and Zero (MVDZ) 5-51
Branch On Not Condition (BNC) 5-13	Move Byte Field and Decrement (MVFD) 5-52
Branch On Not Condition Code (BNCC) 5-14	Move Byte Field and Increment (MVFN) 5-52
Branch On Not Overflow (BNOV) 5-15	Move Word (MVW) 5-53
Branch On Overflow (BOV) 5-15	Register/Register Format 5-53
Branch Indexed Short (BXS) 5-16	Register/Storage Format 5-53
Compare Byte (CB) 5-17	Register to Storage Long Format 5-53
Register/Storage Format 5-17	Storage to Register Long Format 5-54
Storage/Storage Format 5-17	Storage/Storage Format 5-54
Compare Byte Immediate (CBI) 5-18	Move Word Immediate (MVWI) 5-55
Compare Doubleword (CD) 5-19	Storage to Register Format 5-55
Register/Storage Format 5-19	Storage Immediate Format 5-55
Storage/Storage Format 5-19	Move Word Short (MVWS) 5-56
Compare Byte Field Equal and Decrement (CFED) 5-20	Register to Storage Format 5-56
Compare Byte Field Equal and Increment (CFEN) 5-20	Storage to Register Format 5-56
Compare Byte Field Not Equal and Decrement (CFNED) 5-21	Move Word and Zero (MVWZ) 5-57
Compare Byte Field Not Equal and Increment (CFNEN) 5-21	Multiply Word (MW) 5-58
Complement Register (CMR) 5-22	No Operation (NOP) 5-59
Copy Address Key Register (CPAKR) 5-23	AND Word Immediate (NWI) 5-59
System Register/Storage Format 5-23	OR Byte (OB) 5-60
System Register/Register Format 5-23	Register/Storage Format 5-60
Copy Current Level (CPCL) 5-24	Storage/Storage Format 5-60
Copy Console Data Buffer (CPCON) 5-24	OR Doubleword (OD) 5-61
Copy Interrupt Mask Register (CPIMR) 5-25	Register/Storage Format 5-61
Copy In-process Flags (CPIPF) 5-25	Storage/Storage Format 5-61
Copy Level Block (CPLB) 5-26	OR Word (OW) 5-62
Copy Level Status Register (CPLSR) 5-26	Register/Register Format 5-62
Copy Processor Status and Reset (CPPSR) 5-27	Register/Storage Format 5-62
Copy Storage Key (CPSK) 5-27	Storage to Register Long Format 5-63
Copy Segmentation Register (CPSR) 5-28	Storage/Storage Format 5-63
Compare Word (CW) 5-29	OR Word Immediate (OWI) 5-64
Register/Register Format 5-29	Register Immediate Format 5-64
Register/Storage Format 5-29	Storage Immediate Format 5-64
Storage/Storage Format 5-29	Pop Byte (PB) 5-65
Compare Word Immediate (CWI) 5-30	Pop Doubleword (PD) 5-65
Register Immediate Long Format 5-30	Push Byte (PSB) 5-66
Storage Immediate Format 5-30	Push Doubleword (PSD) 5-66
Divide Byte (DB) 5-31	Push Word (PSW) 5-67
Divide Doubleword (DD) 5-32	Pop Word (PW) 5-67
Diagnose (DIAG) 5-33	Reset Bits Byte (RBTB) 5-68
Disable (DIS) 5-34	Register/Storage Format 5-68
Divide Word (DW) 5-35	Storage/Storage 5-68
Enable (EN) 5-36 Fill Byte Field and Decrement (FFD) 5-37	Reset Bits Doubleword (RBTD) 5-69
Fill Byte Field and Decrement (FFD) 5-37 Fill Byte Field and Increment (FFN) 5-37	Register/Storage Format 5-69
	Storage/Storage Format 5-69
Operate I/O (IO) 5-38 Interchange Operand Keys (IOPK) 5-38	Reset Bits Word (RBTW) 5-70
Interchange Registers (IR) 5-39	Register/Register Format 5-70
Jump Unconditional (J) 5-39	Register/Storage Format 5-70
Jump and Link (JAL) 5-40	Storage to Register Long Format 5-71
Jump On Condition (JC) 5-41	Storage/Storage Format 5-71

Reset Bits Word Immediate (RBTWI) 5-72	—
Register Immediate Long Format 5-72	Exclusive OR Byte (XB) 5-102
Storage Immediate Format 5-72	Exclusive OR Doubleword (XD) 5-103
Subtract Byte (SB) 5-73	Exclusive OR Word (XW) 5-104
Subtract Carry Indicator (SCY) 5-73	Register/Register Format 5-104
Subtract Doubleword (SD) 5-74	Register/Storage Format 5-104
Register/Storage Format 5-74	Storage to Register Long Format 5-105
Storage/Storage Format 5-74	Exclusive OR Word Immediate (XWI) 5-105
Set Address Key Register (SEAKR) 5-75	
System Register/Storage Format 5-75	Chapter 6. Floating-Point Feature 6-1
System Register/Register Format 5-75	Data Format 6-1
Set Console Data Lights (SECON) 5-76	Number Representation 6-1
Cat Internal 186 1 B. T. Campana	Floating-Point Numbers 6-1
C 4 T 11 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Binary Integers in Main Storage 6-2
CAT AND A AND A	Normalization 6-2
0 . 0.	Programming Considerations 6-2
Cat Car All San Land	Floating-Point Feature Not Installed 6-2
Coon Device Field F	Floating-Point Registers 6-2
Scan Byte Field Equal and Decrement (SFED) 5-81	Arithmetic Indicators 6-2
Scan Byte Field Equal and Increment (SFEN) 5-81	Floating-Point Exceptions 6-2
Scan Byte Field Not Equal and Decrement (SFNED) 5-82	Level Control 6-3
Scan Byte Field Not Equal and Increment (SFNEN) 5-82	Instruction Termination or Suppression 6-3
Shift Left Circular (SLC) 5-83	Floating-Point Instructions 6-3
Immediate Count Format 5-83	Instruction Formats 6-3
Count in Register Format 5-83	Exception Conditions 6-4
Shift Left Circular Double (SLCD) 5-84	Program Check Conditions 6-4
Immediate Count Format 5-84	Soft Exception Trap Condition 6-4
Count in Register Format 5-85	
Shift Left Logical (SLL) 5-86	Instruction Descriptions 6-5
Immediate Count Format 5-86	Copy Floating Level Block (CPFLB) 6-5
Count in Register Format 5-86	Floating Add (FA) 6-6
Shift Left Logical Double (SLLD) 5-87	General Description (Short precision) 6-6
Immediate Count Format 5-87	Storage/Register Format 6-6
Count in Register Format 5-87	Register to Register Format 6-6
Shift Left and Test (SLT) 5-88	Floating Add Double (FAD) 6-7
Shift Left and Test Double (SLTD) 5-88	General Description (double precision) 6-7
Shift Right Arithmetic (SRA) 5-89	Storage/Register Format 6-7
Immediate Count Format 5-89	Register to Register Format 6-7
Count in Register Format 5-89	Floating Compare (FC) 6-8
Shift Right Arithmetic Double (SRAD) 5-90	Floating Compare Double (FCD) 6-8
Immediate Count Format 5-90	Floating Divide (FD) 6-9
Count in Register Format 5-90	Storage/Register Format 6-9
Shift Right Logical (SRL) 5-91	Register to Register Format 6-9
Immediate Count Format 5-91	Floating Divide Double (FDD) 6-10
Count in Register Format 5-91	Storage/Register Format 6-10
Shift Right Logical Double (SRLD) 5-92	Register to Register Format 6-10
Immediate Count Format 5-92	Floating Multiply (FM) 6-11
Count in Register Format 5-92	General Description (Short precision) 6-11
Store Multiple (STM) 5-93	Storage/Register Format 6-11
Stop (STOP) 5-94	Register to Register Format 6-11
Supervisor Call (SVC) 5-94	Floating Multiply Double (FMD) 6-12
Subtract Word (SW) 5-95	General Description (Double precision) 6-12
Register/Register Format 5-95	Storage/Register Format 6-12
Register/Storage Format 5-95	Register to Register Format 6-12
Storage to Register Long Format 5-96	Floating Move (FMV) 6-13
Storage/Storage Format 5-96	Storage to Register Format 6-13
Subtract Word with Carry (SWCY) 5-97	Register to Storage Format 6-13
Subtract Word Immediate (SWI) 5-98	Register to Register Format 6-13
Register Immediate Long Format 5-98	Floating Move and Convert (FMVC) 6-14
Storage Immediate Format 5-98	Storage to Register Format 6-14
Fest Bit (TBT) 5-99	Register to Storage Format 6-14
Cest Bit and Reset (TBTR) 5-99	Floating Move and Convert Double (FMVCD) 6-15
Fest Bit and Set (TBTS) 5-100	Storage to Register Format 6-15
Fest Bit and Invert (TBTV) 5-100	Register to Storage Format 6-15
Fest Word Immediate (TWI) 5-101	Floating Move Double (FMVD) 6-16
Dominton Income 11 / Y	Storage to Register Format 6-16
Storage Immediate Long Format 5-101	Register to Storage Format 6-16
nvert Register (VR) 5-102	Register to Register Format 6-16

Floating Subtract (FS) 6-17	Read ID 10-5
General Description (Short precision) 6-17	Read Timer Value 10-5
Storage/Register Format 6-17	Read Timer Mode 10-5
Register to Register Format 6-17	Condition Codes Reported for an I/O Instruction 10-5
Floating Subtract Double (FSD) 6-18	I/O Interrupt 10-6
General Description (Double precision) 6-18	Condition Codes Reported for an I/O Interrupt 10-7
Storage/Register Format 6-18	Status After Resets 10-7
Register to Register Format 6-18	D. W. W. D. L. W.
Set Floating Level Block (SEFLB) 6-19	Chapter 11. Teletypewriter Adapter Feature 11-1
	Addressing 11-2
Chapter 7. Input/Output Operations 7-1	Commands 11-3
Operate I/O (IO) Instruction 7-1	Prepare 11-4
Immediate Device Control Block (IDCB) 7-2	Reset Device 11-4
I/O Commands 7-4	Reset to Diagnostic Wrap 11-4
DPC Operation 7-6	Write 11-4
Cycle Steal 7-8	Read 11-5
Start Command 7-8	Read ID 11-5
Device Control Block (DCB) 7-8	Condition Codes Reported for an I/O Instruction 11-5
Cycle Steal Operation 7-10	I/O Interrupt 11-6
Start Cycle Steal Status Operation 7-12	Condition Codes Reported for an I/O Interrupt 11-6
Termination Conditions 7-13	Status After Resets 11-6
I/O Condition Codes and Status Information 7-14	
I/O Instruction Condition Codes 7-15	Chapter 12. Integrated Digital Input/Output Non-
Interrupt Condition Codes 7-15	Isolated Feature 12-1
I/O Status Information 7-16	Digital Input (DI) 12-3
Chaining 7-17	DI External Sync 12-3
DCB Command Chaining 7-17	Process Interrupt (PI) 12-3
	Digital Output (DO) 12-3
Chapter 8. Storage Protection 8-1	DO External Sync 12-4
Storage Protection During Initial Program Load 8-3	Commands 12-4
Storage Protection in Supervisor State 8-3	Addressing 12-5
Address Space Management 8-3	Summary of Digital Input Commands 12-5
Address Space 8-3	Summary of Digital Output Commands 12-6
Active Address Key 8-4	Condition Codes Reported During the Operation I/O
Address Key Values After Interrupts 8-4	Instruction 12-6
Equate Operand Spaces (EOS) 8-5	Digital Input Command Description 12-7
- Delegation Translator	Read DI 12-7
Chapter 9. Storage Address Relocation Translator	Read PI 12-7
Feature 9-1	Read PI with Reset 12-7
Translator Description 9-1 Relocation Addressing 9-3	Read ID 12-7
Relocation Addressing 9-3 Storage Protection When Using the Relocation Translator 9-4	Read Status 12-7
Storage Protection when Using the Relocation Translator 9-4	Prepare 12-8
I/O Storage Access Using the Relocation Translator 9-4 Compability Between the Relocation Translator and	Arm PI 12-8
the Storage Protection Mechanism 9-4	Arm DI External Sync 12-8
Characteristics That Are Similar 9-5	Set Test 0 12-9
Characteristics That Are Dissimilar 9-5	Set Test 1 12-9
Error Recovery Considerations 9-5	Device Reset 12-9 Digital Output Command Descriptions 12-9
Invalid Storage Address 9-5	Digital Output Command 2 company
Protect Check 9-5	Read ID 12-9
Status of Translator After Power Transitions and Resets 9-5	Read DO 12-10
Instruction Execution Time When Using the Translator 9-5	Read Status 12-10
mistraction production time with coars and and	Write DO 12-10
Chapter 10. Timer Feature 10-1	Prepare 12-10 Arm DO External Sync 12-11
Addressing 10-2	Arm DO External Sync 12-11 Set Diagnostic External Sync 12-11
Commands 10-2	
Prepare 10-3	Disable DO 12-11 Device Reset 12-11
Set Timer Period and Initial Value 10-3	Device Reset 12-11 Interrupt Presentation and Status Words 12-12
Set Timer Mode 10-3	DI Status Word and Interrupt ID Word 12-12
Start Timer, Periodic 10-4	DO Status Word and Interrupt ID Word 12-12 DO Status Word and Interrupt ID Word 12-13
Start Timer Aperiodic 10-4	Status After Power Transitions and Resets 12-13
Stop Timer 10-4	
Device Reset 10-5	
DA1120 12000 TO 0	DO Resets 12-13

Chapter 13. IBM 4999 Battery Backup Unit 13-1 Introduction 13-1 Functional Description 13-1 Line Voltage Sensing 13-2 Battery Voltage Sensing 13-2 Controls and Indicators 13-2 Utility Power Switch 13-2 Battery Circuit Breaker 13-3 Reset Switch 13-3 Utility Power Indicator 13-3 Backup Power Indicator 13-3 Standby Indicator 13-3 On Battery Indicator 13-3 Low Battery Indicator 13-3 Offline Indicator 13-3 Processor Power/Thermal Warning 13-3 Appendix A. Instruction Execution Times A-1 Table 1. Instruction Times-Relocation Translator Not Installed or Disabled A-4 Table 2. Instruction Times-Relocation Translator Enabled A-13 Appendix B. Instruction Formats B-1 Appendix C. Assembler Syntax C-1 Coding Notes C-1 Legend for Machine Instruction Operands C-1 Appendix D. Numbering Systems and Conversion Tables D-1 Binary and Hexadecimal Number Notations D-1 Binary Number Notation D-1 Hexadecimal Number System D-1 Hexadecimal – Decimal Conversion Tables D-2 Appendix E. Character Codes E-1 Index X-1 Index of Instructions by Format X-13 Index of Instructions by Name X-16

This publication describes the functional characteristics of the IBM 4955 Processor and the features associated with this processor. It assumes that the reader understands data processing terminology and is familiar with binary and hexadecimal numbering systems. The publication is intended primarily as a reference manual for experienced programmers who require machine code information to plan, correct, and modify programs written in the assembler language.

SUMMARY OF PUBLICATION

- Chapter 1. Introduction is an introduction to the system architecture. It contains a general description of the processor, storage, features, and a list of attachable I/O devices.
- Chapter 2. Processing Unit Description contains a description of the processor hardware including registers and indicators. The section on indicators includes examples of indicator results when dealing with signed and unsigned numbers.

Main storage data formats and addressing are presented in this chapter.

A section titled "Program Execution" is included and covers:

- Basic instruction formats
- Effective address generation
- Processor state control
- Initial program load (IPL)
- Jumping and branching
- Level switching and interrupts
- Stack operations
- Chapter 3. Interrupts and Level Switching describes the priority interrupt levels and the interrupt processing for (1) I/O devices, and (2) class interrupts. Related topics are:
 - Program controlled level switching
 - Interrupt masking facilities
 - Recovery from error conditions
- Chapter 4. Console describes the keys, switches, and indicators for the basic console and the optional programmer console. Typical manual operations such as storing into and displaying main storage are presented.
- Chapter 5. Instructions describes the basic instruction set, including indicator settings and possible exception conditions. Individual instruction word formats are included and contain bit combinations for the operation code and function fields. The instructions are arranged in alphabetical sequence based on assembler mnemonics.

- Chapter 6. Floating-Point Feature describes the optional floating-point feature including the floating-point instruction set.
- Chapter 7. Input/Output Operations describes the I/O commands and control words that are used to operate the I/O devices. Condition codes and status information relative to the I/O operation are also explained. Specific command and status-word bit structures are contained in the I/O device description books.
- Chapter 8. Storage Protection describes the operation of the storage protection mechanism.
- Chapter 9. Storage Address Relocation Translator Feature describes the optional relocation translator feature including:
 - Relocation addressing
 - Effects on storage protection mechanism
 - Error recovery considerations
- Chapter 10. Timer Feature describes the optional timer feature including:
 - Data flow within the attachment
 - I/O commands
 - Condition codes and status information
- Chapter 11. Teletypewriter Adapter Feature describes the use of this optional attachment with an input or output device. The topics covered are:
 - Bit transfer rates
 - I/O commands
 - Condition codes and status information
- Chapter 12. Integrated Digital Input/Output Non-Isolated Feature provides a description of the commands and operations associated with this feature.
- Chapter 13. IBM 4999 Battery Backup Unit describes the components and operation of this feature.
- Appendixes:
 - Instruction execution times
 - Instruction formats
 - Assembler syntax
 - Numbering systems and conversion tables
 - Character codes

RELATED PUBLICATIONS

- IBM Series/1 System Summary, GA34-0035.
- IBM Series/1 Physical Planning Manual, GA34-0029.
- IBM Series/1 4964 Diskette Unit Description, GA34-0023.
- IBM Series/1 4962 Disk Storage Unit Description, GA34-0024.
- IBM Series/1 4974 Printer Description, GA34-0025.
- IBM Series/1 4979 Display Station Description, GA34-0026.
- IBM Series/1 4982 Sensor Input/Output Unit Description, GA34-0027.
- IBM Series/1 Communications Features Description, GA34-0028.
- IBM Series/1 User's Attachment Manual, GA34-0033.

The IBM 4955 Processor is a compact, general purpose computer and has the following general characteristics:

- Four priority interrupt levels-independent registers and status indicators for each level. Automatic and program controlled level switching.
- FET (field effect transistor) main storage-16K bytes basic. Additional storage available in 16K increments (128K bytes maximum). Read or write time is 300 nanoseconds (660 nanoseconds required between two storage access cycles). Odd parity by byte is maintained throughout storage.
- TTL (transistor-transistor logic) processor technology.
- Microprogram control-microcycle nanoseconds.
- Instruction set that includes: stacking and linking facilities, multiply and divide, variable field-length byte operations, and a variety of arithmetic and branching instructions.
- Supervisor and problem states.
- Packaged in a 19-inch rack mountable unit-full width.
- Basic console standard in processor unit. Programmer console optional.
- Channel capability.
 - Asynchronous, multidropped channel.
 - 256 I/O (input/output) devices can be addressed.
 - Direct program control and cycle steal operations.
 - Maximum aggregate burst data rate is 1.6 megabytes (800K words) per second. When multiple cycle stealing devices are interleaved, the aggregate data rate is also 1.6 megabytes per second.

The processor unit contains power and space for additional features and storage. The IBM 4959 Input/Output Expansion Unit is available for additional features.

The processor unit is described in the following sections of this chapter.

IBM 4955 PROCESSOR

Processor Optional Features

- Storage Address Relocation Translator (permits addressing of main storage larger than 64K bytes).
- Storage Addition-16,384 bytes.
 - provides additional storage in 16K byte increments.
 - without storage address relocation translator: an additional 48K bytes (64K bytes total for processor).
 - with storage address relocation translator: 64K bytes beyond normal expansion (128K bytes total for processor).
- Programmer Console.
- Floating-Point.

Processor Description

The basic IBM 4955 Processor includes the processor, 16K bytes of storage, and a basic console. These items are packaged in a unit, called the processor unit. Figure 1-1 shows a block diagram of an IBM 4955 Processor and an IBM 4959 Input/Output Expansion Unit.




Figure 1-1. Block diagram of an IBM 4955 Processor and an IBM 4959 Input/Output Expansion Unit

The processor is microprogram controlled, utilizing a 220 nanosecond microcycle. Circuit technology is TTL (transistor-transistor logic).

Four priority interrupt levels are implemented in the processor. Each level has an independent set of machine registers. Level switching can occur in two ways: (1) by program control, or (2) automatically upon acceptance of an I/O interrupt request. The interrupt mechanism provides 256 unique entry points for I/O devices.

The processor instruction set contains a variety of instruction types. These include: shift, register to register, register immediate, register to (or from) storage, bit manipulation, multiple register to storage, variable byte field, and storage to storage. Supervisor and problem states are implemented, with appropriate privileged instructions for the supervisor.

A floating-point feature is available that supplements the standard instruction set. The floating-point instructions include single and double precision types for: add, subtract, multiply, divide, compare, and move.

The basic console is intended for dedicated systems that are used in a basically unattended environment. Only minimal controls are provided. A programmer console can be added as a feature; this console provides a variety of indicators and controls for operator-oriented systems.

Main storage technology is FET (field-effect transistor). Basic storage supplied is 16K bytes. The storage addition feature is additional storage in 16K byte increments. The maximum total storage is 64K bytes unless the storage address relocation translator feature is installed. This feature increases the addressing capability beyond 64K bytes. The maximum total storage in an IBM 4955 processor is 128K bytes. The read/write access time for main storage is 300 nanoseconds. However, the minimum duration of time between successive storage cycles is 660 nanoseconds. Storage protection is standard. It protects against (1) access (reading and writing) to defined blocks of storage by software or by an I/O operation, and (2) writing in an undesired location within a defined block by software.

I/O devices are attached to the processor through the processor I/O channel. The channel directs the flow of information between the I/O devices, the processor, and main storage. This channel accommodates a maximum of 256 addressable devices.


The channel supports:

- Direct program control operations. Each Operate I/O instruction transfers a byte or word of data between main storage and the device. The operation may or may not terminate in an interrupt.
- Cycle steal operations. Each Operate I/O instruction initiates multiple data transfers between main storage and the device (65,535 bytes maximum). Cycle steal operations are overlapped with processing operations and always terminate in an interrupt.
- Interrupt Servicing. Interrupt requests from the devices, along with cycle steal requests, are presented and polled on the interface concurrently with data transfers.


The processor is packaged in a standard 48.3 cm (19 inch) rack-mountable unit, called the processor unit. All processor units contain an integral power supply, fans, and the basic console. Refer to the Series/1 Physical Planning Manual, GA34-0029, for environmental characteristics. Two processor models are available. Figure 1-2 shows the IBM 4955 Processor Model A and Figure 1-3 shows the IBM 4955 Processor Model B.

IBM 4955 Processor Model A

This model occupies the full width of the standard rack. It has the capacity for up to 64K bytes of storage and eight I/O feature cards. The floating-point feature can be substituted for one of the I/O feature cards.



BR2960



4955 Model A Card Plugging Assignments


The A position is reserved for the I/O cables or (due to voltage limitations) one of the following I/O feature cards:

- Teletypewriter Adapter Feature using TTL voltage levels
- Teletypewriter Adapter Feature using isolated current loop where customer supplies external ±12V power
- Timer Feature
- Customer Direct Program Control Adapter Feature
- 4982 Sensor Input/Output Unit Attachment Feature
- Integrated Digital Input/Output Non-Isolated Feature
- Channel Repower Feature


Figure 1-2. IBM 4955 Processor Model A with a Programmer Console

IBM 4955 Processor Model B

This model occupies the full width of the standard rack. It has the capacity for up to 128K bytes of storage (including the storage address relocation translator feature) and three I/O feature cards. The floating-point feature can be substituted for one of the I/O feature cards.



BR2960



4955 Model B Card Plugging Assignments

The A position is reserved for the I/O cables or (due to voltage limitations) one of the following I/O feature cards:

- Teletypewriter Adapter Feature using TTL voltage levels
- Teletypewriter Adapter Feature using isolated current loop where customer supplies external ±12V power
- Timer Feature
- Customer Direct Program Control Adapter Feature
- 4982 Sensor Input/Output Unit Attachment Feature
- Integrated Digital Input/Output Non-Isolated Feature
- Channel Repower Feature

Figure 1-3. IBM 4955 Processor Model B with a Programmer Console

Input/Output Units and Features

- IBM 4962 Disk Storage Unit (4 models)
 - 4962 Disk Storage Unit Attachment Feature
- IBM 4964 Diskette Unit
 - 4964 Diskette Unit Attachment Feature
- IBM 4979 Display Station
 - 4979 Display Station Attachment Feature
- IBM 4974 Printer
 - 4974 Printer Attachment Feature
- Timers Feature (2 timers)
- Teletypewriter Adapter Feature
- Customer Direct Program Control Adapter Feature

The feature cards for attaching the I/O units can be housed in either the processor unit or the I/O expansion unit.

The timer feature and the teletypewriter adapter feature are described in separate chapters of this manual. Information about the other units can be found in separate publications. The order numbers for these publications are listed in the preface of this manual.

Communications Features

- Asynchronous Communications Single Line Control
- Binary Synchronous Communications Single Line Control
- Binary Synchronous Communications Single Line Control/High Speed
- Synchronous Data Link Control Single Line Control
- Asynchronous Communications 8 Line Control
- Asynchronous Communications 4 Line Adapter
- Binary Synchronous Communications 8 Line Control
- Binary Synchronous Communications 4 Line Adapter
- Communications Power Feature
- Communications Indicator Panel

Refer to the publication, *IBM Series/1 Communications Features Description*, GA34-0028, for a description of these features.

Sensor Input/Output Options

- Integrated Digital Input/Output Non-Isolated Feature
- IBM 4982 Sensor Input/Output Unit
 - 4982 Sensor Input/Output Unit Attachment Feature
- Features for the 4982 Sensor I/O Unit
 - Digital Input/Process Interrupt Non-Isolated
 - Digital Input/Process Interrupt Isolated
 - Digital Output Non-Isolated
 - Analog Input Control
 - Amplifier Multirange
 - Analog Input Multiplexer—Reed Relay
 - Analog Input Multiplexer-Solid State
 - Analog Output.

The integrated digital input/output non-isolated feature provides digital sensor I/O and simple original equipment manufacturer (OEM) access. The feature card can be housed in either the processor unit or the I/O expansion unit. The integrated digital input/output non-isolated feature is explained in Chapter 12.

The 4982 sensor input/output attachment unit feature card is housed in either the processor or the I/O expansion unit. Refer to the publication, Series/1 4982 Sensor Input/ Output Unit Description, GA34-0027, for a description of the 4982 and associated features.

Packaging and Power Options

- IBM 4959 Input/Output Expansion Unit
- IBM 4999 Battery Backup Unit
- IBM 4997 Rack Enclosure

The IBM 4959 Input/Output Expansion Unit is available for adding I/O feature cards beyond the capacity of the processor unit. The capacity of the I/O expansion unit is either (1) fourteen I/O feature cards, or (2) thirteen I/O feature cards plus a channel repower card. A channel repower card is required to power each additional I/O expansion unit.

The IBM 4999 Battery Backup Unit permits the processor unit (excluding external devices) to operate from a user-supplied battery when a loss or dip in line power occurs. The battery backup unit is explained in Chapter 13.

Other Options

Additional options such as communications cables, customer access panel, and a channel socket adapter are also available. For a list and description of system units and features, refer to the Series/1 System Summary, GA34-0035.

Figure 2-1 shows the general data flow for the IBM 4955 Processor. The major functional units shown in the data flow are discussed in the following sections.

MAIN STORAGE

Main storage holds data and instructions for applications to be processed on the system. The data and instructions are stored in units of information called a byte. Each byte consists of eight binary data bits. Associated with each byte is a parity bit. Odd parity by byte is maintained throughout storage; even parity causes a machine check error. Formats shown in this manual exclude the parity bit(s) because they are not a part of the data flow manipulated by the instructions.

The bits within a byte are numbered consecutively, left to right, 0 through 7. When a format consists of multiple bytes, the numbering scheme is continued; for example, the bits in the second byte would be numbered 8 through 15. Leftmost bits are sometimes referred to as high-order bits and rightmost bits as low-order bits.

Bytes can be handled separately or grouped together. A word is a group of two consecutive bytes, beginning on an even address boundary, and is the basic building block of instructions. A doubleword is a group of four consecutive bytes beginning on an even address boundary.

By	/te							
0	0	0	0	0	0	0	1	
\overline{a}							7	•

W	ord														
0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0
0							7	8							15

Addressing Main Storage

Each byte location in main storage is directly addressable. Byte locations in storage are numbered consecutively, starting with location zero; each number is considered the address of the corresponding byte. Storage addresses are 16-bit unsigned binary numbers. This permits a direct addressing range of 65,536 bytes:


Address Range		
16-bit binary address	Hexadecimal	Decimal
0000 0000 0000 0000	0000	0
to	to	to
1111 1111 1111 1111	FFFF	65,535

Note: Addresses that overflow or underflow the addressing range address wrap modulo 65,536.

When the Storage Address Relocation Translator Feature is installed, the 16-bit address is used as a logical address to generate a 24-bit physical address.

Instruction and Operand Address Boundaries

As previously stated, all storage addressing is defined by byte location. Instructions can refer to bits, bytes, byte strings, words, or doublewords as data operands. All word and doubleword operand addresses must be on even byte boundaries. All word and doubleword operand addresses point to the most significant (leftmost) byte in the operand. Bit addresses are specified by a byte address and a bit displacement.



Legend:

AKR - Address key register
ALU - Arithmetic and logic unit

I/O address bus (16 bits)

CIAR - Current instruction address register

CS - Cycle steal Ctr - Counter

IAR - Instruction address register
LSR - Level status register
Mask - Interrupt level mask register

Op - Operation register

Proc - Processor

PSW — Processor status word
SAR — Storage address register
SDR — Storage data register
WA — Work/shift register
Y — Work/shift register
Z — Console data

Figure 2-1. Data flow for the IBM 4955 Processor

I/O address bus (16 bits)

To provide maximum addressing range, some instructions refer to a word displacement that is added to the contents of a register. In these cases, the operand is a word and the register must contain an even byte address for valid results. Effective address generation is described in a subsequent section of this chapter.

All instructions must be on an even byte boundary. This implies that the effective address for all branch type instructions must be on an even byte boundary to be valid.

If any of the aforementioned rules are violated, a program check interrupt occurs with *specification check* set in the processor status word (PSW). The instruction is suppressed.

REGISTERS

Registers in the processor are provided in two categories:

- 1. Per-level register (the register is duplicated for each priority interrupt level)
- 2. Per-system register (the register is provided only once and is used by all priority interrupt levels)

Information that must be saved when a level is preempted is retained in registers supplied for a specific level. Information that pertains only to the current process is kept in registers common to all levels. The registers in each category are listed in this section. Descriptions for each of the registers appear in subsequent sections. Only registers accessible to the program or the operator (via console operations) are discussed.

Registers supplied on a per-system basis:

- Console address key register
- Console data buffer
- Current-instruction address register (CIAR)
- Mask register (interrupt level)
- Processor status word (PSW)
- Segmentation registers (optional) see Chapter 9, Storage Address Relocation Translator Feature.
- Storage address register (SAR)

Registers supplied on a per-level basis:

- Address key register (AKR)
- Floating-point registers (optional) see Chapter 6. Floating-Point Feature.
- General registers (8 per level)
- Instruction address register (IAR)
- Level status register (LSR)

Note. For a specific level, the contents of the AKR, IAR, LSR, and the general registers are known as a level status block (LSB). The LSB is a 22 byte entity used by hardware and software for task control and task switching.

Console Address Key Register

The Console AKR is not addressable by software. When the programmer console is installed, this register is used for certain console operations. Refer to *Programmer Console* in Chapter 4.

Console Data Buffer

The console data buffer is a 16-bit register associated with the programmer console feature. Details of how the buffer is used are explained in the programmer console section of Chapter 4. The contents of the console data buffer can be loaded into a specified general register by using the Copy Console Data Buffer (CPCON) instruction (see Chapter 5).

Current-Instruction Address Register (CIAR)

When the processor enters the stop state, the current-instruction address register (CIAR) contains the address of the last instruction that was executed. The CIAR is not addressable by software. It may be displayed from the optional programmer console. Refer to *Stop State* in this chapter for methods of entering stop state.

Mask Register

The mask register is a 4-bit register used for control of interrupts. Bit 0 controls level 0, bit 1 controls level 1, and so on.

A one bit enables interrupts on a level, while a zero bit disables interrupts. For example if bit 3 is set to a one, interrupts are enabled on level 3.

Processor Status Word (PSW)

The processor status word (PSW) is a 16-bit register used to (1) record error or exception conditions that may prevent further processing, and (2) hold certain flags that aid in error recovery. Error or exception conditions recorded in the PSW result in a class interrupt. Each bit in the PSW is described in detail in Chapter 3. The PSW can be accessed by using the Copy Processor Status and Reset (CPPSR) instruction (see Chapter 5).

The contents of the PSW are as follows:

Bit	Contents
0	Specification check
1	Invalid storage address
2	Privilege violate
3	Protect check
4	Invalid function
5	Floating-point exception
6	Stack exception
7	(not used, always zero)
8	Storage parity check
9	(not used, always zero)
10	CPU control check
11	I/O check
12	Sequence indicator
3	Auto-IPL
14	Translator enabled
15	Power/thermal warning

Storage Address Register (SAR)

The storage address register (SAR) is a 16-bit register that contains the main-storage address for the last attempted processor storage cycle. This register is addressable by the Diagnose instruction and may be altered or displayed from the optional programmer console.

Address Key Register (AKR)

The address key register (AKR) is a 16-bit register that contains three address keys and an address-key control bit. This register is associated with the storage protection mechanism. Separate 3-bit fields contain an address key for (1) instruction address space, (2) operand-1 address space, and (3) operand-2 address space. Refer to Storage Protection and Address Space Management in Chapter 8 for further information.

Bits	Contents
0	Equate operand spaces
1	(not used, always zero)
2	(not used, always zero)
3	(not used, always zero)
4	(not used, always zero)
5	Operand-1 key (bit 0)
6	Operand-1 key (bit 1)
7	Operand-1 key (bit 2)
8	(not used, always zero)
9	Operand-2 key (bit 0)
10	Operand-2 key (bit 1)
11	Operand-2 key (bit 2)
12	(not used, always zero)
13	Instruction space key (bit 0)
14	Instruction space key (bit 1)
15	Instruction space key (bit 2)

General Registers

Subsequently referred to simply as registers, the general registers are 16-bit registers available to the program for general purposes. Eight registers are provided for each level. The R and RB fields in the instructions control the selection of these registers:

R or RB* field value	Register selected
000	Register 0
001	Register 1
010	Register 2
011	Register 3
100	Register 4
101	Register 5
110	Register 6
111	Register 7

*The RB field sometimes contains only the two low-order bits. In this case, registers 4 through 7 cannot be specified.

Instruction Address Register (IAR)

The instruction address register (IAR) is a 16-bit register that holds the main storage address used to fetch an instruction. After an instruction has been fetched, the IAR is updated to point to the next instruction to be fetched.

Note. These registers are sometimes referred to as IAR0, IAR1, IAR2, and IAR3. The numbers represent the priority level associated with the register.

Level Status Register (LSR)

The level status register (LSR) is a 16-bit register that holds the following information for its associated level:

Contents 0 Even indicator 1 Carry indicator 2 Overflow indicator 3 Negative result indicator 4 Zero result indicator 5 (not used, always zero) (not used, always zero) 6 7 (not used, always zero) 8 Supervisor state In process 10 Trace 11 Summary mask 12 (not used, always zero) (not used, always zero) 13 14 (not used, always zero) 15 (not used, always zero)

Indicators (bits 0-4). These bits are set to reflect the result of certain types of instructions; for example: arithmetic, logical, move, and shift instructions. Bits 0, 1, and 2 are also used to hold the condition code following an Operate I/O instruction or after an I/O interrupt. See Arithmetic and Logic Unit in this chapter for additional information about the indicators. Also, specific indicator information for each instruction is provided in Chapter 5.

Supervisor State (bit 8). This bit when set to one indicates that the processor is in the supervisor state. This state allows privileged instructions to be executed. It is set by any of the following:

- 1. Class interrupt
 - a. Machine check condition
 - b. Program check condition
 - c. Power/thermal warning
 - d. Supervisor Call (SVC) instruction
 - e. Soft exception trap condition
 - f. Trace
 - g. Console interrupt
- 2. I/O interrupt
- 3. Initial program load (IPL)

The supervisor state bit can be altered by a Set Level Block (SELB) instruction. For additional information, refer to *Processor State Control* in this chapter.

Class interrupts and I/O interrupts are described in Chapter 3. IPL is discussed in a subsequent section of this chapter.

In Process (bit 9). This bit, when set to one, indicates that a level is currently active or was preempted by a higher priority level before completing its task. Bit 9 is turned off by a Level Exit (LEX) instruction. Bit 9 can also be turned on or off by a Set Level Block (SELB) instruction. Refer to Chapter 3. Interrupts and Level Switching.

Trace (bit 10). This bit, when set to one, causes a trace class interrupt at the beginning of each instruction. The bit can be turned on or off with the Set Level Block (SELB) instruction. The trace bit aids in debugging programs. See *Class Interrupts* in Chapter 3.

Summary mask (bit 11). This bit, when set to zero (disabled), inhibits all priority interrupts on all levels. When this bit is set to one (enabled), normal interrupt processing is allowed. Refer to Summary Mask in Chapter 3 for details relating to control of the summary mask.

ARITHMETIC AND LOGIC UNIT (ALU)

The arithmetic and logic unit (ALU) contains the hardware circuits that perform: addition; subtraction; and logical operations such as AND, OR, and exclusive OR. The ALU performs address arithmetic as well as the operations required to process the instruction operands. Operands may be regarded as signed or unsigned by the programmer. However, the ALU does not distinguish between them. Numbering representation is discussed in a subsequent section of this chapter. For many instructions, indicators are set to reflect the result of the ALU operation. The indicators are discussed in a subsequent section of this chapter.

NUMBERING REPRESENTATION


Operands may be signed or unsigned depending on how they are used by the programmer. An unsigned number is a binary integer in which all bits contribute to the magnitude. A storage address is an example of an unsigned number. A signed number is one where the high-order bit is used to indicate the sign, and the remaining bits define the magnitude. Signed positive numbers are represented in true binary notation with the sign bit (high-order bit) set to zero. Signed negative numbers are represented in two's complement notation with the sign bit (high-order bit) set to one. The two's complement of a number is obtained by inverting each bit of the number and adding a one to the low-order bit position. Two's complement notation does not include a negative zero. The maximum positive number consists of an all-one integer field with a sign bit of zero; whereas, the maximum negative number (the negative number with the greatest absolute value) consists of an all-zero integer field with a one-bit for the sign.

The following examples show: (1) an unsigned 16-bit number, (2) a signed 16-bit positive number, and (3) a signed 16-bit negative number.

Example of an unsigned 16-bit number:


Decimal value Hexadecimal value 65535 FFFF (The largest unsigned number representable in 16 bits.)

Example of a signed 16-bit positive number:




Decimal value Hexadecimal value +32767 7FFF (The largest positive signed number representable in 16 bits.)

When the number is positive, all bits to the left of the most significant bit of the number, including the sign bit, are zero:




Example of a signed 16-bit negative number:




Note. This form of representation yields a negative range of one more than the positive range.

When the number is negative, all bits to the left of the most significant bit of the number, including the sign bit, are set to one:



When a signed-number operand must be extended with high-order bits, the expansion is achieved by prefixing a field in which each bit is set equal to the high-order bit of the operand.

Example of an 8-bit field extended to a 16-bit field:



It must be emphasized that when performing the add and subtract operations, the machine does not regard the number as either signed or unsigned, but performs the designated operation on the values presented. Whether a given add or subtract operation is to be regarded as a signed operation or an unsigned operation is determined by the programmer's view of the values being presented as operands. The carry indicator and the overflow indicator of the LSR are changed on various operations to reflect the result of that operation. This allows the programmer to make result tests for the number representation involved. The carry and overflow indicator settings are explained in the following section.

INDICATORS

The indicators are located in bits 0-4 of the level status register (LSR). Bits 5-7 of the LSR are not used and should be zero. Figure 2-2 shows the indicators and how they are set. The indicator bits are changed or not changed depending on the instruction being executed. Some instructions do not affect the indicators, other instructions change all of the indicators, and still other instructions change only specific indicators. Refer to the individual instruction descriptions in Chapter 5 for the indicators changed by each instruction.




Figure 2-2. How indicators are set for signed and unsigned (logical) operations

The indicators are changed in a specialized manner for certain operations. These operations are described briefly. Additional information is provided in subsequent sections for those operations where more detail is required.

- Add, subtract, or logical operations. The even, negative, and zero indicators are result indicators. For add and subtract operations, the carry and overflow indicators are changed to provide information for both signed and unsigned number representations.
- Multiply and divide operations. Signed number operands are always assumed for these operations. The carry indicator is used to provide a divide by zero indication for the divide instruction. The overflow indicator defines an unrepresentable product for multiply operations. Refer to the individual instruction descriptions in Chapter 5.
- Priority interrupts and input/output operations. The even, carry and overflow indicators are used to form a three-bit condition code that is set as a binary value.
- Compare operations. The indicators are set in the same manner as a subtract operation.
- Shift operations. The carry and overflow indicators have a special meaning for shift left logical operations.
- Complement operations. The overflow indicator is set if an attempt is made to complement the maximum negative number. This number is not representable.

- Set Indicators (SEIND) and Set Level Block (SELB) instructions. All indicators are changed by the data associated with these instructions.
- Floating-point operations. The optional floating-point instructions set the indicators as described in Chapter 6, Floating-Point Feature.

Even, Negative, and Zero Result Indicators.

The even, negative, and zero indicators are called the result indicators. A positive result is indicated when the zero and negative indicators are both off (set to zero). These indicators are set to reflect the result of the last arithmetic, or logical operation performed. A logical operation in this sense includes data movement instructions. See the individual instruction descriptions in Chapter 5 for the indicators changed for specific instructions.

Even, Carry, and Overflow Indicators—Condition Code for Input/Output Operations

The even, carry, and overflow indicators contain the I/O condition code: (1) following the execution of an Operate I/O instruction and (2) following and I/O interrupt.

These indicators are used to form a three-bit binary number that results in a condition code value.

Indica	itors		Condition code
Even	Carry	Overflow	value
0	0	0	0
0	0	1	1
0	1	0	2
0	1	1	3
1	0	0	4
1	0	1	5
1	1	0	6
1	1	1	7

For additional information about condition codes, refer to:

- Branch on Condition Code (BCC) and Branch on Not Condition Code (BNCC) instructions in Chapter 5.
- 2. Condition codes in Chapter 7.

Carry and Overflow Indicators—Add and Subtract Operations

A common set of add and subtract integer operations performs both signed and unsigned arithmetic. Whether a given add or subtract operation is to be regarded as a signed operation or an unsigned operation is determined by the programmer's view of the values being presented as operands. The carry and overflow indicators are set to reflect the result for both cases. The following sections explain the meaning of these indicators for (1) signed numbers and (2) unsigned numbers. Following these two sections, examples are provided for setting the carry indicator and for setting the overflow indicator.

Signed Numbers

For signed addition and subtraction, the overflow indicator signals a result that exceeds the representation capability of the system for the result operand size. When overflow is indicated, the carry indicator and the resulting operand together form a valid result with the carry indicator being the most significant bit. For addition, the carry indicator is the sign (high-order bit) of this result. For subtraction, the carry indicator is the complement of the sign (high-order bit) of the result. A negative result appears in two's complement form. When no overflow is indicated, the carry indicator provides no information about the result.

Figure 2-3 shows how the carry and overflow indicators are set for an add operation when using 16-bit operands. Figure 2-4 provides the same information for a subtract operation.

SIGNED NUMBERS

ADD OPERATION-All possible results (16-bit example)


Indicators		Result v		
Overflow	Carry	Hexadecimal	Decimal	
1		0000 7FFF 8000 	-65536 -32769 -32768	(see note)
	1	FFFE FFFF 0000	-2 -1 0	16-bit represent- able range
1		7FFF 8000 FFFE	+32767 +32768 +65534	(see note)
Note William				/

Note. When overflow occurs, the carry indicator and the result together form a valid 17-bit signed number, of which the carry is the sign, and the result is the magnitude. A negative result is in two's complement form. When no overflow occurs, no useful information is provided by the carry indicator.

Figure 2-3. All possible results of an add operation regarding the operands as signed 16-bit numbers

SIGNED NUMBERS

SUBTRACT OPERATION-All possible results (16-bit example)



- When overflow occurs, the carry indicator and the result form a
 valid 17-bit signed number, of which the carry is the
 complement of the correct sign, and the result is the magnitude.
 A negative result is in two's complement form. When no
 overflow occurs, no useful information is provided by the carry
 indicator.
- 2. The carry indicator may be on or off depending on the operands.

Figure 2-4. All possible results of a subtract operation regarding the operands as signed 16-bit numbers

Unsigned Numbers

For unsigned addition and subtraction, the carry indicator signals that:

- 1. On an add instruction, a carry out of the high-order bit position has occurred (result exceeds result operand size). The carry indicator and the resulting operand together form a valid result of which the carry indicator is the most significant bit.
- 2. On a subtract operation, a borrow beyond the high-order bit position has occurred. A borrow during a subtract operation is defined as either of the following:
 - a. No carry is generated out of the high-order bit position when a two's complement of the subtrahend and add is performed to accomplish the subtract operation.
 - b. The most significant digit of the minuend must be made larger to generate a difference of zero or one when subtracting the most significant digit of the subtrahend; for example, 1 subtracted from 0.

When a borrow is signalled on a subtract operation, the result is in two's complement form.

The overflow indicator provides no useful information about unsigned operations.

Figure 2-5 shows how the carry and overflow indicators are set for an add operation when using 16-bit operands. Figure 2-6 provides the same information for a subtract operation.

UNSIGNED NUMBERS

ADD OPERATION-All possible results (16-bit example)

Indicators		Result ve		
Overflow Carry		Hexadecimal	Decimal	
(note 2)		0000	0)
		•		
		7FFF	32767	16-bit
		8000	32768	representable
		•		range
		•		
		FFFE	65534	i
		FFFF	65535	,
	1	0000	65536)
		•		17-bit range
		•	00202	-
	- 1	7FFF	98303	using carry bit
		8000	98304	(see note 1)
	1	•		1
	∀ 1	FFFE	131070	<i>)</i>


Notes.

- 1. With the carry indicator on, the result and carry form a valid 17-bit unsigned number of which the carry is the most significant bit.
- The overflow indicator may be set; however, it provides no useful information.

Figure 2-5. All possible results of an add operation regarding the operands as unsigned 16-bit numbers

UNSIGNED NUMBERS

SUBTRACT OPERATION—All possible results (16-bit example)



Notes.

- With carry (borrow) on, the result and carry indicator form a valid 17-bit negative number of which the carry is the sign and result is the magnitude in normal two's complement form.
- The overflow indicator may be set; however, it provides no useful information.

Figure 2-6. All possible results of a subtract operation regarding the operands as unsigned 16-bit numbers

Carry Indicator Setting

The carry indicator is used to signal overflow of the result when operands are presented as unsigned numbers. The machine does not regard the numbers as either signed or unsigned, but performs the designated operation (add or subtract) on the values presented. The programmer must interpret the condition of the result for the number representation involved. The machine detects the carry condition during the operation in two ways:

- 1. Add operation—when a carry out of the high-order bit position of the result operand occurs.
- 2. Subtract operation—when a borrow beyond the high-order bit position of the result operand occurs.

Add operation examples. A four-bit operand size is used in the following examples. Note that the unsigned number range for this operand is 0 to 15. No other unsigned number values may be represented for this size operand.

• Addition (carry indicator is not set)

Desired operation: 6 + 9 = 15

Machine operation: Augend 0110

Addend 1001

Result 1111

High-order bit carry = 0

The result fits as an unsigned number. The carry indicator is not set (C=0).

• Addition (carry indicator is set)

Desired operation: 15 + 1 = 16

Machine operation: Augend 1111

Addend 0001

Result 0000

High-order bit carry = 1

Result does not fit as an unsigned number. The carry indicator is set (C-1).

Addition (carry indicator is set)

Desired operation: 15 + 15 = 30

Machine operation: Augend 1111

Addend 1111

Result 1110

High-order bit carry = 1

Result does not fit as an unsigned number. The carry indicator is set (C=1).

Note. The result of adding the two largest numbers can be contained in the operand size and the carry indicator. The carry indicator represents the most significant bit.

Subtract operation examples. The processor performs subtraction by using the complement addition method. The second operand is complemented (two's complement) then an add operation is performed. This is actually a three-way add operation between the minuend, the subtrahend (one's complement), and a constant of one. To provide the correct carry (borrow) indication for the subtraction, the carry result of the complement add operation must be inverted to determine the carry indicator setting. The following examples use a four-bit operand with an unsigned number range of 0 to 15.

• Subtract (carry indicator is not set)

Desired operation: 15 - 1 = 14

Machine operation: Minuend 1111

Subtrahend 1110 one's complement Constant 1 for two's complement

Result 111

High-order bit carry = 1 invert for carry indicator

The result fits as an unsigned number. The carry indicator is not set (C=0).

Note. The carry indicator setting (C=0) for this subtract operation was determined by inverting the complement-add carry.

• Subtract (carry indicator is not set)

Desired operation: 15 - 15 = 0

Machine operation: Minuend 1111

Subtrahend 0000 one's complement
Constant 1 for two's complement

Result 0000

High-order bit carry = 1 invert for carry indicator

The result fits as an unsigned number. The carry indicator is not set (C=0).

• Subtract (carry indicator is set)

The following two examples show the case of a negative result (subtrahend greater than minuend). This negative result cannot be represented in the operand width because all operand bits are used to represent the unsigned number. To flag this condition the carry indicator is set.

Example 1.

Desired operation: 0-1=-1

Machine operation: Minuend 0000

Subtrahend 1110 one's complement
Constant 1 for two's complement

Result 1111

High order bit carry = 0 invert for carry indicator

The result does not fit as an unsigned number. The carry

indicator is set (C=1).

Example 2.

Desired operation: 0-15=-15

Machine operation: Minuend 0000

Subtrahend 0000 one's complement
Constant 1 for two's complement

Result 0001

High-order bit carry = 0 invert for carry indicator

The result does not fit as an unsigned number. The carry

indicator is set (C=1).

Note. When a negative result occurs on a subtract operation, the values may be useful to the programmer. The carry indicator and the result form a signed number. The carry indicator is the sign and the result is the number in two's complement form (see Figure 2-6).

Overflow Indicator Setting

The overflow indicator is used to signal overflow of the result when the operands are presented as signed numbers. The machine does not regard the numbers as either signed or unsigned, but performs the designated operation (add or subtract) on the values presented. The programmer must interpret the condition of the result for the number representation involved. The machine detects this condition by inspection of any carry into and out of the high-order bit (sign position) of the result operand during the operation. The overflow indicator is set (O = 1) for the two cases where the carries disagree:

- 1. A carry into, but no carry out of the sign position
- 2. No carry into, but a carry out of the sign position.

The overflow indicator is not set (O = 0) for the remaining two cases where the carries agree:

- 1. A carry into and out of the sign position.
- 2. No carry into and no carry out of the sign position.

Examples. A four-bit operand size is used in the following examples. Note that the signed number range for a four-bit operand is -8 to +7. No other signed number values may be represented.

• Addition (overflow indicator is not set)

Desired operation: +5 + (+2) = +7

Machine operation: Augend

Addend 0010 0111 Result

Carry into sign position = 0

carries agree Carry out of sign position = 0

The result fits as a signed number. The overflow indicator is not set (O = 0).

Desired operation: -4 + (-4) = -8

1100 two's complement Machine operation: Augend

Addend 1100 two's complement

two's complement 1000 Result

Carry into sign position = 1

Carry out of sign position = 1carries agree

The result fits as a signed number. The overflow indicator is not set (O = 0).

Addition (overflow indicator is set)

Desired operation: +4 + (+4) = +8

Machine operation: Augend 0100

0100 Addend

1000 Result

Carry into sign position = 1

carries disagree Carry out of sign position = 0

The result does not fit as a signed number. The overflow

indicator is set (O = 1).

Desired operation: -4 + (-5) = -9

1100 two's complement Machine operation: Augend

1011 two's complement Addend

0111 Result

Carry into sign position = 0

carries disagree Carry out of sign position = 1

The result does not fit as a signed number. The overflow

indicator is set (O = 1).

Subtraction (overflow indicator is not set)

Desired operation: +7 - (+2) = +5

Machine operation: Minuend

Subtrahend 1101 one's complement 1 for two's complement Constant

0101 Result

Carry into sign position = 1

carries agree Carry out of sign position = 1

The result fits as a signed number. The overflow indicator is not

set (O = 0).

Desired operation: +5 - (-1) = +6

Note. -1 is equal to 1111

Machine operation: Minuend

0000 one's complement Subtrahend 1 for two's complement

Constant 0110

Carry into sign position = 0

Carry out of sign position = 0carries agree

Result

The result fits as a signed number. The overflow indicator is not

set (O = 0).

Subtraction (overflow indicator is set).

Desired operation: +7 - (-2) = +9

Note. -2 is equal to 1110

Machine operation: Minuend 0111

0001 one's complement Subtrahend 1 for two's complement Constant

1001 Result

Carry into sign position = 1

carries disagree Carry out of sign position = 0

The result does not fit as a signed number. The overflow

indicator is set (O = 1).

Desired operation: -3 - (+6) = -9

Machine operation: Minuend 1101 two's complement

Subtrahend 1001 one's complement 1 for two's complment Constant

0111 Result

Carry into sign position = 0

Carry out of sign position = 1 carries disagree

The result does not fit as a signed number. The overflow

indicator is set (O = 1).

Carry and Overflow Indicator—Shift Operations

The carry and overflow indicators are changed only for shift left logical operations and shift left and test operations. These operations affect the indicators as follows:

- 1. The carry indicator is set to reflect the value of the last bit shifted out of the target register (register where bits are being shifted).
- 2. The overflow indicator is set to one if bit-0 of the target register was changed during the shift. Otherwise it is set to zero.

Testing Indicators with Conditional Branch and Jump Instructions

The indicators are tested according to a selected condition when a conditional branch or a conditional jum instruction is executed. The conditions and the indicator tested for each condition are shown in Figure 2-7.

The conditional instructions are:

- Branch on Condition (BC)
- Branch on Not Condition (BNC)
- Jump on Condition (JC)
- Jump on Not Condition (JNC)

The assembler also provides extended mnemonics for the conditions shown in Figure 2-7. Refer to the individua instructions in Chapter 5.

			Indicators tested						
Condition tested by conditional branch or jump instruction	Assembler extended	0	Ĺ	2					
jump instruction	mnemonics	E	0		N	Z			
Zero or equal	BE, BZ, JE, JZ	T	Γ	Τ	Τ	1			
Not zero or unequal	BNE, BNZ, JNE, JNZ	T		T	T	0			
Positive and not zero	BP, JP	\top			0	0			
Not positive	BNP, JNP		Ī		1	1			
Negative	BN, JN			T	1	_			
Not negative	BNN, JNN	_	T	†-	0				
Even	BEV, JEV	1	H	\vdash	-	-			
Not even	BNEV, JNEV	0	 	<u> </u>	-				
Arithmetically less than	BLT, JLT			0	1				
Arithmetically less than or equal	BLE, JLE			0 1	1 0	1			
Arithmetically greater than or equal	BGE, JGE			1 0	1				
Arithmetically greater than	BGT, JGT			1	1 0	0			
Logically less than or equal	BLLE, JLLE		1			1			
Logically less than (carry)	BLLT, JLLT		1		_	_			
Logically greater than	BLGT, JLGT	$ \cdot $	0	_	\dashv	0			
Logically greater than or equal (no carry)	BLGE, JLGE		0						

Legend:	LSR bit	Indicator
	· 0	E - Even
	1	C - Carry
	2	O – Overflow
	3	N - Negative
	4	Z - Zero

Figure 2-7. Indicators tested by conditional branch and jump instructions

Indicators Affected By Compare Operations

A compare operation sets the indicators in the same manner as a subtract operation. The even, negative, and zero indicators reflect the result. The carry and overflow indicators are set as described previously.

Compare instructions provide a test between two operands (without altering either operand) so that conditional branch and jump instructions may be used to control the programming logic flow. The conditions specified in branch and jump instructions are named such that, when the condition of the "subtracted from" operand relative to the other operand is true the jump or branch occurs. Otherwise, the next sequential instruction is executed. This is illustrated in the following example.

• Compare operation example

Instruction Assembler Operands mnemonic name CW R3, R4 Compare word Operation code Function R1R20 1 1 1 0 1 0 0 0 0 1 0 1 1 1 10 11

R3


In this example, the contents of register 3 are subtracted from register 4:

R4

2. 0 0					Decimal Unsigned	Signed
R4 contents	0000	0000	0000	0010	2	+2
R3 contents					65531	- 5
Subtract resu	ılt				-65529	+7
Machine ope	ration	;				
Minuend	0000	0000	0000	0010		
Subtrahend	0000	0000	0000	0100	one's comp	
Constant				1	for two's co	mplement

Result 0000 0000 0000 0111

Indicator Settings:



If the programmer is comparing *unsigned* numbers, such as storage addresses, he should use the logical conditional tests. In this example, assuming unsigned number representation, R4 is logically less than R3 and unequal to R3. Therefore, the following branch instructions would cause a transfer to symbolic location A (assuming register values shown in the example).

CW R3,R4
BLLT A
or
CW R3,R4
BNE A

The complementary tests (BLGT and BE) would not cause a transfer in this case.

If the programmer is comparing signed numbers, he should use the arithmetic conditional tests. In the previous compare word example, assuming signed number representation, R4 is greater than R3 and unequal to R3. The following branch instructions would cause a transfer to symbolic location A.

CW R3,R4 BGT A or CW R3,R4 BNE A

The complementary tests (BLT and BE) would not cause a transfer.

Note. Jump instructions are also available for the logical and arithmetic conditional tests.

It must be emphasized again that the machine does not regard the numbers as either signed or unsigned. The compare word instruction results in a subtract operation being performed on the values presented. The programmer must then choose the correct conditional test (logical or arithmetic) for the number representation involved.

Indicators-Multiple Word Operands

A programmer may desire to work with numbers that cannot be represented in one word or in a doubleword. It may take three or more words to represent the number.

Certain register to register instructions allow the programmer to add or subtract these multi-word operands and then have the indicators reflect the multi-word result. These instructions are:

Add Carry Register (ACY) Add Word With Carry (AWCY) Subtract Carry Register (SCY) Subtract Word With Carry (SWCY)

The following two examples show how the add instructions are used. A subtract operation would be similar. See Chapter 5 for details of the individual instructions.

Example 1. (Equal length operands)

R1	R2	R3	Operand 1, Result
R4	R5	R6	Operand 2

Program steps:

R6,R3
R5,R2
R4,R1


Explanation:

Step 1: The contents of R6 are added to the contents of R3.

Step 2: The contents of R5 are added to the contents of R2 plus any carry from the previous operation.

Step 3: The contents of R4 are added to the contents of R1 plus any carry from the previous operation.

Example 2. (Unequal length operands)



Note. In this example, operand 2 must be an unsigned number or must be positive.

Program Steps:

AW	R6,R3
AWCY	R5,R2
ACY	R1

Explanation:

Step 1: The contents of R6 are added to the contents of R3.

Step 2: The contents of R5 are added to the contents of R2 plus any carry from the previous operation.

Step 3: Any carry from the previous operation is added to the contents of R1.

Note. In both examples the final indicator settings reflect the status of the 3-word result.

Even Set on if the result low-order bit of R3 is zero.

Carry Set on if the result cannot be represented as an unsigned 3-word number.

Overflow Set on if the result cannot be represented as a signed 3-word number.

Negative Set on if the result high-order bit of R1 is one. Zero Set on if all three result registers contain zeros.

PROGRAM EXECUTION


Instruction Formats

The processor instruction formats are designed for efficient use of bit combinations to specify the operation to be performed (operation code) and the operands that participate. Some formats also include (1) an immediate data field or word, (2) an address displacement or address word, and (3) a function field that further modifies the operation code. Various combinations of these fields are used by the individual instructions. Some typical instruction formats are presented in this section. All formats are shown in the section *Instruction Formats* in Appendix B.

One Word Instructions

The basic instruction length is one word (16 bits). The operation code field (bits 0-4) is the only common field for all formats. This field, unless modified by a function field, specifies the operation to be performed. For a format without a function field, bits 5-15 specify the location of operands or data associated with an operand:

Example:



Bits 0-4 Operation code (specifies ABI instruction).

Bits 5-7 General register (0-7).

This register contains data for the second operand.

Bits 8-15 Immediate data for the first operand.

In some cases the operation code is the same for a group of instructions. The format for this group includes a function field. The bit combinations in the function field then determine the specific operation to be performed.

Example:

Assembler Instruction Syntax mnemonic name AW Add Word reg,reg R2 Function R 1 Operation code 0 0 1 1 1 10 11 1.5 7 5

Word instruction.

Bits 0-4 Operation code for a group of instructions.

Bits 5-7 General register (0-7).

This register contains data for the first operand.

Bits 8-10 General register (0-7).

This register contains data for the second operand.

Bits 11-15 Function field.

Modifies the operation code to specify the Add


Note. For other instruction groups, the function field may vary as to location within the format, and also the number of bits used.

Two Word Instructions

The first word of this format is identical to the one-word format. The second word (bits 16-31) contains either immediate data, an address, or a displacement. This word is used to (1) provide data for an operand, or (2) provide a main storage address or displacement for effective address generation (see *Effective Address Generation* in this chapter).

Example:

Assembler Instruction mnemonic Syntax name BAL longaddr,reg Branch and Link Function R 2 X R1Operation code 0 0 1 1 0 15 10 11 12 8



Bits 0-4 Operation code.

Bits 5-7 General register (0-7) for the second operand.

Bits 8-10 General register (0-7) for the first operand.

Bit 11 Indirect addressing bit.

Bits 12–15 Function field.

Bits 16-31 A main storage address used for the first operand.

Note. In this example, the register designated R1 is associated with the second operand in assembler syntax.


Variable Length Instructions

Some instructions use a selectable encoded technique for generating effective addresses. This method is referred to as an address argument technique in subsequent sections. These instruction formats contain a base register (RB) field and an address mode (AM) field. If both operands are using this technique, the format contains an RB and associated AM field for each. These fields are in the first instruction word. The AM field consists of two bits and is referred to in binary notation (AM=00, 01, 10, or 11). If AM is equal to 10 or 11 an additional word is appended to the normal instruction word. For a format that contains two AM fields, two additional words may be appended. See Effective Address Generation in this chapter for a description of the appended words and how they are used.

For instructions with a single storage address argument, the RB field consists of two bits. An RB field of two bits with its associated AM field of two bits are referred to as a 4-bit address argument or addr4 in assembler syntax.

Example:

Instruction Assembler Syntax mnemonic name addr4, reg Compare byte CB R RBAMFunction Operation code 0 1 0 1 0 0 15 5 8 10 11 12



Bits 0-4 Operation Code.

Bits 5-7 General register (0-7) for the second operand.

Bits 8-9 Base register (0-3).

Bits 10-11 Address mode.

Bits 12–15 Function.

Bits 16-31 Appended word for the first operand.


Note. The register specified by the RB field is a general register that is used as a base register for effective address generation.


Some instruction formats have two storage address arguments. In this case, the first operand has a 3-bit RB field giving a 5-bit address argument (addr5 in assembler syntax) and the second operand has a 4-bit address argument.


Example:

Instruction Assembler menmonic Syntax
Add Word AW addr5,addr4

| Operation code | RB1 | RB2 | AM1 | AM2 | Fun |







Bits 0-4	Operation code.
Bits 5-7	Base register $(0-7)$ for the first operand.
Bits 8-9	Base register $(0-3)$ for the second operand.
Bits 10-11	Address mode for the first operand.
Bits 12-13	Address mode for the second operand.
Bits 14-15	Function.
Bits 16-31	Appended word for the first operand.
Bits 32-47	Appended word for the second operand.
	*

Notes.

- 1. If there is no appended word for the first operand (AM1=00 or 01), the second operand word is appended to the instruction word in bits 16-31.
- 2. Registers specified by the RB fields are general registers.

Names of Instruction Formats

Names have been established for several categories of instructions. Each category has the same basic instruction format, therefore, the name is related to the format. In most cases, the name indicates the location of the operands or the type of instruction.

Examples:

- Register/Register Instructions.
 General registers are used by both operands.
- Storage/Storage Instructions.
 Both operands reside in main storage.
- Register/Storage Instructions.
 One operand uses a general register. The other operand resides in main storage.

- Register Immediate Instructions.
 - One operand uses a general register. The other operand uses an immediate data field. The immediate data field is the low order byte of a one-word format or the second word of a two-word (long) format.
- Shift Instructions with Immediate Count.

 This is a shift instruction with the count field contained within the instruction word.
- Storage Immediate Instructions.
 One operand is in main storage. The other operand uses an immediate data field. The immediate data field is the second word of a two-word format.
- Parametric Instructions.
 For this instruction format, a parameter field (bits 8-15) is contained within the instruction word.

Effective Address Generation


For purposes of storage efficiency, certain instructions formulate storage operand addresses in a specialized manner. These instructions have self-contained fields that are used when generating effective addresses. Standard methods for deriving effective addresses are included in this section. Other methods such as bit displacements, are explained in the individual instruction descriptions in Chapter 5.

Programming note: For certain instructions, the effective address points to a control block rather than an operand. These instructions are:

- Copy Floating Level Block (CPFLB) (optional floating-point feature)
- Copy Level Block (CPLB)
- Load Multiple and Branch (LMB)
- Pop Byte (PB)
- Pop Doubleword (PD)
- Push Byte (PSB)
- Push Doubleword (PSD)
- Push Word (PSW)
- Pop Word (PW)
- Set Floating Level Block (SEFLB) (optional floating point feature)
- Set Level Status Block (SELB)
- Store Multiple (STM)


Base Register Word Displacement Short

Instruction format



The five-bit unsigned integer (WD) is doubled in magnitude to form a byte displacement then added to the contents of the specified base register to form the effective address. The contents of the base register must be even.


Example:



Contents of register 1 (RB) 0000 0000 0110 0000 0060 0096 Word displacement (WD) doubled + 0 1000 0000 0110 1000 0068 0104

Base Register Word Displacment


Instruction format



The eight-bit signed integer (WD) is doubled in magnitude to form a byte displacement then added to the contents of the specified base register to form the effective address. The contents of the base register must be even.

The word displacement can be either positive or negative; bit 8 of the instruction word is the sign bit for the displacement value. If this high-order bit of the displacement field is a 0, the displacement is positive with a maximum value of +127 (decimal). If the high-order bit of the displacement field is a 1, the displacement is negative with a maximum value of -128. The negative number is represented in two's complement form.

Example:




Note. This example uses a negative word displacement (-17 hex) shown in two's complement.

Contents of register 6 (RB) 0000 0000 1000 0110 0086 0134 Word displacement (WD) doubled (sign bit is propagated left) +1111 1111 1101 0010 - 2E - 46 Effective address 0000 0000 0101 1000 0058 0088

Four-Bit Address Argument

Instruction format



The Address Mode (AM) has the following significance:

AM=00. The contents of the selected base register form the effective address.

AM=01. The contents of the selected base register form the effective address. After use, the base register contents are incremented by the number of bytes in the operand. For some instructions, the effective address points to a control block rather than an operand. When the effective address points to a control block, the base register contents are incremented by two.

Example:


Operation code	RB		RB AM		
	0	1	0	1	
0 4	8	9	10	11	15

Effective address (contents of register 1) Contents of register 1 after instruction execution		0000	1000 0000	Hex 0080	Dec 0128
Byte operand Word operand Double word operand	0000	0000	1000 0001 1000 0010 1000 0100	0081 0082 0084	0129 0130 0132

Notes.

- 1. For register to storage instructions, if the register specified is the same for both operands, then the register is incremented prior to using it as an operand.
- 2. Certain instructions (storage to storage) have two address arguments. Operand 1 has a 3-bit RB field with its associated AM field. Operand 2 has a 2-bit RB field with its associated AM field. If both RB fields specify the same register and both AM fields are equal to 01, the base register contents are incremented prior to fetching operand 2 and again after fetching operand 2. Assuming the same conditions but with the operand 2 AM field not equal to 01, the base register contents are incremented prior to calculating the effective address for operand 2.
- 3. If the effective address points to a control block rather than an operand, the base register contents are incremented by two.

AM=10. An additional word is appended to the instruction. The word has the following format.



- If RB is zero, the appended word contains the effective address.
- If RB is non-zero, the contents of the selected base register and the contents of the appended word (displacement) are added to form the effective address.

Example:

			٦
O-wation code	RB AM	Address	١
Operation code	1 1 1 0	0 0 0 0 0 0 0 1 0 0 0 0 0 0 0	
	8 9 10 11 12	15 16	1
0 4	0 9 10 11 12	15 10	

Hex Dec

Contents of register 3

0000 1000 0000 0000 0800 2048

Contents of appended word

+0000 0001 0000 0000 0100 0256

Effective address

0000 1001 0000 0000 0900 2304

AM=11. An additional word is appended to the instruction.

• If RB is zero, the appended word has the format:



This address points to a main storage location, on an even byte boundary, that contains the effective address.

Example:

O tion and a	RB	AM							In	dire	ct a	ddi	ress						
Operation code	0 0	1 1		0	0	0	0	0	0	0	0	0	1	0	1	0	0	0	0]
0 4	8 9	10 11	12 15	16															31

Hex Dec


Contents of appended word

0000 0000 0101 0000 0050 0080

Effective address equals contents of storage at

address 0080 (decimal) 0000 0100 0000 0000 0400 1024

• If RB is non-zero, the appended word has the format:




The two displacements are unsigned eight-bit integers. Displacement 2 is added to the contents of the selected base register to generate a main storage address. The contents of this storage location are added to Displacement 1 resulting in the effective address.

Example:


			г — т									
Oper	ation code	RB	AM		Displa	cement 1		D	isplacei	ment	2	
L		1 0	1 1		0 0 1	0 0 1	0 1	0 1	0 0	no	1 1	ام
0	4	8 9	10 11	12 15	5 16		23	24				31

Contents of register 2 Displacement 2	0000	0101	0011 0100	0101 0010	Hex 0535 42	Dec 1333 66
Storage address Contents of storage at	0000	0101	0111	0111	0577	1399
address 1399 (decimal) Displacement 1	0000	0100	0001 0010	0000 0101	0410 25	1040 37
Effective address	0000	0100	0011	0101	0435	1077

Note. This example is invalid for other than a byte operand. Programming note. This addressing mode (AM=11, RB is non zero) is useful for the directorized data concept. For the addr4 or addr5 assembler syntax, the programmer codes the form displacement 1 (register, displacement 2)*. For addr4, the specified register is 1-3. For addr5, the specified register is 1-7. The asterisk denotes indirect addressing.




Five-Bit Address Argument



Operation of this mode is identical to the four-bit argument, but provides additional base registers.


Base Register Storage Address



- If RB is zero, the address field contains the effective address.
- If RB is non-zero, the contents of the selected base register and the contents of the address field are added together to form the effective address.

Note. Bit 11, if a one, specifies that the effective addressing is indirect.

Example: Indirect address




| Hex | Dec | Contents of register 4 | 0000 | 0001 | 0000 | 0000 | 0100 | 0256 | 0410 | 1040 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507 | 0507

Instruction Length Variations for Address Arguments


• One-word instructions that contain a single AM field become two words in length if AM is equal to 10 or 11. The AM appended word follows the instruction word.

Example:




• Two-word instructions that contain a single AM field become three words in length if AM is equal to 10 or 11. The AM word is appended to the first instruction word. The data or immediate field then becomes the third word of the instruction.

Example:



One-word instructions that contain two AM fields (AM1 and AM2) may be one, two, or three words in length depending on the values of AM1 and AM2. The AM1 word is appended first, then the AM2 word is appended.

Example:



Processor State Control

The processor is always in one of the following mutually exclusive states:

- Power off
- Stop
- Load
- Wait
- Run—when in run state, programs can be executed in either:
 - Supervisor state or
 - Problem state

Stop State

The stop state is entered when:

- 1. The Stop key on the programmer console is pressed.
- The STOP instruction is executed and (a) the mode switch
 on the basic console is in the Diagnostic position, and
 (b) the optional programmer console is installed.
- 3. An address-compare occurs and the rate control on the programmer console is in the Stop on Address position.
- 4. An instruction has completed execution and the rate control on the programmer console is in the Instruction Step position.
- 5. An error occurs and the error control on the programmer console is in the Stop on Error position.
- 6. The Reset key on the programmer console is pressed.
- 7. Power-on reset occurs.

Note. Any manual entry into Stop State is via the programmer console. The STOP instruction performs no operation if the programmer console is not installed.

While the processor is in the stop state: (1) the Stop light on the programmer console is on, (2) the functions provided on the console can be activated, and (3) no interrupt requests can be accepted by the processor. The processor exits the stop state when:

- 1. The Load key on the basic console is pressed.
- 2. The Start key on the programmer console is pressed. When the Start key is pressed, the processor returns to the state that was exited before entering stop state. If the run state is entered, one instruction is executed before interrupts are accepted by the processor. If the stop state was entered because of a reset (power-on reset or reset key), pressing the start key causes program execution to begin on level zero with the instruction in location zero of main storage. If the stop state was entered because of an error, with the Stop on Error switch turned on, a system reset must occur to clear the error condition. For more information about system reset, see State of Processor Following a Reset.

Wait State

The processor enters wait state when: (1) a Level Exit (LEX) instruction is executed and no other level is pending, or (2) a Set Level Block (SELB) instruction is executed that sets the current in-process bit off and no level is pending. While the processor is in the wait state, (1) the Wait light on the basic console is on and (2) interrupts can be accepted under control of the system mask register and the summary mask as defined by the LSR of the last active level.

The processor exits the wait state when:

- 1. The Stop key on the programmer console is pressed.
- 2. The Reset key on the programmer console is pressed.
- 3. An I/O interrupt is accepted (the level must be enabled by the summary mask and the mask register).
- 4. A class interrupt occurs. (See *Class Interrupts* in Chapter 3.)

Load State

The processor enters the load state when initial program load (IPL) begins. This occurs:

- 1. When the Load key on the basic console is pressed.
- 2. After a power-on reset if the Mode switch is in the Auto IPL position.
- 3. When an IPL signal is received from a host system.

While the processor is in load state, the Load light on the basic console is on.

The processor exits the load state and enters the run state upon successful completion of the IPL. See Initial Program Load (IPL).

Run State

The processor enters the run state when not in the stop, wait, or load state. Run state is entered:

- 1. From load state upon successful completion of IPL.
- 2. From wait state when an interrupt is accepted.
- 3. From stop state when the start key is pressed. (See Stop

The processor exits run state when entering stop, wait, or load states as previously described.

Supervisor State and Problem State

While in run state, instructions can be executed in either supervisor state or problem state. This is determined by bit 8 of the level status register (LSR):

State

LSR bit 8

Supervisor 1

Problem

Supervisor and problem states are discussed in the following sections.

Supervisor State. The processor enters supervisor state

- 1. A class interrupt occurs. This type of interrupt is caused by the following:
 - a. Machine check condition
 - b. Program check condition
 - c. Power/thermal warning
 - d. Supervisor Call (SVC) instruction
 - e. Soft exception trap condition
 - f. Trace bit (LSR bit 10) set to one
 - g. Console Interrupt key on the programmer console
- 2. An I/O interrupt is accepted.
- 3. After initial program load (IPL) has been completed.

Class interrupts and I/O interrupts are discussed in Chapter

3. Initial program load is discussed in a subsequent section of this chapter.

When the processor is in supervisor state, the full instruction set may be executed. The following privileged instructions may only be executed in supervisor state:

Copy Address Key Register (CPAKR)

Copy Console Data Buffer (CPCON) Note 1

Copy Current Level (CPCL)

Copy In-Process Flags (CPIPF)

Copy Interrupt Mask Register (CPIMR)

Copy Instruction Space Key (CPISK)

Copy Floating Level Block (CPFLB) Note 2

Copy Level Status Block (CPLB)

Copy Operand 1 Key (CPOOK)

Copy Operand 2 Key (CPOTK)

Copy Processor Status and Reset (CPPSR)

Copy Segmentation Register (CPSR) Note 3

Copy Storage Key (CPSK)

Diagnose (DIAG)

Disable (DIS)

Enable (EN)

Interchange Operand Keys (IOPK)

Level Exit (LEX)

Operate I/O (IO)

Set Address Key Register (SEAKR)

Set Console Data Lights (SECON) Note 4

Set Floating Level Block (SEFLB) Note 2

Set Instruction Space Key (SEISK)

Set Interrupt Mask Register (SEIMR)

Set Level Status Block (SELB)

Set Operand 1 Key (SEOOK) Set Operand 1 Key (SEOOK)

Set Operand 2 Key (SEOTK)

Set Segmentation Register (SESR) Note 3

Set Storage Key (SESK)

Notes.

- 1. The resultant data is unpredictable if the programmer console feature is not installed.
- 2. Invalid (soft exception trap) if the floating-point feature is not installed.
- 3. Invalid (program check) if the relocation translator feature is not installed.
- 4. Performs no operation if the programmer console feature is not installed.

Supervisor State overrides the storage protection mechanism. This permits unlimited access to all of main storage regardless of address keys or storage keys (see Chapter 8). When the Storage Address Relocation Translator Feature is installed and enabled, storage protection works differently. Supervisor State can only access the storage defined by the active address keys (see Chapter 9). Address key 0 is implicitly assigned to the supervisor for handling interrupts.

Problem State. This is a state that does not allow the processor to execute the privileged instructions. The processor enters the problem state when the supervisor state bit (LSR bit 8) is turned off. This can be accomplished with a Set Level Status Block (SELB) instruction. This instruction can change the contents of the registers for a selected priority interrupt level.

While the processor is in problem state, privileged instructions cannot be executed. If a privileged instruction execution is attempted, the instruction is suppressed and a program check class interrupt occurs, with privilege violate (bit 2) set in the processor status word.

State of Processor Following a Reset

The term *reset* used in the following sections denotes the reset action that occurs during:

- 1. Power-on reset
- 2. Initial program load (IPL) reset
- 3. System reset initiated by pressing the Reset key on the programmer console

The following registers and conditions are not affected by a reset and must be initialized by the program or operator before they become valid:

- AKR on levels 1-3
- Console data buffer (Programmer Console Feature)
- General registers
- IAR on levels 1–3
- Storage key registers (storage protection)
- Main storage
- Segmentation registers (relocation translator feature)
- Floating-point registers (floating-point feature)

The following registers and conditions are affected by a reset:

- CIAR—set to zeros
- IAR on level zero-set to zeros
- Mask register-set to ones (all levels enabled)
- LSR on level zero
 - Indicators-set to zeros
 - Supervisor state (bit 8)-set on
 - In-process (bit 9)-set on
 - Trace (bit 10)-set to zero (disabled)
 - Summary mask (bit 11)-set on (enabled)
 - All other bits-set to zeros
- AKR on level zero is set to zeros
- PSW-set to zeros except as noted
 - Auto-IPL (bit 13)—set to zero unless the reset was caused by an Auto-IPL
 - Power/thermal (bit 15)—reflects the status of the power/thermal condition
- LSR on levels 1-3-set to zeros
- SAR—set to zeros

Initial Program Load (IPL)

An initial program load function is provided to (1) read an IPL record (set of instructions) from an external storage media, and (2) automatically execute a start-up program. An IPL record is read into storage from a local I/O device or host system. The I/O attachments for the desired IPL sources are prewired at installation time. Two local sources, primary and alternate, can be wired and either can be selected by using the IPL Source switch on the console.

IPL can be started by three methods:

- 1. Manually, by pressing the Load key on the console.
- 2. Automatically, after a power-on condition.
- 3. Automatically, when a signal is received from a host system. The host system can be connected through a communications adapter.

The automatic power-on IPL is selected by a Mode switch on the console. When the Mode switch is in the Auto-IPL position, IPL occurs whenever power turns on (either initially or after a power failure). Auto IPL is useful for unattended systems. A manual IPL can be initiated at any time by pressing the Load key on the console (even when in run state). The Mode switch has no effect on the manual IPL. For Auto-IPL and manual IPL, the local IPL source (primary or alternate) is selected. IPL from a host system can occur at any time and is initiated by the host system. The IPL record is transferred through the host-system device; for example, the communications adapter. When an auto-IPL occurs, bit 13 of the PSW is turned on to indicate the condition to the software. When a manual or host-system IPL occurs, this bit is set to zero.

During IPL, the storage protection mechanism is disabled and main storage is loaded starting at location zero. The length of the IPL record depends on the media used by the IPL source. Upon successful completion of an IPL, the processor enters supervisor state and begins execution on priority level zero. The summary mask is enabled and all priority interrupt levels in the mask register are enabled. The level zero AKR is set to all zeros. The first instruction to be executed is at main storage location zero. The IPL source has a pending interrupt request on level zero. The system program must:

- 1. Perform housekeeping; for example, load vector table addresses in the reserved area of storage (see *Automatic Interrupt Branching* in Chapter 3).
- 2. Issue a Level Exit (LEX) instruction. This allows the processor to accept the interrupt from the IPL source. When the interrupt is accepted, a forced branch is taken using the device-address vector table. The vector table entry is determined by the device address of the IPL source and results in a branch to the proper program routine for handling the interrupt. The device address of the IPL source is set into bits 8–15 of register 7 on level zero. Condition code 3, device end, is reported by the IPL source. For additional information, see I/O Interrupts in Chapter 3.

A system reset always occurs prior to an IPL. However, if any errors occur during the IPL, the results are unpredictable.

Sequential Instruction Execution

Normally, the operation of the processor is controlled by instructions taken in sequence. An instruction is fetched from the main storage location specified in the instruction address register (IAR). The instruction address in the IAR is then increased by the number of bytes in the instruction just fetched. The IAR now contains the address of the next sequential instruction. After the current instruction is executed, the same steps are repeated using the updated address in the IAR.

A change from sequential operation can be caused by branching, jumping, interrupts, level switching, or manual intervention.

Jumping and Branching

The normal sequential execution of instructions is changed when reference is made to a subroutine; when a two-way choice is encountered; or when a segment of coding, such as a loop, is to be repeated. All of these tasks can be accomplished with branching and jumping instructions. Provision is also made for subroutine linkage, permitting not only the introduction of a new instruction address, but also the preservation of the return address and associated information.

The conditional branch and jump instructions are used to test the indicators in the LSR. These indicators are set as the result of I/O operations and most arithmetic or logical operations. Single or multiple indicators are tested as determined by the value in a three-bit field within the instruction. Refer to: (1) Indicators and (2) Testing Indicators with Conditional Branch and Jump Instructions.

Jumping

Jump instructions are used to specify a new instruction address relative to the address in the IAR. The new address must be within -256 to +254 bytes of the byte following the jump instruction.

Note. The jump instruction contains a word displacement that is converted to a byte displacement when the instruction is executed. However, when using the assembler, the programmer specifies a byte value that is converted to a word displacement by the assembler.

Branching

Branch instructions are used to specify a new full-width 16-bit address. A 16-bit value, range 0 to 65535, is contained in the second word of the instruction or in a register. The value in the second word can be used as the effective branch address or added to the contents of a base register to form an effective address. (See Base Register Storage Address in this chapter.)

Level Switching and Interrupts

The processor can execute programs on four different interrupt priority levels. These levels, listed in priority sequence, are numbered 0, 1, 2, and 3 with level 0 having highest priority. The processor switches from one level to another in two ways:

- 1. Automatically, when an interrupt request is accepted from an I/O device operating on a higher priority level than the current level.
- 2. Under program control, by using the Set Level Block (SELB) instruction.

Both types of level switching are discussed in detail in Chapter 3. Class Interrupts and Interrupt Masking Facilities are also discussed in Chapter 3.

Stack Operations

The processing unit provides two types of stacking facilities. Each facility is briefly described in this section. Additional information appears in subsequent sections. The two types of stacking facilities are:

- 1. Data Stacking. This facility provides an efficient and simple way to handle last-in first-out (LIFO) queues of data items and/or parameters in main storage. The data items or parameters are called stack elements. For a given queue (or stack), each element is one, two, or four bytes wide. Instructions for each element size (byte, word, or doubleword) are provided to:
 - a. Push an element into a stack (register to storage).
 - b. Pop an element from a stack (storage to register).
- 2. Linkage stacking. This facility provides an easy method for linking subroutines to a calling program. A word stack is used for saving and restoring the status of general registers and for allocating dynamic work areas. The Store Multiple (STM) instruction stores the contents of the registers into the stack and reserves a designated number of bytes in the stack as a work area. The Load Multiple and Branch (LMB) instruction reloads the registers, releases the stack elements, and causes a branch via register 7 back to the calling program.

Note. The Store Multiple instruction *pushes* a block of information into a stack. This block is referred to as a register block. The Load Multiple and Branch instruction *pops* a register block from a stack.

Data Stacking Description

Any contiguous area of main storage can be defined as a stack. Each stack is defined by a stack control block. Figure 2-8 shows a data stack and its associated *stack control block*. Stack control blocks must be aligned on a word boundary.

The words in the stack control block are used as follows:




Figure 2-8. Relationship of stack control block to data stack

High Limit Address (HLA). This word contains the address of the first byte beyond the area being used for the stack. All data in the stack has a lower address than the contents of the HLA. Note that the HLA points to the first byte beyond the bottom of an empty stack.

Low Limit Address (LLA). This word designates the lowest storage location that can be used for a stack element. Note that the LLA points to the top of a stack.


Top Element Address (TEA). This word points to the stack element that is currently on top of the stack. For empty stacks, the TEA points to the same location as the high limit address (HLA).

Note.

- 1. For word, double word, and register block operations, the HLA, LLA, and TEA must all contain an even address to ensure data alignment on a word boundary.
- 2. The HLA and LLA define a contiguous range of addresses. These addresses must not cross the 64K byte boundary that causes storage to wrap.

Push Operation. When a new element is pushed into a stack, the address value in the TEA is decremented by the length of the element (one, two, or four bytes) and compared against the LLA. If the TEA is less than the LLA, a stack overflow exists. A soft exception trap interrupt occurs with stack exception set in the PSW. The TEA is unchanged. If the stack does not overflow, the TEA is updated and the new element is moved to the top location defined by the TEA.

The following diagram shows how elements are pushed into a stack. Note that each push operation always places an element at a lower address in the stack than the preceding element.




Refer to Chapter 5 for descriptions of the following instructions:

- Push Byte (PSB)
- Push Word (PSW)
- Push Doubleword (PSD)

Pop Operation. When an element is popped from a stack, the TEA is compared against the HLA. If it is equal to or greater than the HLA, an underflow condition exists. A soft exception trap interrupt occurs with *stack exception* set in the PSW. If the stack does not underflow, the stack element defined by the TEA is moved to the specified register and the TEA is incremented by the length of the element.

The following diagram shows how elements are popped from a stack.



Refer to Chapter 5 for descriptions of the following instructions:

- Pop Byte (PB)
- Pop Word (PW)
- Pop Doubleword (PD)

Note. It is possible to pop data from beyond a stack boundary if (1) the TEA is less than the HLA, and (2) the operand size is greater than HLA minus TEA.

Data Stacking Example-Allocating Fixed Storage Areas

Many programs require temporary main storage work areas. It is very useful to be able to dynamically assign such work-area storage to a program only when that storage is needed. Conversely, when work-area storage is no longer needed by a program, it is desireable to free that resource so it may be used by other programs. Use of the stacking mechanism can assist in the programming of the dynamic storage management function.

The following is an example of how storage areas could be allocated using the stacking mechanism.


A stack is initialized with addresses that point to fixed area of storage. Each element in the stack represents the starting address of a block of storage consisting of 512 bytes; e.g., addresses 0200 through 03FF. As storage is needed, the starting address for a block of storage is popped from the stack. When the block of storage is no longer needed, the starting address is pushed back into the stack.

The stack control block, stack, and storage areas appear initially as follows:


Notice that each stack element is one word long; addresses of storage areas are the stack elements; the TEA points to the lowest location of the last element because the initialized stack is *full*. Contrast this with an empty stack, in which the TEA points to the same location as the HIA

Now assume that program A requires a block of storage. Program A (or a storage management function at the request of program A) issues a pop word instruction against the stack control block. The TEA is updated as follows:


Stack control block



Stack control block




Full stack




HLA = 0B08 →

Storage areas




Stack



HLA = 0B08 ---


Storage areas




The word element popped is placed in the register specified by the pop word instruction executed by program A. This is the address of the 512-byte storage area beginning at address 0200.

At this time, assume that program B (operating on a different hardware level than program A) also requires a storage area. It too executes a pop word instruction against the stack. The next element is moved to the register specified and points to the next available storage area and the TEA is updated:


Stack control block



Stack




Storage areas




Now, before any further requests occur, program A terminates its need for a work area. Program A then issues a push word instruction against the stack and returns the address of the area it was using for use by other programs:


Stack control block



Stack



Storage areas



A similar operation will be performed by program B when it releases its storage to the stack, popping address 0400 into location 0B00. While the addresses are obviously shuffled in the stack (from the values initially established), this presents no problem since each program requires only an area of storage—it is not important where that area is located.

Linkage Stacking Description

As previously described a word-stack mechanism may be used for subroutine linkage. This mechanism saves and restores registers and allocates dynamic work areas.

The letters in the following description correspond to the letters in Figure 2-9.

The Store Multiple (STM) instruction specifies:

- A Stack control block address
- B Limit register (RL) number
- Number (N) of words to allocate for work areas

When the STM instruction is executed, the allocate value (N) plus the number of registers saved plus one control word is the requested block size in words. The block size (converted to bytes) is used to decrement the TEA before an overflow check is made. If no overflow occurs the operation proceeds. The link register (R7) and register 0 through the specified limit register (RL) are saved sequentially in the stack. If register 7 is specified as the limit register, only register 7 is stored in the stack. The dynamic work space is allocated and a pointer to the work area is returned in register RL. If no work area is specified, the returned pointer contains the location of R7 in the stack. The values of RL and N are also saved as an entry in the stack. The TEA is updated to point to the new top of stack location.

When a Load Multiple and Branch (LMB) instruction is executed, the values of RL and N are retrieved from the stack and an underflow check is made. The value of RL controls the reloading of the registers; the values of RL and N are used to restore the stack pointer (TEA) to its former status. The contents of register 7 are then loaded into the instruction address register, returning program control to the calling routine.

Linkage Stacking Example-Reenterable Subroutine

A subroutine may be used by programs that operate on different interrupt levels. Rather than providing copies of the subroutine, one copy for each program that needs it, the subroutine can be made reenterable. Here, only one copy of the subroutine is provided; the single copy is used by all requesting programs. Two items must be considered in the reenterable subroutine code:

- Saving the register contents of each calling program. The subroutine is then free to use the same registers, restoring their contents to the calling-program's values just prior to returning to the calling program.
- Preserving the applicable variable data (generated by the subroutine) that is related to each call of the subroutine.
 That is, data associated with one call must not be disturbed when subroutine execution is restarted due to another call from a higher priority program.




Figure 2-9. Word stack for subroutine linkage


and HLA

The stacking mechanism, by means of the STM and LMB instructions, handles the two items just mentioned. As an example, operation could proceed as follows:

- 1. Program A calls the subroutine by means of a branch and link instruction (return address is in R7).
 - BAL SUBRT,7
- 2. The subroutine, in this example, uses registers R3 and R4 during its execution. The subroutine receives (from program A) a parameter list address in R0 and the address of the stack control block in R1. Also, the subroutine requires 20 bytes of work space. Thus, the subroutine executes, upon entry, the following store multiple instruction:

SUBRT STM 4,(1),20

After execution of the STM, the stack contains the following:



HLA ---

- * The last word contains a value that specifies the last register stored (e.g., R4 in this example) and the size of the dynamic work area (in words).
- R4 (the last register stored in the stack) is automatically loaded, during the STM operation, with the address of the work area to be used by the subroutine to hold its work data.
- 3. When subroutine processing for this call is completed, the subroutine executes a single load multiple instruction in order to reload the registers and return (via R7) to the calling program:

LMB (1)

If a second call to the subroutine has occurred prior to execution of the LMB, action similar to that just stated would occur again. However, another stack area would be used. Then, when subroutine execution is completed for the second call, and all higher priority interrupt level processing is completed, a return would be made to the interrupted subroutine for completion of processing for the first call.

Thus, multiple calls to a single subroutine are processed without interfering with the integrity of data associated with any other call to the subroutine.

INTRODUCTION

Efficient operation of a central processor depends on prompt response to I/O device service requests. This is accomplished by an interrupt scheme that stops the current processor operation, branches to a device service routine, handles device service, then returns to continue the interrupted operation. One processor can control many I/O devices; therefore, an interrupt priority is established to handle the more important operations before those of lesser importance. Certain error or exception conditions (such as a machine check) also cause interrupts. These are called class interrupts and are processed in a manner similar to I/O interrupts. Both I/O and class interrupts are explained further in the following sections.

Interrupt priority is established by four priority levels of processing. These levels, listed in priority sequence, are numbered 0, 1, 2, and 3 with level 0 having highest priority. Interrupt levels are assigned to I/O devices via program control. This provides flexibility for reassigning device priority as the application changes.

Processor level switching, under program control, may be accomplished by use of the Set Level Block (SELB) instruction. Details of this method are presented in a separate section of this chapter.

Each of the four priority levels has its own set of registers. These consist of an address key register (AKR), a level status register (LSR), eight general registers (R0-R7), and an instruction address register (IAR). Information pertaining to a level is automatically preserved in these hardware registers when an interrupt occurs.

I/O and class interrupts include automatic branching to a service routine. Fixed locations in main storage are reserved for branch addresses or pointers which are referenced during interrupt processing. This storage allocation is shown in the section Automatic Interrupt Branching in this chapter.

Interrupt masking facilities provide additional program control over the four priority levels. System and level masking are controlled by the *Summary Mask* and the *Interrupt Level Mask Register*. Device masking is controlled by the *Device Mask*. Manipulation of the mask bits can enable or disable interrupts on all levels, a specific level, or for a specific device. See *Interrupt Masking Facilities* in this chapter.

INTERRUPT SCHEME


As previously stated, four priority interrupt levels exist. Each I/O device is assigned to a level, dependent on the application. When an interrupt on a given level is accepted, that level remains active until (1) a Level Exit (LEX) instruction is executed, (2) a Set Level Block (SELB) instruction causes a level switch, or (3) a higher priority interrupt is accepted. In the latter case, the processor switches to the higher level, completes execution (including a LEX or SELB instruction), then automatically returns to the interrupted-from level. This automatic return can be delayed by other higher priority interrupts.


If an interrupt request is pending on the currently active level, it will not be accepted until after execution of a LEX instruction by the current program. If no other level of interrupt is pending when a Level Exit instruction is executed, the processor enters the wait state. In the wait state no processing is performed, but the processor can accept interrupts that are expected to occur. See Figure 3-1.

Supervisor state is entered upon acceptance of all priority interrupts. The *priority* interrupt algorithm is:

- 1. The summary mask must be on (enabled).
- 2. The mask bit (Interrupt Level Mask Register) for the interrupting level must be on (enabled).
- 3. For I/O interrupts the device must have its Device Mask bit on (enabled).
- 4. The interrupt request must be the highest priority of the outstanding requests and higher than the current level of the processor.
- 5. The processor must not be in the stop state.

Class interrupts do not change priority levels. They are processed at the currently active level. If the processor is in the wait state when a class interrupt occurs, priority level 0 is used to process the interrupt.





* This interrupt request cannot be honored until after a LEX instruction has been executed on level 3 to clear the previous interrupt service.

Figure 3-1. Interrupt priority scheme

AUTOMATIC INTERRUPT BRANCHING

Hardware processing of an interrupt includes automatic branching to a service routine. The processor uses a reserved storage area for branch information. The reserved area begins at main storage address 0000. The total size of the area depends on the number of interrupting devices attached. One word (two bytes) is reserved for each interrupting device. The device area begins at address 0030 (Hex); the reserved area is 0000 through 022F (Hex) if 256 devices (maximum number) are attached. These storage locations and contents are shown in Figure 3-2.

Main storage address (Hex)	Contents of word			
022E	Device FF DDB pointer			
,	<i>*</i>			
0032	Device 01 DDB pointer			
0030	Device 00 DDB pointer			
002E	Reserved			
002C	Reserved			
002A	Reserved			
0028	Reserved			
0026	Reserved			
0024	Reserved			
0022	Soft exception trap SIA			
0020	Soft exception trap LSB pointer			
001E	Console interrupt SIA			
001C	Console interrupt LSB pointer			
001A	Trace SIA			
0018	Trace LSB pointer			
0016	Power failure SIA			
0014	Power failure LSB pointer			
0012	SVC SIA			
0010	SVC LSB pointer			
000E	Program check SIA			
000C	Program check LSB pointer			
000A	Machine check SIA			
0008	Machine check LSB pointer			
0006	Reserved			
0004	Reserved			
0002	Restart instruction word 2			
0000	Restart instruction word 1			

Figure 3-2. Reserved storage locations

The reserved storage locations are described as follows:

Storage Location	Contents
(Hex)	
0000-0003	Restart instruction. Following IPL a forced branch is made to location 0000.
0004-0005	Reserved.
0006-0007	Reserved.
0008-0023	Addresses used for class interrupts. The Level Status Block (LSB) pointer is the first address of an area where a level status block will be stored. The Start Instruction Address (SIA) points to the first instruction of a service routine.
0024 - 002F	Reserved
0030-022F	Addresses used for I/O interrupts. The Device Data Block (DDB) pointer is the address of the first word of a device data block. This word is

Note. The area reserved for I/O devices varies in size depending on the number of devices. The device address determines the fixed location to be accessed. For example: Interrupts for device 01 always vector to main storage address 0032. Device addresses range from 00 through FF (Hex).

used to obtain the start instruction address for the service routine. See I/O Interrupts in this

I/O INTERRUPTS


Prepare I/O Device for Interrupt

chapter.

I/O device interrupt parameters are established via program control. The Operate I/O (IO) instruction initiates the device operation and in conjunction with the "Prepare" I/O command tells the device:

- 1. If the device can interrupt.
- 2. What priority level to use for interrupts. See Chapter 5 Instructions and Chapter 7 Input/Output Operations for details of the Operate I/O instruction.

Execution of the Prepare command transfers a word to the addressed device that controls its interrupt parameters. This word has the format:



Bits Contents

0-10 Set to zeros.

11-14 Level. A four-bit encoded field that assigns an interrupt priority level to the device (see note).

Example: 0000-level 0, 0001-level 1, 0010-level 2, 0011-level 3.

15 Device mask or I-bit. This bit sets the interrupt mask in the device. When set to one, the device can interrupt. When set to zero, the device can not request an interrupt.

Note. The 4955 Processor does not recognize priority levels other than zero through three; therefore, bits 11 and 12 must always be set to zero or the interrupt is lost.

An interrupting device is always able to accept and execute a Prepare command, even if it is presently busy or has an interrupt request pending from a previous command. This allows the software to change the device mask and interrupt level at any time.

Present and Accept Interrupt

The I/O device presents an interrupt request on its assigned priority level. This request is applied to the interrupt algorithm for acceptance determination. Following acceptance, the device sends an interrupt ID word and a condition code to the processor. The interrupt ID word consists of an interrupt information byte (IIB) and the device address. Bits 0–7 of this word contain the interrupt information; bits 8–15 contain the device address. The condition code is placed in the even, carry, and overflow indicators for the interrupted-to level. See Chapter 7 for condition codes and interrupt information byte (IIB) details. The following events occur after the processor receives the interrupt ID word (Figure 3-3):

- 1. The processor hardware switches from the registers and status of the interrupted-from level to those of the interrupted-to level.
- 2. The interrupt ID word is placed in register 7 of the interrupted-to level.
- 3. The processor executes an automatic branch.
 - a. The device address is used by hardware to fetch the DDB pointer from reserved storage.
 - b. The DDB pointer is placed in register 1 of the interrupted-to level.
 - c. The DDB pointer is used by hardware to fetch the start instruction pointer.
 - d. The Start Instruction Address (SIA) is loaded into the IAR of the interrupted-to level.
- 4. Execution begins on the new level.




Figure 3-3. Example of I/O interrupt with automatic branching

PROCESSOR STATUS WORD

The processor status word (PSW) is used to record error or exception conditions in the system that may prevent futher processing. It also contains certain status flags related to error recovery. Error or exception conditions recorded in the PSW cause four of the possible seven class interrupts to occur. These are program check, soft exception trap, machine check, and power/thermal warning. See, Class Interrupts, in this chapter.

The PSW is contained in a 16-bit register with the following bit representation:

		Class	
Bit	Condition	Interrupt	Remarks
00	Specification check	Program check	
01	Invalid storage address	Program check	
02	Privilege violate	Program check	
03	Protect check	Program check	
04	Invalid function	Program check or	
		Soft exception trap	
05	Floating-point exception	Soft exception trap	
06	Stack exception	Soft exception trap	
07	Not used	•	always zero
80	Storage parity check	Machine check	•
09	Not used		always zero
10	CPU control check	Machine check	-
11	I/O check	Machine check	
12	Sequence indicator	None	Status flag
13	Auto-IPL	None	Status flag
14	Translator enabled	None	Status flag
15	Power/thermal warning	Power/thermal	Note 1

Note 1. The power/thermal warning class interrupt is controlled by the summary mask.

Program Check Conditions

Bit 00 Specification check. Set to one if the storage address violates the boundary requirements of the specified data type.

Bit 01 Invalid storage address. Set to one when an attempt is made to access a storage address outside the storage size of the system. This can occur on an instruction fetch, an operand fetch, or an operand store.

Bit 02 Privilege violate. Set to one when a privileged instruction is attempted in the problem state (supervisor state bit in the level status register is not on).

Bit 03 Protect check. In the problem state, this bit is set to one when (1) an instruction is fetched from a storage area not assigned to the current operation, (2) the instruction attempts to access a main storage operand in a storage area not assigned to the current operation, or (3) the instruction attempts to change a main storage operand in violation of the read-only control.

Program Check or Soft Exception Trap Condition

Bit 04 Invalid function. Set to one by one of the following conditions:

An illegal operation code or function combination.
 These are:

Op code	Function
00111	All
01000	0001, 0010, 0011, 0101, 0110, 0111
01011	0001, 1001 (When relocation translator feature is not installed)
01011	0101,0111
01100	111
01110	11000, 11010, 11011, 11100, 11110, 11111
01111	1X1XX, 01XXX, 1X011, 10001
10110	All
11011	All
11101	1100, 1101, 1110, 1111

Note. The preceding illegal conditions cause a program check class interrupt to occur.

2. The processor attempts to execute an instruction associated with an uninstalled feature. These are:

Op code	Function
00100	All (Floating-point feature not installed)
01011	0011, 1011 (If the floating-point feature is not installed and the processor is in supervisor state).

Note. The preceding conditions cause a soft-exception-trap class interrupt to occur.

Soft Exception Trap Condition

Bit 05 Floating point exception. Set to one when an exception condition is detected by the optional floating point processor. The arithmetic indicators (carry, even, and overflow) define the specific condition.

Bit 06 Stack exception. Set to one when an attempt has been made to pop an operand from an empty main storage stack or push an operand into a full main storage stack. A stack exception also occurs when the stack cannot contain the number of words to be stored by a Store Multiple (STM) instruction.

Machine Check Conditions

Bit 08 Storage parity. Set to one when a parity error has been detected on data being read out of storage by the processor. This error may occur when accessing a storage location that has not been validated since power on.

Bit 10 CPU control check. A control check will occur if no levels are active but execution is continuing. This is a machine-wide error. (See note).

Bit 11 I/O check. Set to one when a hardware error has occurred on the I/O interface that may prevent futher communication with any I/O device. PSW bit 12 (sequence indicator) is a zero if the error occurred during an Operate I/O instruction and is set to one if the error occurred during a non-DPC transfer. The sequence indicator bit is not an error in itself but reflects the last interface sequence at any time. An I/O check cannot be caused by a software error. (See note.)

Note. The machine check class interrupt initiated by a CPU control check or I/O check causes a reset. The I/O interface, the channel, and all devices in the system are reset as if a Halt I/O (channel directed command) had been executed. The processor, sensor-based output points, and timer values are not reset.

Status Flags

Bit 12 Sequence indicator. This bit reflects the last I/O interface sequence to occur. See I/O Check described above.

Bit 13 Auto IPL. Set to one by hardware when an automatic IPL occurs. Set to zero by a Power on Reset when the mode switch is not in Auto IPL, by pressing the Load key, or by a host-system IPL.

Bit 14 Translator enabled. When the Storage Address Relocation Translator Feature is installed this bit is set to one or zero as follows:

- 1. Set to one (enabled)
 - a. An Enable (EN) instruction is executed with bit 12 of the instruction word set to zero and bit 14 set to one.
- 2. Set to zero (disabled)
 - a. A Disable (DIS) instruction is executed with bit 14 of the instruction word set to one.
 - b. An Enable (EN) instruction is executed with bit 12 of the instruction word set to one.
 - c. A processor reset (power-on reset, check restart, IPL, or system reset key).

Power/Thermal Warning Condition

Bit 15 Power warning and thermal warning. Set to one when these conditions occur (see *Power/Thermal Warning* class interrupt in this chapter). The power/thermal class interrupt is controlled by the summary mask.

CLASS INTERRUPTS

System error or exception conditions can cause seven types of class interrupts. All class interrupts cause the processor to enter supervisor state (LSR bit 8 = 1). Certain class interrupts are further defined in the PSW. Each class interrupt is described in subsequent sections. The seven types, in priority sequence, are:

- 1. Machine check, caused by a hardware error.
- 2. Program check, caused by a programming error.
- 3. Power/thermal warning, caused by a power or thermal irregularity.
- 4. Supervisor call, caused by execution of an SVC instruction.
- 5. Soft exception trap, caused by software.
- 6. Trace, caused by instruction execution (trace enabled in the current LSR).
- 7. Console, caused by a console interrupt when the optional programmer console is installed.

Software can refer to the processor status word for the specific condition and any related status information. The Copy Processor Status and Reset (CPPSR) instruction can be used for this purpose. Power/thermal warning and console interrupts are controlled by the summary mask (LSR bit 11); all other class interrupts cannot be disabled. If the optional programmer console is installed and Check Restart or Stop on Error are selected, machine check and program check interrupts do not occur. See, *Programmer Console Feature*, Chapter 4.

A class interrupt does not cause a change in priority level. However, supervisor state is entered, trace is reset, and all priority interrupt requests are automatically disabled (summary mask bit set to zero). The address key register (AKR) is set as follows: (1) equate-operand-spaces bit is set to zero, (2) ISK and OP2K address keys are set to zero, and (3) OP1K address key is set dependent on the type of class interrupt. The class interrupt is serviced on the level that is active when the condition occurs. If the processor is in the wait state, the interrupt is serviced on priority level 0.

Note. Address key values are set in anticipation of the address spaces required by the interrupt service routine. Refer to Address Space Management in Chapter 8.

Priority of Class Interrupts

Although class interrupts are serviced on the current priority level, they are serviced according to an exception condition priority.

The following table lists the exception conditions in priority sequence with zero being the highest priority. Two exception conditions of the same priority, such as protect check and specification check, may be reported to the PSW simultaneously. The table also shows the associated class interrupt vectors for the exception conditions.

Priority	Exception Condition	Class Interrupt Routine
0	CPU control check I/O check	Machine check
1	Invalid function (Note 1)	
2	Privilege violate	
3	Invalid function (Note 2)	
4	Protect check Specification check	Program check
5	Invalid storage address Specification check	
6	Storage parity	Machine check
7	Power warning Thermal warning	Power/thermal warning
8	Supervisor call	Supervisor call
9	Invalid function (Note 3)	
10	Floating-point exception	Soft exception
11	Stack exception	trap
12	Trace	Trace
13	Console	Console

Note 1. Caused by an illegal operation code or function combination.

Note 2. A Copy Segmentation Register (CPSR) or Set Segmentation Register (SESR) instruction is attempted and the translator feature is not installed.

Note 3. A floating-point instruction is attempted and the floating-point feature is not installed.

Execution of Class Interrupts

Occurrence of a class interrupt causes the processor to enter supervisor state, to disable trace, and to set the summary mask to zero (disable). Reference is made to the reserved area of main storage to:

- 1. Store current level IAR, AKR, registers, and LSR into a level status block (LSB) in main storage.
- 2. Automatically branch to a service routine by using the start instruction address (SIA).

Note. Priority level zero is forced active when a class interrupt occurs in the wait state. The level zero LSB is stored into main storage. The in-process flag (LSR bit 9) is zero in the stored LSB.

Each type of class interrupt has an associated LSB pointer and SIA (see Figure 3-2). Contents of the level status block are as follows:

Main storage
address (LSB)

pointer)

Instruction address register

Address key register

Level status register

Register 0

Register 1

Register 2

Register 3

Register 4

Register 4

Register 5

Register 6

+14 (Hex)

Register 7

The instruction address (contents of IAR) stored in the LSB depends on the type of class interrupt and is shown in the following chart.

			
Type of Class Interrupt	Contents of IAR (Stored in LSB)		
Program check Soft exception trap	Address of instruction that caused the interrupt.		
Supervisor call Trace Console Power/thermal warning	Address of the next instruction.		
Machine check (with Sequence indicator off)	Address of instruction that caused the interrupt.		
Machine check (with Sequence indicator on)	Address of instruction that was being executed at the time of the error.		

Machine Check

A machine check interrupt is caused by a hardware malfunction and is considered a system-wide incident. The three types are:

- 1. Storage parity check (PSW bit 08)
- 2. CPU control check (PSW bit 10)
- 3. I/O check (PSW bit 11)

A level status block is stored, starting at the location in main storage designated by the machine check LSB pointer (contents of storage locations hex 0008 and 0009). The contents of the storage address register (SAR) are loaded into register seven. The last active processor address key is loaded into the OP1K address key of the AKR. The machine check SIA (contents of storage locations hex 000A and 000B) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Note. When the error condition occurs:

- 1. The IAR contains the true address of the first word of the instruction; it is not incremented if the error occurs in the second or third word of a long instruction.
- 2. For a storage parity check, the last active processor key defines the space corresponding to the storage address loaded into R7. For a CPU control check or an I/O check this key and R7 provide no useful information.

Program Check

A program check interrupt is caused by a programming error. The types are:

- 1. Specification check (PSW bit 00).
- 2. Invalid storage address (PSW bit 01).
- 3. Privilege violate (PSW bit 02).
- 4. Protect check (PSW bit 03).
- 5. Invalid function (PSW bit 04).

A level status block is stored, starting at the location in main storage designated by the program check LSB pointer (contents of storage locations hex 000C and 000D). The contents of the storage address register (SAR) are loaded into register seven. The last active processor address key is loaded into the OP1K address key of the AKR. The program check SIA (contents of storage locations hex 000E and 000F) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Note.

- A program check interrupt condition on one priority level does not affect software on other levels.
- 2. For a specification check, an invalid storage address, and a protect check, the last active processor key defines the address space corresponding to the storage address loaded into R7. For privilege violate, this key and R7 provide no useful information.

Power/Thermal Warning (PSW Bit 15)

A power/thermal warning class interrupt is initiated by:

- 1. A power warning signal that is generated when the power line decreases to about 85% of its rated value.
- A thermal warning that occurs if the temperature limits inside the closure are exceeded.

In both cases, the instruction address that is stored in the LSB points to the next instruction to be executed. The starting address for the LSB is designated by the power failure LSB pointer (contents of storage locations hex 0014 and 0015). The OP1K address key in the AKR is set to zero. The power failure SIA (contents of storage locations hex 0016 and 0017) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

A power/thermal warning interrupt can occur when the system is running or in the wait state, assuming (1) the summary mask is enabled and (2) the programmer console is not set to check reset or stop on error. These interrupts are not taken by the processor if the summary mask is disabled.

If the optional battery backup unit is installed and a power warning occurs, PSW bit 15 remains on as long as power is supplied by the battery. If a thermal warning occurs, the processor will power down regardless of the battery backup unit. The minimum time before the processor powers down is 20 milliseconds. The IBM 4999 Battery Backup Unit is explained in Chapter 13.

Power/thermal warning interrupts are not taken by the processor until the first instruction is executed following a power-on reset, an IPL, or exit from stop state.

Note. If the processor is in the wait state when the power/thermal condition occurs:

- 1. The interrupt is serviced on priority level 0. The level 0 LSB is stored into main storage. Additional power/thermal interrupts along with priority interrupts are disabled at this time because the summary mask is set to zero by the class interrupt.
- The instruction address stored in the LSB is unpredictable.

Supervisor Call

A supervisor call class interrupt is initiated by executing an SVC instruction. The SVC instruction is described in Chapter 5. A level status block is stored, starting at the main storage location designated by the supervisor call LSB pointer (contents of storage locations hex 0010 and 0011). The OP2K address key is placed into the OP1K address key in the AKR; then, OP2K, EOS bit, and ISK are set to zero. The supervisor call SIA (contents of storage locations 0012 and 0013) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Soft Exception Trap

A soft exception trap interrupt is caused by software. The types are:

- 1. Invalid function (PSW bit 4)
- 2. Floating-point exception (PSW bit 5)
- 3. Stack exception (PSW bit 6)

These exception conditions may be handled by software; therefore, they do not constitute an error condition.

A level status block is stored, starting at the location in main storage designated by the soft-exception-trap LSB pointer (contents of storage locations hex 0020 and 0021). The contents of the storage address register (SAR) are loaded into register seven. The OP2K address key is placed into the OP1K address key in the AKR. The soft-exception-trap SIA (contents of storage locations hex 0022 and 0023) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Note. R7 contents are unpredictable.

Trace

The trace class interrupt provides an instruction trace facility for software debugging. Instruction tracing may occur on any priority level, and is enabled by the trace bit (LSR bit 10). The tracing occurs when bit 10 of the current LSR is set to one. When trace is enabled, a trace class interrupt occurs at the beginning of each instruction. A level status block is stored, starting at the location in main storage designated by the trace LSB pointer (contents of storage locations hex 0018 and 0019). The trace SIA (contents of storage locations hex 001A and 001B) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Note. After the LSB is stored, and before the next instruction is fetched, supervisor state is set on (LSR bit 8), trace is turned off (LSR bit 10), and the summary mask is disabled (LSR bit 11).

The contents of the address key register (AKR) are set as follows:

- 1. EOS (Bit 0) is set to zero (disabled).
- 2. OP1K address key (bits 5-7) is set to the value of the ISK address kev.
- 3. OP2K address key (bits 9-11) and ISK address key (bits 13-15) are set to zero.

Programming Note. When trace is enabled, a trace class interrupt occurs prior to executing each instruction. Hardware processing of the interrupt provides an automatic branch to the programmer's trace routine. To prevent retracing the same instruction, the program should exit the trace routine by using the Set Level Block (SELB) instruction with the inhibit trace (IT) bit set to one. The inhibit trace bit prevents a trace interrupt from occurring for the duration of one instruction (see SELB instruction in Chapter 5). A double trace of an instruction can also occur when the instruction is interrupted and must be reexecuted. For example: a class interrupt occurs during execution of a variable field length instruction. Under this condition, exit from the class interrupt routine should be via a SELB instruction with the inhibit trace bit set to one.

The occurrence of any class interrupt or priority interrupt causes the trace bit (LSR bit 10) to be set to zero. This action permits tracing only problem state code. If the programmer desires to trace supervisor code, he must make provisions within the service routine to enable the trace bit.

The following three conditions inhibit a trace class interrupt:

1. A Set Level Block (SELB) sets the trace bit on and the in-process bit on in the LSR of a selected level lower than the current level; then, when the selected level becomes active, the first instruction executed is not preceded by a trace interrupt.

- 2. The programmer console is in diagnose mode and a stop instruction is encountered while tracing; then, when the Start Key is depressed, a trace interrupt does not occur prior to executing the first instruction.
- 3. When a level is exited by either a LEX or a SELB instruction and processing is to continue on a pending level, one instruction is executed on the pending level prior to sampling for a trace interrupt.

Console

A console interrupt function is provided when the optional programmer console is installed. To recognize the interrupt, the processor must have the summary mask enabled and be in the run state or wait state. A level status block is stored, starting at the main storage location designated by the console interrupt LSB pointer (contents of storage locations hex 001C and 001D). The OP1K address key is set to zero. The console interrupt SIA (contents of storage locations hex 001E and 001F) is then loaded into the IAR, becoming the address of the next instruction to be fetched.

Notes.

- 1. If the processor is in the wait state when a console interrupt occurs, the interrupt will be serviced on priority level 0.
- 2. If the summary mask is disabled, the console interrupt is ignored since it is not buffered.

RECOVERY FROM ERROR CONDITIONS

Error recovery procedures, initiated by software, depend on several factors:

- 1. Application involved.
- 2. Type of error.
- 3. Number of recommended retries.

The error class interrupt provides an automatic branch to a service routine. This routine can interrogate the PSW for specific error and status information. The routine can then initiate corrective action or retry the failing instruction(s). If an error occurs during a priority interrupt sequence, the priority level switch is completed before the error class interrupt is processed. This facilitates automatic register retention. A reset is generated by machine check class interrupts caused by an I/O check or a CPU control check. No reset is generated by program check or power/thermal warning class interrupts. Error conditions along with error recovery information are presented in the following sections.

Program Check

A program check is caused by a programming error and initiates a program check class interrupt. Error retry depends on the application. All necessary parameters are made available for locating and, if required, correcting the invalid condition. There is no change to operands or priority level during a program check class interrupt. The stored LSB reflects conditions at the time the interrupt occurred and contains:

- The contents of all general registers
- Status information (AKR and LSR contents)
- The address of the failing instruction (IAR contents)

The contents of the storage address register (SAR) are loaded into R7 but has meaning only for specification check, invalid storage address, and protect check. The programmer must reference the PSW to determine the type of program check.

Storage Parity Check

A storage parity error initiates a machine check class interrupt. The error may occur when accessing a storage location that has not been validated since power on. Any retry procedure should include refreshing data in the failing location. Two unsuccessful retries are considered a permanent failure and the storage location should not be used.

CPU Control Check

A CPU control check occurs if hardware detects a malfunction of the processor controls. It is a machine-wide error and initiates a machine check class interrupt. A reset is generated to the channel, the I/O attachment features and all attached I/O devices. The processor, sensor-based output points, and timer values are not reset. The generated reset should clear the error condition, but validity of any previous execution is not guaranteed. No retry is recommended, An IPL should be initiated.

I/O Check

An I/O check condition occurs if a hardware error is detected that may prevent further communication with I/O devices. A machine check class interrupt is initiated and a reset is generated to the I/O attachment features, the channel, and all I/O devices. Error recovery from an I/O check depends on the sequence indicator setting (PSW bit 12).

Sequence indicator set to zero. The error occurred during an Operate I/O instruction. The address of the failing instruction (IAR contents) is available in the stored LSB. Retry should be attempted twice. After two unsuccessful retries, use of the device should be discontinued.

Sequence indicator set to one. The error occurred during an interrupt or cycle steal operation. The instruction address (IAR contents) stored in the LSB is not related to the error. The sequence of events leading to the I/O check is lost, along with all pending interrupt requests within the devices. Retry is not recommended.

Soft Exception Trap

A soft exception trap interrupt is the result of an exception condition that software may chose to handle dynamically. All necessary parameters are available to locate and correct the condition. The address of the instruction (IAR contents) causing the exception is preserved in the level status block in main storage. The processor is not reset. The programmer must reference the PSW to determine the soft-exception type.

PROGRAM CONTROLLED LEVEL SWITCHING

Level switching under program control may be accomplished by using the Set Level Block (SELB) instruction. This instruction is covered in detail in Chapter 5, *Instructions*, and in general it will:

- Specify the location of a level status block (LSB) at an effective address in main storage.
- Specify a selected priority level associated with the main storage LSB.
- Load the main storage LSB into the hardware LSB for the selected level.

Note. The hardware LSB consists of the following hardware registers for the selected level:

- 1. Instruction address register
- 2. Address key register
- 3. Level status register
- 4. Eight general registers (0-7)

The system programmer should become thoroughly familiar with other effects on the processor caused by execution of the SELB instruction. These effects are determined by three factors:

- 1. The current execution level.
- 2. The selected level specified in the SELB instruction.
- 3. The state of the *in-process flag* (Bit 9 of the LSR) contained in the main storage LSB.

Note. Interrupt masking, provided by the summary mask and the interrupt level mask register, does not apply to program controlled level switching.

The main storage LSB and the location of the in-process flag bit are shown in the following diagram:

Main storage effective	
address	IAR
	AKR
	LSR *
	Register 0
	Register 1
	Register 2
	Register 3
	Register 4
	Register 5
	Register 6
EA+14 (Hex)	Register 7
	*In-process flag (bit 9)


0 = off

1 = on

Execution of the SELB instruction may result in level switching or a change in the pending status of a level as described in the following sections.


Selected Level Lower Than Current Level and In-process Flag On

These conditions cause the selected level to be pending. The main storage LSB is loaded into the hardware LSB for the selected level. Execution of a LEX instruction on the current level causes the selected level to become active providing no higher priority interrupts are being requested.




Selected Level Equal to Current Level and In-process Flag On

These conditions cause the selected level to become the current level. The main storage LSB is loaded into the hardware LSB for the selected level.




Selected Level Higher Than Current Level and In-process Flag On

These conditions cause the selected level to become the current level. The main storage LSB is loaded into the hardware LSB for the selected level. This is a level switch to the higher (selected) level and causes the lower level to be pending.




Selected Level Lower Than Current Level and In-process Flag Off

These conditions cause the selected level to be not pending. The main storage LSB is loaded into the hardware LSB for the selected level.




Selected Level Equal to Current Level and In-process Flag Off

These conditions cause an exit from the current level. This exit is identical to executing a LEX instruction with the exception that the main storage LSB is loaded into the hardware LSB for the selected level. Refer to the LEX instruction in Chapter 5.



Selected Level Higher Than Current Level and In-process Flag Off

The main storage LSB is loaded into the hardware LSB for the higher (selected) level.



INTERRUPT MASKING FACILITIES

Three levels of priority interrupt masking are provided to the programmer for control of the interrupt processing. These consist of:

- 1. Summary Mask (LSR bit 11)
- 2. Interrupt Level Mask Register
- 3. Device Mask (I-bit)

Each masking facility has specific control as explained in the following sections.

Summary Mask

The summary mask provides a masking facility for priority interrupts and certain class interrupts. The state of the summary mask (enabled or disabled) is controlled by bit 11 in the level status register (LSR) of the active priority level. When bit 11 is set to zero, the summary mask is disabled and prevents (1) all priority interrupts regardless of priority level, and (2) power/thermal and console class interrupts. All other class interrupts are not masked. When bit 11 is set to one, the mask is enabled and the interrupts are allowed.

The summary mask is disabled and enabled as follows:

Disabled (Set to Zero)

- When a Supervisor Call (SVC) instruction is executed, the summary mask for the active level is disabled.
- Execution of a Disable (DIS) instruction, with bit 15 of the instruction equal to one, causes the summary mask for the active level to be disabled.
- All class interrupts disable the active level summary mask.
- The summary mask for a selected level is disabled by executing a Set Level Block (SELB) instruction with bit 11 of the LSR to be loaded equal to zero.
- The summary mask bits for priority levels 1-3 are set to zero by a system reset, power-on reset, or IPL.

• Enabled (Set to One)


- Execution of an Enable (EN) instruction, with bit 15 of the instruction equal to one, causes the active level summary mask to be enabled.
- The summary mask for a selected level is enabled by executing a Set Level Block (SELB) instruction with bit 11 of the LSR to be loaded equal to one.
- The level zero summary mask is enabled by a system reset, power-on reset, or IPL.
- The summary mask for the interrupted-to level is enabled by a priority interrupt.

Note. If the processor is in the wait state, the summary mask is enabled or disabled as defined by bit 11 in the LSR of the last active priority level.

Interrupt Level Mask Register

The interrupt level mask register is a 4-bit register used for control of interrupts on specific priority levels. Each level is controlled by a separate bit of the mask register as shown below:

Interrupt Level Mask Register



With a bit position set to one, the corresponding priority level is enabled and permits interrupts. With a bit position set to zero, the corresponding priority level is disabled. The Set Interrupt Mask Register (SEIMR) instruction is used to control bit settings in the interrupt level mask register. The Copy Interrupt Mask Register (CPIMR) instruction may be used to interrogate the register.

Note. All levels are enabled (Set to one) by a system reset, power-on reset, or IPL.


Device Mask (I-bit)

Each interrupting device contains a one-bit mask called the device mask or interrupt bit (I-bit). Interrupts by the device are permitted when its device mask is enabled (set to one). With the device mask bit disabled (set to zero), that device cannot cause an interrupt. The device mask is controlled by a *Prepare* command in conjunction with an Operate I/O instruction. See Chapter 5, *Instructions*, and Chapter 7, *Input/output Operations*.


Chapter 4. Console


There are two configurations of consoles available for the IBM 4955 Processor. The Basic Console is standard, and remains with the processor. The Programmer Console is an optional feature that is added to the processor when the option is selected.

Configuration 1
Basic Console



Configuration 2
Basic Console and
Programmer Console





Configuration 1 is primarily intended for those systems that are totally dedicated to a particular application, where operator intervention is not needed during the execution of the application.

Configuration 2 is aimed at operator oriented systems where various programs are entered and executed during the day. This type of environment requires a more versatile console arrangement for program and machine problem determination, and for manual alteration of data and programs in storage.

BASIC CONSOLE

Each IBM 4955 Processor comes equipped with the standard Basic Console. The Basic Console provides the following capabilities:

- Power On/Off switch for the processor card file.
- Load key for IPL (initial program load).
- Load, Wait, Run, and Power On indicators.
- Mode switch to select: Diagnostic mode, Auto IPL, or Normal mode.
- IPL source switch to select a primary or alternate IPL device.

Keys and Switches

Power On/Off

When this switch is placed in the On position, power is applied to the processor unit. After all power levels are up, the Power On indicator is turned on. When this switch is placed in the Off position, power is removed from the processor card file and the Power On indicator is turned off.

IPL Source

This switch selects the I/O device to be used for program loading. In the Primary position, the device that was pre-wired as the primary IPL device is selected. In the Alternate position, the device that was pre-wired as the alternate IPL device is selected.

Load C

Pressing this key causes a system reset, then the initial program load (IPL) sequence is started. The Load indicator is turned on and remains on until the IPL sequence is completed. When the IPL is completed, instruction execution begins at location zero

Mode

This switch has the following positions:

- Auto IPL-In this position, an IPL is initiated after a successful power-on sequence. Bit 13 of the PSW is set to indicate to the software that an automatic IPL was performed. In this mode STOP instructions are treated as
- Normal-This position is for attended operation. In this mode STOP instructions are treated as no-ops.

 Diagnostic—This position has no function without the Programmer Console. This position places the processor diagnostic mode if the Programmer Console is attached. When the processor is in diagnostic mode, STOP instructions cause the processor to enter stop state.

Indicators

Power On


On when the proper power levels are available to the system.

On when the machine is performing an Load initial program load (IPL).

On when an instruction that exits the active Wait level has been executed and no other priority

interrupts are pending.

when the machine is executing Run instructions.



PROGRAMMER CONSOLE

The Programmer Console is an optional feature that can be ordered with the IBM 4955 Processor or may be field installed at a later date. The Programmer Console provides the following capabilities:

- Start and stop the processor.
- Display or alter any storage location.
- System reset.
- Select any of the four interrupt levels for display or alter purposes.
- Display or alter the storage address register (SAR), instruction address register (IAR), console address key register (AKR), console data buffer, or any general purpose register.
- Display but not alter the level status register (LSR), current instruction address register (CIAR), op register, level address key register (AKR), or processor status word (PSW).
- Stop-on-address.
- · Stop-on-error.
- Instruction step.
- · Check restart.
- Request a console interrupt.
- Check indicator, on when a machine check or program check class interrupt has occurred.


The Programmer Console is touch sensitive with a audio tone generator providing an audio response tone whenever a key depression has been accepted and serviced by the processor.

Console Display

When the processor is in run state, the console data buffer is displayed in the data display indicators. The only exception to this is when a Set Console Data Lights instruction writes a message to the data display. This message remains displayed until the processor enters stop state or the Data Buffer Key is pressed. When the Data Buffer Key is pressed, the console data buffer is again displayed in the data display indicators.

When the processor enters stop state, the IAR is displayed in the data display indicators. Any system resource that has a corresponding select key on the console can be displayed while in stop state. Once data has been entered into the console data buffer, it remains there until other data is entered. The console data buffer can be displayed at any time, during either run state or stop state, by pressing the Data Buffer key.

After a power-on reset, the data display indicators are all set on, and the level indicators are set off.




Indicators

A Data Display

- When the processor is in run state, the console data buffer is displayed in the data display indicators.
- When the processor enters stop state, the IAR is displayed unless another system resource is selected.
- To display the contents of the console data buffer after a system resource has been displayed, press the Data Buffer key.

B Check

On when a machine check or program check class interrupt has occurred. The check indicator remains on until either the check condition is cleared, or any console key is pressed while in the stop state. The check condition is cleared by the Reset key, Load key, or the execution of a Copy Processor Status and Reset instruction (which resets the check bits). If a main storage display of a location with a parity error is performed, the check indicator is turned on, or appears to remain on.



Combination Keys/Indicators

There are nine combination key/indicators:

- Level 0, 1, 2, and 3
- Stop
- Stop On Address
- Instruct Step
- Check Restart
- Stop On Error

A Level 0-3

The current active level is always displayed by one of the level indicators. When in the stop state, pressing any of the level keys causes that level to be selected and the associated indicator is turned on.

B Stop

This indicator is on when the processor is in the stop state. Stop state is entered in the following ways:

- By pressing the Stop key.
 - In run state the current instruction is completed.
 - In wait state, stop state is entered directly.
 - In the stop state, the contents of the IAR upon entering stop state are restored to the IAR and displayed in the lights. The level that was active upon entering stop state is reselected (becomes active).
- By execution of the Stop instruction (diagnostic mode only).
- When an address compare occurs in stop-on-address mode.
- When an error occurs in stop-on-error mode.
- By pressing the Reset key.
- When a power-on reset occurs.
- By selecting the Instruction Step mode while in run state.

The Stop On Address key and the Instruction Step key a mutually exclusive. When one is pressed, the other is reset it was on.

C Stop on Address

This key places the processor in stop c address mode. Pressing the Stop On Addre key a second time resets stop on addre mode and turns off the indicator.


Instruction Step Pressing the Instruct Step key places the processor in instruction step mode and turn the Instruction Step indicator on. The Sto On Address indicator is turned off if it we on.

If the processor is in run state, pressin this key causes the processor to enter sto state. Pressing the Instruction Step key second time resets instruction step mode the processor remains in stop state.

To operate in instruction step mode:

- Key the desired starting address and stor into the IAR.
- Press the Instruct Step key.
- Press the Start key. The instruction located at the selected address is executed, the processor returns to stopstate. The IAR is updated to the next instruction address, this address is displayed in the data display indicators.
- Each subsequent depression of the Star key causes one instruction to be executed and the IAR is updated to the next instruction address.

Note. Priority and class interrupts are not inhibited during execution of the instruction.




Stop On Address Mode

Processor must be in stop state to set the compare address.

- 1. If the Storage Address Relocation Feature is not installed go to step 2, otherwise:
 - a. Press AKR key (selects console AKR when all level lights are off).
 - b. Key in the Address Key (ISK bits of AKR).
 - c. Press Store key.
- 2. Press Stop On Address Key.
- 3. Key in selected address.
- 4. Press Store Key. The selected address and address key are placed in the stop on address buffer.
- 5. Press Start Key. Execution begins at current IAR address on the current level.

When the selected address is loaded into the IAR, the processor enters stop state. To exit stop state press the Start key; execution begins at the next sequential address.



The Check Restart key and the Stop On Error key are mutually exclusive. When one is pressed the other is reset if it was on.

E Check Restart

Pressing this key places the processor in check restart mode. While in this mode, a program check, a machine check, or a power/thermal warning class interrupt causes the processor to be reset and execution to restart at address zero on level zero.

Note. The power/thermal warning class interrupt is controlled by the summary mask.

Stop On Error

Pressing this key places the processor in stop on error mode. Any program check, machine check, or power/thermal warning causes the processor to enter stop state. To determine the cause of the error, display the PSW (see table). To restart the processor, press the Reset key then the Start key. Pressing only the Start key, allows the processor to proceed with the class interrupt as if stop mode had not occurred. Note that the check indicator may have been turned off while in stop state. After the class interrupt routine is completed, control may be returned to the instruction that caused the error and an attempt to reexecute the instruction may be made. Note that some instructions are not reexecutable because operand registers or storage locations were changed before the instruction was terminated (because of the initial error). In these cases, the operator must be familiar with the program because manual restoration of affected locations must be made before restart is attempted.

Note. The power/thermal warning class interrupt is controlled by the summary mask.

Processor Status Word (PSW) Table

1,000	, ,	
Bit	Meaning	Category
0	Specification check	Program check
1	Invalid storage address	Program check
2	Privilege violate	Program check
3	Protect check	Program check
4	Invalid function	Soft exception
	(may be program check)	
5	Floating point exception	Soft exception
6	Stack exception	Soft exception
7	Not used	
8	Storage parity check	Machine check
9	Not used	
10	CPU control check	Machine check
11	I/O check	Machine check
12	Sequence indicator	Status flag
13	Auto-IPL	Status flag
14	Translator enabled	Status flag
15	Power/thermal warning	Power/Thermal

Bits not used are always zero.

Keys and Switches

A Reset

This key initiates a system reset that performs the following functions:

- IAR on level zero set to zeros.
- · AKR on level zero set to zeros.
- Console AKR set to zero.
- Interrupt mask set to all levels enabled.
- LSR on level zero—indicators set to zero, summary mask enabled, supervisor state and in-process flag turned on, trace disabled.
- LSRs for levels 1-3 set to zeros.
- PSW set to zero.
- SAR set to zeros.
- CIAR set to zeros.

After the system reset is completed, the processor is placed in the stop state with stop indicator on.

The following resources are not affected by system reset:

- General registers (all levels)
- IARs (levels 1-3)
- AKRs (levels 1-3)
- Storage key stack
- Main storage
- · Console data buffer
- Segmentation registers (relocation translator feature)
- Floating-point registers (floating-point feature)
- Stop on Address buffer.

B Store

This key is effective only when the processor is in stop state. Pressing this key causes the last data entry to be stored in the last selected resource.

C Data Buffer

Pressing this key causes the contents of the console data buffer to be displayed in the data display indicators.


D Console Interrupt

The effect of this key depends on the state of the processor. If the processor is in the stop or load states, this key has no effect. If the processor is in the run or wait state and the summary mask is enabled, a console class interrupt occurs.

E Start

Effective in stop state only. Stop state is exited and the processor resumes execution at the address in the IAR on the current level. If stop state was entered from system reset, execution begins at address zero, level zero. If stop state was entered from wait state, the processor returns to wait state.

Note. The Reset and Console Interrupt keys have an indication (+++) on the face of of the keys. This signifies that additional pressure must be used to activate these keys. This is to minimize the possibility of the operator inadvertently activating these functions.



F PSW

Pressing this key selects the processor status word. The contents of the PSW are displayed in the data display indicators. Data cannot be stored into the PSW from the console.

G Op Reg

Data cannot be stored into the Op register from the console. Pressing this key selects the Op register and displays the contents in the data display indicators.

H CIAR

Pressing this key after entering stop state causes the address of the instruction just executed to be displayed. Data cannot be stored into the CIAR from the console.

J SAR

Pressing this key while in stop state displays the contents of the storage address register. An address can be stored into the SAR to address main storage for display or store operations. Bit 15 of the SAR cannot be set from the console.

K Main Storage

Pressing this key selects main storage as the facility to be accessed by the console. When this key is pressed, the contents of the main storage location addressed by the SAR is displayed in the data display indicators. Procedures for displaying and storing main storage are provided in subsequent sections of this chapter.

0 010 0 000000 00 Stop Reset Check Interrup 0 0 Stop On Instruct Check Error \bigcirc CIAR J G LSR Κ RO R3

Level Dependent Keys

The following keys select registers that are duplicated in hardware for each of the four interrupt levels:


- LSR
- AKR
- IAR
- General purpose registers 0-7

Pressing any of these keys, once a level has been selected, causes the contents of that register to be displayed in the data display indicators.

The level status register (LSR) is displayable only; data cannot be stored into this register.


To display an AKR for a given level, press the AKR key; the console AKR is displayed in the data display indicators, and the level indicators are reset. Press the desired Level key; the contents of the AKR for that level are now displayed. The level AKRs are displayable only. The console AKR is used for console operations only, and data can be stored into or displayed from this register.

Bit 15 of the IARs cannot be changed from the console. Pressing the Store key after selecting an LSR or AKR results in no action taken and no audio tone response.



Data Entry Keys

The sixteen data entry keys are used to enter data into the selected resource.



Example: Data to be entered: F3A8

O- Indicator off

Action Data display indicators Press data entry key F 10 11 Press data entry key 3 Press data entry key A Press data entry key 8 Legend: - Indicator on

Displaying Main Storage Locations

- Machine must be in stop state.
- If the Storage Address Relocation Translator Feature is installed and enabled, start at step 1, otherwise start at step 4.
- Press the AKR key. A
 The contents of the console AKR are displayed in the data display indicators.
- 2. Key in one hex character (new address key). This character is displayed in bits 12-15 of the data display indicators. Bit 12 is ignored when the address key is stored (the key is stored in bits 13-15).
- 3. Press the Store key B to Store the new address key into the AKR.
- 4. Press the SAR key. C
 The contents of the SAR are displayed in the data display indicators.
- Key in the selected address (four hex characters). This address is displayed in the data display indicators.
- 6. Press the Store key. B

 The address that is displayed is stored into the SAR.
- 7. Press the Main Storage key. D

 The contents of the addressed storage location are displayed in the data display indicators. To display sequential main storage locations, continue pressing the Main Storage key. The storage address is incremented by +2 each time the Main Storage key is pressed, and the addressed location is displayed.


Note. The use of the procedure at step 1 through 3, assumes a thorough knowledge of the relocation translator feature and the storage mapping assigned by the program.

Storing Into Main Storage

- Machine must be in stop state.
- If the Storage Address Relocation Translator Feature is installed and enabled, start at step 1, otherwise start at step 4.
- Press the AKR key. A
 The contents of the console AKR are displayed in the data display indicators.
- 2. Key in one hex character (new address key). This character is displayed in bits 12-15 of the data display indicators. Bit 12 is ignored when the address key is stored (the key is in bits 13-15).
- 3. Press the Store key. B to store the new address key into the AKR.
- 4. Press the SAR key. C
 The current contents of the SAR are displayed in the data display indicators.
- 5. Key in the selected address (four hex characters). The address is displayed in the data display indicators.
- 6. Press the Store key. B
 The address displayed in the data display indicators is stored into the SAR.
- Press the Main Storage Key. D
 The contents of the addressed storage location are displayed in the data display indicators.
- 8. Key in the data that is to be stored into main storage. This data is displayed in the data display indicators.
- 9. Press the store key. B

 The data that is displayed is stored at the selected storage location. Each subsequent pressing of the Store key causes the SAR to be incremented by +2, and the data stored at the location is displayed.

Note. The use of the procedure at step 1 through 3, assumes a thorough knowledge of the relocation translator feature and the storage mapping assigned by the program.



Displaying Registers

- Processor must be in Stop State.
- 1. Select the proper level by pressing the appropriate Level key.

The contents of any register associated with the selected level can now be displayed by pressing the register key.

 Press the desired register key. The contents of that register are displayed in the data display indicators.


To display the same register on each level, select the register, then press each level key. Each level selection causes the selected register for that level to be displayed in the data display indicators.

Storing Into Registers

- Processor must be in stop state.
- 1. Select the proper level by pressing the appropriate Level key.
- Press the key for the register where data is to be stored. The contents of that register are displayed in the data display indicators.
- Key in the data that is to be stored. This data is displayed in the data display indicators.
- 4. Press the Store key. C

The data that is displayed is stored into the selected register.

To store into the corresponding register on another level, select the level and proceed with step 3; or, if the same data is to be stored, select the level and press the Store key.



The instructions (excluding floating-point instructions) for the IBM 4955 Processor are described in this chapter. Floating-point instructions are described in Chapter 6. A complete listing of instruction formats is contained in Appendix B. Instruction timings are contained in Appendix A. Indicator settings are listed for each instruction. For additional indicator information, refer to Indicators in Chapter 2.

EXCEPTION CONDITIONS

Exception conditions that might occur during instruction execution are shown in abbreviated form with each instruction description. Refer to the following sections for a detailed description of these conditions.

Program Check Conditions

Invalid Function

(1) An illegal operation code or function combination is encountered during instruction execution, or (2) while in supervisor state, the processor attempts to execute a Copy Segmentation Register (CPSR) or Set Segmentation Register (SESR) instruction and the optional relocation translator feature is not installed.

A program check class interrupt occurs with invalid function (bit 4) set in the PSW.

Invalid Storage Address

Instruction word or operand. One or more words of the instruction or the effective address is outside the installed storage size of the system. The instruction is suppressed unless otherwise noted in the individual instruction description.

A program check class interrupt occurs with invalid storage address (bit 1) set in the PSW.

Privilege Violate

Privileged instruction. A privileged instruction is encountered while in problem state. The instruction is suppressed.

A program check class interrupt occurs with privilege violate (bit 2) set in the PSW.

Protect Check

Instruction fetch or operand access. In the problem state, an instruction is fetched or data is accessed from a storage area not assigned to the current operation.

Operand store. In the problem state, the instruction attempts to change an operand in a storage area assigned as

The instruction is suppressed unless otherwise noted in the individual instruction description. A program check class interrupt occurs with protect check (bit 3) set in the PSW.

Specification Check

Operand address. The generated effective address has violated an even-byte boundary requirement.

Indirect address. When using addressing mode (AM=11), the indirect address is not on an even-byte boundary.

The instruction is suppressed unless otherwise noted in the individual instruction description. A program check class interrupt occurs with specification check (bit 0) set in the PSW.

Soft Exception Trap Conditions

Invalid Function

(1) A floating-point instruction (operation code 00100) is attempted and the floating-point feature is not installed, or (2) a Set Floating Level Block (SEFLB) or Copy Floating Level Block (CPFLB) instruction is attempted while in supervisor state, and the floating-point feature is not installed.

The instruction is suppressed. A soft-exception-trap class interrupt occurs with invalid function (bit 4) set in the PSW.

AB

Stack Exception

(1) The stack is full and a Push instruction or a Store Multiple (STM) instruction is attempted, (2) the stack is empty and a Pop instruction or a Load Multiple and Branch (LMB) instruction is attempted, or (3) the stack cannot contain the number of words to be stored by a Store Multiple instruction.

The instruction is suppressed. A soft-exception-trap class interrupt occurs with *stack exception* (bit 6) set in the PSW.

Note. When the AM field is equal to 01, the register specified by the RB field is incremented before the class interrupt occurs.

INSTRUCTION TERMINATION OR SUPPRESSION


Exception conditions that occur during instruction processing might cause the instruction to be terminated or suppressed. When an instruction is terminated, partial execution has taken place and may have caused a change to registers, indicators, or main storage. When an instruction is suppressed, there has been no execution, therefore, no changes. Refer to *Exception Conditions* in the previous section.

Instruction Descriptions

The following descriptions are in alphabetical sequence based on assembler mnemonics. However, extended mnemonics are listed under the appropriate machine instruction. For example: branching, jumping, and address key register instructions.

ADD BYTE (AB)

AB reg,addr4 addr4,reg



An add operation is performed between the least significant byte of the register specified by the R field and the location specified by the effective address in main storage. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand and high-order byte of the register are unchanged.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the byte. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one byte; i.e., if the sum is less than -2^7 or greater than $+2^7-1$.

If an overflow occurs, the result contains the correct low-order eight bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

ADD BYTE IMMEDIATE (ABI)

ABI

byte,reg

Op	era	tior	ı co	de	Ī	R	Γ	Immediate	
0	0	0	0	0					
0				4	5	7	8		15

The immediate field is expanded to 16 bits by sign propagation to the eight high-order bits. The field is then added to the contents of the register specified by the R field. The result is placed in the register specified by the R field.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Protect Check. Instruction fetch.

ADD CARRY REGISTER (ACY)

ACY

Operation code Function 0 0 0 $0 \ 1 \ 1 \ 0 \ 0$ 0 1 1 1 0

The value of the carry indicator on entry is added to the contents of the register specified by the R2 field, and the result is placed in the register specified by the R2 field. Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Programming Note. This instruction can be used when adding multiple word operands. See Indicators-Multiple Word Operands in Chapter 2.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even. Unchanged.

Negative. Changed to reflect the result.

Zero. If on at entry, changed to reflect the result. If off at entry, it remains off.

Program Check Conditions


Protect Check. Instruction fetch.


AD

ADD DOUBLEWORD (AD)

Register/Storage Format

AD reg,addr4 addr4,reg





An add operation is performed between the register pair specified by the R field (R and R+1) and the doubleword in main storage specified by the effective address. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

If the R field equals 7, register 7 and register 0 are used.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the doubleword. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in the doubleword; i.e., if the sum is less than -2^{31} or greater than $+2^{31}-1$.

If an overflow occurs, the result contains the correct low-order 32 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the indicators is unpredictable.


Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

AD addr5,addr4







The address arguments generate the effective address of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) Doubleword operand 1 is added to doubleword operand 2. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the doubleword. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in the doubleword; i.e., if the sum is less than -2^{31} or greater than $+2^{31}-1$.

If an overflow occurs, the result contains the correct low-order 32 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If RB1 and RB2 specify the same register and AM1=01, the register is incremented before the program check interrupt occurs.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand store, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

ADD WORD (AW)

Register/Register Format

AW

reg,reg

Op	era	tio	n cc	de	1	R <i>1</i>		R2	Г	Fu	nct	ion	
0	1	1	1	0					0	1	0	0	0
0				4	5	7	8	10	11				15

The contents of the register specified by the R1 field are added to the contents of the register specified by the R2 field. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field remain unchanged if R1 and R2 do not specify the same register.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions


Protect Check. Instruction fetch.

Register/Storage Format

AW

reg,addr4 addr4,reg





An add operation is performed between the register, specified by the R field and the location specified by the effective address in main storage. (See Effective Address Generation in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

AW

Storage to Register Long Format



longaddr,reg





The contents of the main storage location specified by an effective address are added to the contents of the register specified by the R1 field. The result is placed in the register specified by the R1 field.

The effective main storage address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0 (direct address). The result from step 1 is the effective address.

Bit 11=1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch.


Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

V addr5,addr4







The address arguments generate the effective addresses of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) Word operand 1 is added to word operand 2. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

ADD WORD WITH CARRY (AWCY)

AWCY

reg,reg

ſ	Op	era	tion	co	de		R1	Τ	R2	Function					
L	0	1	1	1	0					0	1	0	0	1	
_	0				4	5	7	8	10	11				15	

This instruction adds three terms together:

- (R1) the contents of the register specified by the R1 field.
- (R2) the contents of the register specified by the R2 field.
- C the value of the carry indicator at entry.

The contents of the register specified by the R1 field are unchanged if R1 and R2 do not specify the same register. The final result replaces the contents of the register specified by the R2 field.

Programming Note. This instruction can be used when adding multiple word operands. See Indicators-Multiple Word Operands in Chapter 2.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even. Unchanged.

Zero. If on at entry, set to reflect the result. If off at entry, remains off.

Negative. Changed to reflect the result.

Program Check Conditions


Protect Check. Instruction fetch.

AWI

ADD WORD IMMEDIATE (AWI)

Register Immediate Long Format

AWI word,reg[,reg]



The immediate field is added to the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged if R1 and R2 do not specify the same register.

Indicators

16

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word.


Protect Check. Instruction fetch.

Storage Immediate Format


AWI


word,addr4


Format without appended word for effective addressing (AM = 00 or 01)



Format with appended word for effective addressing (AM = 10 or 11)







The immediate field is added to the contents of the location specified by the effective address. (See *Effective Address Generation* in Chapter 2.) The result replaces the contents of the storage location specified by the effective address.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The immediate operand is unchanged.

Indicators

Carry. Turned on if a carry is detected out of the high-order bit position of the word. If no carry is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the sum cannot be represented in one word; i.e., if the sum is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the sum; the carry indicator contains the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

BRANCH UNCONDITIONAL (B)


longaddr


Extended Assembler Mnemonic

BX

vcon

Branch External





An effective branch address is generated and loaded into the instruction address register, becoming the next instruction to be fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11=1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Indicators.

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or effective branch address.

Protect Check. Instruction fetch.

BALS BALS

BRANCH AND LINK (BAL)

BAL


longaddr,reg


Extended Assembler Mnemonic

BALX

vcon,reg

Branch and Link External





The updated value of the instruction address register (the address of the next sequential instruction) is stored into the register specified by the R1 field. An effective branch address is then generated and loaded into the instruction address register, becoming the next instruction to be fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11=1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Programming Note. If R1 and R2 specify the same register the initial contents are used in effective address computation and subsequently overwritten by the return data.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or effective branch address. No branch is taken, but the contents of the register specified by the R1 field are still changed. The instruction is terminated.

Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (indirect address or branch address). The instruction is terminated. No branch is taken but the contents of the R1 register are changed.

BRANCH AND LINK SHORT (BALS)

BALS

(reg,jdisp)*
(reg)*
addr*

0	pera	ıtic	on	co	de	R			Word displac	ement
1	1	1		1	1				L	
0					4	5		7	8	15

The updated contents of the instruction address register (the location of the next sequential instruction) are stored in register 7.

Bit 8 of the word displacement field is propagated left by 7 bit positions and a zero is appended at the low order end, resulting in a 16-bit word. (Word displacement is converted to a byte displacement.) This value is added to the contents of the register specified by R to form an effective address. The contents of the storage location specified by the effective address are stored into the instruction address register, and become the address of the next instruction to be fetched.

Programming Note. If the implied register (R7) is used as a base register, the initial contents of R7 are used in effective address computation and subsequently overwritten by the return data.

Indicators

No indicators are changed.

Program Check Conditions


Invalid Storage Address. Effective address. The instruction is terminated. Branching does not occur but storing of the updated instruction address into R7 does occur.


Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (effective address). The instruction is terminated. Branching does not occur but storing of the updated instruction address into R7 does occur.

BRANCH ON CONDITION (BC)

Mnemonic BC	Operand syntax cond,longaddr	Instruction name Branch on Condition	Condition field bits (see A) Any value listed below
_			Condition
Extended	Operand		field
Mnemonic	syntax	Instruction name	bits (see A)
BE	longaddr	Branch on Equal	000
BOFF	longaddr	Branch if off	000
BZ	longaddr	Branch on Zero	000
BP	longaddr	Branch on Positive	001
BMIX	longaddr	Branch if Mixed	001
BN	longaddr	Branch if Negative	010
BON	longaddr	Branch if On	010
BEV	longaddr	Branch on Even	011
BLT	longaddr	Branch on Arith-	100
		metically Less Than	
BLE	longaddr	Branch on Arith-	101
		metically Less	
		Than or Equal	
BLLE	longaddr	Branch on Logically	110
		Less Than or Equal	
BCY	longaddr	Branch on Carry	111
BLLT	longaddr	Branch on Logically	111
		Less Than	





This instruction tests the condition of the various indicators (LSR bits 0-4). If the condition tested is met, the effective branch address is loaded into the instruction address register and becomes the next address to be fetched.

If the condition tested is not met, the next sequential instruction is fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11=1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Indicators.

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or effective address.

Protect Check. Instruction fetch.



INVERT REGISTER (VR)

VR

reg[,reg]

O	pera	itio	n co	ode	F	21	2	F	unc	tio	$\overline{\imath}$		
0	1	1	1	0					0	1	1	0	1
0				4	5	7	8	10	11				15

The contents of the register specified by the R1 field are one's complemented. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions


Protect Check. Instruction fetch.

EXCLUSIVE OR BYTE (XB)

XB

reg,addr4 addr4,reg





A logical exclusive OR operation is performed between the least significant byte of the register specified by the R field and the main storage location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged. Also, when going from storage to register, bits 0-7 of the register are unchanged.

Example of Exclusive OR Byte:

 Register contents
 0000
 1010
 1100
 0011

 Storage operand
 0110
 0101

 Result
 1010
 0110

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the exclusive OR operation.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

BRANCH ON NOT CONDITION (BNC)

Mnemonic	Operand	Total Car	Condition field
	Syntax	Instruction name	bits (see A)
BNC	cond,longaddr	Branch on Not	Any value
		Condition	listed below
Extended	0		Condition
	Operand		field
mnemonic	Syntax	Instruction name	bits (see A)
BNE	longaddr	Branch on Not Equal	000
BNZ	longaddr	Branch on Not Zero	000
BNOFF	longaddr	Branch if Not OFF	000
BNP	longaddr	Branch on Not	001
		Positive	
BNMIX	longaddr	Branch on Not Mixed	001
BNN	longaddr	Branch on Not	010
BNON	longaddr	Negative	
BNON	longaddr	Branch if Not On	010
BNEV	longaddr	Branch on Not Even	011
BGE	longaddr	Branch on Arith-	100
		metically Greater	
		Than or Equal	
BGT	longaddr	Branch on Arith-	101
		metically	
		Greater Than	
BLGT	longaddr	Branch on Logically	110
		Greater Than	
BLGE	longadd r	Branch on Logically	111
		Greater Than or Equal	
BNCY	longaddr	Branch on No Carry	111





This instruction tests the various indicators (LSR bits 0-4). If the condition tested is met, the effective branch address is loaded into the instruction address register and becomes the next address to be fetched.

If the condition tested is not met, the next sequential instruction is fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11 = 1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or effective address.

Protect Check. Instruction fetch.


BNCC


BRANCH ON NOT CONDITION CODE (BNCC)

BNCC cond,longaddr

Extended mnemonic

BER longaddr Branch on Error (CC Field=111)





The value of the CC field is compared to the even, carry, and overflow indicators. These indicators hold the I/O conditions code: (1) following and I/O instruction or (2) following an I/O interrupt.

CC bit	Indicator
5	Even
6	Carry
7	Overflow

If the conditions do not match, an effective branch address is generated and loaded into the instruction address register, becoming the next instruction to be fetched.

If the conditions match, the next sequential instruction is fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11 = 1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or effective address.

Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (indirect address or branch address).

I/O Condition Codes

The I/O condition codes are summarized in the following tables. Refer to chapter 7 for a detailed description of each condition code value. Also refer to the specific I/O device descriptions because some devices do not report all condition codes.

Condition Codes Reported After I/O Instruction.

Condi- tion Code	Indicators Even	Carry	Overflow	Meanings
0	0	0	0	Device not attached
1	Ö	0	1	Busy
2	0	1	0	Busy after reset
3	0	1	1	Command reject
4	1	0	0	Intervention required
5	1	0	1	Interface data check
6	1	1	0	Controller busy
7	1	1	1	Satisfactory


Condition Codes Reported During an I/O Interrupt.


Condi- tion Code	Indicators Even	Carry	Overflow	Meanings
0	0	0	0	Controller end
1	0	0	1	PCI (program controlled
				interrupt)
2	0	1	0	Exception
3	0	1	1	Device end
4	1	0	0	Attention
5	1	0	1	Attention and PCI
6	1	1	0	Attention and Exception
7	1	1	1	Attention and device end

BRANCH ON NOT OVERFLOW (BNOV)

BNOV

longaddr





The overflow indicator is tested. If the indicator is off, the effective branch address is loaded into the instruction address register and becomes the next address to be fetched.

If the overflow indicator is on, the next sequential instruction is fetched.

The effective branch address is generated as follows:

- The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11 = 1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Indicators

All indicators are unchanged.

Program Check Conditions


Invalid Storage Address. Instruction word or effective address.

Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (indirect address or branch address).

BRANCH ON OVERFLOW (BOV)

BOV longaddr





The overflow indicator is tested. If the indicator is on, the effective branch address is loaded into the instruction address register and becomes the next address to be fetched.

If the overflow indicator is off, the next sequential instruction is fetched.

The effective branch address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0. The result from step 1 is a direct address and is loaded into the instruction address register.

Bit 11 = 1. The result from step 1 is an indirect address. The contents of the main storage location specified by the result are loaded into the instruction address register.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or effective address.


Protect Check. Instruction fetch.

BXS

BRANCH INDEXED SHORT (BXS)

BXS
$$(reg^{1-7}, jdisp)$$

 (reg^{1-7})
addr



Bit 8 of the word displacement field is propagated left seven bit positions and a zero is appended at the low order end, resulting in a 16-bit word. (Word displacement is converted to a byte displacement.) This value is added to the contents of the register specified by the R field, and the result is stored into the instruction address register, becoming the address of the next instruction to be fetched.

Note. The hardware format of this instruction is identical to the format used for the Jump Unconditional (J) and No Operation (NOP) instructions.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address.

Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (branch address).

COMPARE BYTE (CB)

Register/Storage Format

CB addr4,reg

0	pera	itio	n co	ode	Π	R		R	В	AM	1	F	unc	tio	ı
1	1	0	0	0	l			İ				0	1	0	0
0				4	5		7	8	9	10	11	12	,		15

Address	/Displacement
Displacement 1	Displacement 2
16 23	24 31

The contents of the location specified by the effective address in main storage are subtracted from the least significant byte of the register specified by the R field. (Effective Address Generation is explained in Chapter 2.)

Neither operand is changed.

Bit 12 is not used and must be set to zero to avoid future code obsolescence.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address).

Storage/Storage Format

CB addr5,addr4

0	Operation code 0 0 0 0			de	RB1		RB.	2	AM1	AM2	Fu	n
1	0	0	0	0							1	1
0				4	5	7	8 9	,	10 11	12 13	14	75





The address arguments generate the effective addresses of the two operands in main storage. (Effective Address Generation is explained in Chapter 2.) Byte operand 1 is subtracted from byte operand 2. Neither operand is changed.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch or operand access. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Specification Check. Even byte boundary violation (indirect address).

CBI

COMPARE BYTE IMMEDIATE (CBI)

CBI

byte,reg

O_{l}	era	tio	n co	ode	R		Immediate	
1	1	1	1	0	١.			
0				4	5	7	8	15

The immediate field is extended to 16 bits by sign propagation to the eight high-order bit positions. The result is subtracted from the contents of the register specified by the R field. Neither operand is changed.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less the -2^{15} or greater than $+2^{15}-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Protect Check. Instruction fetch.


COMPARE DOUBLEWORD (CD)

Register/Storage Format

CD

addr4,reg

0	per	ati	01	ı co	ode		R		R	В	AM	1	F	unc	tio	n
1	1	C)	1	0				ĺ		!		0	1	0	0
0					4	5		7	8	9	10	11	12			15



The contents of the doubleword in main storage specified by the effective address are subtracted from the contents of the register pair specified by the R field and R+1. (Effective Address Generation is explained in Chapter 2.)

Neither operand is changed.

Bit 12 of the instruction is not used and must be set to zero to avoid future code obsolescence. If the R field equals 7, register 7 and register 0 are used.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the doubleword. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in the doubleword; i.e., if the difference is less than -2^{31} or greater than $+2^{31}-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).


Storage/Storage Format

CD

addr5,addr4







The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) Doubleword operand 1 is subtracted from doubleword operand 2. Neither operand is changed.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the operand. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one doubleword; i.e., if the difference is less than -2^{31} or greater than $+2^{31}-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch or operand access. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Specification Check. Even byte boundary violation (indirect address or operand address).


5-19

CFED CFEN

COMPARE BYTE FIELD EQUAL AND DECREMENT (CFED)

COMPARE BYTE FIELD EQUAL AND INCREMENT (CFEN)

CFED (reg),(reg) CFEN (reg),(reg)



This instruction compares two fields in main storage on a byte for byte basis. Register 7 contains the number of bytes to be compared. This number is decremented after each byte is compared. The register specified by R1 contains the address of operand 1. The register specified by R2 contains the address of operand 2. Operand 1 is subtracted from operand 2, but neither operand is changed. After each byte is compared, the addresses in R1 and R2 are incremented or decremented (determined by bit 13 of the instruction). The operation terminates when either:

- 1. An equal condition is detected, or
- 2. The number of bytes specified in register 7 has been compared.

When an equality occurs, the addresses in the registers point to the next operands to be compared, but the count in R7 is not updated.

Bit 11 of the instruction is not used and must be set to zero to avoid future code obsolescence.

See Scan Byte Field Equal and Decrement (SFED) and Scan Byte Field Equal and Increment (SFEN) for other versions of this machine instruction.

Notes.

- 1. If the specified count in R7 is zero, the instruction performs no operation (No-op).
- 2. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining byte count specified in register 7.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Operand. The instruction is terminated.

Protect Check. Instruction fetch or operand access. The instruction is terminated.

COMPARE BYTE FIELD NOT EQUAL AND DECREMENT (CFNED)

COMPARE BYTE FIELD NOT EQUAL AND INCREMENT (CFNEN)

CFNED (reg),(reg) CFNEN (reg),(reg)



This instruction compares two fields in main storage on a byte for byte basis. Register 7 contains the number of bytes to be compared. This number is decremented after each byte is compared. The register specified by R1 contains the address of operand 1. The register specified by R2 contains the address of operand 2. Operand 1 is subtracted from operand 2, but neither operand is changed. After each byte is compared, the addresses in R1 and R2 are incremented or decremented (determined by bit 13 of the instruction). The operation terminates when either:

- 1. An unequal condition is detected, or
- 2. The number of bytes specified in register 7 has been compared.

When an inequality occurs, the addresses in the registers point to the next operands to be compared, but the count in R7 is not updated.

Bit 11 is not used and must be set to zero to avoid future code obsolescence.

See Scan Byte Field Not Equal and Decrement (SFNED) and Scan Byte Field Not Equal and Increment (SFNEN) for other versions of this machine instruction.

Notes.

- 1. If the specified count in R7 is zero, the instruction performs no operation (no-op).
- 2. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining byte count specified in register 7.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Operand. The instruction is terminated.

Protect Check. Instruction fetch or operand access. The instruction is terminated.

CMR

COMPLEMENT REGISTER (CMR)

CMR

reg[,reg]

<u>,</u>	2000	ıtio	n c	ode	R1		R2		F	unc	tio	n	
0	1	1	1	0					0	0	1	1	0
0				4	5	7	8	10	11	!			15

The contents of the register specified by the R1 field are converted to the two's complement. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged if R1 and R2 do not specify the same register.

Indicators

Carry. Reset. Then turned on if the number to be complimented is zero.

Overflow. Reset. Then turned on if the number to be complemented is the maximum negative number representable.

Even, Negative, and Zero. Unchanged.

Program Check Conditions


Protect Check. Instruction fetch.

COPY ADDRESS KEY REGISTER (CPAKR)

System Register/Storage Format

Mnemonic	<i>Syntax</i>	Instruction name Copy Address Key Register	K field
CPAKR	addr4		011
Extended Mnemonic CPISK CPOOK CPOTK	Syntax addr4 addr4 addr4	Instruction name Copy Instruction Space Key Copy Operand 1 Key Copy Operand 2 Key	K field 000 010 001

O_l	peration cod			ode	Τ	K		R	В	AM	F	unc	tio	n
0	1	0	1	1						1	1	0	1	0
0				4	5		7	8	9	10 11	12	?		15



The contents of the address key register (AKR) field, specified by the K field, are stored into the word location specified by the effective address. The contents of the AKR are unchanged. (Effective Address Generation is explained in Chapter 2.) The K field can specify: (1) a field within the AKR or; (2) the entire AKR.

K field	Address key register field name	Bits
000	Instruction space key	13-15
001	Operand 2 key	9-11
010	Operand 1 key	5-7
011	Address key register	0-15
100	Unused	
101	Unused	
110	Unused	
111	Unused	

Unused K-field values should not be used to avoid future program obsolescence.

If the K field specifies a specific field within the AKR, the specified field is stored in bits 13-15 of the word location in main storage. Bits 0-12 of the word in main storage are set to zero. If the K field specifies the entire AKR, the entire AKR is stored in the word location in main storage.

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

System Register/Register Format

Mnemonic CPAKR Extended	Syntax reg	Instruction name Copy Address Key Register	K field 011
Mnemonic	Syntax	Instruction name	K field
CPISK CPOOK CPOTK	reg reg reg	Copy Instruction Space Key Copy Operand 2 Key Copy Operand 1 Key	000 001
	105	Copy Operand 1 Key	010

o_l	pera	itio	n co	ode	K		R		F	unc	tio	n	
0	1	1	1	1					1	1	0	1	0
0				4	5	7	8	10) 11				15

The contents of the address key register (AKR) field, specified by the K field, are loaded into the register specified by the R field. The contents of the AKR are unchanged. The K field can specify: (1) a field within the AKR, or; (2) the entire AKR.

K field	Address key register field name	Bits
000	Instruction space key	13-15
001	Operand 2 key	9-11
010	Operand 1 key	5-7
011	Address key register	0-15
100	Unused	
101	Unused	
110	Unused	
111	Unused	

Unused K-field values should not be used to avoid future program obsolescence.

If the K field specifies a specific field within the AKR, the specified field is loaded into bits 13-15 of the register in the R field. Bits 0-12 of the register are set to zero. If the K field specifies the entire AKR, the entire AKR is loaded into the register.

Indicators

All indicators are unchanged.

Program Check Conditions

Privilege Violate. Privileged instruction.

CPCL CPCON

COPY CURRENT LEVEL (CPCL)

CPCL reg

ſ	Oı		ıtio.	n co	ode				R2		F	unc	tio	n	
	0	1	1	1	1	0	0	0			1	1	0	0	1
	0				4	5		7	8	10) 11				15

The register specified by the R2 field is loaded as follows:

- Bits 0 through 13 are set to zero.
- Bits 14 and 15 are set to the binary-encoded current level. For example if the current level is three, bits 14 and 15 are set to 11.

Bits 5-7 of the instruction are not used and must be set to zero to avoid future code obsolescence.

Indicators

All indicators are unchanged.

Program Check Conditions

Privilege Violate. Privileged instruction.

COPY CONSOLE DATA BUFFER (CPCON)

CPCON re

O	era	tio	n cc	de	Τ			R2		F	unc	tio	ı	
0	1	1	1	1	0	0	0			1	1	0	0	0
6				4	5		7	8	10	11				15

The contents of the console data buffer are loaded into the register specified by the R2 field. The contents of the buffer are unchanged.

Bits 5-7 of the instruction are not used and must be set to zero to avoid future code obsolescence. If the programmer console is not installed, the data loaded into the specified register is undefined.

Indicators

Carry and Overflow. Unchanged


Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions

Privilege Violate. Privileged instruction.

COPY INTERRUPT MASK REGISTER (CPIMR)

CPIMR addr4





The contents of the interrupt mask register are stored at the word location in main storage specified by the effective address. (See Effective Address Generation in Chapter 2.) The interrupt mask register is unchanged.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The mask is represented in a bit significant manner as follows:

Mask bit	Interrupt level
0	0
1	1
2	2
3	3

Bits 4-15 are set to zero.

A mask bit set to "1" indicates that the level is enabled. A mask bit set to "0" indicates that the level is disabled.

Indicators

All indicators are unchanged.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

COPY IN-PROCESS FLAGS (CPIPF)

CPIPF addr4



The in-process flags for each level are stored at the word location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

The in-process flags are not changed. The flags are stored in a bit significant manner with bit zero representing level zero, and so on. Bits 4-15 are set to zero.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

This instruction permits the supervisor on the current level to inspect the in-process flags of the other levels. The in-process flag, bit 9 of the level status register, is on when a level is active or pending (previously interrupted by a higher level).

Indicators

All indicators are unchanged.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

CPLB CPLSR

COPY LEVEL BLOCK (CPLB)

reg,addr4 **CPLB**



This instruction stores a level status block (LSB) into 11 words of main storage beginning with the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The contents of the LSB and the R field register are not changed.

The register specified by the R field contains the binary encoded level of the LSB to be stored. The binary encoded level is placed in bits 14 and 15 of the register. Bits 0-13 are unused and must be zero.

Using this one instruction, the supervisor can copy the information contained in the hardware registers assigned to a program operating on any level. Most instructions are restricted to the registers associated with the current level. After executing a CPLB instruction, the supervisor can:

- 1. Use the information just stored; for example, the contents of the general registers or the protect key in the LSR.
- 2. Assign the level to another task by executing a set level block (SELB) instruction that points to a different level status block.

In the second case, the supervisor can restart the preempted program at a later time by executing another SELB instruction that points to the previously stored level status block.

Programming Note. If the AM field equals 01, the contents of the register specified by the RB field are incremented by 2.

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or the 11 word main storage area. The instruction is terminated. If the main storage area being accessed is partially outside the installed storage size, a partial data transfer occurs.

Privilege Violate. Privileged instruction.


Specification Check. Even byte boundary violation (indirect address or operand address).

Level Status Block Format

IAK
AKR
LSR
Register 0
Register 1
Register 2
Register 3
Register 4
Register 5
Register 6
Register 7
•


EA=effective address

Format of Register Specified by R in CPLB Instruction



COPY LEVEL STATUS REGISTER (CPLSR)

CPLSR reg



The level status register is loaded into the register specified by the R2 field. The level status register is unchanged. Bits 5-7 of the instruction are not used and must be set to zero to avoid future code obsolescence.

Indicators

All indicators are unchanged.

Program Check Conditions

Protect Check. Instruction fetch.

COPY PROCESSOR STATUS AND RESET (CPPSR)

CPPSR

addr4

O	pera	tio	n cc	ode				R	В	AM	F	unc	tio	n
0	1	0	1	1	0	0	0	İ			1	1	1	1
0				4	5		7	8	9	10 11	12			15



The contents of the processor status word (PSW) are stored at the word location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

This instruction resets bits 0 through 12 of the PSW. Bits 13 through 15 are unchanged.

Bits 5-7 of the instruction are not used and must be set to zero to avoid future code obsolescence.

Indicators

PSW bit

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

Program Status Word (PSW) Format

Meaning


0	Specification check
1	Invalid storage address
2	Privilege violate
3	Protect check
4	Invalid function
5	Floating point exception
6	Stack exception
7	Not used
8	Storage parity check
9	Not used
10	CPU control check
11	I/O check
12	Sequence indicator
13	Auto-IPL
14	Translator enabled
15	Power/thermal warning

COPY STORAGE KEY (CPSK)

Refer to Chapter 8 for a description of the stora protection mechanism.

CPSK

reg,addr4







This instruction stores the contents of a storage k register at the byte location in main storage specified by t effective address. (Effective Address Generation explained in Chapter 2.)

The register specified by the R field contains the ma storage block number for the storage key register to stored. (A storage key register is associated with every 20 bytes of storage.) The block number is binary encoded bits 0-4 of the register. Bits 5-15 are not used and mu be zero to avoid future code obsolescence.

The format of the register specified by the R field is:



The format of the byte at the storage location is:



Bits 4-7, the storage key and read only bit, are the dat from the storage key register for the selected main storag block. Bits 0-3 must be zero to avoid future cod obsolescence.

The contents of the storage key register are unchanged.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address).


CPSR


COPY SEGMENTATION REGISTER (CPSR)

This instruction is invalid if the Storage Address Relocation Translator Feature is not installed. Chapter 9 describes the relocation translator feature.

CPSR

reg,addr4







This instruction stores the contents of a segmentation register into the doubleword location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.)


The register specified by the R field contains the number of the segmentation register to be stored (0-255). This number is composed of three bits from the address key (values 0-7) and the five high-order bits of the logical storage address (values 0-31). Bits 8 through 15 of the register are not used and must be set to zero to avoid future code obsolescence.

The format of the register specified by the R field is:



The format of the segmentation register stored at the effective address is:





Bits 0 through 12 contain the high-order 13 bits of the physical address used by the translator to select a 2K block of storage.

Bit 13, if a one, signifies that the contents of the segmentation register is valid, and translation can be performed. If an attempt is made to use a segmentation register in which bit 13 is a zero, a program check interrupt occurs, with *invalid storage address* set in the PSW.

Bit 14, if a one, signifies that the block is read only. If an attempt is made to write into the block when bit 14 of the associated segmentation register is a one and while in problem state, a program check interrupt occurs, with protect check set in the PSW. The contents of main storage are not changed. When in supervisor state or on a cycle steal access, bit 14 is ignored.

Bits 15 through 31 are not used and must be set to zero to avoid future code obsolescence.

The contents of the segmentation register are unchanged.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Function. Translator not installed.

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

COMPARE WORD (CW)

Register/Register Format

CW

reg,reg

O	Operation code					1	R	R2			Function					
0	1	1	1	0					0	0	1	0	1			
0			,	4	5	7	8	10	11				15			

The contents of the register specified by the R1 field are subtracted from the contents of the register specified by the R2 field. The contents of both registers are unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Protect Check. Instruction fetch.

Register/Storage Format

CW

addr4,reg

O	pera	tio	n co	ode	Г	R		R	В	AM	 [Function				
1	1	0	0	1								0	1	0	0	
0				4	.5		7	R	9	10	11	12	,		15	



The contents of the word in main storage specified by the effective address are subtracted from the contents of the register specified by the R field. (Effective Address Generation is explained in Chapter 2.)

Both operands are unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2¹⁵ or greater than +2¹⁵-1.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).


Storage/Storage Format

CW

addr5,addr4

0	pera	tio	n co	ode	RB	1	RB.	2	AM1	AM2	Fun		
1	0	0	0	1			1			•	1	1	
0				4	.5	7	8	0	10 11	12 13	14	115	





The address arguments generate the effective addresses of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) Word operand 1 is subtracted from word operand 2. Neither operand is changed.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch or operand access. The instruction is terminated. If AM1 equals 01, RB1 may be incremented.


CWI


COMPARE WORD IMMEDIATE (CWI)

Register Immediate Long Format

CWI

word,reg





The immediate field is subtracted from the contents of the register specified by the R1 field. The contents of the register specified by the R1 field are unchanged.

Bits 8-10 are not used and must be set to zero to avoid future code obsolescence.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than $-2^{1.5}$ or greater than $+2^{1.5}-1$.

Even. Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word.

Protect Check. Instruction fetch.


Storage Immediate Format

CWI

word,addr4

Format without appended word for effective

addressing (AM = 00 or 01)






Format with appended word for effective

addressing (AM = 10 or 11)

O	ero	itio	n co	ode	Г			R	В	AM	unc	ınction			
0	1	0	0	0	0	0	0				1	1	1.	1	l
0				4	5		7	8	9	10 11	12			15	•





The immediate word is subtracted from the contents of the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence. Both operands are unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

Even. Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch or operand access.

DIVIDE BYTE (DB)


DB

addr4,reg

Γ	Operation code					Γ	R			В	AM	Function				
L	1	1		1	0	1	<u> </u>						0	0	1	0
	0					4	5		7	8	9	10 11	12	?		15



A divide operation is performed between the word dividend contained in the register specified by the R field and the byte divisor at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The 1-word quotient replaces the contents of the specified register while the 1-word remainder is placed in the register specified by R+1. If the R field specifies register 7, the remainder is placed in register 0.



Indicators

Overflow. Cleared, then turned on if division by zero is attempted, or if the quotient cannot be represented in one word. If overflow occurs, the remaining indicators and the contents of the specified register are undefined.

Carry. Cleared, then turned on (together with the overflow indicator) if the overflow was caused by an attempt to divide by zero.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. If the AM field equals 01, the contents of the register specified by the RB field are incremented.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address.)


DD

DIVIDE DOUBLEWORD (DD)

DD


addr4,reg

Operation code						.R			В	AM	Fi	Function			
1	1	1	0	1				L			1	0	1	0	
0				4	5		7	8	9	10 1.	1 12			15	



A divide operation is performed between the doubleword dividend contained in the registers, specified by the R field and R+1, and the word divisor at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The doubleword quotient replaces the contents of the specified registers (least significant word is in R+1). The one-word remainder is placed in the register specified by R+2.

The R field wraps from 7 to 0; e.g., if R specifies register 6, registers 6, 7, and 0 are used.



Programming Note. If the AM field equals 01, the contents of the register specified by the RB field are incremented by 2.

Indicators

Overflow. Cleared, then turned on if division by zero is attempted, or if the quotient cannot be represented in a doubleword. If overflow occurs, the remaining indicators and the contents of the specified registers are undefined.

Carry. Cleared, then turned on (together with the overflow indicator, if the overflow was caused by an attempt to divide by zero.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).


5-32 GA34-0021

DIAGNOSE (DIAG)

DIAG


ubyte

ſ	Operation code						nct	ion	Parameter	
L	0	1	1	0	0	1	0	1		
	0				4	5		7	8	15



Immediate data	
32	47

The Diagnose instruction is used for controlling or testing various hardware functions in a machine dependent manner. The parameter field has the following general significance:



Bits 10 and 11 are not used and should be set to zero to avoid future code obsolescence.

- If the C bit (bit 13) is set to one, the number 0005 is loaded into Register 0 of the current interrupt level. Software uses this number to determine that the processor is a 4955.
- If the C bit is set to zero, the function bits have the following meanings:

Bits 8 9

0	0	Diagnostic word storage error recovery
0	1	Diagnostic byte storage error recovery
1	0	Local storage to/from main storage
1	1	Enable/disable channel request lines

Diagnostic storage error recovery—This function allows the inhibiting of storage parity generation and checking when using the processor SAR and SDR. The cycle steal storage data register and storage address register can be selected but parity cannot be inhibited. Other bits in the parameter field are as follows:

Bits	Significance
12 = 0	Load storage
12 = 1	Store storage
14 = 0	Inhibit parity check/generation
14 = 1	Enable parity check/generation
15 = 0	Select processor SDR/SAR
15 = 1	Select cycle steal SDR/SAR

The storage address for this storage cycle is contained in R7 while the data register is R0. Note that functions selected by the parameter field apply only to the storage cycle initiated by the execution of this instruction.

Main storage to/from local storage—This function permits the transfer of data between main storage and local storage by directly addressing local storage. Two additional words are appended to the Diagnose instruction when this function is specified.

The bits in the two additional words are defined as follows:

Bits	Significance
16-25	Unused
26-31	Local storage a

26-31 Local storage address 32-47 Data to be transferred

Bit 12 of the parameter field specifies the direction of transfer.

12 = 0 Load immediate data to local storage 12 = 1 Store local storage to immediate data

Programming note: The current level AKR and LSR in local storage are not continuously updated. Use of this instruction to load or store the current level AKR or LSR is not recommended.

Enable/disable I/O interface request lines—This function inhibits and logically isolates the interrupt and cycle steal request lines between the channel and the device.

Bit 14 of the parameter field is used as follows: 14 = 0 Disable channel request lines 14 = 1 Enable channel request lines

Program Check Conditions

Privilege Violate. Privileged instruction.

DIS

DISABLE (DIS)

DIS

ubyte

-	O_l	Operation code					nct	ion	Parameter	
	0	1	1	0	0	0	1	1		
	0				4	5		7	8	15

The facilities designated by one bits in the parameter field are disabled. The bits in the parameter field have the following significance:

Bit	Facility
8	Not used
9	Not used
10	Not used
11	Not used
12	Storage protect*
13	Equate operand spaces (AKR bit 0 set to zero)*
14	Translator (PSW bit 14 set to zero)**
15	Summary mask (LSR bit 11 set to zero)
* ~ ~	. 0 10

^{*} See Chapter 8 and 9.

Note. Bits not used must be set to zero to avoid future code obsolescence.

If parameter bit 14 is set to one and the relocation translator feature is not installed, no action occurs regarding this bit. If parameter bit 14 is set to one and the relocation translator feature is installed and enabled (bit 14 of the PSW is on), the translator is disabled (bit 14 of the PSW is turned off).

Indicators

No indicators are changed.

Program Check Conditions

Privilege Violate. Privileged instruction.


^{**} See Chapter 9.

DIVIDE WORD (DW)

DW


addr4,reg

Operation code					Г	R			RB		AM		Function			
1	1	1	0	1	1						j	0	1	1	0	
0				4	5		7	8	9	10	11	12	!		15	



A divide operation is performed between the word dividend contained in the register specified by the R field and the word divisor at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The one word quotient replaces the contents of the specified register. The one word remainder is placed in the register specified by R+1.

The R field wraps from 7 to 0; that is, if R specifies register 7, registers 7 and 0 are used.



Indicators

Overflow. Cleared, then turned on if division by zero is attempted, or if the quotient cannot be represented in one word. If overflow occurs, the remaining indicators and the contents of the specified registers are undefined.

Carry. Cleared, then turned on (together with the overflow indicator) if the overflow was caused by an attempt to divide by zero.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

EN

ENABLE (EN)

EN

ubyte

0	pera	itio	n co	ode	$F\iota$	inci	tion		Parameter
0	1	1	0	0	0	1	0	l	
0				4	5		7	8	15

The facilities designated by one bits in the parameter field are enabled.

The bits in the parameter field have the following significance:

Bit	Facility
8	Not used
9	Not used
10	Not used
11	Not used
12	Storage protect*
13	Equate operand spaces (AKR bit 0 set to one)*
14	Translator (PSW bit 14 set to one)**
15	Summary mask (LSR bit 11 set to one)
* See C	anters 8 and 9

Note. Bits not used must be set to zero to avoid future code obsolescence.

If bit 12 is equal to 1:

- Bit 14 is not checked.
- Storage protection mechanism is enabled.
- Relocation translator (if installed and enabled) is disabled.

If bit 14 is equal to 1:

- No action occurs if the Storage Address Relocation Translator Feature is not installed.
- If the relocation translator feature is installed, it is enabled.
- The storage protection mechanism (if enabled) is disabled.

Indicators

No indicators are changed.


Program Check Conditions

Privilege Violate. Privileged instruction.

^{**} See Chapter 9.

FILL BYTE FIELD AND DECREMENT (FFD) FILL BYTE FIELD AND INCREMENT (FFN)

FFD reg,(reg)
FFN reg,(reg)



This instruction fills all bytes of a field in main storage with the same bit configuration in each byte. Register 7 contains the number of bytes to be filled (field length). If a field length of zero is specified, the instruction is a no-op. The register specified by R1 contains, in bits 8–15, the byte used to fill the field. The register specified by R2 contains the starting address of the field in main storage.

After each byte in the field is filled:

- 1. The address in R2 is either incremented or decremented, determined by bit 13 of the instruction. This permits filling the field in either direction.
- 2. The length count in R7 is decremented.

The operation ends when the specified field length has been filled (contents of R7 equal zero). At this time, the address in R2 has been updated and points to the byte adjacent to the end of the field.

Bits 11 and 15 of the instruction are not used and must be set to zero to avoid future code obsolescence.

See Move Byte Field and Decrement (MVFD) and Move Byte Field and Increment (MVFN) for other versions of this machine instruction.

Note. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining byte count specified in register 7.

Indicators

Carry. Unchanged

Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect that result of the last byte moved.

Program Check Conditions

Invalid Storage Address. Operand. The instruction is terminated.

Protect Check. Instruction fetch, operand access, or operand store. The instruction is terminated.


IO IOPK

OPERATE I/O (IO)

Refer to Chapter 7 for a detailed description concerning the operation of this instruction.

IO

longaddr





An effective main storage address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:


Bit 11=0 (direct address). The result from step 1 is the effective address.

Bit 11=1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Bits 5-7 of the instruction are not used and must be set to zero to avoid future code obsolescence.

The effective address specifies the location of a two-word control block, called the immediate device control block (IDCB). The IDCB contains the command, device address, and a one-word immediate data field:

IDCB (immediate device control block)





The immediate data field serves two purposes:

- 1. For direct program control (DPC) operations, it holds the data transferred to or from the I/O device.
- 2. For cycle steal operations, it holds the address of the device control block (DCB).

Refer to Chapter 7 for additional information.

Indicators

Even, Carry, and Overflow. Changed to reflect the condition code. See Branch on Condition Code (BCC) or Branch on Not Condition Code (BNCC) instructions.

Negative and Zero. These indicators are not changed.


Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

INTERCHANGE OPERAND KEYS (IOPK) IOPK



The contents of the operand 1 key (OP1K) are interchanged with the contents of the operand 2 key (OP2K) in the address key register. Bits 8-15 of the instruction are not used and must be set to zero to avoid future code obsolescence.

Indicators

All indicators are unchanged.

Program Check Conditions

Privilege Violate. Privileged instruction.

INTERCHANGE REGISTERS (IR)

reg,reg

IR

İ	O_l	pera	tio	n co	ode	Γ	R1	Τ	R2		Ī —	Fu	nct	ion	
	0	1	1	1	0			l			0	0	1	1	1
	0				4	5	7	8		10	11				15

The contents of the register specified by the R1 and R2 fields are interchanged.

Indicators

Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the operand moved from R1 to R2.

Program Check Conditions

Protect Check. Instruction fetch.

JUMP UNCONDITIONAL (J)

jdisp Jaddr



Bit 8 of the word displacement field is propagated left seven bit positions and a zero is appended at the low order end, resulting in a 16-bit word. (Word displacement is converted to a byte displacement.) This value is stored into the instruction address register becoming the address of the next instruction to be fetched.

Note. The hardware format of this instruction is identical to the format used for the Branch Indexed Short (BXS) instruction.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address.

Protect Check. Instruction fetch.

Specification Check. Even byte boundary violation (branch address).

JAL

JUMP AND LINK (JAL)

JAL

jdisp,reg jaddr,reg

O	pera	tior	ıcc	de	<u> </u>	R		Word displacement
1	0	0	1	1				
0				4	.5	7	-8	15

The updated value of the instruction address register (the location of the next sequential instruction) is stored into the register specified by the R field. Bit 8 of the word displacement field is propagated left by seven bit positions and a zero is appended at the low order end, resulting in a 16-bit word. (The word displacement is converted to a byte displacement.) This value is added to the updated contents of the instruction address register, and the result is stored in the instruction address register, becoming the address of the next instruction to be fetched.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address. The instruction is terminated. Branching does not occur, but the storing of the updated instruction address into the register specified by the R field still occurs.

JUMP ON CONDITION (JC)

		\	
16	Operand	_	Condition field
Mnemonic	Syntax	Instruction name	bits (see A)
JC	cond.jdisp cond.jaddr	Jump on Condition	Any value liste below
Extended	Operand		Condition field
Mnemonic	Syntax	Instruction name	bits (see A)
JE	jdisp jaddr	Jump on Equal	000
JOFF	jdisp jaddr	Jump if Off	000
JZ	jdisp jaddr	Jump on Zero	000
JMIX	jdisp jaddr	Jump if Mixed	001
JP	jdisp jaddr	Jump on Positive	001
JON	jdisp jaddr	Jump if On	010
JN	jdisp jaddr	Jump on Negative	010
JEV	jdisp jaddr	Jump on Even	011
JLT	jdisp jaddr	Jump on Arith- metically Less Than	100
JLE	jdisp jaddr	Jump on Arith- metically Less Than	101
JLLE	jdisp	or Equal Jump on Logically	110
JCY	jaddr jdisp jaddr	Less Than or Equal Jump on Carry	111
JLLT	jdisp jaddr	Jump on Logically Less Than	111

1	Op	era	tior	ıco	de	7	Conc	1	Γ	Word displacement
	0	0	0	1	0				l	
	0				4	5	Α	7	8	15

This instruction tests the condition of the various indicators set by a previously executed instruction (for example: an arithmetic, compare, test bit, or test word type of instruction).

If the condition tested is met, bit 8 of the word displacement field is propagated left by seven bit positions and a zero is appended at the low-order end resulting in a 16-bit word. (Word displacment is converted to a byte displacement.) This value is added to the updated value of the instruction address register, becoming the address of the next instruction to be fetched. If the condition tested is not met, the next sequential instruction is fetched.

For additional information about the indicator settings for the various conditions, see Chapter 2.

Indicators

listed

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address.

JCT

JUMP ON COUNT (JCT)


JCT jdisp,reg jaddr,reg

O	era	tior	co	de	Γ	R	T	Word displacement
1	0	1	1	1				
0				4	5	7	8	15

This instruction tests the contents of the register specified by the R field.

If the register contents are not zero, the contents are decremented by one. If the register contents are still not zero, the word displacement is converted to a byte displacement and added to the contents of the updated instruction address register (IAR). This value indicates the location of the next instruction to be fetched.

If the register contents are zero when initially tested, no decrementing occurs. In this case, or when the register contents are zero after decrementing, the next sequential instruction is fetched.



Note. When the register contents are not zero, the word displacement is converted to a byte displacement as follows. Bit 8 of the word displacement field is propagated left by seven bit positions, and a zero is appended at the low-order end. This results in a 16-bit word that has been doubled in magnitude.

Indicators


No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address. The jump does not occur, but the contents of the register specified by the R field are still decremented by one.

JUMP ON NOT CONDITION (JNC)

	Operand		Condition field
Mnemonic	Syntax	Instruction name	bits (see A)
JNC	cond,jdisp	Jump on Not	Any value
	cond,jaddr	Condition	listed below
			Condition
Extended	Operand		field
Mnemonic	Syntax	Instruction name	bits (see A)
JNE	jdisp	Jump on Not Equal	000
	jaddr		000
JNOFF	jdisp	Jump if Not Off	000
	jaddr	-	
JNZ	jdisp	Jump on Not Zero	000
	jaddr		
JNMIX	jdisp	Jump on Not Mixed	001
	jaddr		
JNP	jdisp	Jump on Not	001
	jadd r	Positive	
****		jaddr	
JNON	jdisp	Jump if Not On	010
TAINT	jaddr	*	
JNN	jdisp	Jump on Not Negative	010
JNEV	jaddr	T N. T	044
INEA	jdisp iaddr	Jump on Not Even	011
JGE	3	T A - 1/1	100
JGE	jdisp jaddr	Jump on Arith-	100
	jauur	metically Greater Than or Equal	
JGT	jdisp	Jump on Arith-	101
701	jaddr	metically	101
	jaddr	Greater Than	
JLGT	jdisp	Jump on Logically	110
	jaddr	Greater Than	110
JLGE	jdisp	Jump on Logically	111
	jaddr	Greater Than or Equal	-
JNCY	jdisp	Jump on No Carry	111
	jaddr		



This instruction tests the condition of the various indicators set by a previously executed instruction (for example: an arithmetic, compare, test bit, or test word type of instruction.)

If the condition tested is met, bit 8 of the word displacement field is propagated left by seven bit positions and a zero is appended at the low-order end resulting in a 16-bit word. (Word displacement is converted to a byte displacement.) This value is added to the updated value of the instruction address register, becoming the address of the next instruction to be fetched.

If the condition tested is not met, the next sequential instruction is fetched.

For additional information about the indicator settings for the various conditions, see Chapter 2.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Effective address.

LEX LMB

LEVEL EXIT (LEX)

LEX

[ubyte]

Op	era	tion	co	de	Fu	ncti	on		Parameter
0	1	1	0	0	0	0	1		
0				4	5		7	8	15

When this instruction is executed, the processor exits the current level. The in-process flag (LSR bit 9) for the current level is turned off. Next the instruction tests for (1) pending levels or outstanding priority interrupt requests, and (2) the condition of the summary mask (LSR bit 11) for the level to be exited:

- If pending levels or outstanding requests exist and the summary mask is enabled:
 - A branch is executed to the address contained in the IAR of the highest pending or requesting level.
 - This level then becomes the current level and processing resumes.
- If pending levels or outstanding requests exist and the summary mask is disabled:
 - The priority interrupts are not allowed.
 - The highest pending level becomes the current level and processing resumes.
 - If no levels are pending, the processor goes to the wait state.
- If no levels are pending and no interrupt requests are outstanding, the processor goes to the wait state.

For additional information on level switching, refer to Chapter 3.

Note. When a level is exited by a LEX instruction and processing is to continue on a pending level, one instruction is executed on the pending level prior to sampling for a trace class interrupt.

Indicators

No indicators are changed.

Program Check Conditions

Privilege Violate. Privileged instruction.

LOAD MULTIPLE AND BRANCH (LMB)

Refer to Stack Operations in Chapter 2 for a detailed description concerning the operation of this instruction. The LMB instruction is used in conjunction with the Store Multiple (STM) instruction described later in this chapter.

LMB addr4

Op	era	tion	co	de	Γ			F	₹B	AM		Fu	nct	ion
0	1	0	0	0	0	0	0	l			1	0	1	0
0				4	5		7	8	9	10 11	12			15
				Ad	ldre	ss/	– – Disį	olac	em	ent	_ `			
	Di	pla	cen	nen	t T		_	Γ	Di	splacen	ient	$\overline{2}$		_
							_				_	_	_	

The contents of the registers for the current level are loaded from the stack defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.) The registers to be loaded are defined by the stack entry previously stored by a Store Multiple (STM) instruction. The next instruction is fetched from the storage address contained in register 7.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Programming Note. If the AM field equals 01 the contents of the register specified by the RB field are incremented by 2

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or stack control block. The instruction is terminated.

Protect Check. Instruction fetch or operand access. The instruction is terminated. A partial data transfer occurs if the area of the stack being accessed crosses a protection boundary.

Specification Check.

- 1. Even byte boundary violation (indirect address, stack control block, or stack element).
- 2. Address in R7 is odd.

Soft Exception Trap Condition

Stack Exception. Stack is empty. If the AM field equals 01, the contents of the register specified by the RB field are incremented. The instruction is terminated.


MULTIPLY BYTE (MB)

MB

addr4,reg

O_{l}	era	tio	n co	de	I	3	R	В	AM	Г	Fu	nct	ion
1	_1	1	0	1						0	0	0	1
0				4	5	7	8	9	10 11	12	·		15

A multiply operation is performed between the word multiplier contained in the register specified by the R field and the byte multiplicand at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The word product replaces the contents of the register.



Indicators

Carry. Reset.

Overflow. Cleared, then turned on if the result cannot be represented in 16 bits. If overflow occurs, the contents of the specified register are undefined.

Even, Negative, and Zero. Set to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. If the AM field equals 01, the contents of the register specified by the RB field are incremented.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address).


MD

MULTIPLY DOUBLEWORD (MD)

MD


addr4,reg

Op	era	tior	ı co	de	Γ	R		F	₹B	A	M	F	unc	tio	n
1	1	1	0	1	l							1	0	0	1
\overline{o}				4!	5		7	8	9	10	11	12			15



A multiply operation is performed between the doubleword multiplier contained in the registers specified by the R field and R+1 and the word multiplicand at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The doubleword product replaces the contents of the registers with the least significant word in R+1.

The R field wraps from 7 to 0; that is, if R specifies register 7, registers 7 and 0 are used.



Programming Note. If AM=01, the register specified by the RB field is incremented by 2.

Indicators

Carry. Reset.

Overflow. Cleared, then turned on if the result cannot be represented in 32 bits. If overflow occurs, the contents of the specified registers are undefined.

Even, Negative, and Zero. Set to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


MOVE ADDRESS (MVA)

Storage Address to Register Format

MVA

addr4,reg

O	pera	tio	ı cc	de		R	I	₹ <i>B</i>	AM	F	un	ctio	n
0	1	0	0	0						0	1	0	0
0				4	5	7	8	9	10 11	12			15



The effective address is loaded into the register specified by the R field. (Effective Address Generation is explained in Chapter 2.)

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register specified by the R field.

Program Check Conditions

Invalid Storage Address. Second Instruction word.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address).

Storage Immediate Format

MVA


raddr,addr4


Format without appended word for effective addressing (AM = 00 or 01)






Format with appended word for effective addressing (AM = 10 or 11)







The operand in the immediate field replaces the contents of the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The immediate operand is not changed.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed, but the indicators are set as described.


MVB

MOVE BYTE (MVB)

Register/Storage Format

MVB reg,addr4 addr4,reg





A byte is moved between the least significant byte of the register specified by the R field and the location specified by the effective address in main storage. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the direction of the move:

Bit 12 = 0. The byte is moved from storage to register. The high-order bit of the byte (sign) is propagated to the eight high order bits of the register. This permits the Compare Byte Immediate (CBI) instruction to be used for byte compare operations. The operand in storage is unchanged. Bit 12 = 1. The byte is moved from register to storage. The contents of the register specified by the R field are not changed.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand moved.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


Specification Check. Even byte boundary violation (indirect address).

Storage/Storage Format

MVB addr5,addr4

[p	era	tior	ı cc	de		RB1	RI	32	AM1	AM2	Fun
1		0	0	0	0							0 0
0					4	.5	7	8	9	10 11	12 13	14 15





The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) A byte is moved from operand 1 to operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the byte moved.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

MOVE BYTE IMMEDIATE (MVBI)

MVBI

byte,reg

Op	era	tior	co	de		R	T	Immediate
0	0	0	0	1				
0				4	5	7	8	15

The register specified by the R field is loaded with the immediate operand.

The immediate field of the instruction forms the operand to be loaded. The immediate field is expanded to a sixteen bit operand by propagating the sign bit value through the high order bit positions; this operand is loaded into the register specified by the R field.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register.

Program Check Conditions


Protect Check. Instruction fetch.

MOVE BYTE AND ZERO (MVBZ)

MVBZ addr4,reg

 Operation code
 R
 RB
 AM
 Function

 1
 1
 0
 0
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 1
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0
 0



The byte specified by the effective address is loaded into the least significant byte of the register specified by the R field. (Effective Address Generation is explained in Chapter 2.) The high order bit of the byte (sign) is propagated to the eight high order bits within the register.

The byte specified by the effective address is then set to zeros.

Bit 12 of the instruction is not used and must be set to zero to avoid future code obsolescence.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. The register is loaded but the main storage location is unchanged. The status of the even, negative, and zero indicators is unpredictable.


Specification Check. Even byte boundary violation (indirect address).


MVD

MOVE DOUBLE WORD (MVD)

Register/Storage Format

MVD addr4,reg reg,addr4





A doubleword is moved between the contents of the register pair specified by the R field (R and R+1) and the doubleword location specified by the effective address in main storage. (Effective Address Generation is explained in Chapter 2.) The source operand is unchanged.

The R field wraps from 7 to 0; that is, if R specifies register 7, registers 7 and 0 are used.

Bit 12 of the instruction specifies the direction of the move:

Bit 12 = 0. The doubleword is moved from storage to the register pair.

Bit 12 = 1. The doubleword is moved from the register pair to storage.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand moved.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

MVD addr5,addr4

O	oera	tio	n cc	de	<u> </u>	RB1	RI	32	AM1	AM2	$F\iota$	ın
1	0	0	1	0					L		0	0
\overline{o}				4	5	7	8	9	10 11	12 13	14	15





The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) A doubleword is moved from operand 1 to operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the doubleword moved.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

MOVE DOUBLEWORD AND ZERO (MVDZ)

MVDZ

addr4,reg

Op	era	tion	cc	de		R		I	₹B	AM		Fu	nct	ion
1	1	0	1	0						ļ	0	1	0	1
0				4	5		7	8	9	10 11	12			15

The doubleword specified by the effective address is loaded into the register pair specified by the R field (R and R+1). (Effective Address Generation is explained in Chapter 2.) The R field wraps from 7 to 0; that is, if R specifies register 7, registers 7 and 0 are used.

The doubleword specified by the effective address is then set to zeros.

Bit 12 is not used and must be set to zero to avoid future code obsolescence.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register pair.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.

MVFD MVFN

MOVE BYTE FIELD AND DECREMENT (MVFD) MOVE BYTE FIELD AND INCREMENT (MVFN)

MVFD (reg),(reg) MVFN (reg),(reg)



This instruction moves a specified number of bytes (one byte at a time) from one storage location to another. Register 7 contains the number of bytes to be moved (field length). If a field length of zero is specified, the instruction is a no-op. The register specified by R1 contains the address of operand 1; the register specified by R2 contains the address of operand 2. Operand 1 is moved to operand 2.

After each byte is moved:

- 1. The addresses in R1 and R2 are either incremented or decremented, determined by bit 13 of the instruction. This allows the field to be moved in either direction.
- 2. The length count in R7 is decremented.

The operation ends when the specified field length has been filled (contents of R7 equal zero). At this time, the addresses in R1 and R2 have been updated and point to the next operands.

Bits 11 and 15 of the instructions are not used and must be set to zero to avoid future code obsolescence.

See Fill Byte Field and Decrement (FFD) and Fill Byte Field and Increment (FFN) for other versions of this machine instruction.

Note. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining count specified in register 7.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the last byte moved.

Program Check Conditions


Invalid Storage Address. Operand. The instruction is terminated.

Protect Check. Instruction fetch, operand access, or operand store. The instruction is terminated.

MOVE WORD (MVW)

Register/Register Format

MVW reg,reg



The contents of the register specified by the R1 field replace the contents of the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged.

Indicators

Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Protect Check. Instruction fetch.

Register/Storage Format

MVW reg,addr4 addr4,reg



A word is moved between the contents of the register specified by the R field and the location specified by the effective address in main storage. (Effective Address Generation is explained in Chapter 2.) The source operand is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand moved.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Storage Long Format

MVW reg.longaddr





The contents of the register specified by the R1 field are stored into the main storage location specified by an effective address. This effective address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0 (direct address). The result from step 1 is the effective address.

Bit 11 = 1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result stored from the register specified by the R1 field.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


MVW

Storage to Register Long Format

MVW

longaddr,reg





The register specified by the R1 field is loaded with the contents of the main storage location specified by an effective address. This effective address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0 (direct address). The result from step 1 is the effective address.

Bit 11 = 1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result loaded into the register specified by the R1 field.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).


Storage/Storage Format

MVW

addr5,addr4







The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) A word is moved from operand 1 to operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the word moved.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

MOVE WORD IMMEDIATE (MVWI)

Storage to Register Format

MVWI

word,reg

Operatio	n co	de	Τ	R	_	1	RB	AM		Fu	ncti	on
0 1 0	0	0							0	1	0	0
0		4	5		7	8	9	10 11	12			1.5

The effective address is loaded into the register specified by the R field. (Effective Address Generation is explained in Chapter 2.)

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register specified by the R field.

Program Check Conditions

Invalid Storage Address. Second instruction word.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address).


Storage Immediate Format

MVWI

word,addr4


Format without appended word for effective addressing (AM = 00 or 01)






Format with appended word for effective addressing (AM = 10 or 11)

Op	era	tior	co	de				F	B	AM	F	unc	tio	n
0	1	0	0	0	0	0	0				0	0	0	0
0				4	5		7	8	9	10 11	12			15





The operand in the immediate field replaces the contents of the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The immediate operand is not changed.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


MVWS

MOVE WORD SHORT (MVWS)

Register to Storage Format

MVWS

reg,shortaddr



The contents of the register specified by R1 are stored into the main storage location specified by the effective address. The contents of the register are unchanged.

The effective address is generated as follows:

- 1. The five bit unsigned integer (word displacement) is doubled in magnitude (converted to a byte displacement).
- 2. The result from step 1 is added to the contents of the base register (RB) to form a main storage address.
- 3. Instruction bit 10 is tested for direct or indirect addressing:

Bit 10 = 0 (direct address). The result from step 2 is the effective address.

Bit 10 = 1 (indirect address). The result from step 2 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand stored into main storage.

Program Check Conditions


Invalid Storage Address. Operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage to Register Format

MVWS shortaddr,reg



The contents of the main storage location specified by the effective address are loaded into the register specified by the R1 field. The contents of the main storage location remain unchanged.

The effective address is generated as follows:

- 1. The five bit unsigned integer (word displacement) is doubled in magnitude (converted to a byte displacement).
- 2. The result from step 1 is added to the contents of the base register (RB) to form a main storage address.
- 3. Instruction bit 10 is tested for direct or indirect addressing:

Bit 10 = 0 (direct address). The result from step 2 is the effective address.

Bit 10 = 1 (indirect address). The result from step 2 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the operand loaded into the register specified by the R1 field.

Program Check Conditions

Invalid Storage Address. Operand.

Protect Check. Instruction fetch or operand access.

MOVE WORD AND ZERO (MVWZ)

MVWZ

addr4,reg

O	era	tion	co	de		R		1	₹B	AM	1	F	unc	tio	n
1	1	0	0	1	l			l		ĺ	i	0	1	0	1
0				4	5		7	8	9	10 1	11	12			15

The word specified by the effective address is loaded into the register specified by the R field. (Effective Address Generation is explained in Chapter 2.)

The word specified by the effective address is then set to zeros.

Bit 12 is not used and must be set to zero to avoid future code obsolescence.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the results of the operand loaded.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. The register is loaded but the main storage location is unchanged. The status of the even, negative, and zero indicators is unpredictable.


MW

MULTIPLY WORD (MW)


MW

addr4,reg

Operation	code	T	R	F	B	AM		Fu	nct	ion
1 1 1	0 1						0	1	0	1
0	4	.5	7	8	9	10 11	12			15



A multiply operation is performed between the word multiplier contained in the register specified by the R field and the word multiplicand at the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The word product replaces the contents of the register.



Indicators

Carry. Unchanged.

Overflow. Cleared, then turned on if the result cannot be represented in 16 bits. If overflow occurs, the contents of the specified register are undefined.

Even, Negative, and Zero. Set to Reflect the result.


Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

NO OPERATION (NOP)

NOP



The hardware format of this instruction is identical to the format used for the Branch Indexed Short (BXS) and Jump Unconditional (J) instructions. When bits 5-15 are all zeros, the instruction performs no operation.

Indicators

No indicators are changed.


Program Check Conditions


Protect Check. Instruction fetch.

AND WORD IMMEDIATE (NWI)

NWI

word,reg[,reg]





The immediate field is ANDed bit by bit with the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field. The contents of the register specified by R1 are unchanged unless R1 and R2 specify the same register.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word.


OR BYTE (OB)

Register/Storage Format

OB

reg,addr4 addr4,reg





A logical OR operation is performed between the least significant byte of the register specified by the R field and the location specified by the effective address in main storage. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged. Also, when going from storage to register, bits 0 through 7 of the register are unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

Storage/Storage Format

OB

addr5,addr4

ſ	Op	era	tior	ı co	de	Ī	RB1	RI	32	AM1	AM2	Fu	n
1	1	0	0	0	0	i						0	1
_	0				4	5	7	8	9	10 11	12 13	14	15

The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) A one byte logical OR operation is performed between operand 1 and operand 2. The result replaces operand 2.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


Specification Check. Even byte boundary violation (indirect address).


OR DOUBLEWORD (OD)

Register/Storage Format

OD

addr4,reg reg,addr4





A logical OR operation is performed between the contents of the register pair specified by the R field (R and R+1) and the doubleword in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged. If the R field equals 7, register 7 and register 0 are used.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the results of the OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.


Specification Check. Even byte boundary violation (indirect address or direct address).

Storage/Storage Format

OD

addr5,addr4







The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) A doubleword logical OR operation is performed between operand 1 and operand 2. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

OW

OR WORD (OW)

Register/Register Format

OW reg,reg

Op	era	tior	ı co	de		R1		R2		Fu	ncti	ion	
0	1	1	1	0			l		0	0	0	0	1
0				4	5	7	8	10	11				15

The contents of the register specified by the R1 field are ORed bit by bit with the contents of the register specified by the R2 field. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field remain unchanged unless R1 and R2 specify the same register.

Indicators

Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions

Protect Check. Instruction fetch.

Register/Storage Format

OW reg,addr4 addr4,reg





A logical OR operation is performed between the contents of the register specified by the R field and the location specified by the effective address in main storage. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the OR operation.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Storage to Register Long Format

OW

longaddr,reg





A logical OR operation is performed between the contents of the main storage location specified by an effective address and the contents of the register specified by the R1 field. The result is placed in the register specified by the R1 field.

The effective main storage address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0 (direct address). The result from step 1 is the effective address.

Bit 11=1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result loaded into the register specified by the R1 field.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

OW

addr5,addr4



The address arguments generate the effective addresses of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) A one word logical OR operation is performed between operand 1 and operand 2. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address or operand address).

5-63

OWI


OR WORD IMMEDIATE (OWI)

Register Immediate Format

OWI

word,reg[,reg]

Op	era	tion	co	de	Π	R1			R2			Fu	ncti	on	
0	1	1	1	1	ļ						0	0	0	1	1
0				4	5		7	8		10	11				15



The immediate field is ORed bit by bit with the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field. The contents of the register specified by R1 are unchanged unless R1 and R2 specify the same register.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch.


Storage Immediate Format

OWI

word,addr4


Format without appended word for effective addressing (AM = 00 or 01)






Format with appended word for effective addressing (AM = 10 or 11)

١	Op	era	tior	ı co	de				F	₹B	AM	F	unc	tio	n	
ı	0	1	0	0	0	0	0	0				1	1	0	0	
	0				4	5		7	8	9	10 11	12			15	





A logical OR operation is performed between the immediate field and the contents of the main storage location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The result replaces the contents of the storage location. Bits 5–7 are not used and must be set to zero to avoid future code obsolescence. The immediate operand is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

POP BYTE (PB)

Refer to Stack Operations in Chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PB addr4,reg

Op	era	tion	co	de	Г	-R		I	RB	AM	Г	Fu	nct	ion
_1	1	1	0	1							0	0	1	1
0				4	5		7	8	9	10 11	12			15



The top element of a byte stack is popped from the stack and loaded into the least significant byte of the register specified by the R field. The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or stack control block.

Specification Check. Even byte boundary violation (indirect address or stack control block).


Soft Exception Trap Condition


Stack Exception. Stack is empty. If AM equals 01, the contents of the register specified by the RB field are incremented.

POP DOUBLEWORD (PD)

Refer to Stack Operations in Chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PD addr4,reg





The top element of a doubleword stack is popped from the stack and loaded into the register pair specified by the R field (R and R+1). The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

If the R field equals 7, registers 7 and 0 are used.

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or stack control block. The instruction is terminated. For operand access, partial data is transferred to the register pair if the doubleword being addressed crosses a protection boundary.

Specification Check. Even byte boundary violation (indirect address, stack control block, or stack element).

Soft Exception Trap Condition

Stack Exception. Stack is empty. If the AM field equals 01, the contents of the register specified by the RB field are incremented.


PSB PSD


PUSH BYTE (PSB)

Refer to *Stack Operations* in Chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PSB

reg,addr4





The least significant byte of the register specified by the R field is pushed into the stack. The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address or stack control block).

Soft Exception Trap Condition


Stack Exception. Stack is full. If AM equals 01, the contents of the register specified by the RB field are incremented.


PUSH DOUBLEWORD (PSD)

Refer to *Stack Operations* in chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PSD

reg,addr4





The doubleword operand contained in the register pair specified by the R field (R and R+1) is pushed into the stack. The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

If the R field equals 7, registers 7 and 0 are used.

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or operand store. The instruction is terminated. For operand store (read-only violation), partial data is transferred to the non-read-only area of main storage if the doubleword being stored crosses a protection boundary.

Specification Check. Even byte boundary violation (indirect address, stack control block, or stack element).

Soft Exception Trap Condition

Stack Exception. Stack is full. If the AM field equals 01, the contents of the register specified by the RB field are incremented.


PUSH WORD (PSW)

Refer to *Stack Operations* in Chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PSW

reg,addr4

0	per	atio	n c	ode	Τ	R	T	RB	AM	Г	Fui	ıcti	on
1	1	1	0	1						0	1	0	0
0				4	5	7	8	9	10 11	12	,		15



The word operand contained in the register specified by the R field is pushed into the stack. The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address, stack control block, or stack element).

Soft Exception Trap Condition


Stack Exception. Stack is full. If the AM field equals 01, the contents of the register specified by the RB field are incremented.


POP WORD (PW)

Refer to *Stack Operations* in Chapter 2 for additional information about the operation of this instruction and the associated stack control block.

PW

addr4.reg





The top element of a word stack is popped from the stack and loaded into the register specified by the R field. The stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

Programming Note. If AM equals 01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word, stack control block, or operand.

Protect Check. Instruction fetch, operand access, or stack control block.

Specification Check. Even byte boundary violation (indirect address, stack control block, or stack element).

Soft Exception Trap Condition

Stack Exception. Stack is empty. If the AM field equals 01, the contents of the register specified by the RB field are incremented.


RBTB


RESET BITS BYTE (RBTB)

Register/Storage Format

RBTB

addr4,reg reg,addr4





This instruction operates either:

- 1. Storage to register (instruction bit 12 equals 0) or
- 2. Register to storage (instruction bit 12 equals 1).

Storage to Register. The specified bits are reset in the least significant byte of the register specified by the R1 field. The bit positions turned off correspond to the bit positions containing one-bits in the main storage byte location specified by the effective address. The remaining bits in the low-order byte of the register are unchanged. Also, bits 0–7 of the register and the storage operand are unchanged.

Register to Storage. The specified bits are reset in the main storage byte location specified by the effective address. The bits turned off correspond to the bit positions containing one-bits in the least significant byte of the register specified by the R field. The remaining bits in the storage location are unchanged. The register operand is unchanged.

Note. Effective Address Generation is explained in Chapter 2.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

Storage/Storage

RBTB

addr5,addr4

0	Operation code						RB1	RI	32	AM1	AM2	Fun	
1		0	0	0	0	1						1	0
0					4	5	7	8	9	10 11	12 13	14	15

The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) The bit positions containing one-bits in byte operand 1 determine the bit positions turned off in byte operand 2. The remaining bits in operand 2 are unchanged. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


Specification Check. Even byte boundary violation (indirect address).

RESET BITS DOUBLEWORD (RBTD)

Register/Storage Format

RBTD

addr4,reg reg,addr4



This instruction operates either:

- 1. Storage to register (instruction bit 12 equals 0) or
- 2. Register to storage (instruction bit 12 equals 1).

Storage to Register. The specified bits are reset in the register pair specified by the R field (R and R+1). The bit positions turned off correspond to the bit positions containing one-bits in the doubleword main storage location specified by the effective address. The remaining bits in the register pair are unchanged. The storage operand is unchanged.

Register to Storage. The specified bits are reset in the doubleword main storage location specified by the effective address. The bit positions turned off correspond to the bit positions containing one-bits in the register pair specified by the R field (R and R+1). The remaining bits in the storage operand are unchanged. The register operand is unchanged. If the R field equals 7, registers 7 and 0 are used.

Note. Effective Address Generation is explained in Chapter 2.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

RBTD addr5,addr4





The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) The bit positions containing one-bits in doubleword operand 1 determine the bit positions turned off in doubleword operand 2. The remaining bits in operand 2 are unchanged. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

RBTW

RESET BITS WORD (RBTW)

Register/Register Format

RBTW

reg,reg

Operation code						R1	Γ	R2	Function					
0	1	1	1	0					0	0	0	0	0	
0				4	5	7	8	10	11				15	

The bit positions containing one-bits in the register specified by the R1 field determine the bit positions turned off in the register specified by the R2 field. The remaining bits in the register specified by the R2 field are unchanged. The contents of the register specified by the R1 field are unchanged unless R1 and R2 specify the same register.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions


Protect Check. Instruction fetch.

Register/Storage Format

RBTW

addr4,reg reg,addr4





This instruction operates either:

- 1. Storage to register (instruction bit 12 equals 0) or
- 2. Register to storage (instruction bit 12 equals 1)

Storage to Register. The specified bits are reset in the register specified by the R field. The bit positions turned off correspond to the bit positions containing one-bits in the main storage word location specified by the effective address. The remaining bits in the register are unchanged. The storage operand is unchanged.

Register to Storage. The specified bits are reset in the main storage word location specified by the effective address. The bit positions turned off correspond to the bit postions containing one-bits in the register specified by the R field. The remaining bits in the storage operand are unchanged. The register operand is unchanged.

Note. Effective Address Generation is explained in Chapter 2.

Indicators

Carry and Overflow. Unchanged.

Even. Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Storage to Register Long Format

RBTW

longaddr,reg





The bit positions containing one-bits in the main storage word location specified by the effective address determine the bit positions turned off in the register specified by the R1 field. The remaining bits in the register specified by the R1 field are unchanged. The storage operand is unchanged. The effective address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field to form a main storage address. If the R2 field equals zero, no register contributes to the address generation. The contents of R2 are not changed.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11 = 0 (direct address). The result from step 1 is the effective address.

Bit 11 = 1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

RBTW

addr5,addr4

<i>Op</i>	era 0	tioi 0	n cc	de 1	-	RB1		RB2		AM	11	AM2		Fi 1	<i>in</i> 0
0				4	5		7	8	9	10	11	12	13	14	15
⊢ - 16	Di	spla	cen	nen	-	dres	23		laci	_	-	cem	ent	2	- ¬ · - _ J 31
32	Di	spla	- icer	nen		dres	 ss/I 		_	-	_	emo	ent		- - - 47

The address arguments generate the effective addresses of two operands in main storage. (Effective Address Generation is explained in Chapter 2.) The bit postions containing one-bits in word operand 1 determine the bit positions turned off in word operand 2. The remaining bits in operand 2 are unchanged. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.


For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


RBTWI

RESET BITS WORD IMMEDIATE (RBTWI)

Register Immediate Long Format

RBTWI word,reg[,reg]





The bit positions containing one-bits in the immediate field determine the bit positions to be reset. These bit positions are reset in the operand from the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field.

Example:

 Contents of immediate field
 0000
 0000
 0000
 1111

 Contents of R1 register
 0101
 0101
 0101
 0101

 Result in R2 register
 0101
 0101
 0101
 0000

The contents of the register specified by the R1 field are unchanged unless R1 and R2 specify the same register.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word.


Protect Check. Instruction fetch.

Storage Immediate Format


RBTWI word,addr4


Format without appended word for effective addressing (AM = 00 or 01)






Format with appended word for effective addressing (AM = 10 or 11)







The bit positions containing one-bits in the immediate field determine the bit positions turned off in the main storage location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The immediate operand is unchanged.

Bits 5-7 of the instruction are not used, but should be set to zero to avoid future code obsolescence.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

SUBTRACT BYTE (SB)

SB

reg,addr4 addr4,reg





A subtract operation is performed between the least significant byte of the register specified by the R field and the location specified by the effective address in main storage. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand and high-order byte of the register are unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

If an overflow occurs, the result contains the correct low-order eight bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

SUBTRACT CARRY INDICATOR (SCY)

SCY reg



The value of the carry indicator on entry is subtracted from the contents of the register specified by the R2 field. The result is placed in the register specified by the R2 field. Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Programming Note: This instruction can be used when subtracting multiple word operands. See *Indicators-Multiple Word Operands* in Chapter 2.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even. Unchanged.

Negative. Changed to reflect the result.


Zero. If on at entry, changed to reflect the result. If off at entry, it remains off.

Program Check Conditions

SUBTRACT DOUBLEWORD (SD)

Register/Storage Format

SD reg,addr4 addr4,reg



A subtract operation is performed between the register pair specified by the R field (R and R+1) and the doubleword in main storage specified by the effective address. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

If the R field equals 7, register 7 and register 0 are used.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the doubleword. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in the doubleword; i.e., if the difference is less than -2^{31} or greater than $+2^{31}-1$.

If an overflow occurs, the result contains the correct low-order 32 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

SD addr5,addr4



The address arguments generate the effective addresses of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) Doubleword operand 1 is subtracted from doubleword operand 2. The result replaces operand 2. Operand 1 is unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the doubleword. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in the doubleword; i.e., if the difference is less than -2^{31} or greater than $+2^{31}-1$.

If an overflow occurs, the result contains the correct low-order 32 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

SET ADDRESS KEY REGISTER (SEAKR)

System Register/Storage Format

Mnemonic	Syntax	Instruction name	K field
SEAKR Extended	addr4	Set Address Key Register	011
Mnemonic	Syntax	Instruction name	K field
SEISK	addr4	Set Instruction Space Key	000
SEOOK	addr4	Set Operand 1 Key	010
SEOTK	addr4	Set Operand 2 Key	001

O_l	oera	itio	n	cod	le	Γ	K		1	RB	A	M	I	- Tun	ctic	n
0	1	0	1	. 1	l	l							0	0	1	0
0				4	1	5		7	8	9	10	11	12	?		15

The address key register (AKR) field, specified by the K field, is loaded from the word location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The K field can specify: (1) a field within the AKR or; (2) the entire AKR.

K field	Address key register field name	Bits
000	Instruction space key	13-15
001	Operand 2 key	9-11
010	Operand 1 key	5-7
011	Address key register	0-15
100	Unused	
101	Unused	
110	Unused	
111	Unused	

Unused K-field values should not be used to avoid future program obsolescence.

If the K field specifies a specific field within the AKR, bits 13-15 from the word location in main storage are loaded into the AKR field. If the K field specifies the entire AKR, bits 0-15 from the word location in main storage are loaded into the AKR.

The contents of the word in main storage are unchanged.

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address).

System Register/Register Format

Mnemonic	Syntax	Instruction name	K Field
SEAKR Extended	reg	Set Address Key Register	011
Mnemonic	Syntax	Instruction name	K Field
SEISK	reg	Set Instruction Space Key	000
SEOOK	reg	Set Operand 1 Key	010
SEOTK	reg	Set Operand 2 Key	001

Ope	rati	on	C	ode	Τ	K		R		1	un	ctio	n		
0 1	. 1		1	1						1	0	0	1	0	l
0				4	5	7	8	1	10	11				15	;

The address key register (AKR) field, specified by the K field, is loaded from the register specified by the R field. The contents of the register are unchanged. The K field can specify: (1) a field within the AKR or; (2) the entire AKR.

K field	Address key register field name	Bits
000	Instruction space key	13-15
001	Operand 2 key	9-11
010	Operand 1 key	5-7
011	Address key register	0-15
100	Unused	-
101	Unused	
110	Unused	
111	Unused	

Unused K-field values should not be used to avoid future program obsolescence.

If the K field specifies a specific field within the AKR, bits 13-15 from the register specified by the R field are loaded into the AKR field. If the K field specifies the entire AKR, bits 0-15 from the specified register are loaded in the AKR.

Indicators

All indicators are unchanged.

Program Check Conditions

Privilege Violate. Privileged instruction.

SECON SEIMR

SET CONSOLE DATA LIGHTS (SECON)

SECON reg

O_{I}	pera	tio	n	cc	de	Г			Π	R 2		Fun	ctic	n	
0	1	1	1		1	0	0	0	ļ		1	0	0	0	0
ō					4	5	,	7	8	10	1.	1			15

The contents of the register specified by R2 are stored in the console data lights. The contents of the register are unchanged.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

If the Programmer console is not installed, the instruction performs no operation.

Indicators

All indicators are unchanged.

Program Check Conditions

Privilege Violate. Privileged instruction.

SET INTERRUPT MASK REGISTER (SEIMR)

SEIMR addr4

Oper	atio	n o	ode	Τ			1	R <i>B</i>	AM	F	un	ctio	n	
0 1	0	1	1	0	0	0				0	0	0	0	
0			4	5		7	8	9	10 11	12	!		1.	5

Bits 0-3 of the word location in main storage specified by the effective address are loaded into the interrupt mask register. (Effective Address Generation is explained in Chapter 2.) Bits 4-15 of the word in main storage are not used. The contents of main storage are unchanged.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The mask is represented in a bit significant manner as follows:

Mask bit	Interrupt level
0	0
1	1
2	2
3	3

A mask bit set to "1" indicates that the level is enabled. A mask bit set to "0" indicates that the level is disabled.

Indicators

All indicators are unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

SEIND

SET INDICATORS (SEIND)

SEIND

reg

0	pera	tio.	n c	ode	T				R2	1	Fun	ctio	n	\neg
0	1	1	1	0	0	0	0,			0	1	1	1	1
0				4	5		7	8	10	11				 15

Bits 0 through 4 of the register specified by the R2 field are loaded into bits 0 through 4 of the current level status register (indicators). Bits 5 through 15 of the register specified by R2 are ignored. Bits 5 through 15 of the level status register are unchanged.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The following table shows the indicator bits of the level status register (LSR):

	_	(
LSR bit		Indicator
0		Even
1		Carry
2		Overflow
3		Negative
4		zero

Indicators

Changed as specified by the R2 register.

Program Check Conditions

SELB

SET LEVEL BLOCK (SELB)

Execution of the SELB instruction can cause the processor to change levels. Also, the processor may exit supervisor state. For additional information concerning the processor action when executing this instruction, refer to *Program Controlled Level Switching* in Chapter 3.

SELB reg,addr4

1	O	ero	tio	n c	ode	Π	R		F	₹B	Al	И	F	un	ctio	n	
1	0	1	0	1	1	l					1		0	1	1	0	
١	0				4	5		7	8	9	10	11	12			1.	5

This instruction loads a level status block (LSB) from 11 words of main storage beginning with the location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) The contents of the storage locations are not changed.

The register specified by the R field contains the binary encoded level of the LSB to be loaded. The binary encoded level is placed in bits 14-15 of the register. Bits 1-13 are not used and must be zero to avoid future code obsolescence.

Bit 0 of the register specified by the R field is the inhibit trace (IT) interrupt bit. If bit 0 is a one and the trace bit (bit 10) in the LSR of the target LSB is a one, then both the Set Level Block instruction and the instruction pointed to by the IAR in the target LSB are executed before trace interrupts are allowed.


If bit 0 is zero and the trace bit in the LSR of the target LSB is a one, the Set Level Block instruction is executed and then trace interrupts are allowed.

The target LSB is defined by either (1) the effective address, if the in-process bit is set to one in the LSR of the target LSB and the specified R field level is higher than or equal to the current level, or (2) the currently active LSB when condition 1 is not met.

Level Status Block Format

EA IAR
AKR
LSR
Register 0
Register 1
Register 2
Register 3
Register 4
Register 5
Register 6
EA+20 Register 7
(+14 hex)
EA=effective address

Format of Register Specified by R in Instruction



Programming Notes.

- 1. The Set Level Block instruction with the IT bit equal to one should be used to return from the trace interrupt routine and from a class interrupt routine when the instruction causing the interrupt is to be reexecuted. This is necessary to prevent a double trace of the instruction.
- If the Set Level Block instruction sets the current level in-process bit to zero and the current level trace bit to one, no trace interrupt occurs as the level is exited.
- 3. The registers, AKR, and LSR for the current level are not changed if the specified R field level is other than the current level.
- 4. If the AM field equals 01, the contents of the register specified by the RB field are incremented by 2.

Indicators

All indicators are unchanged if the specified level is other than the current level.

Program Check Conditions

Invalid Storage Address. Instruction word or level status block.

Privilege Violate. Privileged instruction.


Specification Check. Even byte boundary violation (indirect address or level status block address).

SET STORAGE KEY (SESK)

Refer to Chapter 8 for a description of the storage protection mechanism.

SESK


reg,addr4




This instruction loads a storage key register with the contents of the byte location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.)

The register specified by the R field contains the main storage block number for the storage key register to be loaded. (A storage key register is associated with every 2048 bytes of storage.) The block number is binary encoded in bits 0-4 of the register. Bits 5-15 are not used and must be zero to avoid future code obsolescence.

The format of the register specified by the R field is:



The format of the byte at the storage location is:



Bits 4-7 are the storage key and read-only bit for the selected storage block. Bits 0-3 are not used and must be zero to avoid future code obsolescence.

The contents of the storage location are unchanged.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address).

SESR


SET SEGMENTATION REGISTER (SESR)

This instruction is invalid if the Storage Address Relocation Translator Feature is not installed. Chapter 9 describes the relocation translator feature.


This instruction loads a segmentation register with the contents of the doubleword location in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.)


The register specified by the R field contains the number of the segmentation register to be loaded (0-255). This number is composed of three bits from the address key (values 0-7) and the five high-order bits of the logical storage address (values 0-31). Bits 8 through 15 of the register are not used and must be set to zero to avoid future code obsolescence.

The format of the register specified by the R field is:



The format of the doubleword to be loaded into the segmentation register is:





Bits 0 through 12 contain the high-order 13 bits of the physical address used by the translator to select a 2K block of storage.

Bit 13, if a one, signifies that the contents of the segmentation register are valid, and translation can be performed. If an attempt is made to use a segmentation register with bit 13 set to zero, a program check interrupt occurs, with invalid storage address set in the PSW.

Bit 14, if a one, signifies that the block is read only. If an attempt is made to write into the block when bit 14 of the associated segmentation register is a one and while in problem state, a program check interrupt occurs, with protect check set in the PSW. When in supervisor state or on a cycle steal access, bit 14 is ignored. The contents of main storage are not changed.

Bits 15 through 31 are not used and must be set to zero to avoid future code obsolescence.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Function. Translator not installed.


Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

SCAN BYTE FIELD EQUAL AND DECREMENT (SFED)

SCAN BYTE FIELD EQUAL AND INCREMENT (SFEN)

SFED reg,(reg) SFEN reg,(reg)



This instruction compares a field in main storage against a single byte contained in a register. This comparison is made one byte at a time. Register 7 contains the number of bytes to be compared. This number is decremented after each byte is compared.

The register specified by R1 contains, in bits 8-15, the single byte of operand 1. The register specified by R2 contains the starting address of operand 2. Operand 1 is subtracted from operand 2, but neither operand is changed.

After each byte is compared, the address in R2 is incremented or decremented (determined by bit 13 of the instruction). The operation terminates when either:

- 1. An equal condition is detected, or
- 2. The number of bytes specified in register 7 has been compared.

When an equality occurs, the address in the register specified by R2 points to the next operand to be compared, but the count in R7 is not updated.

Bit 11 of the instruction is not used and must be set to zero to avoid future code obsolescence.

See Compare Byte Field Equal and Decrement (CFED) and Compare Byte Field Equal and Increment (CFEN) for other versions of this machine instruction.

Notes.

- 1. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining byte count specified in register 7.
- 2. If the specified count in R7 is zero, the instruction performs no operation (no-op).

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Operand. The instruction is terminated.


Protect Check. Instruction fetch. The instruction is terminated.

SFNED SFNEN

SCAN BYTE FIELD NOT EQUAL AND DECREMENT (SFNED)

SCAN BYTE FIELD NOT EQUAL AND INCREMENT (SFNEN)

SFNED reg,(reg) SFNEN reg,(reg)



This instruction compares a field in main storage against a single byte contained in a register. This comparison is made one byte at a time. Register 7 contains the number of bytes to the compared. This number is decremented after each byte is compared.

The register specified by R1 contains, in bits 8-15, the single byte of operand 1. The register specified by R2 contains the starting address of operand 2. Operand 1 is subtracted from operand 2, but neither operand is changed.

After each byte is compared, the address in R2 is incremented or decremented (determined by bit 13 of the instruction). The operation terminates when either:

- 1. An unequal condition is detected, or
- 2. The number of bytes specified in register 7 has been compared.

When an inequality occurs, the address in the register specified by R2 points to the next operand to be compared, but the count in R7 is not updated.

Bit 11 is not used and must be set to zero to avoid future code obsolescence.

See Compare Byte Field Not Equal and Decrement (CFNED) and Compare Byte Field Not Equal and Increment (CFNEN) for other versions of this machine instruction.

Notes.

- 1. Variable field length instructions can be interrupted. When this occurs and the interrupted level resumes operation, the processor treats the uncompleted instruction as a new instruction with the remaining byte count specified in register 7.
- 2. If the specified count in R7 is zero, the instruction performs no operation (no-op).

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the byte. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one byte; i.e., if the difference is less than -2^7 or greater than $+2^7-1$.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Operand. The instruction is terminated.

SHIFT LEFT CIRCULAR (SLC)

Immediate Count Format

SLC

cnt16,reg

6)p	era	tio	n co	ode	Γ	R		Count		$F\iota$	inci	tion
[0)	0	1	1	0			_	ļ		0	0	0
0)				4	5		7	8	12	13	,	15

The bits in the register specified by the R field are shifted left by the number of bit positions specified in the count field. The bits shifted out of the high-order bit (bit 0) re-enter at the low-order bit (bit 15). A count of zero causes no shifting to take place.

Although the register to be shifted contains only 16 bits, shift count values of 0-31 may be specified. Shift counts greater than 16 lengthen the execution time and provide an effective shift of modulo 16.

Indicators

Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the final contents of the register.


Program Check Conditions

Protect Check. Instruction fetch.

Example:

R3 before shift






Count in Register Format

SLC

reg,reg



The bits in the register specified by the R1 field are shifted left by the number of bits specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field.

The contents of the register specified by the R2 field are unchanged unless the R1 and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the register to be shifted contains only 16 bits, shift count values of 0-255 may be specified. Shift counts greater than 16 lengthen the execution time and provide an effective shift of modulo 16.

Indicators


Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the final contents of the register specified by the R1 field.


Program Check Conditions

Protect Check. Instruction fetch.

Example:







SLCD

SHIFT LEFT CIRCULAR DOUBLE (SLCD)

Immediate Count Format

SLCD

cnt31,reg

O		tio	n co	ode	Γ	R	Count	Fun	ction
0	0	1	1	0	l			1 (0
0				4	5	7	8	12 13	15

The bits in the register pair specified by the R field and R+1 are shifted left by the number of bit positions specified in the count field.

Within the register pair, the register specified by the R field contains the high-order word (bits 0-15); the register specified by R+1 contains the low-order word (bits 16-31). The bits shifted out of the high-order bit (bit 0) re-enter at the low-order bit (bit 31).

If the count is zero, no shifting occurs. If the R field equals 7, registers 7 and 0 are used for the register pair.

Indicators


Carry and Overflow Unchanged.


Even, Negative, and Zero. Changed to reflect the final contents of the two registers.


Program Check Conditions

Protect Check. Instruction fetch.

Example:







Count in Register Format

SLCD

reg,reg

O_l	oera	tio	n cc	de		R1			R2		F	unc	tio	n	
0	1	1	1	0							1	0	1	0	0
0				4	5		7	8		10	11	'			15

The bits in the register pair specified by the R1 field and R1+1 are shifted left by the number of bits specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field.

Within the register pair, the register specified by the R1 field contains the high-order word (bits 0-15); the register specified by R1+1 contains the low-order word (bits 16-31). The bits shifted out of the high-order bit (bit 0) re-enter at the low-order bit (bit 31).

If the count is zero, no shifting occurs. If the R1 field equals 7, registers 7 and 0 are used for the register pair.

The contents of the register specified by the R2 field are unchanged unless the R1 (or R1 + 1) and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the registers to be shifted represent 32 bits, shift count values of 0-255 may be specified. Shift count values greater than 32 lengthen the execution time and provide an effective shift of modulo 32.

Indicators


Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the final contents of the two registers.


Program Check Conditions

Protect Check. Instruction fetch.

Example:







3

SLL

SHIFT LEFT LOGICAL (SLL)

Immediate Count Format

SLL

cnt16,reg

T	21	ero	ıtio	n co	ode	Γ	R	Count		$F\iota$	ıncı	tion
10) .	0	1	1	0					0	0	1
7	ō				4	.5	7	8	12	13	•	15

The bits in the register specified by the R field are shifted left by the number of bit positions specified in the count field. The vacated low-order bit positions of the register are set to zero. A count of zero causes no shifting to take place.

Although the register to be shifted contains only 16 bits, shift count values of 0-31 may be specified. Shift counts greater than 17 lengthen the execution time of the shift instruction and provide an effective shift of 17.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0. If the count is zero, the carry indicator is reset.

Overflow. First reset, then set to a one if the most significant bit in the register (bit 0) has changed during the operation.

Even, Carry, and Overflow. Changed to reflect the final contents of the register.

Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SLL

reg,reg

01	pera	itio	n co	ode	R	2.1	I	₹2	F	unc	tioi	2	
0	1	1	1	0					1	0	0	0	1
0				4	5	7	8	10	11	!			15

The bits in the register specified by the R1 field are shifted left by the number of bits specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field. The vacated low-order bits of the register specified by the R1 field are set to zero.

The contents of the register specified by the R2 field are unchanged unless the R1 and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the register shifted contains only 16 bits, shift count values of 0-255 may be specified. Shift counts greater than 17 lengthen the execution time of the shift instruction and provide an effective shift of 17.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0. If the count is zero, the carry indicator is reset.

Overflow. First reset, then set to a one if the most significant bit in the register (bit 0) has changed during the operation.

Even, Negative, and Zero. Changed to reflect the final contents of the register specified by the R1 field.

Program Check Conditions

SHIFT LEFT LOGICAL DOUBLE (SLLD)

Immediate Count Format

SLLD

cnt31,reg

O_{l}	pera	tio	n co	ode		R		Count		Fu	inci	tion
0	0	1	1	0				:		1	0	1
0				4	5		7	8	12	13		15

The bits in the register pair specified by the R field and R+1 are shifted left by the number of bit positions specified in the count field. The vacated low-order bits of the register pair are set to zero.

Within the register pair, the register specified by the R field contains the high-order word (bits 0-15); the register specified by R+1 contains the low-order word (bits 16-31).

If the shift count is zero, no shifting occurs. If the R field equals 7, registers 7 and 0 are used for the register pair.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0.

Overflow. First reset, then set to a one if the most significant bit in the register pair (bit 0) has changed during the operation.

Even, Negative, and Zero. Changed to reflect the final contents of the two registers.


Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SLLD

reg,reg



The bits in the register pair specified by the R1 field and R1+1 are shifted left by the number of bit positions specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field. The vacated low-order bit positions of the register pair are set to zero.

Within the register pair, the register specified by the R1 field contains the high-order word (bits 0-15); the register specified by R1+1 contains the low-order word (bits 16-31).

If the shift count is zero, no shifting occurs. If the R1 field equals 7, registers 7 and 0 are used for the register

The contents of the register specified by the R2 field are unchanged unless the R1 (R1+1) and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the registers to be shifted represent 32 bits, shift count values of 0-255 may be specified. Shift counts greater than 33 lengthen the execution time of the shift instruction and provide an effective shift of 33.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0.

Overflow. First reset, then set to a one if the most significant bit in the register pair (bit 0) has changed during the operation.

Even, Negative, and Zero. Changed to reflect the final contents of the two registers.

Program Check Conditions

SLT SLTD

SHIFT LEFT AND TEST (SLT)

SLT

reg,reg

0	pera	itio	n co	ode		R <i>1</i>		R2	F	unc	tio	7	
0	1	1	1	0			ĺ		1	1	0	0	1
0				4	5	7	8	1	0 1.	1			15

The bits in the register specified by the R1 field are shifted left. The vacated low-order bit positions of the register are set to zero.

Shifting continues until either one of the following occurs:

- 1. The number of bits specified by the shift count have been shifted. This count is obtained from bits 8 through 15 of the register specified by the R2 field. No shifting occurs if the shift count is zero.
- 2. A one-bit is shifted from the high-order bit (bit 0) to the carry indicator. In this case, the remaining shift count is loaded into bits 8 through 15 of the register specified by the R2 field.

Bits 0 through 7 of the register specified by the R2 field are unchanged; these bits must be set to zero to avoid future code obsolescence.

If the R1 and R2 fields specify the same register, the bits in the register are shifted as specified and, when shifting is complete, the remaining shift count replaces the shifted result.

Although the register to be shifted contains only 16 bits, shift count values of 0-255 may be specified.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0. If the count is zero, the carry indicator is reset.

Overflow. First reset, then set to a one if the most significant bit in the register (bit 0) has changed during the operation.

Even, Negative, and Zero. Changed to reflect the final contents of the register specified by the R2 field.

Program Check Conditions

Protect Check. Instruction fetch.

SHIFT LEFT AND TEST DOUBLE (SLTD)

SLTD

O	pera	tio	n co	ode	R	1	F	22	F	unc	tio	n	
0	1	1	1	0					1	1	1	0	1
0				4	5	7	8	10	11				15

reg,reg

The bits in the register pair specified by the R1 field and R1+1 are shifted left. The vacated low-order bit positions of the register pair are set to zero.

Shifting continues until either one of the following occurs:

- 1. The number of bits specified by the shift count have been shifted. This count is obtained from bits 8 through 15 of the register specified by the R2 field. No shifting occurs if the shift count is zero.
- 2. A one-bit is shifted from the high-order bit to the carry indicator. In this case, the remaining shift count is loaded into bits 8 through 15 of the register specified by the R2 field. Bits 0 through 7 of the register specified by the R2 field are unchanged; these bits must be set to zero to avoid future code obsolescence.

Within the register pair, the register specified by the R1 field contains the high-order word (bits 0–15); the register specified by R1+1 contains the low-order word (bits 16–31). If the R1 field equals 7, registers 7 and 0 are used for the register pair.

If the R1 (or R1+1) and R2 fields specify the same register, the bits in the register are shifted as specified and, when shifting is complete, the remaining shift count replaces the shifted result.

Although the register to be shifted contains only 16 bits, shift count values of 0-255 may be specified.

Indicators

Carry. Set to reflect the last bit shifted out of bit 0. If the count is zero, the carry indicator is reset.

Overflow. First reset, then set to a one if the most significant bit in the register (bit 0) has changed during the operation.

Even, Negative, and Zero. Changed to reflect the final contents of the register specified by the R2 field.

Program Check Conditions

SHIFT RIGHT ARITHMETIC (SRA)

Immediate Count Format

SRA

cnt16,reg

O_l	pera	tio	n co	ode		R		Count		F_{1}	inc	tion
0	0	1	1	0						0	1	1
0				4	5		7	8	12	13		15

The bits in the register specified by the R field are shifted right by the number of bit positions specified in the count field. The value of the sign (the high-order bit) is entered into the vacated high-order bit positions of the register specified by the R field. If the shift count is zero, no shifting takes place.

Although the register to be shifted contains only 16 bits, shift count values of 0-31 may be specified. Shift counts greater than 16 lengthen the execution time of the shift instruction and provide an effective shift of 16.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register.


Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SRA

reg,reg



The bits in the register specified by the R1 field are shifte right by the number of bit positions specified by the shi count. This count is obtained from bits 8 through 15 of tl register specified by the R2 field. The value of the sign (tl high-order bit) is entered into the vacated high-order b positions of the register specified by the R1 field. If the shift count is zero, no shifting takes place.

The contents of the register specified by the R2 field at unchanged unless the R1 and R2 fields specify the sam register. In this case, the register contents are shifted a specified.

Although the register to be shifted is 16 bits, shift cour values of 0-255 may be specified. Shift counts greater tha 16 lengthen the execution time of the shift instruction an provide an effective shift of 16.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the fina contents of the register specified by the R1 field.

Program Check Conditions

SRAD

SHIFT RIGHT ARITHMETIC DOUBLE (SRAD)

Immediate Count Format

SRAD cnt31,reg

O		tio	n co	ode	Γ-	R	Count	Function
0	0	1	1	0	1			1 1 1
0				4	5	7	8	12 13 15

The bits in the register pair specified by the R field and R+1 are shifted right by the number of bit positions specified in the count field. The value of the sign (the high-order bit) is entered into the vacated high-order bit positions of the register pair.

Within the register pair, the register specified by the R field contains the high-order word (bits 0-15); the register specified by R+1 contains the low-order word (bits 16-31).

If the shift count is zero, no shifting occurs. If the R field equals 7, registers 7 and 0 are used for the register pair.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register pair.

Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SRAD reg,reg

Or	era	tio	n c	ode	Τ	R1		Γ	R2		F	unc	tio	1	
0	1	1	1	0	1			١			1	0	1	1	1
0				4	5		7	8		10	11	!			15

The bits in the register pair specified by the R1 field and R1+1 are shifted right by the number of bit positions specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field. The value of the sign (the high-order bit) is entered into the vacated high-order bit positions of the register pair.

Within the register pair, the register specified by the R1 field contains the high-order word (bits 0-15)); the register specified by R1+1 contains the low-order word (bits 16-31).

If the shift count is zero, no shifting occurs. If the R field equals 7, registers 7 and 0 are used for the register pair.

The contents of the register specified by the R2 field are unchanged unless the R1 (or R1 + 1) and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the registers to be shifted represent 32 bits, shift count values of 0-255 may be specified. Shift counts greater than 32 lengthen the execution time of the shift instruction and provide an effective shift of 32.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register pair.

Program Check Conditions

SHIFT RIGHT LOGICAL (SRL)

Immediate Count Format

SRL

cnt16,reg

O_l	pera	tio	n co	ode	Γ	R	_	Count		Fu	nc	tion
0	0	1	1	0	L					0	1	0
0				4	5	- 1	7	8	12	13		15

The bits in the register specified by the R field are shifted right by the number of bit positions specified in the count field. The vacated high-order bit positions of the register are set to zero. A count of zero causes no shifting to take place.

Although the register to be shifted contains only 16 bits, shift count values of 0-31 may be specified. Shift counts greater than 16 lengthen the execution time of the shift instruction and provide an effective shift of 16.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register.


Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SRL

reg,reg



The bits in the register specified by the R1 field are shift right by the number of bit postions specified by the sh count. This count is obtained from bits 8 through 15 of tl register specified by the R2 field. The vacated high-ord bit positions of the register specified by the R1 field are s to zero. A count of zero causes no shifting to take place.

The contents of the register specified by the R2 field a unchanged unless the R1 and R2 fields specify the san register. In this case, the register contents are shifted specified.

Although the register to be shifted contains only 16 bit shift count values of 0-255 may be specified. Shift coun greater than 16 lengthen the execution time of the shi instruction and provide an effective shift of 16.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the fina contents of the register specified by the R1 field.

Program Check Conditions

SRLD

SHIFT RIGHT LOGICAL DOUBLE (SRLD)

Immediate Count Format

SRLD

cnt31,reg

O	Operation code 0 0 1 1 0				Operation code				ode	Γ	R		Count		$F\iota$	inc	tion
0	0	1		1	0						1	1	0				
0			_		4	5		7	8	12	13	3	15				

The bits in the register pair specified by the R field and R+1 are shifted right by the number of bit positions specified in the count field. The vacated high-order bits of the register pair are set to zero.

Within the register pair, the register specified by the R field contains the high-order word (bits 0-15); the register specified by R+1 contains the low-order word (bit 16-31).

If the shift count is zero, no shifting occurs. If the R field equals 7, registers 7 and 0 are used for the register pair.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register.

Program Check Conditions

Protect Check. Instruction fetch.

Count in Register Format

SRLD

reg,reg

O	per	ıtio	n co	ode	F	21		R2	F	unc	tio	1	
0	1	1	1	0	İ		1		1	0	1	1	0
6				4	5	7	8	10	1.	ľ			15

The bits in the register pair specified by the R1 field and R1+1 are shifted right by the number of bit positions specified by the shift count. This count is obtained from bits 8 through 15 of the register specified by the R2 field. The vacated high-order bits of the register pair are set to zero.

Within the register pair, the register specified by the R1 field contains the high-order word (bits 0-15); the register specified by R1+1 contains the low-order word (bits 16-31).

If the shift count is zero, no shifting occurs. If the R1 field equals 7, registers 7 and 0 are used for the register pair.

The contents of the register specified by the R2 field are unchanged unless the R1 (or R1+1) and R2 fields specify the same register. In this case, the register contents are shifted as specified.

Although the registers to be shifted represent 32 bits, shift count values of 0-255 may be specified. Shift counts greater than 32 lengthen the execution time of the shift instruction and provide an effective shift of 32.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the final contents of the register pair.

Program Check Conditions

STORE MULTIPLE (STM)

Refer to Stack Operations in Chapter 2 for additional information about the operation of this instruction. The STM instruction is used in conjunction with the Load Multiple and Branch (LMB) instruction described previously in this chapter.

STM

reg,addr4[,abcnt]

Format without appended word for effective addressing (AM = 00 or 01)

O_l	pera	itio	n co	ode				R	В	AM	F	unc	tio	n
0	1	0	0	0	0	0	0				1	0	0	0
0				4	5		7	8	9	10 11	12	?		15

RL			N
16	18	19	31

Format with appended word for effective addressing (AM = 10 or 11)

01	pera	ıtio.	n co	ode			-	R	В	AM	F	unc	tio	ı
0	1	0	0	0	0	0	0				1	0	0	0
0				4	5		7	8	9	10 11	12	;		15

	Address/L	Displacement									
	Displacement 1	Displacement 2									
16	23 24 31										



The STM instruction stores the contents of a specified number of registers for the current level into a stack. This stack is defined by the stack control block pointed to by the effective address. (Effective Address Generation is explained in Chapter 2.)

The RL field specifies the last register to be stored. Register 7 is stored first, then registers 0 through the register specified by RL. If RL specifies register 7, only register 7 is stored.

The N field specifies the number of words to be allocated in the stack as a dynamic work area. A value of zero is valid.

The new top element address of the stack (incremented by two) is loaded into the last register stored; that is, the register specified by RL. This address points to the low storage end of the dynamic work area (or the last register stored if N=0).

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence

Programming Note. If the AM field equals 01, the content of the register specified by the RB field are incremented by 2.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or stack control block.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. A partial data transfer occurs if the area of the stack being accessed crosses a protection boundary.

Specification Check.

- 1. Even byte boundary violation (indirect address, stack control block, or stack element).
- 2. The value of N is odd.

Soft Exception Trap Condition

Stack Exception.

- 1. Stack is full.
- Stack cannot contain the number of words to be stored; that is:
 - a. Number of words specified by the N field, plus
 - b. The number of registers to be moved, plus
 - c. One control word.

If the AM field equals 01, the contents of the register specified by the RB field are incremented.

STOP SVC

STOP (STOP)

STOP

[ubyte]

ı	Or	era	tio	n cc	ode	Fu	nct	ion	Parameter
				0					
•	0				4	5		7	8 15

The parameter field is ignored by the hardware, and may be used for software flags or indicators.

This instruction is executed only when the Programmer Console is installed and the Mode switch is in the Diagnostic position. Otherwise this instruction performs no operation (no-op). The processor enters the stop state following execution of this instruction. The indicators are unchanged.

Indicators

No indicators are changed.

Program Check Conditions

Protect Check. Instruction fetch.

SUPERVISOR CALL (SVC)

Execution of this instruction causes a *class interrupt*. Additional information appears in Chapter 3.

SVC

ubyte

										_
1	O	era	tio	n cc	de	Fu	nct	ion	Parameter	- {
	0	1	1	0	0	0	0	0		
	7				4	5		7	8 1	5

The instruction address register is incremented by two: The current level status block (LSB) is stored, using an address key of zero, starting at the main storage location specified by the contents of the SVC LSB pointer that resides in main storage location 0010 hexadecimal. The instruction also causes the following events:

- The summary mask (LSR bit 11) is disabled.
- Supervisor state (LSR bit 8) is turned on.
- Trace (LSR bit 10) is turned off.
- Equate operand spaces (AKR bit 0) is turned off.
- Operand 2 key contents are loaded into the operand 1 key.
- Then the operand 2 key and the instruction space key are set to zero.

The parameter field (bits 8-15) is under control of the Programming System. This field is loaded into the low-order byte of register 1. The high-order byte of register 1 is set to zero.

Subsequently, the contents of main storage location 0012 hexadecimal (SVC start instruction address) are loaded into the instruction address register, becoming the address of the next instruction to be fetched.

Indicators

No indicators are changed.

Program Check Conditions

SUBTRACT WORD (SW)

Register/Register Format

SW reg,reg

O_{l}	pera	tio	n co	ode	Π	R1			R2		Fi	unc	tion	1	
0	1	1	1	0							0	1	0	1	0
0				4	5		7	8		10	11				15

The contents of the register specified by the R1 field are subtracted from the contents of the register specified by the R2 field. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field remain unchanged unless R1 and R2 specify the same register.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the register. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.


Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Protect Check. Instruction fetch.

Register/Storage Format

SW reg,addr4 addr4,reg



A subtract operation is performed between the register specified by the R field and the location specified by the effective address in main storage. (See *Effective Address Generation* in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


SW

Storage to Register Long Format

SW

longaddr,reg





The contents of the main storage word location specified by an effective address are subtracted from the contents of the register specified by the R1 field. The result is placed in the register specified by the R1 field.

The effective main storage address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0 (direct address). The result from step 1 is the effective address.

Bit 11=1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than- 2^{15} or greater than+ $2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Storage/Storage Format

SW

addr5,addr4

O	pera	tio	n cc	de	RB.	1	R	B2	AM1	AM2	Fun	1
1	0	1	0	1			l				0 1	J
0				4	5	7	8	9	10 11	12 13	14 15	5

The address arguments generate the effective addresses of two operands in main storage. (See *Effective Address Generation* in Chapter 2.) Word operand 1 is subtracted from word operand 2. The result replaces operand 2.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand. The instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

Protect Check. Instruction fetch, operand access, or operand store. For instruction fetch or operand access, the instruction is terminated. If AM1 equals 01 and the operand 2 effective address is invalid, RB1 is incremented.

For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

SUBTRACT WORD WITH CARRY (SWCY)

SWCY

reg,reg

O	pera	tio.	n co	ode	,	R1		R2		F	unc	tioi	1	
0	1	1	1	0						0	1	0	1	1
0				4	5	7	8	1	0	11				15

If the carry indicator is on at entry (denoting a borrow), a positive one is subtracted from the contents of the register specified by the R2 field. Then the contents of R1 are subtracted from the intermediate result. If the carry indicator is off at entry, the contents of R1 are subtracted from the contents of the register specified by R2. The contents of the register specified by the R1 field are unchanged unless R1 and R2 specify the same register. The final result replaces the contents of the register specified by the R2 field.

Programming Note. This instruction can be used when subtracting multiple word operands. See Indicators-Multiple Word Operands in Chapter 2.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than- 2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even. Unchanged.

Zero. If on at entry, set to reflect the result. If off at entry, remains off.

Negative. Changed to reflect the result.

Program Check Conditions


SWI

SUBTRACT WORD IMMEDIATE (SWI)

Register Immediate Long Format

SWI

word,reg[,reg]



The immediate field is subtracted from the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged unless R1 and R2 specify the same register.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than -2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word.


Protect Check. Instruction fetch.

Storage Immediate Format

SWI


word,addr4


Format without appended word for effective addressing (AM = 00 or 01)





Format with appended word for effective addressing (AM = 10 or 11)





The immediate field is subtracted from the contents of the

main storage location specified by the effective address. (See *Effective Address Generation* in Chapter 2.) The result replaces the contents of the storage location specified by the effective address.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

The immediate operand is unchanged.

Indicators

Carry. Turned on by the detection of a borrow beyond the high-order bit position of the word. If no borrow is detected, the carry indicator is reset.

Overflow. Cleared, then turned on if the difference cannot be represented in one word; i.e., if the difference is less than 2^{15} or greater than $+2^{15}-1$.

If an overflow occurs, the result contains the correct low-order 16 bits of the difference; the carry indicator contains the complement of the high-order (sign) bit.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

TEST BIT (TBT)

TBT

(reg,bitdisp)

Operation code					R	F	un	Bit displaces	nent	
0	1	0	0	1			0	0		
0				4	5	7	8	9	10	15

The bit displacement is added to the byte address contained in the register specified by the R field to form an effective bit address. The bit displacement field is an unsigned six-bit binary integer. The bit at the effective bit address is tested, and the zero and negative indicators are set to reflect the result.

Indicators

Zero and Negative. First reset, then set as follows:

Value of	Indicat	ors
tested bit	Zero	Negative
0	1	0
1	0	1

Even, Carry, and Overflow. Unchanged.

Program Check Conditions

Invalid Storage Address. Operand.

Protect Check. Instruction fetch or operand access.

TEST BIT AND RESET (TBTR)

TBTR

(reg,bitdisp)

O	pera	itio	n co	de		R	F	un	Bit	displacement
0	1	0	0	1			1	0		-
0				4	5	7	8	9	10	15

The bit displacement is added to the byte address contained in the register specified by the R field to form an effective bit address. The bit displacement field is an unsigned six-bit integer.

The bit at the effective address is tested, and the zero and negative indicators are set to reflect the result.

Following the preceding test, the addressed bit is unconditionally set to zero.

Indicators

Zero and Negative. First reset, then set as follow:

Value of	Indicators						
tested bit	Zero	Negative					
0	1	0					
1	0	1					

Even, Carry, and Overflow. Unchanged.

Program Check Conditions

Invalid Storage Address. Operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

TBTS TBTV

TEST BIT AND SET (TBTS)

TBTS (reg,bitdisp)

1	Operation code				<u> </u>	R	Fi	ın	Bit	displacement	
İ	0	1	0	0	1			0	1		
	o				4	5	7	8	9	10	15

The bit displacement is added to the byte address contained in the register specified by the R field to form an effective bit address. The bit displacement field is an unsigned six-bit binary integer.

The bit at the effective address is tested, and the zero and negative indicators are set to reflect the result.

Following the preceding test, the addressed bit is unconditionally set to one.

Indicators

Zero and Negative. First reset, then set as follows:

Value of	Indicat	ors
tested bit	Zero	Negative
0	1	0
1	0	1

Even, Carry, and Overflow. Unchanged.

Program Check Conditions


Invalid Storage Address. Operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

TEST BIT AND INVERT (TBTV)

TBTV

(reg,bitdisp)



The bit displacement is added to the byte address contained in the register specified by the R field to form an effective bit address. The bit displacement field is an unsigned six-bit binary integer.

The bit at the effective address is tested, and the zero and negative indicators are set to reflect the result.

Following the preceding test, the addressed bit is unconditionally inverted.

Indicators

Zero and Negative. First reset, then set as follows:

Value of	Indicate	ors
tested bit	Zero	Negative
0	1	0
1	0	1

Even, Carry, and Overflow. Unchanged.

Program Check Conditions


Invalid Storage Address. Operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

TEST WORD IMMEDIATE (TWI)

Register Immediate Long Format

TWI word,reg



The contents of the register specified by the R1 field are tested against the mask contained in the immediate word of the instruction. The contents of the register specified by the R1 field are not changed.

Mask bits set to one select the bits to be tested in the register.

Example:

Mask 0000 0000 0101 1100 Register 0000 0000 0011 0101 Selected bits 0 1 01

The selected bits are tested for the following: (1) all bits zero, (2) all bits ones, or (3) a combination of one and zero bits (mixed). The zero and negative indicators are set to reflect the result as shown under Indicators.

Instruction bits 8 through 10 are not used and must be set to zero to avoid future code obsolescence.

Indicators

Zero and Negative. Reset, then set as follows:

Indicators

Selected bits	Zero	Negative
All zeros*	1	0
All ones	0	1
Mixed	0	0(postive)

^{*} Also applies when the mask bits are all zeros.

Even, Carry, and Overflow. Unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch.

Storage Immediate

TWI word,addr4


Format without appended word for effective

addressing (AM = 00 or 01)

O_l	oera	tio	n cc	de				R	В	AM	F	unc	tio	n
0	1	0	0	0	0	0	0				1	0	1	1
0				4	5		7	8	9	10 11	12	?		15



Format with appended word for effective addressing (AM = 10 or 11)



The contents of the storage location specified by the effective address are tested against the mask in the immediate word of the instruction. (Effective Address Generation is explained in Chapter 2.) Both operands remain unchanged.

Mask bits set to one select the bits to be tested in the storage operand.

Example:

Mask 0000 0000 0000 1110 Storage operand 0000 0000 0101 1110 Selected bits

The selected bits are tested for the following: (1) all bits zeros, (2) all bits ones, or (3) a combination of one and zero bits (mixed). The zero and negative indicators are set to reflect the result as shown under Indicators.

Bits 5-7 are not used and must be set to zero to avoid future code obsolescence.

Indicators

Zero and Negative. Reset, then set as follows:

	Indicators	
Selected bits	Zero	Negative
All zeros*	1	0
All ones	0	1
Mixed	0	0 (positive)
*Also applies v	vhen the mas	k bits are all zeros.

Even, Carry, and Overflow. Unchanged.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.



INVERT REGISTER (VR)

VR reg[,reg]

Operation code					R1		R2		Function				
0	1	1	1	0					0	1	1	0	1
\overline{o}	-			4	5	7	8	10	11				15

The contents of the register specified by the R1 field are one's complemented. The result is placed in the register specified by the R2 field. The contents of the register specified by the R1 field are unchanged.

Indicators

Carry and Overflow. Unchanged.


Even, Negative, and Zero. Changed to reflect the result.


Program Check Conditions

Protect Check. Instruction fetch.

EXCLUSIVE OR BYTE (XB)

XB reg,addr4 addr4,reg





A logical exclusive OR operation is performed between the least significant byte of the register specified by the R field and the main storage location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged. Also, when going from storage to register, bits 0-7 of the register are unchanged.

Example of Exclusive OR Byte:

 Register contents
 0000
 1010
 1100
 0011

 Storage operand
 0110
 0101

 Result
 1010
 0110

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the exclusive OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.


Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.

Specification Check. Even byte boundary violation (indirect address).

EXCLUSIVE OR DOUBLEWORD (XD)

XD

reg,addr4 addr4,reg



A logical exclusive OR operation is performed between the contents of the register pair specified by the R field (R and R+1) and the doubleword in main storage specified by the effective address. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

If the R field equals 7, registers 7 and 0 are used as the register pair.

Example of Exclusive OR Doubleword:

Register pair

 contents
 0000
 0000
 1010
 1100
 0000
 0000
 1111
 1111

 Storage operand
 0000
 0000
 1101
 0011
 0000
 0000
 1101
 0000
 0000
 1111
 1111
 0000
 0011
 1111

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the exclusive OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. If the doubleword location specified by the effective address crosses a read-only protection boundary, partial data may be stored into the non read-only protected area. The status of the even, negative, and zero indicators is unpredictable.

XW

EXCLUSIVE OR WORD (XW)

Register/Register Format

XW

reg,reg

0	pera	tio	n co	ode	F	21	I	₹2	F	unc	tio	1	\neg
0	1	1	1	0					0	0	0	1	1
0				4	5	7	8	10	11	!			15

The contents of the register specified by the R1 field are exclusive ORed bit by bit with the contents of the register specified by the R2 field. The result is placed in the register specified by the R2 field. The contents of the register specified by R1 are unchanged unless R1 and R2 specify the same register.

Example of Exclusive OR Word:

 Register contents(R1)
 1111 0000 1010 0000

 Register contents(R2)
 0011 1111 0111 1111

 Result
 1100 1111 1101 1111

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the exclusive OR operation.


Program Check Conditions


Protect Check. Instruction fetch.

Register/Storage Format

XW

reg,addr4 addr4,reg





A logical exclusive OR operation is performed between the contents of the register specified by the R field and the main storage location specified by the effective address. (Effective Address Generation is explained in Chapter 2.) Bit 12 of the instruction specifies the destination of the result. The source operand is unchanged.

Example of Exclusive OR Word:

 Register contents (R)
 1111 0000 1010 0000

 Storage operand
 0011 1111 0111 1111

 Result
 1100 1111 1101 1111

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result of the exclusive OR operation.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store. For operand store (read-only violation), the instruction is terminated. Main storage is not changed but the indicators are set as described.


Specification Check. Even byte boundary violation (indirect address or operand address).




Storage to Register Long Format

XW

longaddr,reg





A logical exclusive OR operation is performed between the contents of the register specified by the R1 field and the contents of the main storage word location specified by the effective address. The result is placed in the register specified by the R1 field.

The effective main storage address is generated as follows:

- 1. The address field is added to the contents of the register specified by the R2 field. If the R2 field equals zero, no register contributes to the address generation.
- 2. Instruction bit 11 is tested for direct or indirect addressing:

Bit 11=0 (direct address). The result from step 1 is the effective address.

Bit 11= 1 (indirect address). The result from step 1 is the address of the main storage location that contains the effective address.

Example of Exclusive OR Word:

Register contents (R1) 1111 0000 1010 0000 Storage operand 0011 1111 0111 1111

Result 1100 1111 1101 1111

Rule: Either but not both bits.

Indicators

Carry and Overflow. Unchanged.

Even, Negative, and Zero. Changed to reflect the result loaded into the register specified by the R1 field.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

EXCLUSIVE OR WORD IMMEDIATE (XWI)

XWI word,reg[,reg]





The immediate field is exclusive ORed bit by bit with the contents of the register specified by the R1 field. The result is placed in the register specified by the R2 field. The contents of the register specified by R1 are unchanged unless R1 and R2 specify the same register.

Example of Exclusive OR Word:

Register contents (R1) 1111 0000 1010 0000 Immediate operand 0011 1111 0111 1111 Result 1100 1111 1101 1111

Rule: Either but not both bits.

Indicators

Carry and Overflow, Unchanged.

Even, Negative, and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address, Instruction word.

Protect Check, Instruction fetch.


Chapter 6. Floating-Point Feature


The floating-point feature includes (1) all floating-point instructions and (2) four 64-bit floating-point registers for each of the four priority interrupt levels in the processor. The floating-point instruction set performs calculations on operands with a wide range of magnitude. Results of these calculations are scaled to preserve precision. The floating-point registers are provided to avoid unnecessary storing and loading operations for results and operands.

A floating-point number consists of a signed exponent and a signed fraction. The quantity expressed by this number is the product of the fraction and the number 16 raised to the power of the exponent. The exponent is expressed in excess 64 binary notation; the fraction is expressed as a hexadecimal number having a radix point to the left of the high-order hexadecimal digit.

DATA FORMAT

Two fixed-length formats (short and long) may be used for floating-point data.





Both formats may be used in main storage and in the floating-point registers. The first bit in either format is the sign bit (S). The subsequent seven bit positions are occupied by the characteristic. The fraction field may have either six or 14 hexadecimal digits.

The entire set of floating-point instructions is available for both short and long operands. When single precision (short format) is specified, all operands and results are 32-bit floating-point words. With two exceptions, the rightmost 32-bits of the floating-point registers do not participate in single precision operations and are unchanged by the operations. The two exceptions are (1) the product in multiply operations (it is a 64-bit floating-point word and occupies a full register), and (2) a storage to register move (the low-order 32 bits are set to zero). When double precision (long format) is specified, all operands and results are 64-bit floating-point words.

Although final results in short precision have six fraction digits, intermediate results in add and subtract operations may extend to seven fraction digits. The low-order digit of a seven digit fraction is called the guard digit and serves to increase the precision of the final result. Intermediate results in long precision may extend to 15 fraction digits with the 15th digit being the guard digit.

NUMBER REPRESENTATION

Floating-Point Numbers

The fraction of a floating-point number is expressed in hexadecimal digits. The radix point of the fraction is assumed to be immediately to the left of the high-order fraction digit. To provide the proper magnitude for the floating-point number, the fraction is considered to be multiplied by a power of 16. The characteristic portion, bits 1–7 of both floating-point formats, indicates this power. The bits within the characteristic field can represent numbers from 0 through 127. To accommodate large and small magnitudes, the characteristic is formed by adding 64 to the actual exponent. The range of the exponent is thus –64 through +63. This technique produces a characteristic in excess 64 notation.

Both positive and negative quantities have a true fraction, the difference in sign being indicated by the sign bit. The number is positive or negative accordingly as the sign bit is zero or one.

A floating-point number with zero characteristic, zero fraction, and plus sign is called a true zero. A true zero may arise as the result of an arithmetic operation because of the particular magnitude of the operands. A result is forced to be true zero when an exponent underflow occurs or when a result fraction is zero.

Conversion Example

Convert the decimal number 149.25 to a short-precision floating-point operand.

 The number is decomposed into a decimal integer and a decimal fraction.

2. The decimal integer is converted to its hexadecimal representation.

$$149_{10} = 95_{16}$$

3. The decimal fraction is converted to its hexadecimal representation.

$$0.25_{10} = 0.4_{16}$$

- 4. Combine the integral and fractional parts and express as a fraction times a power of 16 (exponent).
 - $95.4_{16} = (0.954 \times 10^2)_{16}$
- The characteristic is developed from the exponent and converted to binary.
 - base + exponent = characteristic 64 + 2 = 66 1000010
- 6. The fraction is converted to binary and grouped hexadecimally. .954_{1.6} = .1001 0101 0100
- The characteristic and the fraction are stored in short precision format. The sign position contains the sign of the fraction.
 - S Char Fraction
 - 0 1000010 1001 0101 0100 0000 0000 0000

Binary Integers in Main Storage

Signed binary integers occupy storage in one of two fixed length formats:

- 1. One word format (16 bits)
- 2. Doubleword format (32 bits)

Both formats may be used in main storage and are automatically converted to single or double precision floating-point numbers during floating move and convert operations that move data from storage to a floating-point register. Negative signed binary integers are in main storage in twos complement form. They are converted to contain a true fraction. An integer may be moved from main storage to a floating-point register, without conversion, by using the floating move instruction. In this case, the integer is assumed to be a floating-point number.

Floating move and convert operations that move data from a floating-point register to storage accomplish the reverse process; the floating-point number in the register is automatically converted to an integer. This integer result is then placed in main storage. The floating move and floating move and convert operations are fully explained in the section Floating-point Instructions in this chapter.

NORMALIZATION

A quantity can be represented with the greatest precision by a floating-point number of given fraction length when that number is normalized. A normalized floating-point number has a nonzero high-order hexadecimal fraction digit. If one or more high-order fraction digits are zero, the number is said to be unnormalized. The process of normalization consists of shifting the fraction left until the high-order hexadecimal digit is nonzero and reducing the characteristic by the number of hexadecimal digits shifted. A zero fraction is not normalized.

Normalization takes place (1) after the multiply operations, and (2) after the add or subtract operations if an actual subtraction has taken place; for example, +A+(-B), +A-(+B), or -A-(-B). Normalization does not take place following a true addition or division; therefore, unnormalized operands can produce an unnormalized result. Floating-point numbers in main storage are assumed to be normalized.

PROGRAMMING CONSIDERATIONS

Floating-Point Feature Not Installed

An attempt to execute a floating-point instruction when the feature is not installed results in a soft-exception-trap interrupt with *invalid function* set in the PSW. An exception to this rule exists when attempting to execute a floating-point privileged instruction while in problem state. In this case, a program check interrupt occurs, with *privilege violate* set in the PSW.

Floating-Point Registers

Four floating-point registers are provided for each of the four priority interrupt levels associated with the processor. Floating-point register selection is determined by the register (R) field of the instruction. The R field in the instruction format consists of two bits and may be labeled R, R1, and R2 as required by the individual instruction.

Floating-point register selected
Register 0
Register 1
Register 2
Register 3

Note. The floating-point registers are not affected by Reset and must be initialized by the programmer.

Arithmetic Indicators

The processor indicators (carry, overflow, zero, negative, and even) are set or reset at the end of each floating-point instruction. Details of indicator settings are contained in the individual instruction descriptions in this chapter.

Floating-Point Exceptions

Floating-point underflow, overflow, and divide check are considered exception conditions. When these conditions are recognized, a soft-exception-trap class interrupt occurs with floating-point exception (bit 5) set in the PSW. The overflow, carry and even indicators are set as follows:

Overflow Indicator. Set to one by an overflow, underflow, or divide check.

Carry Indicator. Set to one by a divide check.

Even Indicator. Set to one by an underflow.

Floating-Point Overflow

• Add operations—An exponent overflow occurs when a carry from the high-order position of the intermediate-sum fraction causes the characteristic of the sum to exceed 127. The operation is completed by making the characteristic equal to 127. The result fraction is changed to the largest possible value.

- Subtract and compare operations—An exponent overflow occurs when a borrow from the high-order position of the intermediate-sum fraction causes the characteristic of the sum to exceed 127. The operation is completed by making the characteristic equal to 127. The result fraction bits are all changed to one.
- Divide operations—An exponent overflow occurs when the final-quotient characteristic exceeds 127. The operation is completed by forcing the characteristic to 127 and the result fraction to all ones.
- Multiply operations—An exponent overflow occurs when the characteristic of the normalized product exceeds 127 and the fraction is not zero. The operation is completed by forcing the characteristic to 127 and the result fraction to all ones.

Floating-Point Underflow

- Add operations—An exponent underflow occurs when the characteristic of the normalized sum is less than zero and the fraction is not zero. The result sign, characteristic, and fraction are forced to zero.
- Subtract and compare operations—An exponent underflow occurs when the characteristic of the normalized sum is less than zero and the fraction is not zero. The result sign, characteristic, and fraction are forced to zero.
- Divide operations—An exponent underflow occurs when the characteristic of the normalized quotient is less than zero and the fraction is not zero. The result sign, characteristic, and fraction are forced to zero.
- Multiply operations—An exponent underflow occurs when the characteristic of the normalized product is less than zero and the fraction is not zero. The result sign, characteristic, and fraction are forced to zero.

Divide Check

• Divide operations—A divide check occurs when division by zero is attempted. The dividend is not changed.

Level Control

Floating-point instructions are executed in a normal instruction stream on the active priority level in the processor. This level is sampled by the floating-point operation at the beginning of each floating-point instruction. Only program check and machine check class interrupts can occur during execution of floating-point instructions.

Instruction Termination or Suppression

Exception conditions that occur during instruction processing might cause the instruction to be terminated or suppressed. When an instruction is terminated, partial execution has taken place and may have caused a change to registers, indicators, or main storage. When an instruction is suppressed, there has been no execution, therefore, no changes. Refer to *Exception Conditions* in this chapter.

FLOATING-POINT INSTRUCTIONS

The floating-point instruction set provides a variety of instructions that deal with single or double precision floating-point data. The main categories are:

- Arithmetic instructions (add, subtract, multiply, divide, and compare)
- Data movement instructions (with or without conversion of binary integers)


Two privileged instructions are also provided for interrogation of the floating-point registers. They are (1) Copy Floating Level Block (CPFLB) and (2) Set Floating Level Block (SEFLB).


All floating-point instructions use the floating-point registers. One group of instructions (storage/floating-point register) specifies a register for one operand, and an effective main storage address for the other operand. Another group (floating-point register to floating-point register) specifies registers for both operands.

Instruction Formats

Arithmetic and data movement instructions use the following two formats:

Storage/Floating-point Register





Op code field. Specifies floating-point operation.

R field. Specifies a floating-point register.

Function field. Designates function to be performed. (add, subtract, multiply, divide, move, move and convert).

RB and AM fields. Designate the effective address argument. (See effective address generation in Chapter 2.)

P field. Designates precision of floating-point data.

0 = Single precision

1 = Double precision

Second word (Bits 16-31). Address mode appended word for an AM field equal to 10 or 11.

Floating-point Register to Floating-point Register

Operatio	n code		R	1	R	22			Fun	ction	P
		1					0	0			
0	4	.5	6	7	8	9	10	11	12	14	15

Op code field. Specifies floating-point operation.

R1 and R2 fields. Specify floating-point registers.

Bits 10-11. Designate the function modifier. These bits are not used and must be set to zero to avoid future code obsolescence.

Function field. Designates function to be performed.

(add, subtract, multiply, divide, move, compare).

Note. To avoid future code obsolescence, function field bit combination equal to 110 must not be used.

P field. Designates precision of floating-point data.

0 = single precision

1 = double precision

Another instruction format is used for the two privileged instructions (Copy Floating Level Block and Set Floating Level Block). The three-bit R field associated with this format specifies a processor general register (0-7). See the individual instructions for the complete format.

Note. The instruction formats are also shown in Appendix B of this manual.

EXCEPTION CONDITIONS

Exception conditions that might occur during instruction execution are shown in abbreviated form with each instruction description. Refer to the following sections for a detailed description of these conditions.

Program Check Conditions

Invalid Storage Address

Instruction Word or Operand. One or more words of the instruction or the effective address is outside the installed storage size of the system. The register to register instructions are suppressed. The storage/register instructions are terminated.

A program check class interrupt occurs with *invalid* storage address (bit 1) set in the PSW.

Privilege Violate

Privileged Instruction. A privileged instruction is encountered while in problem state. The instruction is suppressed.

A program check class interrupt occurs with *privileged* violate (bit 2) set in the PSW.

Protect Check

Instruction Fetch or Operand Access. In the problem state, an instruction is fetched or data is accessed from a storage area not assigned to the current operation.

Operand Store. In the problem state, the instruction attempts to change an operand in a storage area assigned as read-only.

The register to register instructions are suppressed. The storage/register instructions are terminated. A program check class interrupt occurs with *protect check* (bit 3) set in the PSW.

Specification Check

Operand Address. The generated effective address has violated an even-byte boundary requirement.

Indirect Address. When using addressing mode (AM=11), the indirect address is not on an even-byte boundary.

The register to register instructions are suppressed. The storage/register instructions are terminated. A program check class interrupt occurs with *Specification check* (bit 0) set in the PSW.

Soft Exception Trap Condition

Floating-Point Exception

A floating-point underflow, overflow, or divide check has occurred. The instruction completes execution. A soft-exception-trap class interrupt occurs with floating-point exception (bit 5) set in the PSW.

Invalid Function

An attempt is made to execute a floating-point instruction when the feature is not installed. The register to register instructions are suppressed. The storage/register instructions are terminated. A soft exception trap class interrupt occurs with *invalid function* (bit 4) set in the PSW.

Note. The resulting class interrupt causes the contents of the storage address register (SAR) to be loaded into general register seven. SAR contains either (1) the calculated effective address of data operand 2, or (2) the address of the attempted instruction for register to register operations.

Instruction Descriptions

The following descriptions are in alphabetical sequence based on assembler mnemonics. Indicator settings are listed for each instruction. For additional indicator information, refer to Arithmetic Indicators in this chapter and to Indicators in Chapter 2.

Instruction timings are contained in Appendix A of this manual.

COPY FLOATING LEVEL BLOCK (CPFLB)

CPFLB reg,addr4

O_{l}	era	itio	n co	ode	Π	R		R	В	AM	7		Fui	ıcti	on
0	1	0	1	1	L			İ				1	0	1	1
0				4	5		7	8	9	10	11	12			15

The contents of the floating-point registers (floating level block) for the level specified by the R field register are stored into main storage locations beginning at the specified effective address (EA). All registers remain unchanged. After execution of this instruction, the floating level block appears in main storage as follows:

EA	Contents of floating-point register 0	
	Contents of floating-point register 1	
EA + 24 (II.)	Contents of floating-point register 2	
EA + 24 (Hex)	Contents of floating-point register 3	
	0	63

The general register specified by the R field has the format:

l	0	0	0	0	0	0	0	0	0	0	0	0	0	0	Level
	0													13	14 15

Bits 0-13 are not used and must be zero to avoid future code obsolescence. Bits 14 and 15 hold the binary encoded level of the floating level block associated with this operation. For example: 00 for level 0, 01 for level 1, 10 for level 2, and 11 for level 3.

Programming note. If AM=01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

FA

FLOATING ADD (FA)

General Description (Short precision)

Addition of two floating-point numbers is based on characteristic comparison and fraction addition. The characteristics of the two operands are compared, and the fraction accompanying the smaller characteristic is shifted right, with its characteristic increased by one for each hexadecimal digit shifted, until the two characteristics are equal.

When an operand is shifted right during alignment, the leftmost hexadecimal digit of the field shifted out is retained as a guard digit. The operand that is not shifted is considered to be extended with a low-order zero. Both operands are considered to be extended with low-order zeros when no alignment shift occurs. The 28-bit fractions are then added algebraically to form an intermediate sum.

The intermer ate-sum fraction consists of seven hexadecimal digits and a possible carry. If a carry is present, the sum is shifted right one digit position, to make room for the carry, and the characteristic is increased by one.

After the addition, the intermediate sum is shifted left as necessary to form a normalized number, provided the fraction is not zero. Vacated low-order digit positions are filled with zeros, and the characteristic is reduced by the number of hexadecimal digits shifted. The intermediate-sum fraction is subsequently truncated to the proper result fraction length of six hexadecimal digits.

Storage/Register Format

FA addr4,freg

O	era	tio	n co	de		F	2	R	В	AM	$F\iota$	inci	ion	P
0											0	0	0	0
0				4	5	6	7	8	9	10 11	12	?	14	15

The 32-bit main storage operand specified by the effective address is algebraically added to the 32-bit operand in the floating-point register specified by the R field. The result is placed back into the floating-point register specified by the R field. The main storage operand is unchanged. The low-order 32 bits of the specified floating-point register are unchanged.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FA freg, freg

OI	era	tio	n co	de		R	1	R	2	Г		Fu	inci	tion	P
0	0	1	0	0	1	1				0	0	0	0	0	0
0				4	5	6	7	8	9	10) 11	12	?	14	15

The two 32-bit operands contained in the floating-point registers specified by the R1 and R2 fields are added algebraically. The result is placed back into the floating-point register specified by the R2 field. The R1 register is unchanged when not equal to R2. The low-order 32 bits of the R2 register are unchanged.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

FLOATING ADD DOUBLE (FAD)

General Description (double precision)

Addition of two floating-point numbers is based on characteristic comparison and fraction addition. The characteristics of the two operands are compared and the fraction accompanying the smaller characteristic is shifted right, with its characteristic increased by one for each hexadecimal digit shifted, until the two characteristics are equal. The fractions are then added algebraically to form an intermediate sum.

When an operand is shifted right during alignment, the last hexadecimal digit shifted out of the 64-bit register is preserved as a guard digit with 15 digits participating in the arithmetic.

The long intermediate-sum fraction consists of 15 hexadecimal digits and a possible carry. If a carry is present, the sum is shifted right one digit position, and the characteristic is increased by one.

After the addition, the intermediate sum including the guard digit is shifted left as necessary to form a normalized number, provided the fraction is not zero. Vacated low-order digit positions are filled with zeros, and the characteristic is reduced by the number of hexadecimal digits shifted.

Storage/Register Format

FAD addr4,freg

0	pera	tio	n co	de		R		R	В	AM	$F\iota$	inct	ion	P
0	0	1	0	0	0			l			0	0	0	1
0				4	5	6	7	8	9	10 11	12	?	14	15

The 64-bit main storage operand specified by the effective address is algebraically added to the 64-bit operand in the floating-point register specified by the R field. The result is placed back into the floating-point register specified by the R field. The main storage operand is unchanged.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FAD freg,freg



The two 64-bit operands contained in the floating-point registers specified by the R1 and R2 fields are added algebraically. The result is placed back into the floatingpoint register specified by the R2 field. The R1 register is unchanged when not equal to R2.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

FC FCD

FLOATING COMPARE (FC)

FC

freg,freg

Or	era	tio	n co	de	Γ	R	1	R	2			Fu	nct	ion	P
0	0	1	0	0	1	ı				0	0	1	0	1	0
0				4	-5	6	7	8	9	10	11	12	?	14	15

The 32-bit operand contained in the floating-point register specified by the R1 field is algebraically subtracted from the 32-bit operand contained in the floating-point register specified by the R2 field. Contents of both floating-point registers remain unchanged. See *Floating Subtract* for details of the subtract operation.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.


Program Check Condition

Protect Check. Instruction fetch.

FLOATING COMPARE DOUBLE (FCD)

FCD

freg,freg



The 64-bit operand contained in the floating-point register specified by the R1 field is algebraically subtracted from the 64-bit operand contained in the floating-point register specified by the R2 field. Contents of both floating-point registers remain unchanged. See *Floating Subtract Double* for details of the subtract operation.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

FLOATING DIVIDE (FD)

Storage/Register Format

FD addr4,freg

O	pera	tio	n cc	ode		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0	L		1			0	1	1	0
0				4	5	6	7	8	9	10 11	12	,	14	7.5

The 32-bit dividend contained in the floating-point register specified by the R field is divided by the 32-bit divisor at the main storage location specified by the effective address. The 32-bit quotient is placed back in the floating-point register specified by the R field. The low-order 32 bits of the specified floating-point register are unchanged. No remainder is preserved. The main storage operand is unchanged.

The floating-point division is based on characteristic subtraction and fraction division. The operands are assumed to be normalized. The difference between the dividend and divisor characteristics plus 64 is used as the characteristic of the intermediate quotient.

The sign of the quotient is determined by the rules of algebra unless the quotient is made a true zero; in this case, the sign is made plus.

All dividend and divisor fraction digits participate in forming the fraction of the quotient. The quotient fraction will be a 24-bit normalized result if the dividend and the divisor are normalized.

Indicators

Overflow. Turned on by divide check, exponent overflow, or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Turned on by divide check. Otherwise, the indicator is reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow, underflow, or divide check.

Register to Register Format

FD freg,freg



The 32-bit dividend contained in the floating-point register specified by the R2 field is divided by the 32-bit divisor contained in the floating-point register specified by the R1 field. The 32-bit quotient is placed back in the floating-point register specified by the R2 field. No remainder is preserved. The low-order 32 bits of the R2 register are unchanged. The R1 register is unchanged when not equal to R2.

The floating-point division is based on characteristic subtraction and fraction division. The operands are assumed to be normalized. The difference between the dividend and divisor characteristics plus 64 is used as the characteristic of the intermediate quotient.

The sign of the quotient is determined by the rules of algebra unless the quotient is made a true zero; in this case, the sign is made plus.

All dividend and divisor fraction digits participate in forming the fraction of the quotient. The quotient fraction will be a 24-bit normalized result if the dividend and divisor are normalized.

Indicators

Overflow. Turned on by divide check, exponent overflow, or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Turned on by divide check. Otherwise, the indicator is reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow, underflow, or divide check.

FDD

FLOATING DIVIDE DOUBLE (FDD)

Storage/Register Format

FDD addr4,freg

Oi	pera	tio	n co	de	Γ-	R		R	В	AM	Fu	nct	ion	P	ı
0	0	1	0	0	0						0	1	1	1	
0				4	5	6	7	8	9	10 11	12	?	14	15	

The 64-bit dividend contained in the floating-point register specified by the R field is divided by the 64-bit divisor at the main storage location specified by the effective address. The 64-bit quotient is placed back in the floating-point register specified by the R field. No remainder is preserved. The main storage operand is unchanged.

Floating-point division is based on characteristic subtraction and fraction division. The operands are assumed to be normalized. The difference between the dividend and divisor characteristics plus 64 is used as the characteristic of the intermediate quotient.

All dividend and divisor fraction digits participate in forming the fraction of the quotient. The quotient fraction will be a 56-bit normalized result if the dividend and divisor are normalized.

The sign of the quotient is determined by the rules of algebra unless the quotient is made a true zero; in this case, the sign is made plus.

Indicators

Overflow. Turned on by divide check, exponent overflow, or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Turned on by divide check. Otherwise, the indicator is reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow, underflow, or divide check.

Register to Register Format

FDD freg,freg



The 64-bit dividend contained in the floating-point register specified by the R2 field is divided by the 64-bit divisor contained in the floating-point register specified by the R1 field. The 64-bit quotient is placed back in the floating-point register specified by the R2 field. No remainder is preserved. The R1 register is unchanged when not equal to R2.

Floating-point division is based on characteristic subtraction and fraction division. The operands are assumed to be normalized. The difference between the dividend and divisor characteristics plus 64 is used as the characteristic of the intermediate quotient.

All dividend and divisor fraction digits participate in forming the fraction of the quotient. The quotient fraction will be a 56-bit normalized result if the dividend and divisor are normalized.

The sign of the quotient is determined by the rules of algebra unless the quotient is made a true zero; in this case, the sign is made plus.

Indicators

Overflow. Turned on by divide check, exponent overflow, or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Turned on by divide check. Otherwise, the indicator is reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow, underflow, or divide check.

FLOATING MULTIPLY (FM)

General Description (Short precision)

Multiplication of two floating-point numbers is based on exponent addition and fraction multiplication. The operands are assumed to be normalized. The sum of the characteristics of the operands less 64 is used as the characteristic of the intermediate product. When the result is normalized without requiring any postnormalization, the intermediate-product fraction is the result fraction, and the intermediate-product characteristic becomes the final-product characteristic. When the intermediate-product fraction has one leading zero digit, it is shifted left one digit position and the intermediate-product characteristic is reduced by one.

The multiplier and multiplicand have six-digit fractions. The product fraction has 14 digits. The two low-order fraction digits always zero, unless overflow occurs.

Storage/Register Format

FM

addr4,freg

O_{I}	oera	tio	n cc	de		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0	l				1	0	1	0	0
0				4	5	6	7	8	9	10 11	12	?	14	15

The 32-bit main storage operand specified by the effective address and the 32-bit operand contained in the floating-point register specified by the R field are multiplied. The normalized result is placed back into the floating-point register specified by the R field. The main storage operand is unchanged.

The sign of the product is determined by the rules of algebra unless all digits of the product fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

When either or both operand fractions are zero, the result is made a true zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FM

freg,freg

O_{I}	oera	tia	n cc	de		R	1	R	2	Π		Fu	nct	ion	P
0	0	1	0	0	1					0	0	0	1	0	0
0				4	5	6	7	8	9	10) 11	12	?	14	15

The two 32-bit operands contained in the floating-point registers specified by the R1 and R2 fields are multiplied and the normalized result is placed back into the floating-point register specified by the R2 field. The R1 register is unchanged when not equal to R2.

The sign of the product is determined by the rules of algebra unless all digits of the product fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

When either or both operand fractions are zero, the result is made a true zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

FMD


FLOATING MULTIPLY DOUBLE (FMD)

General Description (Double precision)

Multiplication of two floating-point numbers is based on exponent addition and fraction multiplication. The operands are assumed to be normalized. The sum of the characteristics of the operands less 64 is used as the characteristic of the intermediate product. When the result is normalized without requiring any postnormalization, the intermediate-product fraction is the result fraction, and the intermediate-product characteristic becomes the final-product characteristic. When the intermediate-product fraction has one leading zero digit, it is shifted left one digit position and the intermediate-product characteristic is reduced by one. The multiplier and multipicand fractions have 14 digits and the result-product fraction is truncated to 14 digits.

Storage/Register Format

FMD addr4,freg



The 64-bit main storage operand specified by the effective address and the 64-bit operand contained in the floating-point register specified by the R field are multiplied. The normalized result is placed back into the floating-point register specified by the R field. The main storage operand is unchanged.

The sign of the product is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

When either or both operand fractions are zero, the result is made a true zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FMD freg,freg

Op	era	tio	ı co	de		R	1	R	2					ion		ı
0	0	1	0	0	1					0	0	0	1	0	1	J
0				4	5	6	7	8	9	10	11	12	?	14	15	

The two 64-bit operands contained in the floating-point registers specified by the R1 and R2 fields are multiplied. The normalized result is placed back into the floating-point register specified by the R2 field. The R1 register is unchanged when not equal to R2.

The sign of the product is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

When either or both operand fractions are zero, the result is made a true zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.


FLOATING MOVE (FMV)

Storage to Register Format

FMV

addr4,freg

O_l	era	tloi	n co	de		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0			ļ			1	0	1	0
0				4	5	6	7	8	9	10 11	12	?	14	15



The 32-bit floating-point number in the main storage locations specified by the effective address is loaded into the floating-point register specified by (1) the R field and (2) the current interrupt level. The main storage operand is unchanged. The low order 32 bits of the 64-bit register are set to zeros.

Indicators

Carry. Reset.

Overflow, Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result loaded into the register.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Storage Format

FMV

freg,addr4

Op	era	tioi	ı co	de		R		R	В	AM	Fu	ncti	ion	P
0	0	1	0	0	0						1	1	1	0
0				4	5	6	7	8	9	10 11	12	;	14	15



The 32-bit floating-point number contained in the high-order 32 bits of the floating-point register specified by the R field is stored in the main storage locations specified by the effective address. The register specified by the R field is unchanged.

Indicators

Carry. Reset.

Overflow, Reset.

Even. Reset

Negative and Zero. Changed to reflect the stored result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Register Format

FMV

freg,freg

Oper	a	tio	n cc	de		R	1	R	2			Fu	nct	ion	P
0 ()	1	0	0	1					0	0	1	0	0	0
0				4	5	6	7	8	9	10	11	12	,	14	7.5

The 32-bit operand contained in the floating-point register specified by the R1 field is moved to the floating-point register specified by the R2 field. The low-order 32 bits of the R2 register are set to zeros. The floating-point register specified by R1 is unchanged when not equal to R2.

Bit 13 of the instruction, along with bits 10 and 11, must be set to zero to avoid future code obsolescence.

Indicators

Carry. Reset.

Overflow. Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

FMVC

FLOATING MOVE AND CONVERT (FMVC)

Storage to Register Format

FMVC

addr4,freg

Or	era	tio	ı co	de		R		R	В	AM	Fu	nct	ion	P
0			0								1	0	0	0
0				4	5	6	7	8	9	10 1	1 12	2	14	15

The 16-bit signed binary integer in the main storage location specified by the effective address is converted to a 32-bit floating-point number with low-order zeros inserted; then loaded into the floating-point register specified by (1) the R field and (2) the current interrupt level. The low-order 32 bits of the register are set to zero. The 64-bit register is normalized with zeros inserted at the low-order positions during normalization. The main storage operand is unchanged.

Indicators

Carry. Reset.

Overflow. Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result loaded into the register.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Storage Format

FMVC

freg,addr4

Or	era	tio	n cc	de		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0						1	1	0	0
0				4	5	6	7	8	9	10 11	12	?	14	15



The 32-bit floating-point number contained in the high-order 32 bits of the floating-point register specified by the R field is converted to a signed 16-bit binary integer and stored at the main storage location specified by the effective address. For proper conversion to occur, the floating-point number must be normalized. During execution, the eight low-order bits of the fraction are truncated prior to conversion. Any fraction remaining after conversion is also truncated. The register specified by the R field is unchanged.

If the characteristic of the floating-point number is negative, the integer stored is zero.

Indicators

Carry. Reset.

Overflow. Turned on if the converted number is larger than +2¹⁵-1 or less than -2¹⁵. In this case, the largest possible value is stored (-2¹⁵ if negative overflow or 2¹⁵-1 if postitive overflow). Otherwise, the indicator is reset.

Even. Reset.

Negative and Zero. Changed to reflect the stored integer.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address or operand address).

FLOATING MOVE AND CONVERT DOUBLE (FMVCD)

Storage to Register Format

FMVCD addr4,freg

O_l	oera	tio	n cc	de		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0						1	0	0	1
0				4	5	6	7	8	9	10 11	12	?	14	15

The 32-bit signed binary integer in the main storage location specified by the effective address is converted to a 64-bit floating-point number with low-order zeros inserted; then loaded into the floating-point register specified by (1) the R field and (2) the current interrupt level. The 64-bit register is normalized with zeros inserted at the low-order positions during normalization. The main storage operand is unchanged.

Indicators

Carry. Reset.

Overflow. Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result loaded into the register.

Program Check Conditions


Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Storage Format

FMVCD freg,addr4



The 64-bit floating-point number contained in t floating-point register specified by the R field is convert to a signed 32-bit binary integer and stored at the ma storage location specified by the effective address. F proper conversion to occur, the floating-point number mu be normalized. During execution, the 24 low-order bits the fraction are truncated prior to conversion. Any fractic remaining after conversion is also truncated. The regist specified by the R field remains unchanged.

If the characteristic of the floating-point number negative, the integer stored is zero.

Indicators

Carry. Reset.

Overflow. Turned on if the converted number is larger tha $+2^{31}$ -1 or less than -2^{31} . In this case, the largest possib value is stored $(-2^{31}$ if negative overflow or 2^{31} -1 positive overflow). Otherwise, the indicator is reset.

Even. Reset.

Negative and Zero. Changed to reflect the stored integer.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, c operand store.

Specification Check. Even byte boundary violatio (indirect address or operand address).

FMVD

FLOATING MOVE DOUBLE (FMVD)

Storage to Register Format

FMVD

addr4,freg

Ī	<u>Э</u> р	era	tio	n co	de		R		R	В	AM	Fu	nct	ion	P
	0	0	1	0	0	0						1	0	1	1
	<u> </u>				4	5	6	7	8	9	10 11	12	2	14	15

The 64-bit floating-point number in the main storage location specified by the effective address is loaded into the floating-point register specified by (1) the R field and (2) the current interrupt level. The main storage operand is unchanged.

Indicators

Carry. Reset.

Overflow, Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result loaded into the register.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.


Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Storage Format

FMVD

freg,addr4

											-			- 2
O	era	tio	n co	de		R		R	В	AM	Fu	nct	ion	P
0	0	1	0	0	0	1		l			1	1	1	1
0				4	5	6	7	8	9	10 1	1 12	?	14	1 15



The 64-bit floating-point number contained in the register specified by the R field is stored in the main storage location specified by the effective address. The register specified by the R field remains unchanged.

Indicators

Carry. Reset.

Overflow. Reset.

Even.Reset.

Negative and Zero. Changed to reflect the stored result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch, operand access, or operand store.

Specification Check. Even byte boundary violation (indirect address or operand address).

Register to Register Format

FMVD

freg,freg

Or	era	tio	ı co	de		R	1	R	2			Fu	nct	ion	P
0	0	1	0	0	1					0	0	1	0	0	1
6				4	5	6	7	8	9	10	11	12	?	14	15

The 64-bit operand contained in the floating-point register specified by the R1 field is moved to the floating-point register specified by the R2 field. The floating-point register specified by the R1 field is unchanged.

Bit 13 of the instruction, along with bits 10 and 11, must be set to zero to avoid future code obsolescence.

Indicators

Carry. Reset.

Overflow. Reset.

Even. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

FLOATING SUBTRACT (FS)

General Description (Short precision)

Subtraction of two floating-point numbers is based on characteristic comparison and fraction subtraction. The characteristics of the two operands are compared, and the fraction accompanying the smaller characteristic is shifted right, with its characteristic increased by one for each hexadecimal digit shifted, until the two characteristics are equal.

When an operand is shifted right during alignment, the leftmost hexadecimal digit of the field shifted out is retained as a guard digit. The operand that is not shifted is considered to be extended with a low-order zero. Both operands are considered to be extended with low-order zeros when no alignment shift occurs. The 28-bit fractions are then subtracted algebraically to form an intermediate sum.

The intermediate-sum fraction consists of seven hexadecimal digits and a possible borrow. If a borrow is present, the sum is shifted right one digit position, and the characteristic is increased by one.

After the subtraction, the intermediate sum is shifted left as necessary to form a normalized number, provided the fraction is not zero. Vacated low-order digit positions are filled with zeros and the characteristic is reduced by the number of hexadecimal digits shifted. The intermediate-sum fraction is subsequently truncated to the proper result-fraction length of six hexadecimal digits.

Storage/Register Format

FS addr4,freg

O	pera	tio	n co	de		R	 R	B	AM	Fu	nct	ion	P
0	0	1	0	0	0		ļ		AM	0	0	1	0
0				4					10 11				

The 32-bit main storage operand specified by the effective address is algebraically subtracted from the 32-bit operand contained in the floating-point register specified by the R field. The result is placed back in the floating-point register specified by the R field. The low-order 32 bits of the specified floating-point register are unchanged. The main storage operand is unchanged.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FS freg,freg

O_{I}	era	tio	n cc	de		R	1	R	2			Fu	nct	ion	P
0	0	1	0	0	1			l		0	0	0	0	1	0
0				4	5	6	7	8	9	10	11	12		14	1.5

The 32-bit operand contained in the floating-point register specified by the R1 field is algebraically subtracted from the 32-bit operand contained in the floating-point register specified by the R2 field. The result is placed back in the floating-point register specified by the R2 field. The low-order 32 bits of the R2 register are unchanged. The R1 register is unchanged when not equal to R2.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristics is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

FLOATING SUBTRACT DOUBLE (FSD)

General Description (Double precision)

Subtraction of two floating-point numbers is based on characteristic comparison and fraction subtraction. The characteristics of the two operands are compared and the fraction accompanying the smaller characteristic is shifted right, with its characteristic increased by one for each hexadecimal digit shifted, until the two characteristics are equal.

When an operand is shifted right during alignment, the last hexadecimal digit shifted out of the 64-bit register is preserved as a guard digit with 15 digits participating in the arithmetic. The fractions are then subtracted algebraically to form an intermediate sum.


The long intermediate-sum fraction consists of 15 hexadecimal digits and a possible borrow. If a borrow is present, the sum is shifted right one digit position, and the characteristic is increased by one.

After the subtraction, the intermediate sum including the guard digit is shifted left as necessary to form a normalized number, provided the fraction is not zero. Vacated low-order digit positions are filled with zeros, and the characteristic is reduced by the number of hexadecimal digits shifted.

Storage/Register Format

FSD addr4,freg

7)p	er	71	tioi	n ce	ode		R		R	В	AM	Fu	inct	ion	P
	_	0				0							0	0	1	1
()					4	5	6	7	8	9	10 11	12	2	14	15



The 64-bit main storage operand specified by the effective address is algebraically subtracted from the 64-bit operand contained in the floating-point register specified by the R field and the result is placed back in the floating-point register specified by the R field. The main storage operand is unchanged.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Protect Check. Instruction fetch or operand access.

Specification Check. Even byte boundary violation (indirect address or operand address).

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.

Register to Register Format

FSD freg,freg

Oį	era	tio	n co	de		R	1	R	2			Fu	nct	ion	P
0	0	1	0	0	1	l		l		0	0	0	0	1	1
0				4	5	6	7	8	9	10	11	12	?	14	1 15

The 64-bit operand contained in the floating-point register specified by the R1 field is algebraically subtracted from the 64-bit operand contained in the floating-point register specified by the R2 field. The result is placed back in the floating-point register specified by the R2 field. The R1 register is unchanged when not equal to R2.

The sign of the sum is determined by the rules of algebra unless all digits of the intermediate-sum fraction are zero; in this case, the sign is made plus and the result characteristic is forced to zero.

Indicators

Overflow. Turned on by an exponent overflow or exponent underflow. Otherwise, the indicator is reset.

Even. Turned on by an exponent underflow. Otherwise, the indicator is reset.

Carry. Reset.

Negative and Zero. Changed to reflect the result.

Program Check Condition

Protect Check. Instruction fetch.

Soft Exception Trap Condition

Floating-point Exception. Overflow or underflow.


SET FLOATING LEVEL BLOCK (SEFLB)

SEFLB

reg,addr4

0	per	atio	n c	ode	Γ	R		R	В	AM	I	une	etic	n
0	1	0	1	1							0	0	1	1
0				4	5		7	8	9	10 11	12	?		15

A floating level block in main storage is loaded into the floating-point registers for the level specified by the R field register. The generated effective address (EA) specifies the beginning address of the floating level block. The contents of main storage and the R field register remain unchanged. The floating level block appears in main storage as follows:



The general register specified by the R field has the format:

Bits 0-13 are not used and must be zero to avoid future code obsolescence. Bits 14 and 15 hold the binary encoded level of the floating level block associated with this operation. For example: 00 for level 0, 01 for level 1, 10 for level 2, and 11 for level 3.

Programming note. If AM=01, the register specified by the RB field is incremented by two.

Indicators

No indicators are changed.

Program Check Conditions

Invalid Storage Address. Instruction word or operand.

Privilege Violate. Privileged instruction.

Specification Check. Even byte boundary violation (indirect address or operand address).

Chapter 7. Input/Output Operations

Input/output (I/O) operations involve the use of input/output devices. These devices are attached to the processor and main storage via the I/O channel. The channel directs the flow of information between the I/O devices and the processor/main storage. The I/O channel can accommodate a maximum of 256 addressable devices. The general data flow is shown in Figure 7-1.




Figure 7-1. Block diagram of Series/1 Model 5 system

The channel supports three basic types of operations:

- Direct Program Control (DPC) Operations—An immediate data transfer is made between main storage and the device for each Operate I/O instruction. The data may consist of one byte or one word. The operation may or may not terminate with an interrupt.
- Cycle Steal Operations—An Operate I/O instruction can initiate cycle stealing data transfers of up to 65,535 bytes between main storage and the device. Cycle steal operations are overlapped with processing operations. Word or byte transfers, command chaining, burst mode, and program controlled interrupt can be supported. All cycle stealing operations terminate with an interrupt.

• Interrupt Servicing—Four preemptive priority interrupt levels are available to facilitate device service. The device interrupt level is assignable by the program. In addition, the device interrupt capability may be masked under program control. Interrupt requests, along with cycle steal requests, are presented and polled on the interface concurrently with DPC and cycle steal data transfers.

The channel provides comprehensive-error checking including time-outs, sequence checking, and parity checking. Error, exception, and status reporting are facilitated by (1) recording condition codes in the processor during execution of Operate I/O instructions, and (2) recording condition codes and an Interrupt Information Byte (IIB) in the processor during interrupt acceptance. Additional status words may be used by the device as necessary to describe its status (see I/O Condition Codes and Status Information in this chapter).

The I/O channel is asynchronous and multidropped. It consists of the following major line groups:

- Address Bus—A bidirectional bus used for device Selection and for passing commands to devices during Operate I/O Instructions. The address bus is also used for the passing of main storage addresses from the devices to the channel during cycle steal data transfers.
- Data Bus—A bidirectional bus used for passing data and control information to or from devices during Operate I/O Instructions. The data bus is also used for passing device addresses and an interrupt information byte to the processor during interrupt acceptance.
- Control Lines—Unidirectional lines and busses used for (1) interrupt and cycle steal requests, (2) condition code and status reporting, (3) resets, and (4) basic control of sequences.

OPERATE I/O (IO) INSTRUCTION

The Operate I/O (IO) instruction initiates all I/O operations from the processor It is a privileged instruction and is independent of specific I/O parameters. The generated effective address points to an immediate device control block (two words) in main storage. For details of the Operate I/O Instruction refer to Chapter 5.

Immediate Device Control Block (IDCB)

The location in storage specified by the Operate I/O instruction contains the first word of the IDCB. The IDCB contains an I/O command that describes the specific nature of the I/O operation and is used by the channel for execution of the operation. The IDCB must always be on a word address boundary and has the following format:

IDCB (immediate device control block)

Command field		Device address field	
0	7	8	15

Immediate data field	
16	31

Command field (bits 0-7)

Bit 0 Channel directed. If this bit is equal to one, the I/O command is directed to the channel rather than to a specific device.

Bit 1 Read/Write. If this bit is equal to one, the data contained in the immediate field is transferred to the addressed I/O device. If this bit is equal to zero, the immediate field contains the data received from the I/O device at the conclusion of the IO instruction.

Bits 2-3 Function. This field specifies the general type of I/O operation to be performed (see Figure 7-2).

Bits 4-7 Modifier. This field contains four bits for further specification of a function, if required (see Figure 7-2).


Device address field (bits 8-15)

This byte contains the I/O device address. The address range is 00 through FF (hex).

Immediate data field (bits 16-31)

This field contains a data word for DPC operations. It contains the address of a device control block for cycle steal operations.

Figure 7-2 shows the relationship of the IDCB and the Operate I/O instruction. It also contains a chart of the various I/O commands. The Start command and the Start Cycle Steal Status command are used to initiate cycle steal operations. The remaining commands are used for DPC operations only.



^{*}Indirect addressing bit.

Figure 7-2. IDCB and I/O commands

^{**}Modifier XXXX is device dependent excluding system defined modifiers. Other modifiers are system defined.


^{***}To avoid future code obsolescence, this command format must not be used.


I/O Commands

This section describes each I/O command and shows the related IDCB. The command field (bits 0-7) of the IDCB contains the binary value of the command. An X in this field means the value is device dependent.


Read


IDCB (immediate device control block)





IDCB (immediate device control block)







This command transfers a word or byte from the addressed device to the data word of the IDCB. If a single byte is transferred, it is placed in bits 24-31 of the data word with bits 16-23 set to zeros. Correct parity is always maintained and checked for both bytes on the I/O interface. The individual devices may use either the 0X or 1X type of read command.


Read ID

IDCB (immediate device control block)





This command transfers an identification (ID) word from the device to the data word of the IDCB. The device identification word contains physical information about the device and may be used to determine the devices that are attached to the system. This word is not related to the interrupt ID word associated with interrupt processing. The device ID word format is:



Bits 0-12 Unique identification code for the device

Bit 13 Zero-not a controller device or the device does not report delayed command reject.

One-controller device or any device that reports

delayed command reject.


Bit 14 Zero—not a cycle steal device
One—cycle steal device


Bit 15 Zero-IBM device One-OEM device

Note. A controller may control more than one I/O device and is not directly addressable, but is not transparent to software. That is, the controller may cause busy or exception conditions as opposed to those caused by an attached I/O device.

Read Status


IDCB (immediate device control block)







This command transfers a device status word from the device to the data word of the IDCB. Contents of the status word are device dependent.


Write







IDCB (immediate device control block)




Immediate dat	a field	
	Data word	
16		31

This command transfers a word or byte to the addressed device from the data word of the IDCB. The individual device may use either format of the command. If a single byte is to be transferred, it must be placed in bits 24–31 of the data word and bits 16–23 must be set to zero. A byte oriented device may ignore bits 16–23 (including the parity bit on the I/O interface) but these bits should be zeros to avoid future code obsolescence.

Note. The second word of the IDCB is fetched by the channel and placed on the I/O data bus (in good parity) even if not required by the device.

Prepare

IDCB (immediate device control block)




Immediat	e data field				
	Zeros		Leve	el	I
16		26	27	30	31


This command transfers a word (to the addressed device that controls the device interrupt parameters. The word i transferred from the immediate data field of the IDCB in the format shown. A priority interrupt level is assigned to the device by the *level* field. The I-bit (device mask controls the device interrupt capability. If the I-bit equal 1, the device is allowed to interrupt. If the I-bit equals 0 the device cannot interrupt. See *Prepare I/O Device fo. Interrupt* in Chapter 3.

Note. The IBM 4955 Processor does not recognize a priority level other than 0-3. Lost interrupts result if a device is prepared for a level other than 0-3.

Control

IDCB (immediate device control block)







This command initiates a control action in the addressed device. A word, or byte, transfer from the data word of the IDCB to the addressed device may or may not occur, depending on device requirements. If a single byte is to be transferred it must be placed in bits 24-31 of the data word and bits 16-23 must be set to zero.

Note. The second word of the IDCB is fetched by the channel and placed on the I/O data bus (in good parity) even if not required by the device.

Device Reset

IDCB (immediate device control block)







This command resets the addressed device. A pending interrupt from this device (or a busy condition) is cleared. The device mask (I-bit) is not changed. There is no change to the assigned priority level for the device. The residual address (device status) and output sensor points are not affected. Parity checking of the IDCB data word is not performed.

Start

IDCB (immediate device control block)






This command initiates a cycle steal operation for the addressed device. The second word of the IDCB is transferred to the device. It contains a 16-bit logical storage address of a device control block (DCB) to be used by the device. See *Cycle Steal* in this chapter.

Start Cycle Steal Status

IDCB (immediate device control block)





Immediate data field	
DCB address	
16	31

This command initiates a cycle steal operation for the addressed device. Its purpose is to collect status information from the addressed device. The second word of the IDCB is transferred to the device and contains a 16-bit logical address of a device control block (DCB). See *Start Cycle Steal Status Operation* in this chapter.

Halt I/O

IDCB (immediate device control block)






This is a *channel* directed command that causes a halt of all I/O activity on the I/O channel and resets all devices. No data is associated with this command. All pending device interrupts are cleared. Device priority-interrupt-level assignments and device masks (I-bits) are unchanged. The residual address (device status) and output sensor points are not affected.

DPC OPERATION

A DPC operation causes an immediate transfer of data or control information to or from an I/O device. An Operate I/O instruction must be executed for each data transfer and causes the following events to occur (refer to Figure 7-3).

- 1. The Operate I/O instruction points to an IDCB in main storage.
- 2. The I/O channel uses the IDCB to select the addressed device and to determine the operation to perform.
- 3. The channel sends data to the device from main storage, or from the device to main storage.
- 4. The device presents a condition code to the processor.

Note. The DPC operation may end with a priority interrupt if the device has this capability. When the processor accepts the interrupt request, the device sends an interrupt condition code and an interrupt ID word. Refer to I/O Interrupts in Chapter 3.



*Indirect addressing bit

Figure 7-3. Direct program control I/O operation

CYCLE STEAL

The cycle steal mechanism allows data service to or from an I/O device while the processor is processing instructions. This overlapped operation allows multiple data transfers to be started by one Operate I/O instruction. The processor executes the Operate I/O instruction, then continues processing instructions while the I/O device steals main storage data cycles when needed. The operation always ends with a priority interrupt from the device. The channel resolves contention among multiple devices requesting cycle steal transfers. The channel also resolves contention for priority interrupts on the same level.

All cycle steal operations are started by an Operate I/O instruction. The IDCB contains either a *Start* command or a *Start Cycle Steal Status* command. The immediate field of the IDCB contains the address of a device control block (DCB) that is fetched by the device. The DCB contains specific parameters of the cycle steal operation. See *Device Control Block* in this chapter.

The cycle steal operation includes certain capabilities that are provided on a device feature basis:

- 1. Burst mode
- 2. DCB command chaining
- 3. Programmed controlled interrupt (PCI)
- 4. Suppress exception (SE)
- 5. Storage addresses and data transfers by byte or word


See the *Device Control Block* section and the *Chaining* section of this chapter for details of these facilities.


All cycle steal operations terminate with a priority interrupt, providing, the device has executed a successful *Prepare* command, with the device mask (I-bit) enabled. If the device mask is disabled, the interrupt presentation is blocked and the device remains busy until the condition is cleared or serviced.

Start Command

A cycle steal operation begins after successful execution of the *Start* command. The IDCB, pointed to by an Operate I/O instruction, has the format:

IDCB (immediate device control block)





The command modifier (X) is device dependent. The DCB address always specifies a word boundary and is the starting storage address of the DCB. This address is used by the device to fetch the DCB, using the cycle steal mechanism.

Device Control Block (DCB)

The DCB is an eight-word control block residing in the supervisor area of main storage. It describes the specific parameters of the cycle stealing operation. The device fetches the DCB using a cycle steal address key of zero. The format of the DCB is shown in Figure 7-4.




Figure 7-4. Device control block

The DCB words have the following meanings: Control Word

Bit 0 Chaining flag. If this bit is equal to one, a DCB chaining operation is indicated. After completing the current DCB operation, the device does not interrupt (excluding PCI interrupts). Instead the device fetches the next DCB in the chain. Refer to the Chaining section in this chapter.

Bit 1 Programmed controlled interrupt (PCI). If this bit is equal to one, the device presents a programmed controlled interrupt (PCI) at the completion of the DCB fetch. Data transfers associated with the DCB may commence even if the PCI is pending. If the PCI is pending when the device encounters the next interrupt causing condition, the PCI condition is discarded by the device and replaced with the new interrupt condition.

Bit 2 Input flag. The setting of this bit tells the device the direction of data transfer.

0 = Output (main storage to device)

1 = Input (device to main storage)

For bidirectional data transfers under one DCB operation, this bit must be set to one. For control operations involving no data transfer, this bit must be set to zero.

Bit 3 Reserved. This bit must be set to zero to avoid future code obsolescence.

Bit 4 Suppress exception (SE). If this bit is equal to one, reporting of device specified exception conditions are suppressed. The device continues the operation. The classes of exception conditions that can be suppressed are device dependent. For example: an incorrectlength-record condition could be suppressed. An exception that occurs during a DCB fetch operation can not be suppressed. Refer to the individual device publications.

Bits 5-7Cycle steal address key. This key is presented by the device during data transfers. It is used to ascertain storage access authorization (See Chapter 8, Storage Protection).

Bits 8-14 Modifier. These bits may be used to describe functions unique to a particular device.

Bit 15 Burst mode. If this bit is equal to one, the transfer of data takes place in burst mode. This mode dedicates the channel to the device until the last data transfer associated with this DCB is completed. This bit is device dependent if burst mode is not supported by the device.

Device Parameter Words 1-3

These parameter words are device-dependent control words and are implemented as required.

Device Parameter Word 4

If suppress exception (SE) is used by a device, this word specifies a 16-bit main storage address called the status address. This address points to a residual status block that is stored when the following two conditions are met:

- 1. The SE bit (bit 4 of the DCB control word) is set to one.
- 2. All data transfers for the current DCB have been successfully completed.

Note. Address key zero is used when storing the residual status block.

The size of the residual status block varies from two to 16 words depending on the individual device. The first word contains the residual byte count. The second word contains device status flags. Additional words (maximum of 14) contain device dependent status information. Refer to the individual device publications for information pertaining to the device status.

If suppress exception is not used by a device, the device parameter word 4 is device dependent and has the same meaning as parameter words 1-3.

Programming note. Information contained within the residual status block may also be reported by the device during a start cycle steal status operation.

Device Parameter Word 5

If the DCB chaining bit (bit 0 of the control word) is equal to one, this word specifies a 16-bit main storage address of the next DCB in the chain. If chaining is not supported by the device, this parameter word is device dependent.

Count

The count word contains a 16-bit unsigned integer representing the number of data bytes to be transferred for the current DCB. Count is specified in bytes with a range of 0 through 65,535. The count specification must be even for word-only devices.

Data Address

This word contains the starting main storage address for the data transfer.

Programming Considerations When using the DCB

- 1. Only those words required for the cycle stealing operation are fetched by the device and they may be fetched in any order. Contents of the words must be specified correctly; if not, the device may record a DCB specification check in the interrupt status byte and terminate the cycle steal operation.
- The DCB address, the chain address, and the status address must be even (word boundary). If the DCB address is odd, the device records the command reject condition code and terminates the cycle steal operation. An odd chain address or status address results in a DCB specification check.

Note. Condition code and status recording are explained in detail in a separate section of this chapter.

Cycle Steal Operation

A cycle steal operation is presented in the following chart. Condition codes used in the chart are fully explained in the section I/O Condition Codes and Status Information in this chapter.

Cycle steal major steps Remarks

Prepare I/O device

- 1. Execute IO instruction.
- 2. IDCB contains *Prepare* command and interrupt parameters.
- 3. Device presents condition code 7 (satisfactory).

Start cycle steal

- 1. Execute IO instruction.
- 2. IDCB contains Start command and points to a DCB.
- 3. Device presents condition code 7.

Device fetches DCB

- 1. Device uses cycle steal mechanism to fetch DCB.
- 2. Cycle steal address key of zero is used.

Data transfer

- 1. Data is transferred to or from the device in word or byte format.
- 2. Transfer continues until count in DCB is exhausted.
- 3. DCB specifies cycle steal address key for data area.

Termination (no error condition)

- 1. Device presents interrupt request.
- 2. Channel polls I/O attachment feature and accepts requests.
- Device sends interrupt ID word and interrupt condition code 3 (device end).

Termination (Exception condition)

- 1. Device presents interrupt request.
- 2. Channel polls I/O attachment feature and accepts request.
- 3. Device sends interrupt ID word and interrupt condition code 2 (exception).

Note. Other events that might occur during the cycle steal operation are:

Chaining

- Device completes the current DCB operation but does not present an interrupt request.
- 2. Device fetches next DCB in the

Program Controlled interrupt

- 1. Device fetches DCB (PCI bit = 1).
- Device initiates an interrupt and sends an interrupt ID word and interrupt condition code 1 (PCI).

Figure 7-5 shows the relationship between the Operate I/O instruction, the IDCB, and the DCB for a cycle steal operation.





Figure 7-5. Example of cycle steal control information

Start Cycle Steal Status Operation


This operation is initiated by a Start Cycle Steal Status command. The IDCB format is:





Immediate data field	
DCB address	
16	31

The purpose of this operation is to obtain residual parameters from the device if the previous cycle steal operation terminates due to an error or exception condition. The DCB format is the same as that for a normal cycle steal operation, with some words and fields set to zeros (see Figure 7-6). Data is transferred to main storage starting at the data address specified in the DCB. This data consists of residual parameters and device dependent status information and has the following format:



Residual address. This word contains the main storage address of the last attempted cycle steal transfer associated with a *Start* command. If an error occurs during a start cycle steal status operation, this address is not altered. The residual address may be a data address, a DCB address, or a residual-status-block address and is cleared only by a power-on reset. Following a power-on reset the residual address is:

- 0000 (Hex) for a byte-oriented device.
- 0001 (Hex) for a word-oriented device.

It is updated to the current cycle-steal storage address upon execution of cycle steal transfers. For word transfers, the residual address points to the high-order byte of the word. Device reset, Halt I/O, machine check, and system reset have no effect on the residual address in the device.

Device cycle-steal-status word 1. This word contains the residual byte count of a device. The residual byte count is initialized by the count field of a DCB associated with a *Start* command, and is updated as each byte of data is successfully transferred via a cycle steal operation. It is not updated by cycle-steal transfers into the residual status block. The residual byte count is not altered if an error occurs during a start cycle steal status operation. It is reset by (1) power-on reset, (2) system reset, (3) device reset, (4) Halt I/O, and (5) machine check condition.

Note. The contents of the device cycle-steal-status word 1 are device dependent if the device does not: (1) implement suppress exception (SE), or (2) store a residual byte count as part of its cycle-steal status.

Device dependent. These are device dependent status words. The number and contents of these words are specified by the individual device. Three conditions can cause bits to be set in the device dependent status words.

- Execution of an I/O command that causes an exception interrupt.
- 2. Asynchronous conditions in the device that indicate an error, exception, or a state condition.
- 3. As defined by the individual device.

The bits are reset as follows:

- 1. For the first condition listed above, the bits are reset by the acceptance of the next I/O command (except Start Cycle Steal Status) following the exception interrupt. These bits are also reset by a power-on reset, system reset, or execution of a Halt I/O command.
- 2. For the second condition, the bits are reset on a device dependent basis.
- 3. For the third condition, the bits are reset as defined by the individual device.

Programming Note.

Concerning the DCB for the start cycle steal status operation:

- 1. Bits designated as zero are not checked by hardware (see Figure 7-6).
- 2. The count is specified in bytes.
- 3. The maximum count is device dependent.
- 4. The validity of a count value less than the maximum value is device dependent.
- 5. If the maximum count is exceeded, or a count value is specified that indicates the partial storing of a word length parameter, the device records a *DCB* specification check in the ISB and terminates the operation.
- 6. An odd data address also results in a DCB specification check.

'ord	DCB (device control block)
0	Control word
v	0 0 1 0 0 Addr key 0 0 0 0 0 0 0 0
1	Not used (zeros)
2	Not used (zeros)
3	Not used (zeros)
4	Not used (zeros)
5	Not used (zeros)
6	Byte count
7	Data address
	0 15

Figure 7-6. DCB for start cycle steal status operation

Termination Conditions

The following chart shows the action that occurs at the end of a DCB operation depending on the function specified and the exception conditions encountered:

		Suppressible	Non-Suppressible	No
CHN	SE	exception	exception	exception
0	0	I(XCT)	I(XCT)	I(DE)
0	1	I(PDE)	I(XCT)	I(PDE)
1	0	I(XCT)	I(XCT)	CC
1	1	*I(PDE)/CC	I(XCT)	I(PDE)

CC - DCB command chain

CHN - Chaining flag (bit 0 of the DCB control word)

I(DE) - Device end interrupt

I(PDE) - Permissive device end interrupt (see device end interrupt I(XCT) - Exception interrupt

SE - Suppress exception (bit 4 of the DCB control word)

*Dependent on the specific exception condition in the individua device.

I/O CONDITION CODES AND STATUS INFORMATION

Each time an Operate I/O instruction is issued, the device, controller, or channel immediately reports to the processor a condition code pertaining to execution of the I/O command. Three bits are used to encode a condition code value (range 0 through 7). The bits are recorded in the even, carry, and overflow positions of the LSR and may be interrogated by specific instructions such as *Branch on Condition Code* and *Branch on Not Condition Code*. (See BCC and BNCC in Chapter 5).

Condition codes are also reported during a priority interrupt. These codes pertain to an operation that continues beyond execution of the Operate I/O instruction. In this case, the device must be able to present an interrupt. Along with the interrupt condition code, the device also transfers an interrupt ID word to the processor. Bits 0 through 7 of the interrupt ID word contain status information related to the interrupt processing and are called the interrupt information byte.

Figure 7-7 presents an overall view of condition code reporting along with status information. Details of each ondition code and status byte are discussed in the following sections.




Figure 7-7. Condition codes and status information

I/O Instruction Condition Codes

LSR

Condition

These codes are reported during execution of an Operate I/O instruction.

Conaition	LSK				
code (CC)	positi	on	Over-	Reported	
value	Even	Carry	flow	by	Meaning
0	0	0	0	channel	Device not attached
1	0	0	1	device	Busy
2	0	1	0	device	Busy after reset
3	0	1	1	chan/dev	Command reject
4	1	0	1	device	Intervention required
5	1	0	1	chan/dev	Interface data check
6	1	1	0	controller	Controller busy
7	1	1	1	chan/dev	Satisfactory
CC=0					by the channel when ed to the system.
CC=1	execu device comm exits interre when interre subsec	te a constant the bunch constant the bunch constant constant the constant constant the constant the an example.	mmand s the at requ sy stat ertain sternal hen th priorit	because it is busy state up ires an interru- te when the p devices also event occur- nis condition y interrupt	when it is unable to in the busy state. The pon acceptance of a ppt for termination. It processor accepts the enter the busy state is that results in an code is reported, a from the addressed
CC=2	unable the de quiesc	e to exercise the exercise to	ecute a is not l ate. N	a command b had sufficient	time to return to the occurs to indicate
CC=3	when: 1. A co 2. Th co 3. Th ex inc	commande device mmande IDC ample: correct When ect, it o	and is a set. set is in a set. set is in a set. set is in a set in	issued that is an improper tains an incommendation and incommendation of the commendation of the control of the	ombination. e reports command CB.
CC=4	Interv	ention	require	ed. Reported	by the device when it

Intervention required. Reported by the device when it is unable to execute a command due to a condition requiring manual intervention to correct.

CC=5 Interface data check. Reported by the device or the channel when a parity error is detected on the I/O data bus during a data transfer.

CC=6 Controller busy. This condition is reported by a device controller, not the addressed device, when the controller is busy. It is reported only by controllers that have two or more devices attached (each device having a unique address). When this condition code is reported, a subsequent controller-end interrupt always occurs.

CC=7 Satisfactory. Reported by the device or channel when it accepts the command.

These condition codes are mutually exclusive and have a priority sequence. That is; beginning with CC=7, each successive condition code through CC=0 takes precedence over the previous code. For example, if a device cannot accept a command because it is busy, it reports CC=1, irrespective of error conditions encountered.

Note. The only exception is CC=6 (controller busy). This condition code may have a variable priority depending on the particular controller.

Interrupt Condition Codes

These condition codes are reported by the device or controller during priority interrupt acceptance.

controller	during	priori	ity int	errupt accep			
Condition	LSR						
code (CC)	positi	ion	Over-	Reported			
value	Even		flow	by	Meaning		
0	0	0	0	controller	Controller end		
1	0	0	1	device	Program controlled		
-	v	U	-	device	interrupt (PCI)		
2	0	1	0	device	Exception		
3	ő	1	1	device	Device end		
4	1	Ô	0	device	Attention		
5	î	0	1	device	Attention and PCI		
6	1	1	õ	device	Attention and		
	_	-	Ü	40,100	exception		
7	1	1	1	device	Attention and		
					device end		
CC=0	Contr	oller	end 1	Reported by	a controller when		
	contro	aller h	usv (10) instruction	condition code) has		
	been	previo	uslv r	eported one	or more times. It		
	signifi	ies that	the c	ontroller is no	ow free to accept I/O		
	comm	ands f	or dev	ices under its	s control. The device		
	addre	ss renc	orted v	vith controlle	er end is always the		
	lowes	t addr	ess (n	umerical valu	ie) of the group of		
	device	s serv	iced 1	ov the contr	oller. The interrupt		
	inform	nation	byte. i	in the interru	pt ID word, is set to		
	zero.		,,,,,,	ar the interru	pt 1D word, is set to		
CC=1	Progra	m coi	ntrolle	intormint	Reported when the		
00 1							
		interrupt indicates that a DCB with the PCI bit set to one has been transferred by cycle steal to the device					
	and no	n error	OT AVC	ention conditi	on has occurred.		
CC=2							
CC-2					error or exception		
		condition is associated with the interrupt. The condition is described in the interrupt status byte					
CC 2				ependent stati			
CC=3	Device	e end.	Repor	ted when no	error, exception, or		
	attent	ion co	nditio	n has occur	red during the I/O		
					ot the result of a PCI.		
					rminated normally.		
					a normal end while		
	suppo	rting s	uppres	s exception	(SE bit set to one),		
				_	status byte is set to		
				•	ermissive device end		
					or exceptions may		
					sed. Pertinent status		
					sidual status block.		
CC=4					errupt was caused by		
					ecution of an Operate		
	I/O in	structio	on. Ad	ditional statu	s information is not		
	_			•	es further definition;		
	for exa	ample,	code b	its for a keybo	oard function.		
CC-5	4 44		1 DOT	D 1 1	44 41 1 DOT		

The interrupt condition codes are mutually exclusive with each other but have no priority sequence.

and exception are both present.

and device end are both present.

are both present.

Attention and PCI. Reported when attention and PCI

Attention and exception. Reported when attention

Attention and device end. Reported when attention

CC=5

CC=6

CC=7

I/O Status Information

Acceptance of an I/O interrupt causes the device to present an interrupt ID word to the processor. Presentation of the interrupt ID word is explained in Chapter 3 (see I/O Interrupts). This word has the following format:

Interrupt ID word

IIB Device address

Bits 0-7 Interrupt information byte (IIB). For interrupt condition codes 2 and 6, the IIB has a special format and is called an interrupt status byte (ISB). Refer to interrupt status byte in this section. For most other interrupt condition codes, implementation of the IIB is device dependent. Exceptions are:

1. CC = 0—the IIB is set to zero.

2. CC = 3 or 7-bit zero is set as described under CC=3. Refer to individual device publications.

Bits 8-15 Device address. This byte contains the address of the interrupting device.

Interrupt Status Byte (ISB)

The ISB is a special format of the interrupt information byte (IIB) and contains detailed information on the nature of the interrupt. The ISB is reported only for error or exception conditions (interrupt condition codes 2 or 6). The ISB bits are normally set as a result of:

- 1. Status errors that occur during a DPC operation that cannot be indicated via a condition code.
- 2. Status errors that occur during a cycle steal operation. The ISB is never reported as zero unless the condition code presentation of 2 or 6 is singular in meaning for devices that do not cycle steal. After the processor has accepted the interrupt request, the device resets the ISB.

Bits 0-7 of the two special formats are explained in the following sections.

ISB (devices that do not cycle steal:

Bit 0 Device dependent status available. This bit set to one signifies that additional status information is available from the device. The information content and method of reading is described in the individual device publications.

Bit 1 Delayed Command reject. This bit is set to one if the device cannot execute the command (specified in the IDCB) due to an incorrect parameter in the IDCB, or it cannot execute the command due to its present state. For example: (1) The IDCB specifies an incorrect function/modifier combination, or (2) The device is temporarily not ready. The operation in progress is terminated. Interrupt condition code 2 or 6 is also reported. Command reject is set in the ISB only if the device cannot report IO instruction condition codes for the condition.

Bits 2-7 Device dependent. These bits, if used, are described in the individual device publications.

ISB (Cycle stealing device):

Bit 0

Bit 2

Device dependent status available. This bit, when set to one, signifies that: (1) additional status information is available from the device, or (2) the device is in an improper state to execute a function specified by a DCB.

The operation is terminated. The content and method of reading the additional status information is described in the individual device publications.

Note. When bit 0 of the ISB is equal to one and bits 2-7 are zeros, the contents of the residual-address word (cycle steal status) are defined by the device.

Bit 1 Delayed command reject. This bit is set to one if the device cannot execute the command due to one of the following conditions:

- 1. The IDCB contains an incorrect parameter. Examples are (a) an odd-byte DCB address, or (b) an incorrect function/modifier combination.
- The present state of the device, such as a not ready condition, prevents execution of an I/O command specified in the IDCB.

Delayed command reject is set in the ISB only if the device cannot report IO instruction condition codes for the condition. The operation is terminated. The DCB is not fetched.

Incorrect length record. This bit is set to one when the device encounters a mismatch between byte count and actual record length after beginning execution of the DCB. For example: the byte count is reduced to zero (with chaining flag off) and no end of record encountered. Incorrect length record is not reported when the SE bit is set to one. Reporting of incorrect length record is a device dependent feature and may be implemented regardless of the suppress exception feature. The operation is terminated.

Bit 3 DCB specification check. This bit is set to one when the device cannot execute a command due to an incorrect parameter specification in the DCB. Examples are (1) an odd-byte DCB chaining or status address, (2) the byte count is odd for a word-only device, (3) an odd-byte data address for a word-only device, (4) an invalid command or bit in the control word, or (5) an incorrect count.

The operation is terminated.

Bit 4 Storage data check. This error condition applies to cycle steal output operations only. If the bit is set to one, it indicates that the main storage location accessed during the current output cycle contained bad parity. Parity in main storage is not corrected. The device terminates the operation. The bad parity data is not transferred to the I/O interface. No machine check condition occurs.

- Bit 5 Invalid storage address, When set to one, this bit indicates one of the following conditions:
 - 1. During a cycle steal operation, the device has presented a main storage address that is outside the storage size of the system.
 - 2. A cycle stealing device has attempted to access storage through a segmentation register and the valid bit in the segmentation register is set to zero. Note that the relocation translator feature must be installed and enabled before this condition can occur.

Invalid storage address can occur on a data transfer or on a DCB fetch operation. In either case, the cycle steal operation is terminated.

- Bit 6 Protect check. When set to one, this bit indicates that the I/O device attempted to access a main storage location and presented an incorrect address key.
- Bit 7 Interface data check. This bit set to one indicates that a parity error has been detected on the I/O interface during a cycle steal data transfer. The condition may be detected by the channel or the I/O device. In either case, the operation is terminated.

CHAINING

The purpose of chaining is to allow the programmer to sequence an I/O device through a set of operations. This chaining function is called DCB command chaining and is specified by the chaining flag (bit 0) in the DCB control word.

When the current DCB indicates a chaining operation (bit 0 of the control word set to one), device parameter word 5 of the DCB contains a main storage address. This address points to the next DCB in the chain. The device completes the current operation but does not present an interrupt request (excluding PCI) to the processor. Instead, the device fetches the next DCB in the chain and continues operation.

Note. The chaining operation has no effect on programmed controlled interrupt (PCI). These interrupts, when specified in the DCB, still occur at the completion of the DCB fetch operation.

DCB Command Chaining

When DCB command chaining is specified, each DCB fetched by the device is interpreted as a new operation (or function) to be performed. The DCB may be equal to, but not a continuation of, the operation specified by the previous DCB.

Chapter 8. Storage Protection

The storage protection mechanism is provided as a basic part of the IBM 4955 Processor. This chapter describes the operation of the storage protection mechanism when the Storage Address Relocation Translator Feature is not installed or is disabled. When the relocation translator feature is installed and enabled, the storage protection mechanism, as described in this chapter, is disabled and all storage protection is controlled by the relocation translator. See Chapter 9, Storage Address Relocation Translator Feature.


The state of the storage protection mechanism is controlled by the Enable (EN) and the Disable (DIS) instructions described in Chapter 5. When enabled, it protects against: (1) access (reading and writing) to defined blocks of storage by software or by an I/O operation, and (2) writing in an undesired location within a defined block by software.

Storage is divided into blocks of 2048 bytes (Figure 8-1). Each block has an associated storage key register containing a three-bit storage key and a read-only bit. The storage key and the read-only bit are set into a storage key register by the Set Storage Key (SESK) instruction. The Copy Storage Key (CPSK) instruction can be used to read out the storage key register. Both instructions are described in Chapter 5.

Thirty-two storage key registers are installed; one for each block of storage up to the maximum storage size of 64K bytes. This means that the SESK instruction can specify a main storage block greater than the amount of storage installed on the system without causing a program check.

The processor determines storage-access authorization by comparing a storage key against an address key. Each priority level has an associated address key register (AKR). This register contains three address-key fields for: (1) operand 1, (2) operand 2, and (3) instruction space (figure 8-1). Each address-key field is three bits long. The address key used for a particular storage access is determined by the type of operand being accessed and is called the active address key. Proper access is determined by comparing the active address key against the storage key. If writing into storage is involved, the access is further controlled by the read-only bit associated with the storage block. See the Address Space Management section of this chapter for more details on the active address key and the AKR. The address keys in the AKR are assigned by the supervisor using the appropriate system register instructions: (1) Set Address Key Register (SEAKR), (2) Set Instruction Space Key (SEISK), (3) Set Operand 1 Key (SEOOK), and (4) Set Operand 2 Key (SEOTK). They can be read by the Copy Level Block (CPLB) instruction or the appropriate system register instructions: (1) Copy Address Key Register (CPAKR), (2) Copy Instruction Space Key (CPISK), (3) Copy Operand 1 Key (CPOOK), and (4) Copy Operand 2 Key (CPOTK).

When the storage protection mechanism is enabled, one or more of the following conditions must be true to authorize an attempt to access storage:



- For a main storage access, the storage key A must match the active address key B except as noted below:
 - -<u>Supervisor state</u>. Access to any area of storage, regardless of address keys or storage keys.
 - -Storage key of 7. Unprotected any address key can be used.
- The read-only control is ignored by an I/O cycle-steal access or when in supervisor state.

Figure 8-1. Storage protection mechanism

- 1. The machine is in supervisor state.
- 2. The storage key of the addressed block must be set to seven. If attempting to write into storage, the read-only bit must be set to zero.
- 3. The storage key of the addressed block must equal the active address key. If attempting to write into storage, the read-only bit must be set to zero.

If none of the three conditions is true:

- The storage access is prevented.
- The contents of main storage are not changed.
- A program check interrupt occurs with *protect check* set in the processor status word.

Programming Notes.

- 1. A storage key of seven allows access to any storage location within the block regardless of the active address key. However, the read-only control cannot be violated.
- 2. An active address key of zero is not a master key. The storage protection mechanism (if enabled) should be disabled prior to dumping the contents of storage to an I/O device.

^{*}The information is shown in the storage key register as it appears to the programmer.

For certain hardware functions that involve the access of main storage, the storage protection mechanism is suppressed. In the following cases, no storage protection checking is performed until the hardware function is completed:

- 1. During initial program load (see Storage Protection during Initial Program Load in this chapter).
- 2. While the system is in the stop state and a main storage access is being performed from the programmer console (optional feature).
- 3. While level status blocks are being stored by the hardware during class interrupts.

I/O devices must have one of the following conditions true to authorize an attempt to access storage:

- 1. The storage key of the addressed block must be set to seven.
- 2. The storage key of the addressed block must equal the active I/O cycle-steal address key.

Note that the read-only bit is ignored during cycle-steal access to main storage. The I/O cycle-steal address key is specified in the device control block (DCB). The DCB is used to control the cycle steal operation as explained in Chapter 7, Input/Output Operations.

STORAGE PROTECTION DURING INITIAL PROGRAM LOAD

During initial program load (IPL), the storage protection mechanism is disabled. IPL is preceded by a hardware reset and no instructions are executed until the IPL terminates. At the successful completion of IPL, the processor enters supervisor state on priority level zero with all address keys in the address key register set to zero.

STORAGE PROTECTION IN SUPERVISOR STATE

Supervisor state overrides the storage protection mechanism. The supervisor has unlimited access to all of main storage. Any of the following events cause the processor to enter supervisor state:

- 1. A priority interrupt.
- 2. A class interrupt.
- 3. A successful IPL and a subsequent I/O interrupt.

Note. Occurrence of these events results in specific values being set in the address keys in the affected address key register. These address-key values are described in the section Address Space Management in this chapter.


When the processor exits supervisor state, via a Set Level Block (SELB) instruction, storage protection functions are resumed. The processor is now in the problem state and makes reference to the current address-key register for the active address key.


Note. Storage protection in supervisor state is changed when the relocation translator feature is installed and enabled. This change is described in Chapter 9, Storage Address Relocation Translator Feature.

ADDRESS SPACE MANAGEMENT

Address Space

Each priority level in the processor has an associated address key register (AKR). Each register contains three address keys and an equate operand spaces (EOS) bit.





EOS Equate operand spaces. This bit when set to one causes all data operands to use the OP2K address key. See Equate Operand Spaces section in this chapter.

Operand 1 key. These bits contain the binary-coded OP1K operand 1 address key with bit 7 as the low-order bit.

OP2K Operand 2 key. These bits contain the binary-coded operand 2 address key with bit 11 as the low-order bit.

ISK Instruction space key. These bits contain the binary-coded instruction-space address key with bit 15 as the low-order bit.

An address key defines a particular address space where:

- The address space is a range of logically contiguous storage.
- The address space is accessible by the effective address without intervention by a resource management function. That is, the address space is not greater than 64K bytes.


All instruction fetches occur within the address space defined by the instruction space key (ISK). For storage to storage instructions, all reads and writes concerning data operand 1 occur in the address space defined by the operand 1 key (OP1K). All reads and writes concerning data operand 2 occur in the address space defined by the operand 2 key (OP2K).

Examples:

ISK = OP1K = OP2K. For instruction processing, all storage accesses occur within the same address space.

ISK ≠ OP1K, OP1K = OP2K. Instruction fetches occur in the ISK address space. Data access occurs in the OP2K address space.

ISK \neq OP1K \neq OP2K (Refer to Figure 8-2). The instruction fetch occurs in the ISK address space. The source-data operand access (storage to storage operations) occurs in the OP1K address space. All other data operand accesses occur in the OP2K address space.



Assembler syntax for address spaces

OP1K	OP2K			
addr5	addr4	Example:	AW	addr5,addr4
(reg)	(reg)	Example:	MVFD	(reg), (reg)
	(reg, bitdisp)			
	longaddr			
	shortaddr			

Notes.

- 1. OP1K is only used for the source operand in Storage to Storage operations.
- OP2K is used for storage data access in all other operations (excluding Branch/Jump).

Figure 8-2. Data movement in address spaces when ISK ≠ OP1K ≠ OP2K

I/O operations that access main storage also use an address key. Cycle steal operations (read or write) use the cycle-steal address key specified within the device control block. An address key of zero is used when the device fetches the device control block. DPC operations that write data to storage use the OP2K address key. The cycle steal and DPC operations are explained in Chapter 7, Input/Output Operations.

Other defined usage of the address key register:

- 1. All indirect access for branching uses the ISK.
- Effective address generation (access of indirect storage address) occurs in the address space of the particular data operand.
- 3. Storage access via the console is defined by the ISK. Stop on Address is based on the ISK when the translator feature is installed and enabled.
- 4. System reset and IPL set all address keys and the EOS bit to zero.

Active Address Key

At any point in time, one of four address keys may be used to access storage. The key in use is called the active address key and may be either the ISK, OP1K, OP2K, or the cycle-steal address key. The address key in use (active) depends on the type of operation being performed at a specific instant in time. When the storage protection mechanism is enabled, the active address key is used to determine storage access authorization. When the relocation translator feature is installed and enabled, the active address key defines storage access through a particular block of segmentation registers. See Chapter 9, Storage Address Relocation Translator Feature.

Address Key Values After Interrupts

When priority or class interrupts occur, certain values are set into the address keys of the affected AKR. These values anticipate the address spaces that the programmer might need for interrupt processing. The following chart shows the resulting AKR for each type of interrupt.

Resulting AKR values					
EOS	OP1K	OP2K	ISK		
0	0	0	0		
0	Note 1	0	0		
0	Note 2	0	0		
0	Note 2	0	0		
0	Note 1	0	0		
0	Note 3	0	0		
0	0	0	0		
0	0	0	0		
	EOS 0 0 0 0 0	EOS OPIK 0 0 0 Note 1 0 Note 2 0 Note 2 0 Note 1 0 Note 3	EOS OP1K OP2K 0 0 0 0 Note 1 0 0 Note 2 0 0 Note 2 0 0 Note 1 0 0 Note 3 0		

Note 1. OP1K is set to the preceding key contained in OP2K.

Note 2. OP1K is set to the last active processor address key.

Note 3. OP1K is set to the preceding key contained in the ISK.

All interrupt service routines are presumed to reside in address space zero; therefore, the ISK and OP2K are set to zero when an interrupt occurs. Necessary information for processing a specific interrupt may reside in an address space other than zero. The address key related to the particular interrupt is placed in OP1K. The OP1K is set in anticipation of a storage to storage move of information from the interrupting address space to address space zero. Note. Class interrupts cause a hardware controlled storing of a level status block. This operation uses address key zero.

EQUATE OPERAND SPACES (EOS)

The equate operand spaces bit (bit 0) in the address key register provides a control to modify the active address key definition for data operands. When the EOS bit is set to one (enabled), all processor data fetches occur within a single address space. The processor uses the OP2K address key for storage access. The OP1K is unchanged but is ignored. When the EOS bit is set to zero(disabled), the OP1K address key functions in a normal manner.

Equate operand spaces (EOS) may be enabled by (1) an Enable (EN) instruction, (2) a Set Level BLock (SELB) instruction, or (3) a Set Address Key Register (SEAKR) instruction. EOS may be disabled by (1) a Disable (DIS) instruction, (2) a Set Level Block (SELB) instruction, or (3) a Set Address Key Register (SEAKR) instruction. These instructions are described in Chapter 5.

Chapter 9. Storage Address Relocation Translator Feature

The Storage Address Relocation Translator Feature is an optional feature for the IBM 4955 Processor Model B only.

The relocation translator feature permits addressing of main storage locations beyond 64K bytes. Therefore, the feature is required when main storage is larger than 64K bytes. The reason for this requirement is that addresses, without this feature, are 16 bits long and provide an addressing capability of:

 Hexadecimal
 Decimal

 0000
 0

 to
 to

 FFFF
 65,535

Addresses generated in relocation mode are 24 bits long. The 24-bit address provides an addressing *capability* of:

 Hexadecimal
 Decimal

 000000
 0

 to
 to

 FFFFFF
 16,777,215


This addressing range should not be confused with main storage size, which is a maximum of 128K bytes for the IBM 4955 Processor Model B.

Besides address generation, storage protection also functions differently in relocation mode. When the translator feature is installed and enabled, the storage protection mechanism as described in Chapter 8 is disabled and all storage protection is under control of the translator. Refer to Storage Protection when Using the Relocation Translator in this chapter.

TRANSLATOR DESCRIPTION

The translator feature provides 8 stacks of 16-bit segmentation registers. The stacks are numbered 0 through 7 to correspond to the 8 possible values of the address keys. Each stack consists of 32 registers (0 through 31):

Segmentation registers



Thus, 256 segmentation registers are provided in the relocation translator. Note that only one translator can be installed in the IBM 4955 Processor Model B.

The eight stacks of segmentation registers are under supervisory program control. Four privileged instructions are provided:

- Set Segmentation Register (SESR). This instruction loads one segmentation register.
- Copy Segmentation Register (CPSR). This instruction allows the supervisor to inspect the contents of a segmentation register.
- Enable (EN). This instruction enables the relocation translator. Until the translator is enabled, 16-bit addressing is in effect for the low-order 64K bytes of storage. Any storage above 64K bytes is not accessible to the programs until the translator is enabled.
- Disable (DIS). This instruction disables the relocation translator.

Refer to Chapter 5 for descriptions of the preceding instructions.

Mapping of main storage is achieved through the segmentation registers. Each segmentation register controls 2K-byte segments of storage. The SESR instruction is used to load each segmentation register with a unique physical segment address. This segment address is the physical address of a 2K-byte segment of storage. Note however, that more than one segmentation register can be loaded with the same segment address. For example: stack 0, register 15 (associated with the supervisor address key of 0) can be loaded with the same number as stack 3, register 6. This arrangement allows the supervisor (for example) to address control blocks within a problem program even though the address key for the supervisor is different than the key for the problem program. Once loaded, each stack of segmentation registers contains a complete map of 64K bytes scattered in 2K-byte physical segments. A separate set of segmentation registers for each address-key value allows fast task switching without the need for saving or restoring the storage map.

RELOCATION ADDRESSING

This section describes how the relocation translator generates a 24-bit address to address any byte in storage. Figure 9-1 shows an example of address translation. The letters in the following steps correspond to the letters on the figure.

- The active address key from the address key register selects a segmentation register stack. The address key pertains to the instruction being executed on the current priority level.
- The five high-order bits (0 through 4) of the 16-bit address (generated for the instruction being executed) select a segmentation register within the stack selected in step A. These bits define the logical segment.
- The 24-bit address is generated. The 13 high-order bits (0 through 12) are from the segmentation register; these bits specify the physical address of a 2K-byte segment of storage.
- The 11 low-order bits (bits 13 through 23) of the 24-bit address are the 11 low-order bits (5 through 15) of the 16-bit logical address (generated for the instruction being executed); these bits specify the byte address within the 2K-byte segment.




Figure 9-1. Address translation example

STORAGE PROTECTION WHEN USING THE RELOCATION TRANSLATOR

When the translator is installed but disabled by a Disable (DIS) instruction with parameter field bit 14 set, the operation of the storage protection mechanism is exactly as described in Chapter 8. When the translator is installed and enabled by an Enable (EN) instruction (with parameter field bit 14 set to one and bit 12 set to zero) the storage protection mechanism is disabled.

When the translator is enabled, the storage protection mechanism by itself no longer protects against inadvertent writing or instruction access of main storage. This function is undertaken by the translator. To this end, the storage key registers are ignored by the hardware. As previously described, the address keys are used to select stacks of segmentation registers. There are eight such stacks in the translator with 32 segmentation registers in each stack. Address key 0 is implicitly assigned to the supervisor for handling interrupts. Address key 0 is also used for (1) cycle steal DCB fetching, and (2) storing of the residual status block. Chapter 8 describes the method of setting and reading the address keys. Because each stack of segmentation registers has access to storage only within its assigned region, protection is provided against writing into storage or fetching instructions from another region.

The translator also provides no-access and read-only protection within the regions controlled by each stack of segmentation registers. This allows storage protection of shared segments of storage. Bits 13 and 14 of the segmentation registers are used for this purpose:

Bit 13 (valid bit). When set to one, this bit specifies that the contents of the segmentation register are valid; the segmentation register can be used to perform the translation. When bit 13 is a zero, the segmentation register cannot be used for translation (no access). If translation is attempted, a program check interrupt occurs with *invalid storage address* (ISA) set in the program status word. This is called a *logical ISA*.

Bit 14 (read-only bit). When set to a one, this bit specifies that the block is read only. If an attempt is made to write into storage using a segmentation register with the read-only bit set to one, a program check interrupt occurs with *protect check* set in the program status word. Storage is not changed. Bit 14 is ignored by a cycle steal access, or when in supervisor state.

I/O STORAGE ACCESS USING THE RELOCATION TRANSLATOR

All storage access requests from I/O devices are translated by the same mechanism that handles storage requests from the processor. The device control block (DCB) must reside in the supervisor's address space. Therefore; all I/O devices must use address key 0 to gain access to the DCB and to store the residual status block. The address key of the process requiring a cycle steal operation resides in the DCB. The I/O device presents this address key along with a 16 bit logical address to the translator. This allows the I/O device to directly address the storage space for a particular process. The address key allows I/O storage protection to be established between address spaces assuming the supervisor ensures the integrity of the DCBs.

COMPATIBILITY BETWEEN THE RELOCATION TRANSLATOR AND THE STORAGE PROTECTION MECHANISM

The storage protection mechanism (as described in Chapter 8) has similar characteristics to those of the relocation translator; also, there are certain characteristics that are dissimilar. The programmer should be familiar with these characteristics in order to write code that migrates from a system using the storage protection mechanism to one using the relocation translator.

The two sets of characteristics are listed below and require the following definitions:

- Storage protect system—the storage protection mechanism is enabled. The relocation translator (if installed) is disabled.
- Translator system—the storage protection mechanism is disabled. The relocation translator is enabled.

Characteristics That Are Similar

- 1. The active address key defines the storage that may be addressed at any point in time.
- 2. For a storage protect system, the storage key registers define access control to a 2K-byte block of storage. For a translator system, the segmentation registers define access control to a 2K-byte block of storage.
- 3. Within the storage defined by an address key, a read-only area may be designated. The read-only areas are defined for 2K-byte blocks.
- 4. No protect check occurs when accessing storage in supervisor state.
- 5. I/O cycle-steal access to main storage is unaffected by the read-only bit.
- 6. The storage protection mechanism or the relocation translator may be either enabled or disabled using the Enable (EN) or Disable (DIS) instructions.
- 7. For a storage protect system, a storage key of 7 defines a common area accessible by any address key. A translator system can reproduce this function by mapping the same logical address in all address spaces into a unique physical address.

Characteristics That Are Dissimilar

- 1. In a storage protect system, supervisor state allows access to all of main storage, irrespective of address keys or storage keys. In a translator system, supervisor state may only access the storage defined by the active address kev.
- 2. In a storage protect system, the total storage defined by address keys is less than or equal to 64K-bytes. In a translator system, the total storage defined by address keys is less than or equal to 512K-bytes at an instant in
- 3. In a translator system, the address space defined by an address key starts at logical address zero. In a storage protect system, the address space defined by an address key starts on various 2K-byte block boundaries.
- 4. The instructions used to load and store storage key registers are different from the instructions used to load and store segmentation registers.
- 5. In a translator system, an I/O device should not receive protect checks. In a storage protect system, it is possible for an I/O device to receive protect checks.
- 6. Due to the address mapping capability of a translator system, certain mappings from logical to physical address space are difficult to emulate in a storage protect system. For example: a common area exclusive to only two address keys.
- 7. In a translator system, PSW bit 14 provides status information on whether the translator is enabled or disabled. There is no status bit to provide this information concerning the storage protection mechanism.

ERROR RECOVERY CONSIDERATIONS

Invalid Storage Address

If a program check interrupt with invalid storage address (ISA) set in the program status word occurs when the relocation translator is enabled, it has two possible meanings:

- 1. Mapping occurred into a real storage address, but that segment of storage is not installed on the machine. This error is called a physical ISA.
- 2. Bit 13 (valid bit) of the segmentation register was not set when mapping was attempted. This signifies that the contents of the segmentation register are invalid. This error is called a logical ISA.

The specific nature of the ISA can be resolved as follows:

- 1. Store the segmentation register following the program check interrupt.
- 2. Test the segmentation register for the presence of bit 13.
- 3. If bit 13 is a one, the supervisor's concept of the actual storage installed on the machine is incorrect.

Protect Check

When the translator is enabled, a program check interrupt with protect check set in the PSW is caused by an attempt to write into storage using a segmentation register with bit 14 (read-only) set to one.

When the translator is disabled, protect check in the PSW can be set by the storage protection mechanism (if it is enabled). Refer to Chapter 8 for additional information about the storage protection mechanism.

To resolve the cause of the protect check error, the supervisor must determine if the translator is enabled.

STATUS OF TRANSLATOR AFTER POWER TRANSITIONS AND RESETS

The translator is enabled only by the Enable (EN) instruction. The translator is disabled by the following:

- 1. Disable (DIS) instruction
- 2. Power on reset
- 3. Check restart
- 4. Initial program load (IPL)
- 5. System reset key (Programmer Console Feature)

Notes.

- 1. A machine check does not disable the translator.
- 2. The segmentation registers are not reset when the translator is disabled.

INSTRUCTION EXECUTION TIME WHEN USING THE TRANSLATOR

The translator, when enabled, adds 220 nanoseconds to each reference to main storage. When the translator is disabled, storage references proceed at normal speed (660 nanoseconds).


This chapter provides a functional description and programming information for the Timer Feature. For publications containing other types of information, refer to the preface of this manual.

The Timer Feature has two separately addressable 16 bit timers on one attachment. Each timer can be used as: (1) an interval timer; (2) a pulse counter or; (3) a pulse duration counter.

Associated with each timer is a 16 bit auto-load register that can be set by program control. The auto-load register automatically reloads the timer when the timer has counted past zero. This provides the capability of generating periodic interrupts on 65,536 possible base values of the timer without program intervention.

Each timer has a mode register that selects one of four standard internal time bases or an external timebase. The four standard time bases are 1, 5, 25, and 50 microseconds. The external timebase, provided by the user, can be equal to or greater than 1 microsecond (less than 1000 kHz) for TTL input, or 20 microseconds (worse case) for filtered TTL input.

Communication between the processor and the timer attachment is initiated by the processor. All timer functions (control, read) must be initiated with Operate I/O instructions stored in the processor.




* Indirect addressing bit

The address field (bits 16-31) and the contents of the register specified in the R2 field (bits 8-10) of the Operate I/O instruction generate an effective address that points to a main storage location containing an Immediate Device Control Block (IDCB). IDCBs are doubleword blocks of storage reserved by programs for storage of device directed commands (Refer to Chapter 5 and Chapter 7 in this manual for a more detailed description of the Operate I/O instruction.)

ADDRESSING

Either timer on the attachment card can be addressed by the 8-bit address field in the IDCB (bits 8-15).

IDCB (immediate device control block)




Immediate data field	
	31
16	31

The attachment card is addressed by bits 8-14. Field installable connectors on the attachment card allow any 7-bit address, (bits 8-14), to be selected.

Bit 15 selects one of the two timers on the attachment card. If bit 15 is 0, timer 0 is selected. If bit 15 is 1, timer 1 is selected. There is no connector on the attachment card for bit 15.


COMMANDS



Two types of I/O functions can be issued to the timer attachment by the processor: control and read. The specific type of function is defined in the command field (bits 0-7) of the IDCB. The timer attachment also responds to the channel-directed Halt I/O command.

Prepare

IDCB (immediate device control block)




Immediat	Immediate data field				
	Ze	eros Level			
16		26 27 30 3			
Bits 27–30	Level	Bit 31			
0000 0001	0 1	0 = interrupts not allowed			
0010 0011	2	1 = interrupts allowed			


The Prepare command loads the interrupt level and I bit into the prepare register. Both timers share one prepare register and are prepared simultaneously—same level and I bit—by one Prepare command. The device address field in the IDCB can indicate either timer.

The I bit (bit 31) determines if the timer can report an I/O interrupt. If the I bit equals 0, I/O interrupts are not reported. If the I bit equals 1, I/O interrupts are reported. The interrupt level (bits 27–30) is the priority level on which the timer reports I/O interrupts. Level 0 is the highest priority level; level 3 is the lowest. Condition code 1 (busy) is not reported for this command. If condition code 5 (interface data check) is reported, the command is not executed.

Set Timer Period and Initial Value

IDCB (immediate device control block)







This command loads bits 16-31 of the IDCB into the auto-load register of the addressed timer. The data in the auto-load register is then loaded into the timer. This 16 bit value is selected by the user and can be any value from 0 to 65,536 (0000-FFFF hex). This value, in conjunction with the time base selected by the Set Timer Mode command, establishes the time interval for device end interrupts. (See I/O Interrupt in this chapter.)

No interrupt is reported by the timer to the Sct Timer Period and Initial Value command. If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.

Set Timer Mode

IDCB (immediate device control block)






The Set Timer Mode command loads bits 16–31 of the IDCB into the mode register for the addressed timer. The desired time base can be selected by bits 28–30. For example: if bits 28–30 are set to 010, the timer counts once every 25 microseconds at a frequency of 40,000 cycles per second. If the user selected time base is specified, bits 28–30 set to xx1, any external time base greater than 1 microsecond (less than 1000 kHz) for TTL input or 20 microseconds (worse case) for filtered TTL input, can be supplied to the timer. The time base selected, in conjunction with the value used in the Set Timer Period and Initial Value command, establishes the time interval for device end interrupts. (See I/O Interrupt in this chapter.)

Bit 31 allows the user to provide an external gate to the timer. When this gate is enabled and activated by the user, and the timer is set to run state; the timer counts with the selected timebase. When the external gate is deactivated, the timer stops. No interrupt is reported by the timer to this command. If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.

Start Timer, Periodic

IDCB (immediate device control block)



Immediate data field	
Zeros	
16	31

External Gate Not Enabled


The addressed timer is set to run state and started. Device end interrupts are reported each time the timer is clocked once more after the count has reached zero. The value of the auto-load register is set into the timer when the device end interrupt is reported. Any selected timebase can be used. If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.


External Gate Enabled

If the external gate is enabled, the addressed timer is set to run state. The timer starts when the external gate becomes active after receipt of the start command. Device end interrupts are reported each time the timer is clocked once more after the count has reached zero. The value of the auto-load register is set into the timer when the device end interrupt is reported. When the external gate becomes inactive, the timer stops, run state is reset, and an interrupt is reported. (See *Condition Codes Reported for an I/O Interrupt* in this chapter.) If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.

Start Timer Aperiodic

IDCB (immediate device control block)






External Gate Not Enabled


The addressed timer is set to run state and started. Device end interrupts are reported each time the timer is clocked once more after the count has reached zero. The value of the auto-load register is **not** set into the timer when the device end interrupt is reported. The time period for the first device end interrupt depends on the initial value set in the timer and the timebase selected. The time period for subsequent device end interrupts depends on the timer maximum value and the timebase selected. Any selected timebase can be used. If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.


External Gate Enabled

If the external gate is enabled, the addressed timer is set to run state. The timer starts when the external gate becomes active after receipt of the start command. Device end interrupts are reported each time the timer is clocked once more after the count has reached zero. The value of the auto-load register is not set into the timer when the device end interrupt is reported. When the external gate becomes inactive, the timer stops, run state is reset, and an interrupt is reported. (See *Condition Codes Reported for an I/O Interrupt* in this chapter) If condition code 1 (busy) or condition code 5 (interface data check) is reported, the command is not executed.

Stop Timer









The addressed timer is stopped and timer run state is reset. Residual interrupts are reset. (A residual interrupt is an interrupt detected during execution of the command, caused by (1) a clocking of the timer or (2) the external gate becoming inactive just after the timer has made a decision to accept and execute the command.) If the timer is interrupt pending, condition code 1 (busy) is reported and the command is not executed. If condition code 5 (interface data check) is reported the command is not executed.

Device Reset






The Device Reset command stops the addressed timer and resets timer run state. The mode register and any pending or residual interrupts for the addressed timer are reset. The timer and auto-load register are not reset. Condition code 1 (busy) or condition code 5 (interface data check) are not reported to this command.

Read ID

IDCB (immediate device control block)





Immediate data field	
Z	eros
16	31

The ID word from the addressed timer is loaded into bits 16-31 of the IDCB. The timer ID word is 0028 (hex). No interrupt is reported by the timer to this command. The device identification word contains physical information about the device. This word can be used to determine the devices that are attached to the system. Condition code 1 (busy) is not reported. If condition code 5 (interface data check) is reported, the command is not executed.

Read Timer Value

IDCB (immediate device control block)







The value of the addressed timer is loaded into bits 16-31 of the IDCB. No interrupt is reported by the timer to this command. Condition code 1 (busy) is not reported. If condition code 5 (interface data check) is reported, the command is not executed.

Read Timer Mode

IDCB (immediate device control block)





The value of the mode register of the addressed timer is loaded into bits 16-31 of the IDCB in the same format as specified under the Set Timer Mode command. No interrupt is reported by the timer to this command. Condition code 1 (busy) is not reported. If condition code 5 (interface data check) is reported, the command is not executed.

CONDITION CODES REPORTED FOR AN I/O INSTRUCTION

Condition code	Meaning
0	Device not attached—reported if the Timer Feature is addressed but is not installed on the system.
1	Busy—reported when the timer is unable to execute a command because it is in the busy state. A timer is in the busy state when the timer is in the run state or in an interrupt pending state.
2	Not reported
3	Command reject—reported if the command issued is outside the defined command set for the Timer Feature.
4	Not reported
5	Interface data check—reported if a parity error occurs on the data bus during data transfer.
6	Not reported
7	Satisfactory-reported when a command is accepted.

I/O INTERRUPT

The timer attachment can initiate an I/O interrupt if the I bit in the prepare register has been set to 1 by the Prepare command.

Device end interrupts are reported each time the timer is clocked once more after the count has reached zero. The time base selected and the initial value set in the timer are used to establish the time intervals for device end interrupts. The relationship of these values is:

$$B(V+1) = T$$

where

B = time base selected by the Set Timer Mode command.

V = value set into the timer by the Set Timer Period and Initial Value command.

T = time interval of device end interrupts.

The constant 1 is added to the value V because device end interrupts are not reported until the timer has been clocked once more after the count has reached zero.

Example: You want device end interrupts reported every 100 microseconds and you elect to use a time base of 5 microseconds. Using the formula B(V+1) = T, the value to be set into the timer by a Set Timer Period and Initial Value command is 13 (hex).

$$V = \frac{T}{B} - 1$$

$$V = \frac{100}{5} - 1$$

$$V = 20 - 1$$

V = 19 (decimal): 13 (hex)

The time interval of the first device end interrupt reported after the timer accepts a start command, or the external gate becomes active, may vary by as much as the value of the time base selected. This is due to the asynchronous condition between:

- 1. The internal free running oscillator or external user clock, and
- 2. The program setting of the timer run state or the activation of the external gate.

This variance in time occurs only once each time the timer is started.

The condition code reported during interrupt acceptance defines the interrupt.

CONDITION CODES REPORTED FOR AN I/O INTERRUPT

Condition Code	Meaning
0	Not reported
1	Not reported
2	Exception—reported when an overrun has occurred in the timer. Overrun means a device end interrupt occurs while a previous device end interrupt is pending in the timer.
3	Device end—reported when the timer is clocked once more after the count has reached zero.
4	Attention—reported when an external gate cycle ends prior to a device end interrupt. Timer run state is reset.
5	Not reported
6	Attention and Exception—reported if an external gate cycle ends and an overrun condition is present in the timer. Timer run state is reset.
7	Attention and Device end-reported if an external gate cycle ends and device end are detected at the same time. Timer run state is reset.

STATUS AFTER RESETS

Condition	Reset					
	Timer	Auto-load reg.	Prepare reg.	Mode reg.	Pending interrupts	Timer run state
Power on reset	X (to all 1's)	X (to all 1's)	X	X	X	X
System reset			X	X	X	X
Halt I/O				x	X	X
Device reset				Y	Y	Y

X = reset in both timers

Y = reset in addressed timer only

Chapter 11. Teletypewriter Adapter Feature

This chapter provides a functional description and programming information. For publications containing other types of information, refer to the preface of this manual.

The Teletypewriter Adapter feature is an input/output device attachment. This attachment provides circuitry between the I/O channel and a standard Teletype* "input/output unit" or equivalent. One of the following bit transfer rates can be selected:

bits per second


The bit transfer rate that the Teletypewriter Adapter can accept is selectable on the attachment logic card by a connector at installation time. The connector can be changed if another I/O device is attached that operates on a different bit transfer rate.

Attachment options between the Teletypewriter Adapter and the attached device are selectable via field installable connectors at installation time. The connectors can be changed if another I/O device is attached that utilizes a different type connection. Three input options—Isolated Contact Sense, TTL, and EIA—and two output options—Solid State Switch/TTL, and EIA—are available.

Also, two outputs—Solid State Switch for Write Control and Solid State Switch for Read Control—are available to the user. These two outputs are controlled by modifier bit 7 in the Write and Read command. (See Write command and Read command in this chapter.) These two outputs can be used for non-IBM or RPQ hardware device control.

The Teletypewriter Adapter supports full duplex operation. Data can be concurrently transmitted and received between the Teletypewriter Adapter and the attached device. Any of the 256 hex data codes can be transmitted or received.

Communication between the processor and the device attached to the Teletypewriter Adapter is initiated by the processor. All Teletypewriter Adapter functions (control, write, read) must be initiated with Operate I/O instructions stored in the processor.



^{*}Trademark of Teletype Corporation

The address field (bits 16-31) and the contents of the register specified in the R2 field (bits 8-10) of the Operate I/O instruction generate an effective address that points to a main storage location containing an Immediate Device Control Block (IDCB). IDCBs are doubleword blocks of storage reserved by programs for storage of device directed commands (Refer to Chapter 5 and Chapter 7 in this manual for a more detailed description of the Operate I/O instruction.)

The Teletypewriter Adapter can perform Initial Program Load (IPL). A field installable connector on the attachment logic card designates the Teletypewriter Adapter as either the primary or alternate IPL source. If the attachment logic card has the connector installed to designate the Teletypewriter Adapter as the primary IPL source and the IPL Source switch on the console is in the Primary position, the Teletypewriter Adapter is selected to perform the IPL when the Load key is pressed. If the connector is installed in the alternate position, the IPL Source switch on the console must be in the Alternate position for the Teletypewriter Adapter to perform IPL. If the field installable connector on the attachment logic card is not installed, the Teletypewriter Adapter cannot be selected for IPL. (Refer to Chapter 4 in this manual for a more detailed description of the IPL Source Switch.)

The IPL record length is 256 bytes and starts at main storage location zero.

ADDRESSING

The attached device is addressed by the 8-bit address field in the IDCB (bits 8-15).



Field installable connectors on the Teletypewriter Adapter attachment logic card provide the capability of selecting any one of 256 addresses (00-FF hex) for the attached device.

COMMANDS


The Teletypewriter Adapter performs two types of receive operations. An understanding of these two types is necessary before discussing commands and condition codes.

• Normal receive operation.

A byte of data from the attached device is loaded into the receive data register. An attention interrupt is reported at the completion of the operation. The data remains in the receive data register until (1) read at least once by the program and (2) a subsequent normal receive operation is initiated.


• Overrun receive operation.


An overrun receive operation is initiated if the attached device begins to transmit data to the Teletypewriter Adapter and the receive data register, previously loaded by a normal receive operation, has not been read at least once by the program. The character in the receive data register is not lost. The character that caused the overrun is lost. An exception interrupt is reported at the completion of an overrun receive operation.



Three types of I/O functions can be issued to the Teletypewriter Adapter by a processor; control, write, read. The specific type of function is defined in the command field (bits 0-7) of the IDCB. The Teletypewriter Adapter also responds to the channel-directed Halt I/O command.


Prepare







The Prepare command loads the interrupt level and I bit into the Teletypewriter Adapter prepare register. The I bit (bit 31) determines if the Teletypewriter Adapter can report an I/O interrupt. If the I bit equals 0, I/O interrupts are not reported. If the I bit equals 1, I/O interrupts are reported. The interrupt level (bits 27–30) is the level on which the Teletypewriter Adapter reports I/O interrupts. Level 0 is the highest priority level; level 3 is the lowest. The Teletypewriter Adapter does not report condition code 1 (busy) to this command. If condition code 5 (interface data check) is reported, the command is not executed.

Reset Device









The Reset Device command resets all registers except the prepare field register and the transmit data register. The write and read control interface lines are disabled. Pending interrupts and condition codes are reset. The Teletypewriter Adapter does not report condition code 1 (busy) or condition code 5 (interface data check) to this command.

Reset to Diagnostic Wrap

IDCB (immediate device control block)






The Reset to Diagnostic Wrap command (1) resets pending interrupts, condition codes, all registers in the Teletypewriter Adapter except the prepare register, and (2) disables the read and write control interface lines. The Teletypewriter Adapter is placed in a diagnostic wrap state.


In the diagnostic wrap state, commands can be issued to the Teletypewriter Adapter for testing purposes. An attached device may or may not be attached to the Teletypewriter Adapter. If a Write command is issued, data is sent to the Teletypewriter Adapter transmit data register and to the attached device if present. At the completion of the transmit operation, a device end interrupt is reported. The data is also sent to the Teletypewriter Adapter receive data register, and at the completion of the receive operation an attention interrupt is reported. For checking purposes, the Teletypewriter Adapter can be forced into an overrun condition by not reading the receive data register after the attention interrupt is accepted, and then issuing another Write command. The Teletypewriter Adapter does not report condition code 1 (busy) or condition code 5 (interface data check) to this command.

Exit from the diagnostic wrap state is by a Reset Device command, Halt I/O, system reset, or power on reset.

Write

IDCB (immediate device control block)







Bit 7 = 0 Write control interface line is disabled Bit 7 = 1 Write control interface line is enabled

The Write command loads bits 24-31 of the IDCB into the Teletypewriter Adapter transmit data register. The Teletypewriter Adapter then transfers the byte serially by bit to the attached device. If command field bit 7=0, the write control interface line is disabled. If command field bit 7=1, the write control interface line is enabled. A device end interrupt is reported at the completion of the data transfer. If the Teletypewriter Adapter is in a write busy or interrupt pending state, condition code 1 (busy) is reported and the command is not executed. If condition code 5 (interface data check) is reported, the command is not executed.

Read

IDCB (immediate device control block)






Bit 7 = 0 Read control interface line is disabled

Bit 7 = 1 Read control interface line is enabled

The Read command loads the byte contained in the Teletypewriter Adapter receive data register into bits 24-31 of the IDCB. If command field bit 7=0, the read control interface line is disabled. If command field bit 7=1. the read control interface line is enabled. No interrupts result from the execution of this command. If the Teletypewriter Adapter is in a read busy or interrupt pending state, condition code 1 (busy) is reported and the command is not executed. If condition code 5 (interface data check) is reported, the command is not executed. Note that the byte in the receive data register is not changed as a direct result of a Read command. The data in the receive data register is changed by a normal receive operation.

Read ID

IDCB (immediate device control block)



Immediate data field	
Zeros	
16	21

The Read ID command loads the device ID byte into bits 24-31 of the IDCB. The device ID for the Teletypewriter Adapter is 10 hex. The device identification word contains physical information about the device. This word can be used to determine the devices that are attached to the system. The Teletypewriter Adapter does not report condition code 1 (busy) to this command. If condition code 5 (interface data check) is reported, the command is not executed.

CONDITION CODES REPORTED FOR AN I/O INSTRUCTION

Condition Code

Meaning

1

2

3

4

5

6

Device not attached-reported if the Teletypewriter Adapter is addressed but is not installed on the system.

Busy-reported by the Teletypewriter Adapter under the following conditions:

- 1. To a Write command-the Teletypewriter Adapter is executing a transmit operation to the attached device or has a device end interrupt pending (write busy or interrupt pending).
- 2. To a Read command-the Teletypewriter Adapter is executing a normal receive operation or has an attention or exception interrupt pending (read busy or interrupt pending). The Teletypewriter Adapter is not busy to a Read command by reason of executing an overrun receive operation.

Busy is reported to any command outside of the defined command set for the Teletypewriter Adapter if the Teletypewriter Adapter is in the write busy, read busy or interrupt pending states. Since the Teletypewriter Adapter supports full duplex operation-simultaneous read and write-the Teletypewriter Adapter can be write busy or read busy or interrupt pending at the same time.

Not reported

Command reject-reported if the command issued is outside the defined command set for the Teletypewriter Adapter.

Not reported

Interface data check-reported if a parity error occurs on the data bus during data transfer.

Not reported

7 Satisfactory-reported when a command is accepted.

I/O INTERRUPT

The Teletypewriter Adapter initiates an I/O interrupt, if the I bit in the prepare register has been set to 1 by the Prepare command, under the following conditions:

- Attention—a normal receive operation has been completed.
- Exception—an overrun receive operation has been completed.
- Device end—a transmit operation has been completed.

Attention, exception, and device end interrupts can be pending at the same time. If an exception interrupt and device end interrupt are pending at the same time, the exception interrupt takes precedence at interrupt reporting time. The reporting and acceptance of the exception interrupt does not reset a pending device end interrupt. The condition code reported during interrupt acceptance defines the interrupt. The Teletypewriter Interface does not utilize the interrupt information byte (IIB) of the interrupt ID word. The IIB is always presented as zeros. (Refer to Chapter 7, Condition Codes and Status Information, in this manual).

CONDITION CODES REPORTED FOR AN I/O INTERRUPT

Condition Code	Meaning
0	Not reported
1	Not reported
2	Exception—reported when the Teletypewriter Adapter has completed at least one overrun receive operation. A device end interrupt may be pending, but exception interrupt takes precedence in reporting.
3	Device end—reported at completion of the execution of a Write command or completion of an IPL operation. No exception interrupt is pending at interrupt reporting time.
4	Attention—reported when the Teletypewriter Adapter has completed a normal receive operation.
5	Not reported
6	Attention and Exception—reported when the Teletypewriter Adapter has completed a normal receive operation and has completed at least one overrun receive operation.
7	Attention and Device end—reported at completion of the execution of a Write command or completion of an IPL operation and the Teletypewriter Adapter has completed a normal receive operation.

STATUS AFTER RESETS

All registers, pending interrupts and condition codes are reset by a power on reset or a system reset.

A Halt I/O command, or a Reset to Diagnostic Wrap command resets all registers except the prepare field register. Pending interrupts and condition codes are reset.

A Reset Device command resets all registers except the prepare register and the transmit data register. Pending interrupts and condition codes are reset.

Chapter 12. Integrated Digital Input/Output Non-Isolated Feature

The Integrated Digital I/O Non-Isolated feature allows the user to add digital sensor I/O or non-IBM devices. This chapter provides a functional description and programming information. For publications containing other types of information, refer to the preface of this manual.

The Integrated Digital I/O feature has the following general characteristics:

- Two 16-point groups of non-isolated digital input/process interrupt (DI/PI).
- Two 16-point groups of non-isolated digital output (DO).
- Four device addresses—one for each DI/PI or DO group. All four devices prepared for interrupts with one Prepare command.
- External synchronization for each group of DI and DO-this user attachment feature permits asynchronous data transfers.
- Interrupts can be initiated by an external sync input (one input for each DI or DO group) or by a "0" to "1" transition on a PI point.
- The Integrated Digital I/O feature is contained on one logic card and can be plugged into either the processor unit or IBM 4959 I/O Expansion Unit.
- Commands for the Integrated Digital I/O feature are compatible with the digital commands for the Sensor Input/Output Unit (except those associated with diagnostic programs). Note however, that the Sensor Input/Output Unit does not have DO external synchronization.

Figure 12-1 shows a simplified data flow for the Integrated Digital I/O feature. Refer to this figure while reading the following sections.




Figure 12-1. Digital I/O simplified data flow

DIGITAL INPUT (DI)

The Integrated Digital I/O feature has two groups of digital input/process interrupt. Each group of digital input has:

- 16 user-input points that sense the value of non-isolated voltage input.
- One 16-position DI data register for reading unlatched data.
- One 16-position PI data register for reading latched data.
- An external sync input line and a ready output line.
- Interrupt capability from either external sync or process interrupt.

Each digital input group has a unique device address and responds to specific commands. Addressing and commands are discussed in subsequent sections of this chapter. The data registers and the functions performed by DI/PI are described in the remainder of this section.

Each position of the DI data register follows the state of the corresponding user-input point until the register is read. The data in the register is held (1) during a read command or (2) when the external sync input becomes active while in external sync mode. In the second case, the data remains held until the resulting interrupt is serviced and the ready line is activated. (For additional information, see DI External Sync.)

Each position of the PI data register records, with a 1-bit, the first 0-bit to 1-bit transition on the corresponding user-input point. The data in the register remains until reset by one of the following:

- 1. Read PI with Reset command
- 2. Arm PI command
- 3. Device Reset command
- 4. System reset
- 5. Power-on reset

When a bit in the PI data register becomes active, a process interrupt is generated if PI mode was previously set with an Arm PI command. (For additional information, see *Process Interrupt*.)

A DI/PI group can be tested using two special commands: (1) Set Test Ones and (2) Set Test zeros. When the appropriate command is executed, the user inputs are disabled, either ones or zeros are placed on the input receivers, and the external sync receiver is pulsed. Then when subsequent read commands are issued, the group responds exactly as if the actual user inputs had been set, including the PI and external sync functions.

DI External Sync

The external sync capability consists of two signal lines, an input line called external sync and an output line called ready. A DI group is set to external sync mode by execution of the Arm DI External Sync command. When external sync mode is armed and the system is ready for more DI data, the ready line from the DI group is set active. The user places data on the input points, then activates the external sync line. When the external sync line becomes active, the data in the DI data register is assumed to be good and the contents of the register are held. Then an interrupt is posted, and the ready line becomes inactive and stays inactive until the appropriate command, normally Read DI, is executed. The external sync line must then perform another transition from the "0" to the "1" state to cause another interrupt.

External sync mode is reset by an Arm PI command, a Device Reset command, a Halt I/O command, or any reset condition. (See *Status after Power Transitions or Resets* in this chapter.)

Process Interrupt (PI)

A digital input group is set to PI mode using the Arm PI command. The process interrupt function is performed by logically ORing the bits in the PI data register of the DI group. That is, any bit in the register becoming active generates an interrupt.

PI mode is reset by an Arm DI External Sync command, a Device Reset Command, a Halt I/O command, or any reset condition. (See Status after Power Transitions or Resets in this chapter.)

DIGITAL OUTPUT (DO)

The Integrated Digital I/O feature has two groups of digital output. Each DO group has:

- 16 output points to the user. Each point provides a non-isolated, unipolar current switch or TTL (transistor-transistor logic) compatible output voltage.
- One 16-position DO data register.
- An external sync input line and a ready output line.
- Interrupt capability from the external sync input line.

Each digital output group has a unique device address and responds to the commands discussed later in this chapter. Data is stored into the DO data register using the Write DO command. The DO data register is reset only by a power-on reset.

A DO group can be tested using three special commands: (1) Disable DO (2) Read DO, and (3) Set Diagnostic External Sync. The Disable DO command disables the user outputs. The Read DO command reads the contents of the DO data register. The Set Diagnostic External Sync command disables the user outputs and simulates the user's external sync line.


DO External Sync

The DO external sync capability consists of two signal lines, an input line called external sync and an output line called ready. A DO group is set to external sync mode by execution of the Arm DO External Sync command. When a Write DO command is executed in external sync mode and the data on the DO output is good, an active level on the external sync input line causes the ready line to become active. The user signifies receipt of the data by deactivating the external sync line. Then an interrupt is posted, and the ready line becomes inactive. The ready line stays inactive until another Write DO Command is executed and the external sync input becomes active again. The external sync line must perform another transition from the "1" to the "0" state to cause another interrupt.

External sync mode is reset by a Device Reset command, a Halt I/O command, or any reset condition. (See Status after Power Transitions or Resets in this chapter.)

COMMANDS

The Integrated Digital I/O feature is connected to the processor through the I/O channel. Direct Program Control (DPC) commands are used for all I/O operations; that is, cycle steal mode is **not** implemented. The Operate I/O instruction (IO) is executed for each command.





*Indirect addressing bit

The Operate I/O instruction generates an effective address that points to an immediate device control block (IDCB). The IDCB contains a command field, a device address field, and an immediate data field. Refer to Chapter 7 for additional information about I/O operations.

Addressing

The Integrated Digital I/O feature has four device addresses, one for each 16-point group.






The first six (high-order) bits of the device address field of the IDCB are defined by field installable connectors on the Digital I/O feature card. The last two bits of the field define the I/O groups. Bit values of 00 and 01 in bits 14 and 15 define the DI groups and bit values of 10 and 11 define the DO groups.

Summary of Digital Input Commands


The two DI groups execute the device-directed commands shown in the following illustration.



Summary of Digital Output Commands

The two DO groups execute the device-directed commands shown in the following illustration.

IDCB (immediate device control block)



Condition Codes Reported During the Operate I/O Instruction

The following table is a summary of the condition code values that can be reported when the Operate I/O instruction is executed.

Command	Condition code values							
	CC0	CC1	CC2	CC3	CC4	CC5	CC6	CC7
00 Read DI	X	X				X		X
01 Read PI	X					\mathbf{x}		X
02 Read PI with Reset	X	\mathbf{X}				X		X
20 Read ID	X					X		X
21 Read DO	X					X		X
28 Read Status	X					X		X
48 Write DO	X	X				X		X
60 Prepare	X					X		X
68 Arm PI	\mathbf{x}	X				X		X
69 Arm DI External Sync	X	X				\mathbf{X}		X
69 Arm DO External Sync	X	X				\mathbf{x}		X
6A Set Test 0	X	X				X		X
6B Set Test 1	X	X				X		X
6B Set Diagnostic Ext Sync	X	X				X		X
6C Disable DO	X	X				X		X
6F Device Reset	X							X

Legend:

CC0 = Device not attached

CC1 = Busy

CC2 = Busy after reset

CC3 = Command reject

CC4 = Intervention required

CC5 = Interface data check


CC6 = Controller busy

CC7 = Satisfactory

DIGITAL INPUT COMMAND DESCRIPTION

Read DI

IDCB (immediate device control block)




Immediate data field	
Data from DI group	
16	31

The Read DI command transfers the 16 bits of the DI data register into the immediate data field of the IDCB. If external sync mode is armed, the ready line of the addressed DI group is activated to indicate that the system is ready for more data.

If external sync mode is armed and an interrupt is pending, condition code 1 (busy) is returned and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

Read PI

IDCB (immediate device control block)




Immediate data field	
Data from PI	
16	31

The Read PI command transfers the 16 bits of the PI data register into the immediate data field of the IDCB. The PI data register is not reset.

If condition code 5 (interface data check) is reported, the command is not executed.

Read PI with Reset

IDCB (immediate device control block)




Immediate data field	
Data from PI	
16	31


The Read PI with Reset command transfers the 16 bits o the PI data register into the immediate data field of the IDCB. At the end of the command cycle, the latched data in the PI data register is reset.

If PI mode is armed and an interrupt is pending condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

Read ID

IDCB (immediate device control block)






ID word from a DI group


The Read ID command transfers a one-word identification field, called the DI ID word, into the immediate data field of the IDCB. The hexadecimal value of the DI ID word is C010. The device identification word contains physical information about the device. This word can be used to determine the devices that are attached to the system.

If condition code 5 (interface data check) is reported, the command is not executed.

Read Status

IDCB (immediate device control block)







The Read Status Command transfers the DI status word into the immediate data field of the IDCB.


If condition code 5 (interface data check) is reported, the command is not executed.


After the Read Status Command is executed the DI status word bits in the second word of the IDCB have the following meaning:



Prepare









Execution of this command prepares the Integrated Digital I/O feature to interrupt on the level defined in the immediate data field of the IDCB. All groups of DI and DO (four device addresses) are prepared to the same level and are enabled by the same I-bit. Previous Prepare commands are overridden.

If condition code 5 (interface data check) is reported, the command is not executed.

Arm PI






Execution of this command sets the addressed digital input group to the PI mode and resets the PI register. If external sync mode was armed, it is reset.


If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

See *Process Interrupt* in this chapter for information about the use of this command.

Arm DI External Sync

IDCB (immediate device control block)






Execution of this command sets the addressed DI group to the external sync mode. If PI mode was armed, it is reset. The ready line is activated.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

See DI External Sync in this chapter for information about the use of this command.

Set Test 0

IDCB (immediate device control block)



Immediate data field	
Zeros	
16	31


The Set Test 0 command sets a diagnostic mode that disables the user inputs including external sync. The ready line is disabled. The command places zero bits on the digital input receivers and activates the external sync receiver with a pulse. If external sync is armed, an interrupt is posted.

Subsequent read commands result in all zeros from the DI data register. The data in the PI data register is governed by previous user inputs and intervening commands.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

Set Test 1

IDCB (immediate device control block)



Immediate data field	
Zeros	
16	31


The Set Test 1 command sets a diagnostic mode that disables the user inputs including external sync. The ready line is disabled. The command places one bits on the digital input receivers and activates the external sync receiver with a pulse. If external sync is armed, an interrupt is posted.


Subsequent read commands result in all one bits from the DI data register. The data in the PI data register is initially all one bits and thereafter is governed by intervening commands.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

Device Reset

IDCB (immediate device control block)






Execution of this command resets the following items for the addressed digital input group:


- 1. Any pending interrupt
- 2. Arm condition for PI mode
- 3. Arm condition for External Sync mode
- 4. Status word
- 5. PI data register
- 6. DI data register

DIGITAL OUTPUT COMMAND DESCRIPTIONS

Read ID

IDCB (immediate device control block)







ID word from a DO group


The Read ID command transfers a one-word identification field, called the DO ID word, into the immediate data field of the IDCB. The hexadecimal value of the DO ID word is C018. The device identification word contains physical information about the device. This word can be used to determine the devices that are attached to the system.

If condition code 5 (interface data check) is reported, the command is not executed.

Read DO








The Read DO command transfers the contents of the DO data register into the immediate data field of the IDCB. This command is used primarily for diagnostic purposes.

If condition code 5 (interface data check) is reported, the command is not executed.

Read Status

IDCB (immediate device control block)




Immediate data field	
Status word from DO group	
16	31

The Read Status command transfers the DO status word into the immediate data field of the IDCB.


If condition code 5 (interface data check) is reported, the command is not executed.


After the Read Status command is executed, the DO status word bits in the second word of the IDCB have the following meanings:



Write DO

IDCB (immediate device control block)







This command transfers the contents of the immediate data field of the IDCB into the DO data register. If external sync mode is armed and no interrupt is pending, the ready line for the DO group is enabled.

If an interrupt is pending or ready is active in the external sync mode, condition code 1 (busy) is reported and the command is not executed. Also, when condition code 5 (interface data check) is reported, the command is not executed.

Prepare

IDCB (immediate device control block)







Execution of this command prepares the Integrated Digital I/O feature to interrupt on the level defined in the immediate data field of the IDCB. All groups of DI and DO (four device addresses) are prepared to the same level and are enabled by the same I-bit. Previous Prepare commands are overridden.

If condition code 5 (interface data check) is reported, the command is not executed.

Arm DO External Sync

IDCB (immediate device control block)






Execution of this command sets the addressed DO group to the external sync mode.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, if condition code 5 (interface data check) is reported, this command is not executed.

Set Diagnostic External Sync

IDCB (immediate device control block)




Immediate data field	
Zeros	
16	31


Execution of this command sets a diagnostic mode that disables the user's external sync input. The ready line and the DO outputs are also disabled. The command activates external sync with a pulse on the input receiver. If external sync mode is armed a Disable DO command has been executed, and no interrupt is pending, an interrupt is posted.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, if condition code 5 (interface data check) is reported, the command is not executed.

Disable DO

IDCB (immediate device control block)







This command sets a diagnostic mode that disables the line drivers for the 16 digital outputs, the ready line, and the user's external sync input. A zero level is forced on all outputs.

If an interrupt is pending, condition code 1 (busy) is reported and the command is not executed. Also, if condition code 5 (interface data check) is reported, the command is not executed.

Device Reset

IDCB (immediate device control block)





Execution of this command resets the following items for the addressed digital output group:

- 1. Any pending interrupt
- 2. Arm condition for DO external sync
- 3. Status word
- 4. Diagnostic mode

The DO data register is not reset.

INTERRUPT PRESENTATION AND STATUS WORDS


The Integrated Digital I/O feature presents only interrupt condition code 4 (attention). Interrupts for a DI group are initiated by (1) the external sync input becoming active while in external sync mode or (2) any bit in the PI register becoming active while in PI mode. Interrupts for a DO group are initiated by the external sync input becoming inactive while in external sync mode.

Because all devices are prepared to interrupt on the same level, interrupts from more than one device are stacked. The device with the lowest device address presents its interrupt first. All other interrupts waiting in the stack at that time are cleared before the same device can present a second interrupt. That is, if devices 0, 1, and 2 have interrupts stacked, device 0 presents its interrupt first. Device 0 cannot present another interrupt until the interrupts for device 1 and device 2 have been presented.

When an interrupt is accepted by the channel, the digital group presents an interrupt ID word. This word contains an IIB (interrupt information byte) in bits 0–7 and the device address in bits 8–15. The format of the IIB for the DI groups and for the DO groups appears in the following sections. Note that the IIB presented in the interrupt ID word has the same format as the first byte of the status word transferred into the immediate data field of the IDCB when a Read Status command is executed.


DI Status Word and Interrupt ID Word


As previously stated, bits 0-7 in the DI status word have the same meaning as those in the IIB. The meanings of each bit are defined as follows:



DO Status Word and Interrupt ID Word

Bits 0—7 in the DO status word have the same meanings as those in the IIB. The meanings of each bit are defined as follows:





STATUS AFTER POWER TRANSITIONS AND RESETS

DI Resets

• Halt I/O Command or Machine Check Reset. Either of these conditions reset: (1) arm conditions for PI mode or external sync mode, (2) diagnostic mode, (3) ready lines, and (4) any pending interrupts.

The following are **not** reset:

- the prepared level and I-bit and
- PI and DI data register.
- System Reset. This condition resets: (1) arm conditions for PI mode or external sync mode, (2) diagnostic mode, (3) ready lines, (4) any pending interrupts, (5) the prepared level and I-bit, and (6) the PI and DI data registers.
- Power On Reset. This condition resets: (1) arm conditions for PI mode and external sync mode, (2) diagnostic mode, (3) ready lines, (4) any pending interrupt, (5) the prepared level and I-bit, and (6) the PI and DI data registers.

DO Resets

• Halt I/O Command or Machine Check Reset. Either of these conditions reset: (1) arm conditions for external sync mode, (2) diagnostic mode, (3) ready lines, and (4) any pending interrupts.

The following are not reset:

- the prepared level and I-bit and
- the DO data register.
- System Reset. This condition resets: (1) arm conditions for external sync mode, (2) diagnostic mode, (3) ready lines, (4) any pending interrupts, and (5) the prepared level and I-bit.


The DO data registers are not reset.

• Power On Reset. This condition resets: (1) arm conditions for external sync mode, (2) diagnostic mode, (3) ready lines, (4) any pending interrupts, (5) the prepared level and I-bit, and (6) the DO data registers.

INTRODUCTION

This chapter provides a functional description of the Battery Backup Unit. For publications containing other types of information, refer to the preface of this manual.

The IBM 4999 Battery Backup Unit (Figure 13-1) allows the processor unit to be powered and cooled from a usersupplied battery in the event of an ac power failure. Only the processor can be powered, as the primary intent is to prevent data loss in main storage. The processor unit must be configured for 100-127 volts ac (nominal). The IBM 4999 is not intended to back up the I/O expansion unit or any I/O devices. The backed-up processor unit can contain either 64K bytes ro 128K bytes of storage and can be fully populated with I/O feature cards.



BR2971

Figure 13-1. IBM M82A Battery Backup Unit

FUNCTIONAL DESCRIPTION

The IBM 4999 Battery Backup Unit is connected to the ac line voltage and to a user-supplied 12-volt type battery and a user-supplied charger unit. The processor plugs into a receptacle on the back of the IBM 4999. Normal line voltage is delivered to the processor unit unless a loss or dip in the ac voltage occurs. In this event, a dc-to-ac inverter turns on and supplies a square wave ac voltage to the processor unit (including the cooling fans). If the ac power returns before the battery capacity is exceeded, the IBM 4999 switches back to the ac line voltage.

Line Voltage Sensing

The line voltage sensing circuitry takes advantage of the energy storing capability of the power supply in the processor unit. This power supply can continue to supply adequate voltage while switching from the ac line to the inverter.

When the line voltage falls below the set point (80 volts) the sensing circuitry makes a logical (and irreversible) decision to transfer from the ac line to the battery-powered inverter. Once this decision is made, 15 milliseconds is required to complete the switch-over to the inverter. That amount of time is not enough to cause the power supply input voltage to drop below a point that would cause a self-initiated power-down sequence. Once the processor unit is on battery power, it remains so for at least one-half second.

Battery Voltage Sensing

The battery voltage is monitored continuously. If the battery voltage falls below approximately 11.2 volts, the Low Battery indicator is turned on, but no other action is taken.

During the time the inverter is on, if the battery voltage drops below approximately 10.8 volts, the inverter is turned off and the processor unit is switched back to the ac line. This occurs whether the line voltage has returned, or not returned. The condition just described is called an offline shutdown and is indicated by the Offline indicator on the front panel. After such a shutdown, the backup system is inoperative until the battery voltage recovers to approximately 12 volts and the Reset button (on the front panel) has been pressed.

CONTROLS AND INDICATORS

The controls and indicators are located on the front panel (Figure 13-2).

Utility Power Switch

When this rocker switch is placed in the On position, ac power is applied to the Battery Backup Unit and the Utility Power indicator turns on. Power is also supplied to the receptacle for the processor unit.

When the switch is placed in the Off position, ac power is removed from the Battery Backup Unit and from the receptacle for the processor unit. The Utility Power Indicator is turned off.




Figure 13-2, Controls and Indicators

Battery Circuit Breaker

The 70 ampere circuit breaker on the front panel operates automatically if excessive battery current is drawn. The circuit breaker can also be operated manually. When the circuit breaker is pushed in, the battery is connected and the Backup Power indicator is on. When the circuit breaker is pulled out, the battery is disconnected and the Backup Power indicator is off.

Reset Switch

This switch is a momentary pushbutton. Operation of the pushbutton resets the Battery Backup Unit after power is initially turned on or after an offline shutdown if the battery voltage has recovered to at least 12 volts.

Utility Power Indicator

This indicator is on when the Utility Power switch is in the On position and ac line voltage is available to the IBM 4999 Battery Backup Unit.

Backup Power Indicator

This indicator is always on when battery power is available and the Battery Circuit Breaker is engaged.

Standby Indicator

This indicator is on when the following conditions are satisfied:

- 1. The Utility Power switch is in the On position.
- 2. The processor unit power supply is on.
- 3. The ac line voltage is above the set point (80 volts).
- 4. An offline condition is not present; that is, the battery voltage has not fallen below approximately 10.8 volts.

On Battery Indicator

This indicator is on when backup power is being supplied from the battery-powered inverter. The on-battery mode occurs within 15 milliseconds after sensing a line voltage below the set point (80 volts).

While in the on-battery mode, both the ac line voltage and the battery voltage are monitored. If the battery voltage drops below approximately 11.2 volts, the Low Battery indicator is turned on, but no further action is taken. If the battery voltage falls below approximately 10.8 volts, an offline shutdown occurs.

Assuming no offline shutdown has occurred, when the ac line voltage returns to at least 100.8 volts, the Battery Backup Unit switches back to the standby mode within 15 milliseconds. Once the processor unit is on battery power, it remains so for at least one-half second.

Note. The processor unit must be initially powered from the ac line before the IBM 4999 Battery Backup Unit allows the backup mode to occur. If the line voltage is too low to permit the processor to be powered-on from the line, then it cannot be powered-on from the 4999. The line voltage can be below the set point (80 volts) but still power-on the processor. In this case, the 4999 takes over as soon as power is up and uses battery power until the line voltage exceeds 87.5 volts.

Low Battery Indicator

This indicator turns on whenever the battery voltage falls below approximately 11.2 volts. Once the Low Battery indicator is activated, it is not turned off until the battery voltage recovers to approximately 12.5 volts.

Offline Indicator

This indicator turns on when the battery voltage drops below approximately 10.8 volts.

If the Battery Backup Unit was in the on battery mode, the processor unit is switched back to the ac line. If the line voltage has not returned, the processor unit is powered down.

If the Battery Backup Unit was in standby mode, the processor unit continues operating from the ac line as long as the line is normal. If the ac line drops, the Battery Backup Unit does not transfer to the battery and the processor unit is powered down.

The offline indicator remains on until:

- 1. The battery voltage has recovered to approximately 12 volts, and
- 2. The Reset button has been pressed.

PROCESSOR POWER/THERMAL WARNING

When an ac power failure occurs, the power/thermal warning condition in the processor unit remains active as long as the processor unit is being powered by the battery. If a thermal warning occurs, the processor unit is powered down, irrespective of the battery backup system. For additional information about a power/thermal warning, refer to Class Interrupts in Chapter 3.

Appendix A. Instruction Execution Time

This appendix contains two tables:

Table 1: Instruction execution times when the Storage Address Relocation Translator feature is not installed or is disabled.

Table 2: Instruction execution times when the Storage Address Relocation Translator feature is en-

The instructions in each table are in alphabetical sequence based on assembler mnemonics. Figure A-1 is used with Table 1. Figure A-2 is used with Table 2.

Key to symbols for tables in this appendix:

IXCy to s	ymbols for tables in this appendix:
Symbol	Meaning
A	Additional time for the bit number tested (see TBTV note).
AM1	Additional time for operand 1 addressing mode (see Figure A-1 or A-2).
AM2	Additional time for operand 2 addressing mode (see Figure A-1 or A-2).
BT	Bit number of tested bit (see TBTV note).
CL	Current level.
CT	The count value at the beginning of instruction execution.
D	Additional time for the Disable instruction (see EN note).
E	Additional time for the Enable instruction (see EN note).
IP	In-process flag.
K	The bit number of the left most one bit (see SLTD note 2).
RL	Limit register (LMB and STM instructions).
RS	Additional addressing-mode time for register/storage instructions (see Figure A-1 or A-2).
SL	Selected level.
X	Additional time for addressing mode when AM = 01 (see Figure A-1 or A-2).
Y	Additional time for addressing mode when AM = 01 (see Figure A-1 or A-2).
*	Indirect address

Use this figure with Table 1.

Instructions that use addressing mode (AM) for effective address generation require additional time that must be added to the base time for execution.

RS-the additional time for register/storage instructions

AM	Time (RS)
00	220
01	440
10 RB=0	880
10 RB≠0	1100
11 RB=0	1540
11 RB≠0	2420

• AM1, AM2, X, Y-the additional time for storage/storage instructions

AM	Time (AMI)	Time (AM2)	X	Y
00	220	220	0	0
01	440	440	220	440
10 RB=0	880	880	0	0
10 RB≠0	1100	1100	0	0
11 RB=0	1540	1540	0	0
11 RB≠0	2420	2420	0	0

Example:

For an instruction time equal to 5720+(AM1+Y)+AM2 if AM1=01 and AM2=11 (RB \neq 0) then total instruction time is 5720+(440+440)+2420=9020

· Assembler syntax for address modes

Assembler Synta	x	Address Modes
addr4	addr5	(see Note 1)
(reg^{0-3})	(reg)	00
$(reg^{0-3})+$	(reg)+	01
addr	addr	10 RB=0
(reg ¹⁻³ , waddr)	(reg ¹⁻⁷ , waddr)	10 RB≠0
addr*	addr*	11 RB=0
$disp1(reg^{1-3}, disp2)*$	disp1 (reg $^{1-7}$, disp2)*)
$disp(reg^{1-3})*$	$disp(reg^{1-7})*$	11 PR-40
$(reg^{1-3})^*$	(reg ¹⁻⁷)*	> 11 RB≠0
$(reg^{1-3}, disp)*$	$(reg^{1-7}, disp)*$	<i>)</i>

Note 1. Register/storage instructions use assembler syntax addr4 for address mode (AM).

Storage/storage instructions use assembler syntax:

- (1) addr5 for address mode for operand 1 (AM1), and
- (2) addr4 for address mode for operand 2 (AM2).

Figure A-1. Additional instruction times for addressing mode when the relocation translator is not installed or is disabled.

Instructions that use addressing mode (AM) for effective address generation require additional time that must be added to the base time for execution.

• RS-the additional time for register/storage instructions

AM	Time (RS
00	440
01	660
10 RB=0	1320
10 RB≠0	1540
11 RB=0	2200
11 RB≠0	3080

 AM1, AM2, X, Y-the additional time for storage/storage instructions

AM	Time (AM1)	Time (AM2)	X	Y
00	440	440	0	0
01	660	660	220	440
10 RB=0	1320	1320	0	0
10 RB≠0	1540	1540	0	0
11 RB=0	2200	2200	0	0
11 RB≠0	3080	3080	0	0

Example:

For an instruction time equal to 6820+(AM1+Y)+AM2 if AM1=01 and AM2=11 (RB $\neq 0$) then total instruction time is 6820+(660+440) +3080=11000

• Assembler syntax for address modes

```
Assembler Syntax
                                                             Address Modes
addr4
                              addr5
                                                             (see Note 1)
(reg^{0-3})
                               (reg)
                                                             00
(reg^{0-3})+
                              (reg)+
                                                             01
addr
                              addr
                                                             10 RB=0
(reg^{1-3}, waddr)
                               (reg1-7, waddr)
                                                             10 RB≠0
addr*
                              addr*
                                                             11 RB=0
disp1(reg^{1-3}, disp2)*
                              disp1 (reg1-7, disp2)*
disp(reg^{\bar{1}-3})^*
                              disp(reg<sup>1-7</sup>)*
                                                             11 RB≠0
(reg1-3)*
                              (reg^{1-\frac{1}{7}})*
                              (reg<sup>1-7</sup>, disp)*
(reg1-3, disp)*
```

Note 1. Register/storage instructions use assembler syntax addr4 for address mode (AM).

Storage/storage instructions use assembler syntax:

- (1) addr5 for address mode for operand 1 (AM1), and
- (2) addr4 for address mode for operand 2 (AM2).

Figure A-2. Additional instruction times for addressing mode when the relocation translator is enabled.

TABLE 1. INSTRUCTION TIMES—RELOCATION TRANSLATOR NOT INSTALLED OR DISABLED

NOT INS	TALLED OR DISABLE	Ŋ	The state of the state of
	•	Contan	Execution time (nanoseconds)
Mnemonic	Instruction name	Syntax reg,addr4	2420+RS
AB	Add Byte	addr4,reg	1540+RS
ABI	Add Byte Immediate	byte,reg	1100
ACY	Add Carry Register	reg	1540
AD	Add Double Word	reg,addr4	4180+RS
		addr4,reg	3300+RS
		addr5,addr4	5720+(AM1+Y)+AM2
AW	Add Word	reg,reg	1100
		reg,addr4 addr4,reg	2420+RS 1540+RS
		addr4,reg addr5,addr4	3080+(AM1+Y)+AM2
		20010 30002 1	$R = 0$ $R \neq 0$
		longaddr,reg	2420 2420
		longaddr*,reg	2860 3080
AWCY	Add Word With Carry	reg,reg	1540
AWI	Add Word Immediate	word,reg[,reg]	1980
		word,addr4	3740+RS
В	Branch Unconditional	longaddr	1760
		longaddr*	2420
BAL	Branch and Link	longaddr,reg	1980 2640
		longaddr*,reg	2200
BALS	Branch and Link Short	(reg,jdisp)* (reg)*	2200
		addr*	2200
BALX	Branch and Link External		See BAL
Dillin			Branch
			Not taken Taken
BC	Branch on Condition	cond,longaddr	1540 1760
		cond,longaddr*	1540 2420
			Branch Not taken Taken
		11.	
BCC	Branch on Condition Code	cond,longaddr cond,longaddr*	1540 1760 1540 2420
D.CIV	Describes Course	cond,iongaddi	See BC
BCY	Branch on Carry		See BC
BE	Branch on Equal		See BNCC
BER	Branch on Error Branch on Even		See BC
BEV	Branch on Arithmetically		See BNC
BGE	Greater Than or Equal		BOO BIVO
BGT	Branch on Arithmetically		See BNC
201	Greater Than		
BLE	Branch on Arithmetically		See BC
	Less Than or Equal		
BLGE	Branch on Logically		See BNC
	Greater Than or Equal		See BNC
BLGT	Branch on Logically Greater Than		See DIVC
BLLE	Branch on Logically		See BC
DLLE	Less Than or Equal		
BLLT	Branch on Logically		See BC
	Less Than		
BLT	Branch on Arithmetically		See BC
	Less Than		

Table 1 (Part 1 of 10)

Mnemonic BMIX	Instruction name Branch if Mixed	Syntax	Execution time (nanoseconds) See BC	
BN	Branch on Negative		See BC	
	zamon on riogative		Branch	
			Not taken Taken	
BNC	Branch on Not Condition	cond,longaddr	1540 1760	
		cond,longaddr*	1540 2420	
			Branch	
DNGG	B 1 22 2		Not taken Taken	
BNCC	Branch on Not Condition Code	cond,longaddr cond,longaddr*	1540 1760	
BNCY	Branch on No Carry	cond,iongadur	1540 2420	
BNE	Branch on Not Equal		See BNC	
BNER	Branch if Not Error		See BNC See BCC	
BNEV	Branch on Not Even		See BCC See BNC	
BNMIX	Branch if Not Mixed		See BNC	
BNN	Branch on Not Negative		See BNC	
BNOFF	Branch if Not Off		See BNC	
BNON	Branch if Not On		See BNC	
			Branch	
			Not taken Taken	
BNOV	Branch on Not Overflow	longaddr	1540 1760	
		longaddr*	1540 2420	
BNP	Branch on Not Positive		See BNC	
BNZ	Branch on Not Zero		See BNC	
BOFF	Branch if Off		See BC	
BON	Branch if ON		See BC	
			Branch	
BOV	Branch on Overflow	longaddr	Not taken Taken 1540 1760	
	==	longaddr*	1540 1760	
BP	Branch on Positive	· ·	See BC	
BX	Branch External	vcon	See B	
BXS	Branch Indexed Short	(reg ¹⁻⁷ ,jdisp)	1320	
		(reg^{1-7})	1320	
D.7	D 1 7	addr	1320	
BZ CB	Branch on Zero	11.4	See BC	
	Compare Byte	addr4,reg addr5,addr4	1540+RS 2200+AM1+AM2	
CBI	Compare Byte Immediate	byte,reg	1100	
CD	Compare Double Word	addr4,reg addr5,addr4	3080+RS 4620+AM1+AM2	
CFED	Compare Byte Field Equal and Decrement	(reg),(reg)	1540+(3080 x CT)	See CFNEN note
CFEN	Compare Byte Field Equal and Increment	(reg),(reg)	1540+(3080 x CT)	See CFNEN note
CFNED	Compare Byte Field Not Equal and Decrement	(reg),(reg)	1540+(3080 x CT)	See CFNEN note
CFNEN	Compare Byte Field Not Equal and Increment	(reg),(reg)	1540+(3080 x CT)	See note
	Note. For CFED, CFEN, CFN is terminated by a comparison	ED, and CFNEN, subtraccondition.	ct 880 if the instruction	

Table 1 (Part 2 of 10)

			Execution time	
Mnemonic	Instruction name	Syntax	(nanoseconds)	
CMR	Complement Register	reg[,reg]	1320	
CPAKR	Copy Address	addr4	3080+RS	
	Key Register	reg	1760	
CPCL	Copy Current Level	reg	1540	
CPCON	Copy Console Data Buffer	reg	1540	
CPFLB	Copy Floating Level Block	reg,addr4	18260+RS	
CPIMR	Copy Interrupt Mask Register	addr4	2640+RS	
CPIPF	Copy In-Process Flags	addr4	2640+RS	
CPISK	Copy Instruction	addr4	3080+RS	
	Space Key	reg	1760	
CPLB	Copy Level Block	reg,addr4	13200+RS SL=CL 12540+RS SL≠CL	
CPLSR	Copy Level Status Register	reg	1100	
CPOOK	Copy Operand 1 Key	addr4	3080+RS	
Crook	Copy Operand 1 Key	reg	1760	
CPOTK	Copy Operand 2 Key	addr4	3080+RS	
01011		reg	1760	
CPPSR	Copy Processor Status and Reset	addr4	2640+RS	
CPSK	Copy Storage Key	reg,addr4	3740+RS	
CPSR	Copy Segmentation Register	reg,addr4	3520+RS	
CW	Compare Word	reg,reg	1100	
	-	addr4,reg	1540+RS	
		addr5,addr4	2200+(AM1+X)+AM2	
CWI	Compare Word Immediate	word,reg word,addr4	1980 3080+RS	
DB	Divide Byte	addr4,reg	24220+RS 28380+RS 32780+RS 3520+RS 5500+RS	Minimum Average Maximum Divide by zero Overflow
DD	Divide Double Word	addr4,reg	41800+RS 49940+RS 58960+RS 2420+RS 5060+RS	Minimum Average Maximum Divide by zero Overflow
DIAG	Diagnose	ubyte	See chart	
	If instruction bit 13 is on:		<i>Time</i> 1760	
	If instruction bit 13 is off, che bits as follows:	ck other		
	8 9 12 14	15		
	0 X 0 0	0	3520	
	0 X 0 0	1	5060	
	0 X 0 1	0	3300	
	0 X 0 1	1	4840	
	0 X 1 0	0	3300 4620	
	$egin{array}{cccccccccccccccccccccccccccccccccccc$	1 0	3080	
	0 X 1 1	1	4400	
	1 0 0 X	X	3300	
	1 0 1 X	X	3740	
	1 1 X X	X	2200	
	Note. X can be either 0 or 1.			

Table 1 (Part 3 of 10)

							Execution time	
Mnemonic	Instruct	ion nar	ne		S	yntax	(nanoseconds)	
DIS	Disable				u	by te	1760+D	See EN note
DW	Divide V	Vord			a	ddr4,reg	22220+RS 26400+RS 31900+RS 2420+RS 4400+RS	Minimum Average Maximum Divide by zero Overflow
EN	Enable				u u	by te	1760+E	See note
							lues of D and	
	E are ba	sed on	instruc	ction-w	ord bits	s 12–15.		
	12	13	14	15	D	\boldsymbol{E}		
	0	0	0	0	0	0		
	0	0	0	1	220	0		
	0 0	0 0	1 1	0 1	220 440	220 220		
	0	1	0	0	440	220		
	Õ	1	Õ	1	660	220		
	0	1	1	0	660	440		
	0	1	1	1	880	440		
	1	0	0	0	220	0		
	1 1	0 0	$0 \\ 1$	1 0	440 440	0 0		
	î	0	1	1	660	0		
	1	1	0	0	660	220		
	1	1	0	1	880	220		
	1	1	1	0	880	220		
T) A	1	1	1	1	1100	220	10100.70	
FA	Floating	, Add			ac	ldr4,freg	10120+RS 25740+RS	Minimum Maximum
					fr	eg,freg	8360	Minimum
							23980	Maximum
FAD	Floating	Add D	ouble		ac	idr4,freg	11440+RS	Minimum
							49060+RS	Maximum
					fr	eg,freg	8580	Minimum
FC	Til o o tim o	. C			c	6	47080	Maximum
FC	Floating	Comp	are		11	eg,freg	7700 22660	Minimum Maximum
FCD	Floating	Comp	are Do	uble	fr	eg,freg	7920	Minimum
	11044416	, comp	20	4010		05,1105	42680	Maximum
FD	Floating	Divide	:		a	ddr4,freg	28160+RS	Minimum
							34540+RS	Maximum
					fı	eg,freg	26180	Minimum
EDD				_			31240	Maximum
FDD	Floating	g Divide	Doub	le	a	ddr4,freg	53240+RS	Minimum
					fi	eg,freg	66660+RS 50160	Maximum Minimum
						05,1105	62260	Maximum
FFD	Fill Byte	e Field	and		re	eg,(reg)	1540+(1980 x CT)	
	Decreme	ent						
FFN	Fill Byte		and		re	eg,(reg)	1540+(1980 x CT)	
	Increme							
FM	Floating	, Multip	oly		a	ddr4,freg	19360+RS	Minimum
					£.	og free	22220+RS 16500	Maximum Minimum
					11	eg,freg	19140	Minimum Maximum
FMD	Floating	Multir	ılv		a.	ddr4,freg	23760+RS	Minimum
	Double	, <u></u>			a		30140+RS	Maximum
					f	eg,freg	20240	Minimum
							26400	Maximum

Table 1 (Part 4 of 10)

16	To a description of the second	g	Execution to		
Mnemonic	Instruction name	Syntax	(nanosecono	(S)	
FMV	Floating Move	addr4,freg	6380+RS		
		freg,freg	4400		
		freg,addr4	6380+RS		
FMVC	Floating Move and Convert	addr4,freg	12100+RS 16940+RS		Minimum Maximum
		freg,addr4	8360+RS 17380+RS		Minimum Maximum
FMVCD	Floating Move and Convert Double	addr4,freg	12100+RS 28160+RS		Minimum Maximum
		freg,addr4	11220+RS 30800+RS		Minimum Maximum
FMVD	Floating Move Double	addr4,freg	7480+RS		
		freg,freg	5500		
		freg,addr4	8360+RS		
FS	Floating Subtract	addr4,freg	10120+RS		Minimum
1.2	Floating Subtract		25740+RS		Maximum
		freg,freg	8360 23980		Minimum Maximum
FSD	Floating Subtract Double	addr4,freg	11440+RS		Minimum
			49060+RS		Maximum
		freg,freg	8580		Minimum
			47080		Maximum
			R = 0	$R \neq 0$	
IO	Operate I/O	longaddr	4400	4400	See note
	1	longaddr*	4840	5060	See note
	Note. Channel and device times	, and the second	1760)		
IOPK	Interchange Operand Keys	must be udded (typically	1760).		
IR	Interchange Registers	reg,reg	1320		
J	Jump Unconditional	jdisp jaddr	880 880		
JAL	Jump and Link	jdisp,reg jaddr,reg	1320 1320		
		Judur,reg	Jump		
			Not taken	Taken	
JC	Jump on Condition	cond,jdisp	1100	1320	
		cond,jaddr	1100	1320	
			CT=0	CT=1	CT > 1
JCT	Jump on Count	jdisp,reg	1540	1760	1980
		jaddr,reg	1540	1760	1980
JCY	Jump on Carry		See JC		
JE	Jump on Equal		See JC		
JEV	Jump on Even		See JC		
JGE	Jump on Arithmetically Greater Than or Equal		See JNC		
JGT	Jump on Arithmetically Greater Than		See JNC		
JLE	Jump on Arithmetically Less Than or Equal		See JC		
JLGE	Jump on Logically Greater Than or Equal		See JNC		
JLGT	Jump on Logically Greater Than		See JNC		
JLLE .	Jump on Logically Less Than or Equal		See JC		
JLLT	Jump on Logically Less Than		See JC		

Table 1 (Part 5 of 10)

			Execution time		
Mnemonic	Instruction name	Syntax	(nanoseconds)		
JLT	Jump on Arithmetically Less Than		See JC		
JMIX	Jump if Mixed		See JC		
JN	Jump on Negative		See JC		
			Jump		
		•	Not taken Taken		
JNC	Jump on Not Condition	cond,jdisp	1100 1320		
JNCY	Towns on No Co.	cond,jaddr	1100 1320		
	Jump on No Carry		See JNC		
JNE	Jump on Not Equal		See JNC		
JNEV	Jump on Not Even		See JNC		
JNMIX	Jump if Not Mixed		See JNC		
JNN	Jump on Not Negative		See J NC		
JNOFF	Jump if Not Off		See JNC		
JNON	Jump if Not On		See JNC		
JNP	Jump on Not Positive		See JNC		
JNZ	Jump on Not Zero		See JNC		
JOFF	Jump if Off		See JC		
JON	Jump if On		See JC		
JP	Jump on Positive		See JC		
JZ	Jump on Zero		See JC		
LEX	Level Exit	[ubyte]	2860		
LMB	Load Multiple and Branch	addr4	7700+RS RL=7 8580+(660xRL)+RS RL#7		
MB	Multiply Byte	addr4,reg	10340+RS 16940+RS 23320+RS	Minimum Average Maximum	
MD	Multiply Doubleword	addr4,reg	10780+RS 26400+RS	Minimum Average	
M37.4	Mana Adduses	114	41800+RS	Maximum	
MVA	Move Address	addr4,reg addr,addr4	2200+RS 3520+RS		
MVB	Move Byte	reg,addr4	2200+RS		
		addr4,reg	1760+RS		
MATTER	W . D . T	addr5,addr4	2860+AM1+AM2		
MVBI	Move Byte Immediate	byte,reg	880		
MVBZ	Move Byte and Zero	addr4,reg	2640+RS		
MVD	Move Doubleword	reg,addr4	3300+RS		
		addr4,reg addr5,addr4	2420+RS 4620+AM1+AM2		
MVDZ	Move Doubleword and Zero	addr4,reg	3740+RS		
MVFD	Move Byte Field and Decrement	(reg),(reg)	1540+(2200 x CT)		
MVFN	Move Byte Field and Increment	(reg),(reg)	1540+(2200 x CT)		
MVW	Move Word	reg,reg	1100		
		reg,addr4	2200+RS		
		addr4,reg	1540+RS		
		addr5,addr4	2860+(AM1+X)+AM2		
			$R = 0$ $R \neq 0$		
		reg,longaddr	2640 2640		
		reg,longaddr* longaddr,reg	3080 3300 2420 2420		
		longaddr*,reg	2860 3080		
			_555		

Table 1 (Part 6 of 10)

			Execution time	
Mnemonic	Instruction name	Syntax	(nanoseconds)	
MVWI	Move Word Immediate	word,reg	2200	
		word,addr4	3520+RS	
MVWS	Move Word Short	reg,shortaddr	2640	
		reg,shortaddr* shortaddr,reg	3520 2420	
		shortaddr*,reg	3080	
MVWZ	Move Word and Zero	addr4,reg	2420+RS	
MW	Multiply Word	addr4,reg	9460+RS	Minimum
			16060+RS	Average
			22440+RS	Maximum
NOP	No Operation		880	
NWI	And Word Immediate	word,reg[,reg]	1980	
OB	OR Byte	reg,addr4	2420+RS	
		addr4,reg addr5,addr4	1540+RS	
OD	OR Doubleword	reg,addr4	3080+AM1+AM2 4180+RS	
OD	OK Doubleword	addr4,reg	3300+RS	
		addr5,addr4	5500+AM1+AM2	
OW	OR Word	reg,reg	1100	
		reg,addr4	2420+RS	
		addr4,reg	1540+RS	
		addr5,addr4	3080+(AM1+X)+AM2	
		144	$R = 0 \qquad \qquad R \neq 0$	
		longaddr,reg longaddr*,reg	2420 2420 2860 3080	
OWI	OR Word Immediate	word,reg[,reg]	1980	
3 2		word,addr4	3520+RS	
PB	Pop Byte	addr4,reg	5720+RS	
PD	Pop Doubleword	addr4,reg	5940+RS	
PSB	Push Byte	reg,addr4	5500+RS	
PSD	Push Doubleword	reg,addr4	5940+RS	
PSW	Push Word	reg,addr4	5060+RS	
PW	Pop Word	addr4,reg	5280+RS	
RBTB	Reset Bits Byte	reg,addr4	2420+RS	
		addr4,reg	1540+RS	
DDTD	Deart Dite Devillered	addr5,addr4	3080+AM1+AM2	
RBTD	Reset Bits Doubleword	reg,addr4 addr4,reg	4180+RS 3300+RS	
		addr5,addr4	5500+AM1+AM2	
RBTW	Reset Bits Word	reg,reg	1100	
		reg,addr4	2420+RS	
		addr4,reg	1540+RS	
		addr5,addr4	3080+(AM1+X)+AM2	
		1	$R = 0 \qquad \qquad R \neq 0$	
		longaddr,reg longaddr*,reg	2420 2420 2860 3080	
RBTWI	Reset Bits Word	word,reg[,reg]	1980	
··-	Immediate	word,addr4	3520+RS	
SB	Subtract Byte	reg,addr4	2420+RS	
•		addr4,reg	1540+RS	
SCY	Subtract Carry Indicator	reg	1540	
SD	Subtract Doubleword	reg,addr4	4180+RS	
		addr4,reg addr5,addr4	3300+RS 5720+(AM1+Y)+AM2	
		addio,addiT	JIZU (AMII I JTAMIZ	

Table 1 (Part 7 of 10)

Mnemonic	Instruction name	G	Execution time	
SEAKR	Set Address Key	<i>Syntax</i> addr4	(nanoseconds) 2420+RS	
JL/IIII	Register	reg	2420+KS 2200	
SECON	Set Console Data Lights	reg	1540	
SEFLB	Set Floating Level Block	reg,addr4	14740+RS	
SEIMR	Set Interrupt Mask Register	addr4	2420+RS	
SEIND	Set Indicators	reg	2420	
SEISK	Set instruction Space Key	addr4 reg	2420+RS 2200	
SELB	Set Level Block	reg,addr4	11220 IP off and SL <ci 10780="" 12320="" and="" ip="" off="" sl="">CI 11220 IP on and SL<ci 11440="" 12100="" and="" ip="" on="" sl="">CI</ci></ci>	L L
	Note. IP = in process flag; SL =	selected level; CL = curi		
SEOOK	Set Operand 1 Key	addr4	2420+RS	
		reg	2200	
SEOTK	Set Operand 2 Key	addr4	2420+RS	
anar	a . a	reg	2200	
SESK	Set Storage Key	reg,addr4	3960+RS	
SESR	Set Segmentation Register	reg,addr4	2860+RS	
SFED	Scan Byte Field Equal and Decrement	reg,(reg)	1540+(2680 x CT)	See SFNEN note
SFEN	Scan Byte Field Equal and Increment	reg,(reg)	1540+(2680 x CT)	See SFNEN note
SFNED	Scan Byte Field Not Equal and Decrement	reg,(reg)	1540+(2680 x CT)	See SFNEN note
SFNEN	Scan Byte Field Not Equal and Increment	reg,(reg)	1540+(2680 x CT)	See note
	Note. For SFED, SFEN, SFNE instruction is terminated by a co		880 if the	
SLC	Shift Left Circular	cnt16,reg	1980 1980+110 x (CT+1)	Zero count
			1980+110 x (CT+1) 1980+110 x (CT)	Odd count Even count
		reg,reg	1760	Zero count
			1760+110 x (CT+1) 1760+110 x (CT)	Odd count Even count
SLCD	Shift Left Circular	cnt31,reg	2640	Zero count
	Double	,0	2640+110 x (CT+1)	Odd count
			2640+110 x (CT)	Even count
		reg,reg	2200	Zero count
			2200+110 x (CT+1) 2200+110 x (CT)	Odd count Even count
SLL	Shift Left Logical	cnt16,reg	2200	Zero count
			2200+110 x (CT+1)	Odd count
		***	2200+110 x (CT)	Even count
		reg,reg	1980 1980+110 x (CT+1)	Zero count Odd count
			1980+110 x (CT)	Even count
SLLD	Shift Left Logical	cnt31,reg	2860	Zero count
	Double	•	2860+110 x (CT+1)	Odd count
		#0.0 #0.0	2860+110 x (CT)	Even count
		reg,reg	2420 2420+110 x (CT+1)	Zero count Odd count
			2420+110 x (CT+1) 2420+110 x (CT)	Even count

Table 1 (Part 8 of 10)

Marin ania	T		Sum to a	Execution ti		
Mnemonic		action name	Syntax	2860+660 x		See SLTD note (1)
SLT	Shift	Left and Test	reg,reg	2860+660 x 3960+660 x		See SLTD note (1)
				2640	· K	See SLTD note (2)
SLTD	Shift	Left and Test	reg,reg	3080+660 x	СТ	See note (1)
SLID	Doub		105,105	4180+660 x		See note (2)
	Бойо	10		2860		See note (3)
	Notes	7				
	(1)	The shift count goes to ze	ro before a shifted bit is	s set into		
	(-)	the carry indicator.				
	(2)	A shifted bit is set into the	-			
		count goes to zero. $K = b$		ne bit.		
	(3)	The initial operand is zero		1000		.
SRA	Shift	Right Arithmetic	cnt16,reg	1980	(CT 11)	Zero count
				1980+110 x 1980+110 x		Odd count Even count
			reg,reg	1760	(C1)	Zero count
			108,108	1760+110 x	(CT+1)	Odd count
				1760+110 x		Even count
SRAD	Shift	Right Arithmetic	cnt31,reg	2640		Zero count
	Doub	_		2640+110 x	(CT+1)	Odd count
				2640+110 x	(CT)	Even count
			reg,reg	2200	(C/T) 1)	Zero count
				2200+110 x 2200+110 x		Odd count Even count
CDI	G1. : C1	D:-1-4 T:1	and16 man	1980	(C1)	Zero count
SRL	Sniit	Right Logical	cnt16,reg	1980+110 x	(CT+1)	Odd count
				1980+110 x		Even count
			reg,reg	1760		Zero count
			-	1760+110 x	(CT+1)	Odd count
				1760+110 x	(CT)	Even count
SRLD		Right Logical	cnt31,reg	2640		Zero count
	Doub	ole		2640+110 x	-	Odd count
			**************************************	2640+110 x 2200	(C1)	Even count Zero count
			reg,reg	2200+110 x	(CT+1)	Odd count
				2200+110 x		Even count
STM	Store	Multiple	reg,addr4[,abcnt]	9900+RS F	RL=7	
		•		10780+(880	xRL)+RS R	L 7
STOP	Stop		[ubyte]	1540		
SVC	Supe	rvisor Call	ubyte	14300		
SW	Subt	ract Word	reg,reg	1100		
			reg,addr4	2420+RS		
			addr4,reg	1540+RS		
			addr5,addr4	3080+(AM1		
				R = 0	$R \neq 0$	
			longaddr,reg	2420	2420	
awa:	0.1.		longaddr*,reg	2860	3080	
SWCY		ract Word With Carry	reg,reg	1540		
SWI	Subt	ract Word Immediate	word,addr4 word,reg[,reg]	3520+RS 1980		
ГВТ	Test	Ri+	(reg,bitdisp)	4400+A		See TBTV note
TBTR		Bit and Reset	(reg,bitdisp)	5060+A		See TBTV note
TBTS		Bit and Set On	(reg,bitdisp)	5060+A		See TBTV note
TBTV		Bit and Invert	(reg,bitdisp)	5060+A		See note
1014	1021	mand mivert	(10B) ottuisp)	5000 · A		200
T-11- 1 (D)		2.10)				

Table 1 (Part 9 of 10)

Mnemonic	Instruction name	Syntax	Execution to					
	Note. For TBT, TBTR, TBTS, a	Note. For TBT, TBTS, and TBTV:						
	A = 0 if BT is zero. $A = 110 \times BT$ if BT is even. $A = 110 \times (BT+1)$ if BT is odd.							
	BT = bit number of tested bit (ra	nge 0-7).						
TWI	Test Word Under Mask Immediate	word,reg	2420 2640		All bits = 0 All bits $\neq 0$			
		word,addr4	3080+RS 3300+RS		All bits = 0 Any bits $\neq 0$			
VR	Invert Register	reg[,reg]	1320					
XB	Exclusive OR Byte	reg,addr4 addr4,reg	2420+RS 1540+RS					
XD	Exclusive OR Doubleword	reg,addr4 addr4,reg	4180+RS 3300+RS					
XW	Exclusive OR Word	reg,reg reg,addr4 addr4,reg	1100 2420+RS 1540+RS					
		, 0	R = 0	$R \neq 0$				
		longaddr,reg longaddr*,reg	2420 2860	2420 3080				
XWI	Exclusive OR Word Immediate	word,reg[,reg]	1980					

Table 1 (Part 10 of 10)

TABLE 2. INSTRUCTION TIMES-RELOCATION TRANSLATOR ENABLED

Execution time

Mnemonic	Instruction name	Syntax	(nanosecono	ls)
AB	Add Byte	reg,addr4	2860+RS	
		addr4,reg	1760+RS	
ABI	Add Byte Immediate	byte,reg	1320	
ACY	Add Carry Register	reg	1760	
AD	Add Double Word	reg,addr4	5060+RS	
		addr4,reg	3740+RS	
		addr5,addr4	6820+(AM1	+Y)+AM2
AW	Add Word	reg,reg	1320	
		reg,addr4	2860+RS	
		addr4,reg addr5,addr4	1760+RS 3520+(AM1	+V)+ \M2
		audio,audi+	R = 0	$R \neq 0$
		longaddr,reg	3080	3080
		longaddr*,reg	3740	3960
AWCY	Add Word With Carry	reg,reg	1760	
AWI	Add Word Immediate	word,reg[,reg]	2420	
		word,addr4	4400+RS	
В	Branch Unconditional	longaddr	2200	
		longaddr*	3080	
BAL	Branch and Link	longaddr,reg	2420	
		longaddr*,reg	3300	
BALS	Branch and Link Short	(reg,jdisp)*	2640	
		(reg)*	2640	
		addr*	2640	
BALX	Branch and Link External		See BAL	
			Branch	T-1
	.		Not taken	Taken
BC	Branch on Condition	cond,longaddr cond,longaddr*	1980 1980	2200 3080
		cond,iongaddr*	1980	2080

Table 2 (Part 1 of 10)

Mnemonic	Instruction name	Syntax	Execution (
			Branch Not taken	Taken
BCC	Branch on Condition Code	cond,longaddr cond,longaddr*	1980 1980	2200 3080
BCY	Branch on Carry	, 0	See BC	
BE	Branch on Equal		See BC	
BER	Branch on Error		See BNCC	
BEV	Branch on Even		See BC	
BGE	Branch on Arithmetically Greater Than or Equal		See BNC	
BGT	Branch on Arithmetically Greater Than		See BNC	
BLE	Branch on Arithmetically Less Than or Equal		See BC	
BLGE	Branch on Logically Greater Than or Equal		See BNC	
BLGT	Branch on Logically Greater Than		See BNC	
BLLE	Branch on Logically Less Than or Equal		See BC	
BLLT	Branch on Logically Less Than		See BC	
BLT	Branch on Arithmetically Less Than		See BC	
BMIX	Branch if Mixed		See BC	
BN	Branch on Negative		See BC	
			Branch	<i>a</i> . 1
BNC	Branch on Not Condition	aand langaddu	Not taken 1980	Taken 2200
BNC	Branch on Not Condition	cond,longaddr cond,longaddr*	1980	3080
			Branch	
			Not taken	Taken
BNCC	Branch on Not Condition	cond,longaddr	1980	2200
	Code	cond,longaddr*	1980	3080
BNCY	Branch on No Carry		See BNC	
BNE	Branch on Not Equal		See BNC	
BNER	Branch if Not Error		See BCC	
BNEV	Branch on Not Even		See BNC	
BNMIX	Branch if Not Mixed		See BNC	
BNN	Branch on Not Negative		See BNC See BNC	
BNOFF BNON	Branch if Not Off Branch if Not On		See BNC	
DIVOIN	Branch ii Not On		Branch	
			Not taken	Taken
BNOV	Branch on Not Overflow	longaddr	1980	2200
		longaddr*	1980	3080
BNP	Branch on Not Positive		See BNC	
BNZ	Branch on Not Zero		See BNC	
BOFF	Branch if Off		See BC	
BON	Branch if ON		See BC	
			Branch Not taken	Taken
BOV	Branch on Overflow	longaddr longaddr*	1980 1980	2200 3080
BP	Branch on Positive		See BC	
BX	Branch External	vcon	See B	
Table 2 (Pa	rt 2 of 10)			

A-14 GA34-0021

			Execution time	
Mnemonic	Instruction name	Syntax	(nanoseconds)	
BXS	Branch Indexed Short	(reg ¹⁻⁷ ,jdisp)	1540	
		(reg^{1-7})	1540	
D.77	D 1 7	addr	1540	
BZ	Branch on Zero		See BC	
СВ	Compare Byte	addr4,reg addr5,addr4	1760+RS 2420+AM1+AM2	
CBI	Compare Byte Immediate	byte,reg	1320	
CD	Compare Double Word	addr4,reg addr5,addr4	3520+RS 5280+AM1+AM2	
CFED	Compare Byte Field Equal and Decrement	(reg),(reg)	1760+(3520 x CT)	See CFNEN note
CFEN	Compare Byte Field Equal and Increment	(reg),(reg)	1760+(3520 x CT)	See CFNEN note
CFNED	Compare Byte Field Not Equal and Decrement	(reg),(reg)	1760+(3520 x CT)	See CFNEN note
CFNEN	Compare Byte Field Not Equal and Increment	(reg),(reg)	1760+(3520 x CT)	See note
	Note. For CFED, CFEN, CFNE is terminated by a comparison co	D, and CFNEN, subtraction	t 880 if the instruction	
CMR	Complement Register	reg[,reg]	1540	
CPAKR	Copy Address	addr4	3300+RS	
	Key Register	reg	1980	
CPCL	Copy Current Level	reg	1760	
CPCON	Copy Console Data Buffer	reg,addr4	1760	
CPFLB	Copy Floating Level Block	reg	21780+RS	
CPIMR	Copy Interrupt Mask Register	addr4	2860+RS	
CPIPF	Copy In-Process Flags	addr4	2860+RS	
CPISK	Copy Instruction Space Key	addr4 reg	3300+RS 1980	
CPLB	Copy Level Block	reg,addr4	15620+RS SL=CL 14960+RS SL+CL	
CPLSR	Copy Level Status Register	reg	1320	
CPOOK	Copy Operand 1 Key	addr4	3300+RS	
~~~~~~		reg	1980	
CPOTK	Copy Operand 2 Key	addr4	3300+RS	
CPPSR	Copy Processor Status	reg addr4	1980 2860+RS	
	and Reset			
CPSK	Copy Storage Key	reg,addr4	4180+RS	
CPSR	Copy Segmentation Register	reg,addr4	3960+RS	
CW	Compare Word	reg,reg	1320	
		addr4,reg addr5,addr4	1760+RS 2420+(AM1+X)+AM2	
CWI	Compare Word Immediate	word,reg word,addr4	2420 3520+RS	
DB	Divide Byte	addr4.reg	24440+RS	Minimum
DD	Divide By te	audi+,ieg	28600+RS	Average
			33000+RS	Maximum
			3740+RS	Divide by zero
			5720+RS	Overflow
DD	Divide Double Word	addr4,reg	42020+RS	Minimum
			50160+RS 59180+RS	Average Maximum
			2640+RS	Maximum Divide by zero
			5280+RS	Overflow

Table 2 (Part 3 of 10)

							Execution time	
Mnemonic	Instruct	tion na	me		$S_{\mathcal{I}}$	vntax	(nanoseconds)	
DIAG	Diagnos	se			ul	oy te	See chart	
							Time	
	If instru	iction l	bit 13 i	s on:			1980	
	If instru bits as f			s off, c	heck otl	ner		
	8	9	12	14	15			
	0	X	0	0	0		5280	
	0	X	0	0	1		5500	
	0	X	0	1	0		3740	
	0	X	0	1	1		5060	
	0	X	1	0	0		3740	
	0 0	X X	1 1	0 1	1 0		4840 3520	
	0	X	1	1	1		4620	
	1	0	Ô	X	X		3960	
	1	0	1	X	X		4400	
	1	1	X	X	X		2420	
	Note.	X can b	e eithe	r 0 or	1.			
DIS	Disable				uł	y te	1760+D	See EN note
DW	Divide V	Word			ac	ldr4,reg	22440+RS	Minimum
							26620+RS	Average
							32120+RS	Maximum
							2640+RS	Divide by zero
							4620+RS	Overflow
EN	Enable					by te	1760+E	See note
						ons, the values 12–15.	s of D and	
	12	asea on 13	1118true 14	211011-w 15	vora bits D	E 12–13.		
	0	0	0	0	0	0		
	0	0	0	1	220	0		
	0	0	1	0	220	220		
	0	0	1	1	440	220		
	0	1	0	0	440	220		
	0	1	0	1	660	220		
	0	1	1	0	660	440		
	0 1	1 0	1 0	1 0	880 220	440 0		
	1	0	0	1	440	0		
	1	0	1	0	440	ő		
	1	0	1	1	660	0		
	1	1	0	0	660	220		
	1	1	0	1	880	220		
	1	1	1	0	880	220		
	1	1	1	1	1100	220	10500.75	
F <b>A</b>	Floatin	g Add			ac	ldr4,freg	10780+RS 26400+RS	Minimum Maximum
					fr	eg,freg	8580	Minimum
						05,1105	24200	Maximum
FAD	Floatin	g Add l	Double		ac	ldr4,freg	12540+RS	Minimum
		0					50160+RS	Maximum
					fr	eg,freg	8800	Minimum
							47300	Maximum
FC	Floatin	g Comp	pare		fr	eg,freg	7920	Minimum
							22880	Maximum
FCD	Floatin	g Comp	pare Do	ouble	fr	eg,freg,	8140	Minimum
							42900	Maximum

Table 2 (Part 4 of 10)

			Europetion		
Mnemonic	Instruction name	Syntax	Execution t (nanosecond		
FD	Floating Divide	addr4,freg	28820+RS 35200+RS	,	Minimum Maximum
		freg,freg	26180 31460		Minimum Maximum
FDD	Floating Divide Double	addr4,freg	54180+RS 67760+RS		Minimum Maximum
		freg,freg	50380 62480		Minimum Maximum
FFD	Fill Byte Field and Decrement	reg,(reg)	1760+(2200	x CT)	
FFN	Fill Byte Field and Increment	reg,(reg)	1760+(2200	x CT)	
FM	Floating Multiply	addr4,freg	20020+RS 22880+RS		Minimum Maximum
		freg,freg	16720 19360		Minimum Maximum
FMD	Floating Multiply Double	addr4,freg	24860+RS 31240+RS		Minimum Maximum
FD 414		freg,freg	20460 26460		Minimum Maximum
FMV	Floating Move	addr4,freg	7040+RS		
		freg,freg freg,addr4	4620 7040+RS		
FMVC	Floating Move and	addr4,freg	12540+RS		Minimum
	Convert	freg,addr4	17380+RS 8800+RS 17820+RS		Maximum Minimum Maximum
FMVCD	Floating Move and Convert Double	addr4,freg	12760+RS 28820+RS		Minimum Maximum
		freg,addr4	11880+RS 31460+RS		Minimum Maximum
FMVD	Floating Move Double	addr4,freg	8580+RS		
		freg,freg freg,addr4	5720 9460+RS		
FS	Floating Subtract	addr4,freg	10780+RS 26400+RS		Minimum Maximum
		freg,freg	8580 24200		Minimum Maximum
FSD	Floating Subtract Double	addr4,freg	12540+RS 50160+RS		Minimum Maximum
		freg,freg	8800 47300		Minimum Maximum
			R = 0	$R \neq 0$	
Ю	Operate I/O	longaddr longaddr*	5280 5940	5280 6160	See note See note
	Note. Channel and device times	must be added (typically	1760).		
IOPK	Interchange Operand Keys		1980		
IR	Interchange Registers	reg,reg	1540		
J	Jump Unconditional	jdisp jaddr	1100 1100		
JAL	Jump and Link	jdisp,reg jaddr,reg	1540 1540		
		jauui,iog	Jump	m.i.	
IC	I Co. 41/	4 1 41	Not taken	Taken	
JC	Jump on Condition	cond,jdisp cond,jaddr	1320 1320	1540 1540	

Table 2 (Part 5 of 10)

Mnemonic	Instruction name	Syntax	Execution time (nanoseconds)		
miemome	marketton name	Symax	CT=0	CT=1	CT> 1
JCT	Jump on Count	jdisp,reg	1760	1980	2200
JC1	Jump on Count	jaddr,reg	1760	1980	2200
JCY	Jump on Carry	, , ,	See JC		
JE	Jump on Equal		See JC		
JEV	Jump on Even		See JC		
JGE	Jump on Arithmetically		See JNC		
	Greater Than or Equal				
JGT	Jump on Arithmetically Greater Than		See JNC		
JLE	Jump on Arithmetically Less Than or Equal		See JC		
JLGE	Jump on Logically Greater Than or Equal		See JNC		
JLGT	Jump on Logically Greater Than		See JNC		
JLLE	Jump on Logically Less Than or Equal		See JC		
JLLT	Jump on Logically Less Than		See JC		
JLT	Jump on Arithmetically Less Than		See JC		
JMIX	Jump if Mixed		See JC		
JN	Jump on Negative		See JC		
			Jump		
			Not taken	Taken	
JNC	Jump on Not Condition	cond,jdisp cond,jaddr	1320 1320	1540 1540	
JNCY	Jump on No Carry		See JNC		
JNE	Jump on Not Equal		See JNC		
JNEV	Jump on Not Even		See JNC		
JNMIX	Jump if Not Mixed		See JNC		
JNN	Jump on Not Negative		See J NC		
JNOFF	Jump if Not Off		See JNC		
JNON	Jump if Not On		See JNC		
JNP	Jump on Not Positive		See JNC		
JNZ	Jump on Not Zero		See JNC		
JOFF	Jump if Off		See JC		
JON	Jump if On		See JC See JC		
JP	Jump on Positive		See JC See JC		
JZ	Jump on Zero Level Exit	[ubuto]	3080		
LEX		[ubyte] addr4	8800+RS	DI -7	
LMB	Load Multiple and Branch		9900+(880	x RL)+RS I	
MB	Multiply Byte	addr4,reg	10560+RS 17160+RS 23540+RS		Minimum Average Maximum
MD	Multiply Doubleword	addr4,reg	11000+RS 26620+RS 42020+RS		Minimum Average Maximum
MVA	Move Address	addr4,reg addr,addr4	2200+RS 3960+RS		
MVB	Move Byte	reg,addr4 addr4,reg addr5,addr4	2640+RS 1980+RS 3300+AM1	+ <b>AM</b> 2	

Table 2 (Part 6 of 10)

16	<b>.</b>	_	Execution time		
Mnemonic	Instruction name	Syntax	(nanoseconds)		
MVBI	Move Byte Immediate	byte,reg	1100		
MVBZ	Move Byte and Zero	addr4,reg	3080+RS		
MVD	Move Doubleword	reg,addr4	3960+RS		
		addr4,reg	2860		
MVDZ	Move Doubleword and	addr5,addr4	5500+AM1+AM2		
	Zero	addr4,reg	4620+RS		
MVFD	Move Byte Field and Decrement	(reg),(reg)	1760+(2640 x CT)		
MVFN	Move Byte Field and Increment	(reg),(reg)	1760+(2640 x CT)		
MVW	Move Word	reg,reg	1320		
		reg,addr4	2640+RS		
		addr4,reg	1760+RS		
	•	addr5,addr4	3300+(AM1+X)+AM2		
			$R = 0$ $R \neq 0$		
		reg,longaddr	3300 3300		
		reg,longaddr*	3960 4180		
		longaddr,reg	3080 3080		
		longaddr*,reg	3740 3960		
MVWI	Move Word Immediate	word,reg word,addr4	2200 3960+RS		
MVWS	Move Word Short	reg,shortaddr	3080		
		reg,shortaddr*	4180		
		shortaddr,reg	2860		
MVWZ	Maria Wand and Zana	shortaddr*,reg	3740		
	Move Word and Zero	addr4,reg	2860+RS		
MW	Multiply Word	addr4,reg	9680+RS 16280+RS 22660+RS	Minimum Average Maximum	
NOP	No Operation		1100	Maximum	
NWI	And Word Immediate	word,reg[,reg]	2420		
OB	OR Byte	reg,addr4			
OB	OR Byte	addr4,reg	2860+RS 1760+RS		
		addr5,addr4	3520+AM1+AM2		
OD	OR Doubleword	reg,addr4	5060+RS		
		addr4,reg	3740+RS		
		addr5,addr4	6600+AM1+AM2		
OW	OR Word	reg,reg	1320		
		reg,addr4	2860+RS		
		addr4,reg	1760+RS		
		addr5,addr4	3520+(AM1+X)+AM2		
			$R = 0 \qquad \qquad R \neq 0$		
		longaddr,reg longaddr*,reg	3080 3080 3740 3960		
OWI	OR Word Immediate	word,reg[,reg]	2420		
		word,addr4	4180+RS		
PB	Pop Byte	addr4,reg	6600+RS		
PD	Pop Doubleword	addr4,reg	7040+RS		
PSB	Push Byte	reg,addr4	6380+RS		
PSD	Push Doubleword	reg,addr4	7040+RS		
PSW	Push Word	reg,addr4	5960+RS		
PW	Pop Word	addr4,reg	6160+RS		
		<del>-</del>			

Table 2 (Part 7 of 10)

			Execution ti	ime	
Mnemonic	Instruction name	Syntax	(nanosecond	ls)	
RBTB	Reset Bits Byte	reg,addr4	2860+RS		
		addr4,reg addr5,addr4	1760+RS 3520+AM1+	ΔΜ2	
RBTD	Reset Bits Doubleword	reg,addr4	5060+RS	11112	
11212	20000 2000 2000 00000 00000	addr4,reg	3740+RS		
		addr5,addr4	6600+AM1+	AM2	
RBTW	Reset Bits Word	reg,reg reg,addr4	1320 2860+RS		
		addr4,reg	1760+RS		
		addr5,addr4	3520+(AM1	+X)+AM2	
			R = 0	$R \neq 0$	
		longaddr,reg	3080	3080	
		longaddr*,reg	3740	3960	
RBTWI	Reset Bits Word Immediate	word,reg[,reg] word,addr4	2420 4180+RS		
SB	Subtract Byte	reg,addr4	2860+RS		
DD .	Suctinet By te	addr4,reg	1760+RS		
SCY	Subtract Carry Indicator	reg	1760		
SD	Subtract Doubleword	reg,addr4	5060+RS		
		addr4,reg addr5,addr4	3740+RS 6820+(AM1	+V)+AM2	
SEAKR	Set Address Kev	addr4	2640+RS	· 1 / · A.M.2	
SEARK	Register	reg	2420		
SECON	Set Console Data Lights	reg	1760		
SEFLB	Set Floating Level Block	reg,addr4	18480+RS		
SEIMR	Set Interrupt Mask Register	addr4	2640+RS		
SEIND	Set Indicators	reg	2640		
SEISK	Set instruction Space Key	addr4 reg	2640+RS 2420		
SELB	Set Level Block	reg,addr4		ff and SL <cl< td=""><td></td></cl<>	
				ff and SL=CL	
				ff and SL>CL n and SL <cl< td=""><td></td></cl<>	
				n and SL=CL	
				n and SL>CL	
	Note. IP = in process flag; SL =	· ·			
SEOOK	Set Operand 1 Key	addr4	2640+RS 2420		
SEOTK	Set Operand 2 Key	reg addr4	2640+RS		
SEOTK	Set Operand 2 Rey	reg	2420		
SESK	Set Storage Key	reg,addr4	4400+RS		
SESR	Set Segmentation Register	reg,addr4	3080+RS		
SFED	Scan Byte Field Equal and Decrement	reg,(reg)	1760+(308)	0 x CT)	See SFNEN note
SFEN	Scan Byte Field Equal and Increment	reg,(reg)	1760+(3080	0 x CT)	See SFNEN note
SFNED	Scan Byte Field Not Equal and Decrement	reg,(reg)	1760+(3080	•	See SFNEN note
SFNEN	Scan Byte Field Not Equal and Increment	reg,(reg)	1760+(3080	0 x CT)	See note
	Note. For SFED, SFEN, SFNE instruction is terminated by a co		880 if the		

Table 2 (Part 8 of 10)

Mnemonic	Instr	uction name	Syntax	Execution time (nanoseconds)	
SLC	Shift	Left Circular	cnt16,reg	2200 2200+110 x (CT+1) 2200+110 x (CT)	Zero count Odd count Even count
			reg,reg	1980 1980+110 x (CT+1) 1980+110 x (CT)	Zero count Odd count Even count
SLCD	Shift Doub	Left Circular le	cnt31,reg	2860 2860+110 x (CT+1) 2860+110 x (CT)	Zero count Odd count Even count
			reg,reg	2420 2420+110 x (CT+1) 2420+110 x (CT)	Zero count Odd count Even count
SLL	Shift	Left Logical	cnt16,reg	2420 2420+110 x (CT+1) 2420+110 x (CT)	Zero count Odd count Even count
			reg,reg	2200 2200+110 x (CT+1) 2200+110 x (CT)	Zero count Odd count Even count
SLLD	Shift Doub	Left Logical le	cnt31,reg	3080 3080+110 x (CT+1) 3080+110 x (CT)	Zero count Odd count
			reg,reg	2640 2640+110 x (CT+1) 2640+110 x (CT)	Even count Zero count Odd count Even count
SLT	Shift	Left and Test	reg,reg	3080+660 x CT 4180+660 x K 2860	See SLTD note (1) See SLTD note (2) See SLTD note (3)
SLTD	Shift Doub	Left and Test le	reg,reg	3300+660 x CT 4400+660 x K 3080	See note (1) See note (2) See note (3)
	Notes	•			See Hote (5)
	(1)	The shift count goes to ze	ero before a shifted bit is	s set into	
	(2)	the carry indicator. A shifted bit is set into the count goes to zero. $K = 1$	oit number of leftmost o		
SRA	(3) Shift	The initial operand is zero	0,		
		Right Arithmetic	cnt16.reg	2200	Zero count
		Right Arithmetic	cnt16,reg	2200 2200+110 x (CT+1)	Zero count Odd count
		Right Arithmetic		2200+110 x (CT+1) 2200+110 x (CT)	Odd count Even count
		Right Arithmetic	cnt16,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980	Odd count Even count Zero count
		Right Arithmetic		2200+110 x (CT+1) 2200+110 x (CT)	Odd count Even count
SRAD		Right Arithmetic		2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860	Odd count Even count Zero count Odd count Even count Zero count
SRAD	Shift Doub	Right Arithmetic	reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1)	Odd count Even count Zero count Odd count Even count Zero count Odd count
SRAD		Right Arithmetic	reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860	Odd count Even count Zero count Odd count Even count Zero count Odd count Even count
SRAD		Right Arithmetic	reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1)	Odd count Even count Zero count Odd count Even count Zero count Odd count
	Doub	Right Arithmetic le	reg,reg cnt31,reg reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT)	Odd count Even count Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count
SRAD SRL	Doub	Right Arithmetic	reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT)	Odd count Even count Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Count Count Even count
	Doub	Right Arithmetic le	reg,reg cnt31,reg reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT)	Odd count Even count Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Odd count Even count Odd count
	Doub	Right Arithmetic le	reg,reg cnt31,reg reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT)	Odd count Even count Odd count Even count Odd count Even count Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count
	Doub	Right Arithmetic le	reg,reg cnt31,reg reg,reg cnt16,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT+1) 2200+110 x (CT+1) 2200+110 x (CT+1)	Odd count Even count Odd count Even count Odd count Even count Odd count Even count Odd count Even count Odd count Even count Cero count Odd count Even count Odd count Even count Odd count Even count Odd count
SRL	Doub. Shift	Right Arithmetic le Right Logical	reg,reg cnt31,reg reg,reg cnt16,reg reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT)	Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Codd count Even count Even count Even count Even count Codd count Even count
	Doub. Shift	Right Arithmetic le Right Logical	reg,reg cnt31,reg reg,reg cnt16,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT+1) 2200+110 x (CT+1) 2200+110 x (CT+1)	Odd count Even count Odd count Even count Odd count Even count Odd count Even count Odd count Even count Odd count Even count Cero count Odd count Even count Odd count Even count Odd count Even count Odd count
SRL	Shift Shift	Right Arithmetic le Right Logical	reg,reg cnt31,reg reg,reg cnt16,reg reg,reg cnt31,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT+1) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT+1) 2860+110 x (CT)	Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Codd count Even count
SRL	Shift Shift	Right Arithmetic le Right Logical	reg,reg cnt31,reg reg,reg cnt16,reg reg,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT+1) 2860+110 x (CT)	Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Count Zero count Count Zero count Count Zero count Count Zero count Count Even count
SRL	Shift Shift	Right Arithmetic le Right Logical	reg,reg cnt31,reg reg,reg cnt16,reg reg,reg cnt31,reg	2200+110 x (CT+1) 2200+110 x (CT) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT) 2420 2420+110 x (CT+1) 2420+110 x (CT) 2200 2200+110 x (CT+1) 2200+110 x (CT+1) 1980 1980+110 x (CT+1) 1980+110 x (CT) 2860 2860+110 x (CT+1) 2860+110 x (CT+1) 2860+110 x (CT)	Odd count Even count Zero count Odd count Even count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Odd count Even count Zero count Count Even count Zero count Count Even count

16	T	S	Execution to		
Mnemonic	Instruction name	Syntax	(nanosecono	•	
STM	Store Multiple	reg,addr4[,abcnt]	11220+RS RL=7 12320+(1100 x RL)+RS RL≠7		
STOP	Ston	[ubyte]	1760	O A RL)·RS	KD/ /
SVC	Stop Supervisor Call	ubyte	17380		
SW	Supervisor Can Subtract Word	reg,reg	1320		
SW	Subtract word	reg,addr4	2860+RS		
		addr4,reg	1760+RS		
		addr5,addr4	3520+(AM1	+Y)+AM2	
			R = 0	$R \neq 0$	
		longaddr,reg	3080	3080	
		longaddr*,reg	3740	3960	
SWCY	Subtract Word With Carry	reg,reg	1760		
SWI	Subtract Word Immediate	word,addr4	4180+RS		
mp.m	m mt	word,reg[,reg]	2420		C TDTI
TBT	Test Bit	(reg,bitdisp)	4840+A		See TBTV note
TBTR	Test Bit and Reset	(reg,bitdisp)	5720+A		See TBTV note
TBTS	Test Bit and Set On	(reg,bitdisp)	5720+A		See TBTV note
TBTV	Test Bit and Invert	(reg,bitdisp)	5720+A		See note
	Note. For TBT, TBTR, TBTS, a	na ibiv:			
	A = 0 if BT is zero. $A = 110 \times BT$ if BT is even.				
	$A = 110 \times (BT+1)$ if BT is odd.				
	BT = bit number of tested bit (ra	ange 0-7).			
TWI	Test Word Under Mask	word,reg	2860		All bits $= 0$
	Immediate		3080		All bits $\neq 0$
		word,addr4	3520+RS		All bits = 0
***		,	3740+RS 1540		Any bits $\neq 0$
VR	Invert Register	reg[,reg]	2860+RS		
XB	Exclusive OR Byte	reg,addr4 addr4,reg	1760+RS		
XD	Exclusive OR Doubleword	reg,addr4	5060+RS		
AD	Exclusive OR Doubleword	addr4,reg	3740+RS		
XW	Exclusive OR Word	reg,reg	1320		
		reg,addr4	2860+RS		
		addr4,reg	1760+RS	,	
			R = 0	$R \neq 0$	
		longaddr,reg	3080	3080	
*****	n dei onw	longaddr*,reg	3740	3960	
XWI	Exclusive OR Word Immediate	word,reg[,reg]	2420		
	immediate				


Table 2 (Part 10 of 10)


# Appendix B. Instruction Formats

The following instruction formats are shown in ascending sequence based on operation code. Bits zero through four of the first instruction word comprise the operation code field. Bit combinations are shown for each operation code along with the hexadecimal representation.

Some instructions contain a function field that modifies the operation code to form individual instructions within a group. Each chart shows the function field bit combinations in hexadecimal and in ascending sequence. The assembler mnemonic, assembler syntax, and instruction name are listed for the individual instructions. The asterisk shown with the assembler syntax indicates indirect addressing.


Refer to Chapter 2, Effective Address Generation, for a description of the Address Mode (AM) appended words.





byte,reg

Add Byte Immediate







MVBI

byte,reg

Move Byte Immediate






Extended mnemonics: JCY, JE, JEV, JLE, JLLE, JLLT, JLT, JMIX, JN, JOFF, JON, JP, JZ

O	era	tio	n co	de	Cond		Word displace	ement
0	0	0	1	1				
0				4	5	7	8	15
_		_	_	~	~	_		~~~~
		1			8-F		X	X

1 8-F X X JNC cond,jdisp Jump on Not Condition

JNC cond,jaddr Jump on Not Condition


Extended mnemonics: JGE, JGT, JLGE, JLGT, JNCY, JNE, JNEV, JNMIX, JNN, JNP, JNZ



	,			
2 0-3 X	0	FA	addr4,freg	Floating Add
	1	FAD	addr4,freg	Floating Add Double
	2	FS	addr4,freg	Floating Subtract
	3	FSD	addr4,freg	Floating Subtract Double
	4	FM	addr4,freg	Floating Multiply
	5	FMD	addr4,freg	Floating Multiply Double
	6	FD	addr4,freg	Floating Divide
	7	FDD	addr4,freg	Floating Divide Double
	8	FMVC	addr4,freg	Floating Move and Convert
	9	FMVCD	addr4,freg	Floating Move and Convert Double
	A	FMVC	freg,addr4	Floating Move and Convert
	В	FMVCD	freg,addr4	Floating Move and Convert Double
	C	FMV	addr4,freg	Floating Move
	D	FMVD	addr4,freg	Floating Move Double
	E	F <b>MV</b>	freg,addr4	Floating Move
	F	FMVD	freg,addr4	Floating Move Double

O	oera	tio	n cc	de		R	!	R	2			Func		P
0	0	1	0	0	1					0	0	l		
0				4	5	6	7	8	9	10	11	12	14	15
_	_	<b>~~</b>	_	へ.	_	<u>~</u>	_	^	-	~	_	<u> </u>	~	_
		2			4	-7				X			0-F	7

2 4-7 X	0	FA	freg,freg	Floating Add
	1	FAD	freg,freg	Floating Add Double
	2	FS	freg,freg	Floating Subtract
	3	FSD	freg,freg	Floating Subtract Double
	4	FM	freg,freg	Floating Multiply
	5	FMD	freg,freg	Floating Multiply Double
	6	FD	freg,freg	Floating Divide
	7	FDD	freg,freg	Floating Divide Double
	8	FMV	freg,freg	Floating Move
	9	FMVD	freg,freg	Floating Move Double
	A	FC	freg,freg	Floating Compare
	В	FCD	freg,freg	Floating Compare Double
	С	(must not be used)	)	Executes FMV
	מ	(must not be used)	)	Executes FMVD
	E	(must not be used)	)	Executes FC
	F	(must not be used)	)	Executes FCD





2 8-F X	0	MVFD	(reg),(reg)	Move Byte Field and Decrement
	1	(unused)		
	2	CFNED	(reg),(reg)	Compare Byte Field Not Equal and Decrement
	3	CFED	(reg),(reg)	Compare Byte Field Equal and Decrement
	4	MVFN	(reg),(reg)	Move Byte Field and Increment
	5	(unused)		
	6	CFNEN	(reg),(reg)	Compare Byte Field Not Equal and Increment
	7	CFEN	(reg),(reg)	Compare Byte Field Equal and Increment
	8	FFD	reg,(reg)	Fill Byte Field and Decrement
	9	(unused)		
	A	SFNED	reg,(reg)	Scan Byte Field Not Equal and Decrement
	В	SFED	reg,(reg)	Scan Byte Field Equal and Decrement
	c	FFN	reg,(reg)	Fill Byte Field and Increment
	D	(unused)		
	E	SFNEN	reg,(reg)	Scan Byte Field Not Equal and Increment
	F	SFEN	reg,(reg)	Scan Byte Field Equal and Increment


$O_{l}$	oera	tio	n co	de	Ι	R	T	Count		Func	tion
0	0	1	1	0			ı				
0				4	5		7	8	12	13	15
_	$\overline{}$		$\sim$	_	~	_	ハ		$\sim$	~	_
	3				0-2	7		X		0-F	,

3 0-7 X 0,8	SLC	cnt16,reg	Shift Left Circular
1,9	SLL	cnt16,reg	Shift Left Logical
2,4	SRL	cnt16,reg	Shift Right Logical
3,Е	SRA	cnt16,reg	Shift Right Arithmetic
4,0	SLCD	cnt31,reg	Shift Left Circular Double
5,1	SLLD	cnt31,reg	Shift Left Logical Double
6,E	SRLD	cnt31,reg	Shift Right Logical Double
7,F	SRAD	cnt31,reg	Shift Right Arithmetic Double

# 3xxx 4xxx









Note 1. Use format without immediate field.


Opr





O	era	tio	n co	ode	П	R		Word displacement	
0	1	0	1	0	l			-	
0				4	5		7	8	15
_				~		_	_		
		5			0-	-7		X	X

5	0	0	0	NOP	No Operation	
	0	X	X	J	jdisp	Jump Unconditional
				J	jaddr	Jump Unconditional
	1-7	X	х	BXS	$(reg^{1-7}, jdisp)$	Branch Indexed Short
				BXS	(reg ¹⁻⁷ )	Branch Indexed Short
				BXS	addr	Branch Indexed Short




5 8-F       X       0       SEIMR       addr4       Set Interrupt Mask Register         1 SESR       reg,addr4       Set Segmentation Register         2 SEAKR       addr4       Set Address Key Register (Note 2)         3 SEFLB       reg,addr4       Set Floating Level Block         4 SESK       reg,addr4       Set Storage Key         5 (invalid)       SELB       reg,addr4         6 SELB       reg,addr4       Set Level Status Block         7 (invalid)       CPIMR       addr4       Copy Interrupt Mask Register         9 CPSR       reg,addr4       Copy Segmentation Register         A CPAKR       addr4       Copy Address Key Register (Note 3)         B CPFLB       reg,addr4       Copy Floating Level Block         C CPSK       reg,addr4       Copy Storage Key         D CPIPF       addr4       Copy In-Process Flags         E CPLB       reg,addr4       Copy Level Block         C CPSR       addr4       Copy Processor Status and Reset					
2 SEAKR addr4 Set Address Key Register (Note 2) 3 SEFLB reg,addr4 Set Floating Level Block 4 SESK reg,addr4 Set Storage Key 5 (invalid) 6 SELB reg,addr4 Set Level Status Block 7 (invalid) 8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block	5 8-F X	0	SEIMR	addr4	Set Interrupt Mask Register
3 SEFLB reg,addr4 Set Floating Level Block 4 SESK reg,addr4 Set Storage Key 5 (invalid) 6 SELB reg,addr4 Set Level Status Block 7 (invalid) 8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		1	SESR	reg,addr4	Set Segmentation Register
4 SESK reg,addr4 Set Storage Key  5 (invalid)  6 SELB reg,addr4 Set Level Status Block  7 (invalid)  8 CPIMR addr4 Copy Interrupt Mask Register  9 CPSR reg,addr4 Copy Segmentation Register  A CPAKR addr4 Copy Address Key Register (Note 3)  B CPFLB reg,addr4 Copy Floating Level Block  C CPSK reg,addr4 Copy Storage Key  D CPIPF addr4 Copy In-Process Flags  E CPLB reg,addr4 Copy Level Block		2	SEAKR	addr4	Set Address Key Register (Note 2)
5 (invalid) 6 SELB reg,addr4 Set Level Status Block 7 (invalid) 8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		3	SEFLB	reg,addr4	Set Floating Level Block
6 SELB reg,addr4 Set Level Status Block 7 (invalid) 8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		4	SESK	reg,addr4	Set Storage Key
7 (invalid) 8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		5	(invalid)		
8 CPIMR addr4 Copy Interrupt Mask Register 9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		6	SELB	reg,addr4	Set Level Status Block
9 CPSR reg,addr4 Copy Segmentation Register A CPAKR addr4 Copy Address Key Register (Note 3) B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		7	(invalid)		
A CPAKR addr4 Copy Address Key Register (Note 3)  B CPFLB reg,addr4 Copy Floating Level Block  C CPSK reg,addr4 Copy Storage Key  D CPIPF addr4 Copy In-Process Flags  E CPLB reg,addr4 Copy Level Block		8	CPIMR	addr4	Copy Interrupt Mask Register
B CPFLB reg,addr4 Copy Floating Level Block C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		9	CPSR	reg,addr4	Copy Segmentation Register
C CPSK reg,addr4 Copy Storage Key D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		A	CPAKR	addr4	Copy Address Key Register (Note 3)
D CPIPF addr4 Copy In-Process Flags E CPLB reg,addr4 Copy Level Block		В	CPFLB	reg,addr4	Copy Floating Level Block
E CPLB reg,addr4 Copy Level Block		С	CPSK	reg,addr4	Copy Storage Key
		D	CPIPF	addr4	Copy In-Process Flags
F CPPSR addr4 Copy Processor Status and Reset		E	CPLB	reg,addr4	Copy Level Block
		F	CPPSR	addr4	Copy Processor Status and Reset

Note 2. Use format with K field.


Extended mnemonics: SEISK, SEOTK, SEOOK

Note 3. Use format with K field.

Extended mnemonics: CPISK, CPOTK, CPOOK



6	0	X X SVC	ubyte	Supervisor Call
	1	LEX	[ubyte]	Level Exit
	2	EN	ubyte	Enable
ı	3	DIS	ubyte	Disable
ı	4	STOP	[ubyte]	Stop
	5	DIAG	ubyte	Diagnose
	6	IOPK		Interchange Operand Keys
- 1	7	(invalid)		opolalia Roys




Note 4. Extended mnemonics: BCY, BE, BEV, BLE, BLLE,


BLLT, BLT, BMIX, BN, BOFF, BON, BP, BZ

Note 5. Extended mnemonics: BGE, BGT, BLGE, BLGT, BNCY,


BNE, BNEV, BNMIX, BNN, BNOFF, BNON, BNP, BNZ


Note 6. Extended mnemonic: BX
Note 7. Extended mnemonic: BALX
Note 8. Extended mnemonic: BNER
Note 9. Extended mnemonic: BER






Operation co	ode 0	R1 R.	2 Function								
0	4 5	7 8	10 11 15								
$\mathcal{I}_{\tilde{7}}$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$										
		1, 3, 3,	7, 9, B, D, F								
Γ											
7 0-7	0	SLC	<b>2</b> 00 <b>2</b> 00	Shift Left Circular							
7 1 1	1 1		reg,reg								
	$\begin{vmatrix} 1 \end{vmatrix}$	SLL	reg,reg	Shift Left Logical							
	2	SRL	reg,reg	Shift Right Logical							
	3	SRA	reg,reg	Shift Right Arithmetic							
	4	SLCD	reg,reg	Shift Left Circular Double							
	5	SLLD	reg,reg	Shift Left Logical Double							
	6	SRLD	reg,reg	Shift Right Logical Double							
	7	SRAD	reg,reg	Shift Right Arithmetic Double							
	8	(invalid)									
	9	SLT	reg,reg	Shift Left and Test							
	A	(invalid)									
	В	(invalid)									
	c	(invalid)									
	D	SLTD	reg,reg	Shift Left and Test Double							
	E	(invalid)									
	F	(invalid)									








Note 10. Use format with K field.


Extended mnemonics: SEISK, SEOTK, SEOOK


Note 11. Use format with K field.

Extended mnemonics: CPISK, CPOTK, CPOOK



# 8xxx 9xxx







Operation cod	e RB1	RB2	AM1	AM2	Fun	47 3	7
0	4 5 7	8 9	10 11	12 13	14 15 1	6 31 32	47
	<b>_</b>		$\sim$	<u> </u>	$\sim$		
9	0 - 7		X	0	-F	AM appended words	


$9 \ 0-7 \ X \ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	MVD	addr5,addr4	Move Double Word
1,5 9,D	OD	addr5,addr4	OR Double Word
2,6 A,E	RBTD	addr5,addr4	Reset Bits Double Word
3,7 B,F	CD	addr5,addr4	Compare Double Word


	$O_l$	oera	tio	n cc	de	Π	R		Word displace	ment
	1	0	0	1	1					
	0				4	5		7	8	15
`	_		_	_	<u> </u>	_	~	_	~~	
		9	9			8	-F		X	X

9 8-F X X	JAL	jdisp,reg	Jump and Link
	JAL	jaddr,reg	Jump and Link












 $\mathbf{X}$ X Illegal operation code (Program check condition)

# Bxxx Cxxx




B 8-F X X	JCT	jdisp,reg	Jump on Count
	JCT	jaddr,reg	Jump on Count






C 8-F X	0	MVW	-44-4	N
C  0-1   A	"	IMI A AM	addr4,reg	Move Word
	1	OW	addr4,reg	OR Word
	2	RBTW	addr4,reg	Reset Bits Word
	3	XW	addr4,reg	Exclusive OR Word
	4	CW	addr4,reg	Compare Word
	5	MVWZ	addr4,reg	Move Word and Zero
	6	AW	addr4,reg	Add Word
	7	SW	addr4,reg	Subtract Word
	8	MVW	reg,addr4	Move Word
	9	OW	reg,addr4	OR Word
	A	RBTW	reg,addr4	Reset Bits Word
	В	xw	reg,addr4	Exclusive OR Word
	E	AW	reg,addr4	Add Word
	F	SW	reg,addr4	Subtract Word

# Dxxx





D 0-7 X	0	MVD	addr4,reg	Move Double Word
	1	OD	addr4,reg	OR Double Word
	2	RBTD	addr4,reg	Reset Bits Double Word
	3	XD	addr4,reg	Exclusive OR Double Word
	4	CD	addr4,reg	Compare Double Word
	5	MVDZ	addr4,reg	Move Double Word and Zero
	6	AD	addr4,reg	Add Double Word
	7	SD	addr4,reg	Subtract Double Word
	8	MVD	reg,addr4	Move Double Word
	9	OD	reg,addr4	OR Double Word
	A	RBTD	reg,addr4	Reset Bits Double Word
i	В	XD	reg,addr4	Exclusive OR Double Word
	E	AD	reg,addr4	Add Double Word
	F	SD	reg,addr4	Subtract Double Word
	_			




D 8-F X X


Illegal operation code (Program check condition)







# Exxx Fxxx








F 0-7 X X CBI byte,reg Compare Byte Immediate





## Appendix C. Assembler Syntax

#### CODING NOTES

- 1. Data flow, when it modifies a field, is always from left
- 2. Registers used in effective address calculations are always in parentheses.
- 3. An address specification followed by an asterisk indicates indirect addressing. Here, the effective address is the contents of the addressed storage location.
- 4. The (reg)+ format indicates that, after use, the contents of reg are increased by the number of bytes addressed.

### Legend for Machine Instruction Operands

addr*

abent An absolute value or expression representing the size of a work storage area to be allocated by the Store Multiple (STM) instruction. The value you code must be an even number in the range 0-16382.

An address value. Code an absolute or relocatable addr expression in the range 0-65535.

addr4 An address value that you code in one of the following forms:

> (reg⁰⁻³) The effective address is the contents of the register reg⁰⁻³.

> $(reg^{0-3}) +$ The effective address is the contents of the register reg⁰⁻³. After an instruction uses it, the contents of the register are increased by the number of bytes

addressed by the instruction.

addr The effective address is the value of addr, unless the instruction and addr are within the range of the same USING statement. If they are, the assembler computes the effective address as a displacement (-32768 to +32767

> or 0 to 65535) from the base register, which must be reg¹⁻³.

> The effective address is the contents of storage at the address defined by addr, unless the instruction and addr are within the domain and range of the same USING statement. If they are, the assembler computes the effective address as the contents of storage at the address defined by a displacement (0-255) from the base register, which must be reg¹⁻³.

(reg1-3, waddr) The effective address is the contents of the register reg1-3,

added to the value of waddr.

disp1(reg1-3,disp2)* The effective address is calculated as follows: The contents of the register reg1-3 are added to the value of the displacement disp2 to form an address. The contents of that storage location are added to the value of disp1 to form the

effective address.

disp(reg1-3)* The effective address is the contents of storage at the address defined by the contents of reg¹⁻³,

added to the value of disp.

(reg1-3)* The effective address is the contents of storage at the address defined by the contents of reg¹⁻³.

(reg1-3,disp)* The contents of reg1-3 are added to disp, forming an address. The contents of storage at that address form the effective address.

For the byte addressing, the effective address can be even or odd. For word or doubleword addressing, the effective address must be even.

An address value that you code in one of the following

(reg) The effective address is the

contents of the register reg.

The effective address is the (reg) + contents of the register reg. After an instruction uses it, the contents of the register are increased by the number of bytes

addressed by the instruction. The effective address is the value

of addr, unless the instruction and addr are within the domain and range of the same USING statement. If they are, the assembler computes the effective address as a displacement (-32768 to +32767 or 0 to

65535) from the base register,

which must be reg¹⁻⁷.

The effective address is the contents of storage at the address defined by addr, unless the instruction and addr are within the domain and range of the same

USING statement. If they are, the assembler computes the effective address as the contents of storage at the address defined by a displacement (0-255) from the base register, which must be

reg1-7.

addr5

addr

addr*

Assembler Syntax C-1

The effective address is the contents of reg¹⁻⁷, added to the contents of storage at the address defined by addr, unless the value of waddr. instruction and addr are within disp1(reg1-7, disp2)*The effective address is calculated the domain and range of the same as follows: The contents of the register reg1-7 are added to the USING statement. If they are, the value of the displacement disp2 to assembler computes the effective address as the contents of storage form an address. The contents of at the address defined by a that storage location are added to displacement (-32768 to +32767 the value of disp1 to form the or 0 to 65535) from the base effective address. register, which must be reg¹⁻⁷. disp(reg1-7)* The effective address is the (reg1-7,waddr) The effective address is the contents of storage at the address contents of reg¹⁻⁷, added to the defined by the contents of reg¹⁻⁷, value of waddr. added to the value of disp. (reg1-7,waddr)* The contents of the reg1-7, plus (reg1-7)* The effective address is the waddr, form an address. The contents of storage at the address contents of storage at that defined by the contents of reg¹⁻⁷. form the effective location The contents of reg1-7 are added (reg1-7,disp)* address. to disp, forming an address. The (reg1-7) The effective address is the contents of storage at that address contents of the register reg¹⁻⁷. form the effective address. (reg1-7)* The effective address is the For byte addressing, the effective address can be even contents of storage at the address or odd. For word or doubleword addressing, the defined by the contents of reg1-7. effective address must be even. raddr An address value. Code a relocatable expression in the bitdisp A displacement into a bit field. Code an absolute value range 0-65535. or expression in the range 0-63. A general-purpose register. Code either a predefined reg A byte value. Code an absolute value or expression in byte register symbol (R0-R7) or a symbol that is equated the range -128 to +127 or 0 to 255. to the desired register number (0, 1, 2, 3, 4, 5, 6, or cnt16 A single word (one register) shift count. Code an 7). Symbols are equated with EQUR statements, absolute value or expression in the range 0-16. which must precede the instruction using the register A doubleword (register pair) shift count. Code an cnt31 symbol. absolute value or expression in the range 0-31. reg⁰⁻³ A general-purpose register. Code either a predefined A condition code value. Code an absolute value or cond register symbol (R0-R3) or a symbol that is equated expression in the range 0-7. to the desired register number (0, 1, 2, or 3). Symbols A byte address displacement. Code an absolute value disp are equated with EQUR statements, which must precede the instruction using the register symbol. or expression in the range 0-255. A floating-point register. Code either a predefined reg1-3 A general-purpose register. Code either a predefined freg floating register symbol (FR0-FR3) or a symbol that register symbol (R1-R3) or a symbol that is equated is equated to the desired register number (0, 1, 2, or to the desired register number (1, 2, or 3). Symbols 3). Symbols are equated with EQUR statements, are equated with EQUR statements, which must which must precede the instruction using the register precede the instruction using the register symbol. reg1-7 A general-purpose register. Code either a predefined The address of an instruction that is within -256 to jaddr register symbol (R1-R7) or a symbol that is equated +254 bytes of the byte following a jump instruction. to the desired register number (1, 2, 3, 4, 5, 6, or 7). Code a relocatable expression. Symbols are equated with EQUR statements, which must precede the instructions using the register jdisp A displacement from the byte following a jump instruction. Code an absolute value or expression in symbol. the range -256 to +254. shortaddr An address value that you code in one of the following longaddr An address value that you code in one of the following forms: forms: (reg⁰⁻³,wdisp) The effective address is the value of wdisp added to the contents of addr The effective address is the value reg⁰⁻³. of addr, unless the instruction and addr are within the domain and (reg⁰⁻³,wdisp)* The effective address is the range of the same USING contents of storage at the address statement. If they are, the defined by the value of wdisp assembler computes the effective added to the contents of reg⁰⁻³. address as a displacement (reg⁰⁻³) The effective address is the (-32768 to +32767 or 0 to contents of  $(reg^{0-3})$ . 65535) from the base register, which must be  $reg^{1-7}$ .

addr*

The effective address is the

(reg1-7, waddr)

The effective address is the  $(reg^{0-3})*$ contents of storage at the address defined by the contents of  $reg^{0-3}$ . To use this form, the instruction addr and addr must be in the domain and range of the same USING statement. The assembler computes a displacement (0-62) and register combination that refers to the requested location. Same as addr, except the addr* assembler computes the effective address as the contents of storage at the address defined by a displacement (0-62) and register combination. Note. For addr and addr*, the base register must be reg⁰⁻³. An unsigned byte value or mask. Code an absolute value or expression in the range 0-255. An ordinary symbol that is defined externally from the current source program. A one-word address value. Code an absolute or relocatable expression in the range -32768 to +32767

ubyte

vcon

waddr

wdisp

word

or 0 to 65535.

An even byte address displacement. Code an absolute

value or expression in the range 0-62.

# Appendix D. Numbering Systems and Conversion Tables


# Binary and Hexadecimal Number Notations

## Binary Number Notation

A binary number system, such as is used in System/X, uses a base of two. The concept of using a base of two can be compared with the base of ten (decimal) number system.


Decimal number	Binary number
0	= 0
1	= 1
2	= 10
3	= 11
4	= 100
5	= 101
6	= 110
7	= 111
8	= 1000
9	= 1001

### Example of a decimal number:



As shown above, the decimal number system allows counting to ten in each position from units to tens to hundreds to thousands, etc. The binary system allows counting to two in each position. Register displays in the System/X are in binary form: a bit light on is a 1; a bit light off is a 0.

### Example of a binary number:



## Hexadecimal Number System

It has been noted that binary numbers require about three times as many positions as decimal numbers to express the equivalent number. This is not much of a problem to the computer; however, in talking and writing or in communicating with the computer, these binary numbers are bulky. A long string of 1's and 0's cannot be effectively transmitted from one individual to another. Some shorthand method is necessary.

The hexadecimal number system fills this need. Because of the simple relationship of hexadecimal to binary, numbers can be converted from one system to another by inspection. The base or radix of the hexadecimal system is 16. This means there are 16 symbols: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, A, B, C, D, E, and F. The letters A, B, C, D, E; and F represent the 10-base system values of 10, 11, 12, 13, 14, and 15, respectively.

Four binary positions are equivalent to one hexadecimal position. The following table shows the comparable values of the three number systems.

Binary	Hexadecimal
0000	0
0001	1
0010	2
0011	3
0100	4
0101	5
0110	6
0111	7
1000	8
1001	9
1010	A
1011	В
1100	C
1101	D
1110	E
1111	F
	0000 0001 0010 0011 0100 0101 0110 0111 1000 1001 1010 1011 1100 1101 1110

At this point, all 16 symbols have been used, and a carry to the next higher position of the number is necessary. For example:

Decimal	Binary	Hexadecimal
16	0001 0000	10
17	0001 0001	11
18	0001 0010	12
19	0001 0011	13
20	0001 0100	14
21	0001 0101	15

-and so on-

Remember that as far as the internal circuitry of the computer is concerned, it understands only binary. But an operator can look at a series of lights on the computer console showing binary 1's and 0's, for example: 0001 1110 0001 0011, and say that the lights represent the hexadecimal value 1E13, which is easier to state than the string of 1's and 0's.


For numbers outside the range of the table, add the following values to the tables figures:

Hexadecimal	Decimal
1000	4096
2000	8192
3000	12288
4000	16384
5000	20480
6000	24576
7000	28672
8000	32768

## Hexadecimal-Decimal Conversion Tables

The table in this appendix provides for direct conversion of decimal and hexadecimal number in these ranges:

Hexadecimal Decimal
000 to FFF 0000 to 4095



	<del>'</del> 0	1	2	3	4	5	6	7	8	9	A	В	С	D	E	F
20_	0512	0513	0514	0515	0516	0517	0518	0519	0520	0521	0522	0523	0524	0525	0526	0527
21_	0528 0544	0529 0545	0530 0546	0531 0547	0532 0548	0533 0549	0534 0550	0535 0551	0536 0552	0537 0553	0538 0554	0539 0555	0540 0556	0541 0557	0542 0558	0543
23_	0560	0561	0562	0563	0564	0565	0566	0567	0568	0569	0570	0571	0572	0573	0574	0559 0575
24_	0576	0577	0578	0579	0580	0581	0582	0583	0584	0585	0586	0587	0588	0589	0590	0591
25_ 26_	0592 0608	0593 0609	0594 0610	0595 0611	0596 0612	0597 0613	0598 0614	0599 0615	0600 0616	0601 0617	0602 0618	0603 0619	0604 0620	0605 0621	0606 0622	0607 0623
27_	0624	0625	0626	0627	0628	0629	0630	0631	0632	0633	0634	0635	0636	0637	0638	0639
28_ 29_	0640	0641 0657	0642 0658	0643 0659	0644 0660	0645 0661	0646 0662	0647	0648	0649	0650	0651	0652	0653	0654	0655
2A_	0672	0673	0674	0675	0676	0677	0678	0663 0679	0664 0680	0665 0681	0666 0682	0667 0683	0668 0684	0669 0685	0670 0686	0671 0687
2B_	0688	0689	0690	0691	0692	0693	0694	0695	0696	0697	0698	0699	0700	0701	0702	0703
2C_ 2D_	0704 0720	$0705 \\ 0721$	0706 0722	0707 0723	0708 0724	0709 0725	0710 0726	$0711 \\ 0727$	0712 0728	0713 0729	0714 0730	0715 0731	$0716 \\ 0732$	0717 0733	0718 0734	$0719 \\ 0735$
2E_	0736	0737	0738	0739	0740	0741	0742	0743	0744	0745	0746	0747	0748	0749	0750	0751
2F_	0752	0753	0754	0755	0756	0757	0758	0759	0760	0761	0762	0763	0764	0765	0766	0767
30_ 31_	0768	0769 0785	0770 0786	0771 0787	0772	0773	0774	0775	0776	0777	0778	0779	0780	0781	0782	0783
32_	0800	0801	0802	0803	0788 0804	0789 0805	0790 0806	0791 0807	0792 0808	0793 0809	0794 0810	$0795 \\ 0811$	0796 0812	0797 0813	0798 0814	0799 0815
33_	0816	0817	0818	0819	0820	0821	0822	0823	0824	0825	0826	0827	0828	0829	0830	0831
34_ 35_	0832 0848	0833 0849	0834 0850	0835 0851	0836 0852	0837 0853	0838 0854	0839 0855	0840 0856	0841 0857	0842 0858	0843 0859	0844 0860	0845 0861	0846 0862	0847
36	0864	0865	0866	0867	0868	0869	0870	0871	0872	0873	0874	0875	0876	0877	0878	0863 0879
37_	0880	0881	0882	0883	0884	0885	0886	0887	0888	0889	0890	0891	0892	0893	0894	0895
39_	0896 0912	0897 0913	0898 0914	0899 0915	0900 0916	0901 0917	0902 0918	0903 0919	0904 0920	$0905 \\ 0921$	0906 0922	0907 0923	0908 0924	0909 0925	0910 0926	0911 0927
3A_   3B_	0928	0929	0930	0931	0932	0933	0934	0935	0936	0937	0938	0939	0940	0941	0942	0943
3C_	0944 0960	0945 0961	0946 0962	0947 0963	0948 0964	0949 0965	0950 0966	0951	0952	0953	0954	0955	0956	0957	0958	0959
3D_	0976	0977	0978	0979	0980	0981	0982	0967 0983	0968 0984	0969 0985	0970 0986	$0971 \\ 0987$	0972 0988	0973 0989	0974 0990	0975 0991
3E_ 3F_	0992 1008	0993 1009	0994 1010	0995 1011	0996 1012	0997 1013	0998 1014	0999	1000	1001	1002	1003	1004	1005	1006	1007
	1000	1003	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023
1																
40	0	1	2	3	4	5	6	7	8	9	A	В	С	D	E	F
40_ 41_	0 1024 1040	1 1025 1041	2 1026 1042	3 1027 1043	1028 1044	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039
41_ 42_	1024 1040 1056	1025 1041 1057	1026 1042 1058	1027 1043 1059	1028 1044 1060	1029 1045 1061	1030 1046 1062	1031 1047 1063	1032 1048 1064	1033 1049 1065	1034 1050 1066	1035 1051 1067	1036 1052 1068	1037 1053 1069	1038 1054 1070	1039 1055 1071
41_ 42_ 43_	1024 1040 1056 1072	1025 1041 1057 1073	1026 1042 1058 1074	1027 1043 1059 1075	1028 1044 1060 1076	1029 1045 1061 1077	1030 1046 1062 1078	1031 1047 1063 1079	1032 1048 1064 1080	1033 1049 1065 1081	1034 1050 1066 1082	1035 1051 1067 1083	1036 1052 1068 1084	1037 1053 1069 1085	1038 1054 1070 1086	1039 1055 1071 1087
41_ 42_	1024 1040 1056 1072 1088 1104	1025 1041 1057 1073 1089 1105	1026 1042 1058 1074 1090 1106	1027 1043 1059 1075 1091 1107	1028 1044 1060	1029 1045 1061	1030 1046 1062	1031 1047 1063	1032 1048 1064	1033 1049 1065	1034 1050 1066	1035 1051 1067	1036 1052 1068	1037 1053 1069	1038 1054 1070 1086 1102	1039 1055 1071 1087 1103
41_ 42_ 43_ 44_ 45_ 46_	1024 1040 1056 1072 1088 1104 1120	1025 1041 1057 1073 1089 1105 1121	1026 1042 1058 1074 1090 1106 1122	1027 1043 1059 1075 1091 1107 1123	1028 1044 1060 1076 1092 1108 1124	1029 1045 1061 1077 1093 1109 1125	1030 1046 1062 1078 1094 1110 1126	1031 1047 1063 1079 1095 1111 1127	1032 1048 1064 1080 1096 1112 1128	1033 1049 1065 1081 1097 1113 1129	1034 1050 1066 1082 1098 1114 1130	1035 1051 1067 1083 1099 1115 1131	1036 1052 1068 1084 1100 1116 1132	1037 1053 1069 1085 1101 1117 1133	1038 1054 1070 1086 1102 1118 1134	1039 1055 1071 1087 1103 1119 1135
41_ 42_ 43_ 44_ 45_	1024 1040 1056 1072 1088 1104 1120 1136	1025 1041 1057 1073 1089 1105 1121 1137	1026 1042 1058 1074 1090 1106 1122 1138	1027 1043 1059 1075 1091 1107 1123 1139	1028 1044 1060 1076 1092 1108 1124 1140	1029 1045 1061 1077 1093 1109 1125 1141	1030 1046 1062 1078 1094 1110 1126 1142	1031 1047 1063 1079 1095 1111 1127 1143	1032 1048 1064 1080 1096 1112 1128 1144	1033 1049 1065 1081 1097 1113 1129 1145	1034 1050 1066 1082 1098 1114 1130 1146	1035 1051 1067 1083 1099 1115 1131 1147	1036 1052 1068 1084 1100 1116 1132 1148	1037 1053 1069 1085 1101 1117 1133 1149	1038 1054 1070 1086 1102 1118 1134 1150	1039 1055 1071 1087 1103 1119 1135 1151
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_	1024 1040 1056 1072 1088 1104 1120 1136 1152	1025 1041 1057 1073 1089 1105 1121 1137 1153	1026 1042 1058 1074 1090 1106 1122 1138 1154	1027 1043 1059 1075 1091 1107 1123 1139 1155	1028 1044 1060 1076 1092 1108 1124 1140	1029 1045 1061 1077 1093 1109 1125 1141 1157	1030 1046 1062 1078 1094 1110 1126 1142 1158	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1196	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4D_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243	1036 1052 1068 1084 1100 1116 1132 1148 1164 1186 1212 1228 1244	1037 1059 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1196 1212	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4D_ 4E_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1212 1228 1244 1260 1276	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4D_ 4E_ 50_ 51_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275	1036 1052 1068 1084 1100 1116 1132 1148 1164 1196 1212 1228 1244 1260 1276 1292 1308	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278	1039 1055 1071 1087 11087 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4D_ 4E_ 4F_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323	1036 1052 1068 1084 1100 1110 1132 1148 1164 1196 1212 1228 1244 1260 1276 1292 1308 1324	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4F_ 50_ 51_ 52_ 53_ 54_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1280 1296 1312 1328 1344	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1311 1347	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1349	1030 1046 1062 1078 1094 1112 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4D_ 4E_ 4F_ 50_ 51_ 52_ 53_ 54_ 55_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1296 1312 1328 1344 1360	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1236 1250 1266 1282 1298 1314 1330 1346 1362	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1336 1348 1364	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1337 1349 1365	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1366	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351 1367	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336 1352 1368	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1370	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1196 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356 1372	1037 1053 1069 1085 1101 11117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358 1374	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359 1375
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4D_ 4E_ 4F_ 50_ 51_ 52_ 53_ 54_ 56_ 57_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1280 1296 1312 1328 1344	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1311 1347	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1349	1030 1046 1062 1078 1094 1112 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359
41_ 42_ 43_ 44_ 45_ 48_ 49_ 4A_ 4B_ 4C_ 4F_ 50_ 51_ 52_ 53_ 54_ 55_ 56_ 57_ 58_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1286 1312 1328 1344 1360 1376 1392 1408	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361 1377 1393 1409	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346 1362 1378 1394 1410	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363 1379 1395 1411	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348 1364 1380 1396 1412	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1349 1365 1381 1397 1413	1030 1046 1062 1078 1094 11126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1368 1382 1398 1414	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351 1363 1363 1379 1415	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336 1352 1368 1384 1400 1416	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369 1385 1401 1417	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1376 1402 1418	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371 1403 1419	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356 1372 1388 1404 1420	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373 1389 1405 1421	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358 1374 1390 1406 1422	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359 1375 1391 1407 1423
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 4A_ 4B_ 4C_ 4B_ 50_ 51_ 52_ 53_ 54_ 55_ 56_ 57_ 58_ 55_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1296 1312 1328 1344 1360 1376 1392	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361 1377 1393	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346 1362 1378 1394 1410 1426	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363 1379 1395 1411	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348 1364 1380 1396	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1365 1381 1395 1413 1429	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1366 1382 1398	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1367 1383 1399 1415 1431	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1326 1336 1368 1384 1400 1416 1432	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369 1385 1401 1417 1433	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1370 1386 1402	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371 1387 1409 1419	1036 1052 1068 1084 1100 1116 1132 1148 1164 1196 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356 1372 1388 1404 1420 1436	1037 1053 1069 1085 1101 11117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373 1389 1405 1421 1437	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358 1374 1390 1406 1422 1438	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359 1375 1391 1407
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 4A_ 4B_ 4C_ 4B_ 50_ 51_ 52_ 53_ 54_ 55_ 56_ 57_ 58_ 58_ 58_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1296 1312 1328 1344 1360 1376 1392 1408 1424 1440 1456	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361 1377 1393 1409 1425 1441 1457	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346 1362 1378 1394 1416 1426 1442 1458	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363 1379 1395 1411 1427 1443 1459	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348 1364 1380 1396 1412 1428 1444 1460	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1349 1365 1381 1397 1413 1429 1445 1461	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1366 1382 1398 1414 1430 1446 1462	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351 1367 1383 1399 1415 1441 1447 1463	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336 1352 1368 1384 1400 1416	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369 1385 1401 1417	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1376 1402 1418	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371 1403 1419	1036 1052 1068 1084 1100 1116 1132 1148 1164 1180 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356 1372 1388 1404 1420	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373 1389 1405 1421	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358 1374 1390 1406 1422	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359 1375 1391 1407 1423
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 49_ 4A_ 4B_ 4C_ 4F_ 50_ 51_ 52_ 53_ 54_ 55_ 56_ 57_ 58_ 59_ 5A_ 5B_ 5C_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1296 1312 1328 1344 1360 1376 1392 1408 1424 1440 1456 1472	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361 1377 1393 1409 1425 1441 1457 1473	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1256 1266 1282 1298 1314 1330 1346 1362 1378 1394 1410 1426 1442 1458 1474	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363 1379 1395 1411 1443 1459 1475	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348 1364 1380 1396 1412 1424 1444 1460 1476	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1259 1285 1301 1317 1333 1349 1365 1381 1397 1413 1425 1445 1461 1477	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1366 1382 1398 1414 1430 1446 1462 1478	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351 1367 1383 1399 1415 1441 1447 1463 1479	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336 1352 1368 1352 1400 1416 1432 1448 1464 1480	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369 1385 1401 1417 1449 1465 1481	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1370 1481 1492 1418 1418 1450 1466 1482	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371 1403 1419 1435 1451 1467 1483	1036 1052 1068 1084 1100 1116 1132 1148 1164 1196 1212 1228 1244 1260 1276 1292 1308 1324 1340 1356 1372 1388 1404 1420 1436 1452 1468 1484	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373 1389 1405 1421 1433 1469 1485	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1294 1310 1326 1342 1358 1374 1390 1406 1422 1438 1454 1470 1486	1039 1055 1071 1087 1103 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1311 1327 1343 1359 1375 1391 1407 1423 1435 1455 1471 1487
41_ 42_ 43_ 44_ 45_ 46_ 47_ 48_ 4A_ 4B_ 4C_ 4B_ 50_ 51_ 52_ 53_ 54_ 55_ 56_ 57_ 58_ 58_ 58_	1024 1040 1056 1072 1088 1104 1120 1136 1152 1168 1184 1200 1216 1232 1248 1264 1296 1312 1328 1344 1360 1376 1392 1408 1424 1440 1456	1025 1041 1057 1073 1089 1105 1121 1137 1153 1169 1185 1201 1217 1233 1249 1265 1281 1297 1313 1329 1345 1361 1377 1393 1409 1425 1441 1457	1026 1042 1058 1074 1090 1106 1122 1138 1154 1170 1186 1202 1218 1234 1250 1266 1282 1298 1314 1330 1346 1362 1378 1394 1416 1426 1442 1458	1027 1043 1059 1075 1091 1107 1123 1139 1155 1171 1187 1203 1219 1235 1251 1267 1283 1299 1315 1331 1347 1363 1379 1395 1411 1427 1443 1459	1028 1044 1060 1076 1092 1108 1124 1140 1156 1172 1188 1204 1220 1236 1252 1268 1284 1300 1316 1332 1348 1364 1380 1396 1412 1428 1444 1460	1029 1045 1061 1077 1093 1109 1125 1141 1157 1173 1189 1205 1221 1237 1253 1269 1285 1301 1317 1333 1349 1365 1381 1397 1413 1429 1445 1461	1030 1046 1062 1078 1094 1110 1126 1142 1158 1174 1190 1206 1222 1238 1254 1270 1286 1302 1318 1334 1350 1366 1382 1398 1414 1430 1446 1462	1031 1047 1063 1079 1095 1111 1127 1143 1159 1175 1191 1207 1223 1239 1255 1271 1287 1303 1319 1335 1351 1367 1383 1399 1415 1441 1447 1463	1032 1048 1064 1080 1096 1112 1128 1144 1160 1176 1192 1208 1224 1240 1256 1272 1288 1304 1320 1336 1352 1368 1384 1400 1416 1432 1448 1464	1033 1049 1065 1081 1097 1113 1129 1145 1161 1177 1193 1209 1225 1241 1257 1273 1289 1305 1321 1337 1353 1369 1385 1401 1417 1433 1449 1465	1034 1050 1066 1082 1098 1114 1130 1146 1162 1178 1194 1210 1226 1242 1258 1274 1290 1306 1322 1338 1354 1370 1386 1402 1418 1434 1450 1466	1035 1051 1067 1083 1099 1115 1131 1147 1163 1179 1195 1211 1227 1243 1259 1275 1291 1307 1323 1339 1355 1371 1403 1419 1435 1451 1467	1036 1052 1068 1084 1100 1116 1132 1148 1164 1186 1212 1228 1244 1260 1276 1292 1308 1324 1340 1350 1372 1388 1404 1422 1436 1452 1468	1037 1053 1069 1085 1101 1117 1133 1149 1165 1181 1197 1213 1229 1245 1261 1277 1293 1309 1325 1341 1357 1373 1389 1405 1421 1437 1453 1469	1038 1054 1070 1086 1102 1118 1134 1150 1166 1182 1198 1214 1230 1246 1262 1278 1394 1310 1326 1342 1358 1374 1390 1406 1422 1438 1454 1470	1039 1055 1071 1087 11087 1119 1135 1151 1167 1183 1199 1215 1231 1247 1263 1279 1295 1311 1327 1343 1359 1375 1391 1407 1423 1435 1455 1471

j

<u>- '</u>	-0	1	2	3	4	5	6	7	8	9	A	В	С	D	Æ	F
60_	1536	1537	1538	1539	1540	1541	1542	1543	1544	1545	1546	1547 1563	1548 1564	1549 1565	1550 1566	1551 1567
61_ 62_	1552 1568	1553 15 <del>6</del> 9	1554 1570	1555 1571	$1556 \\ 1572$	1557 1573	1558 1574	1559 1575	1560 1576	1561 1577	1562 1578	1579	1580	1581	1582	1583
63_	1584	1585	1586	1587	1588	1589	1590	1591	1592 1608	1593 1609	1594 1610	1595 1611	1596 1612	1597 1613	1598 1614	1599 1615
64_ 65_	1600 1616	1601 1617	1602 1618	1603 1619	1604 1620	1605 1621	160 <del>6</del> 1622	1607 1623	1624	1625	1626	1627	1628	1629	1630	1631
66_	1632	1633 1649	1634 1650	1635 1651	1636 1652	1637 1653	1638 1654	1639 1655	1640 1656	1641 1657	1642 1658	1643 1659	1644 1660	1645 1661	1646 1662	1647 1663
67_ 68_	1648 1664	1665	1666	1667	1668	1669	1670	1671	1672	1673	1674	1675	1676	1677	1678	1679
69_ 6A_	1680 1696	1681 1697	1682 1698	1683 1699	1684 1700	1685 1701	1686 1702	1687 1703	1688 1704	1689 1705	1690 1706	1691 1707	1692 1708	1693 1709	1694 1710	1695 1711
6B_	1712	1713	1714	1715	1716	1717	1718	1719	1720	1721	1722	1723	1724	1725	1726	1727
6C_ 6D_	1728 1744	1729 1745	1730 1746	1731 1747	1732 1748	1733 1749	1734 1750	1735 1751	1736 1752	1737 1753	1738 1754	1739 1755	1740 1756	1741 1757	1742 1758	1743 1759
6E_	1760	1761	1762	1763	1764	1765	1766	1767	1768	1769	1770 1786	1771 1787	$1772 \\ 1788$	1773 1789	1774 1790	1775 1791
6F_	1776	1777	1778	1779	1780	1781	1782	1783	1784	1785 1801	1802	1803	1804	1805	1806	1807
70_ 71_	1792 1808	1793 1809	1794 1810	1795 1811	1796 1812	1797 1813	1798 1814	1799 1815	1800 1816	1817	1818	1819	1820	1821	1822	1823
72_	1824 1840	1825 1841	$1826 \\ 1842$	1827 1843	$1828 \\ 1844$	1829 1845	1830 1846	1831 1847	$1832 \\ 1848$	1833 1849	1834 1850	1835 1851	$1836 \\ 1852$	1837 1853	1838 1854	1839 1855
74_	1856	1857	1858	1859	1860	1861	1862	1863	1864	1865	1866	1867	1868	1869	1870	1871
75_ 76_	1872 1888	1873 1889	1874 1890	1875 1891	$1876 \\ 1892$	1877 1893	1878 1894	1879 1895	1880 1896	1881 1897	1882 1898	1883 1899	1884 1900	1885 1901	1886 1902	1887 1903
77_	1904	1905	1906	1907	1908	1909	1910	1911	1912	1913	1914	1915	1916	1917	1918	1919
78_ 79_	1920 1936	1921 1937	1922 1938	1923 1939	1924 1940	1925 1941	1926 1942	1927 1943	1928 1944	1929 1945	1930 1946	1931 1947	1932 1948	1933 1949	1934 1950	1935 1951
7A_ 7B_	1952	1953	1954	1955	1956	1957	1958	1959	1960 1976	1961 1977	1962 1978	1963 1979	1964 1980	1965 1981	1966 1982	1967 1983
7C_	1968 1984	1969 1985	1970 1986	1971 1987	1972 1988	1973 1989	1974 1990	1975 1991	1992	1993	1994	1995	1996	1997	1998	1999
7D_	2000	2001	2002	2003	2004	2005	2006	2007 2023	2008 2024	2009 2025	2010 2026	2011 2027	2012 2028	2013 2029	2014 2030	2015 2031
7E_	2016	2017	2018	2019	2020	2021	2022	2023								2047
7F_	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2041
			2034	2035 3	2036	2037 5	2038 6	2039	2040 8	9	A A	B	C C	D D	E	F
7F_ 80_	0 2048	2033 1 2049	2 2050	3 2051	4 2052	5 2053	6 2054	7 2055	8 2056	9 2057	A 2058	B 2059	C 2060	D 2061	E 2062	F 2063
7F_	0	2033	2	3 2051 2067 2083	4 2052 2068 2084	5 2053 2069 2085	6 2054 2070 2086	7 2055 2071 2087	8 2056 2072 2088	9 2057 2073 2089	A 2058 2074 2090	B 2059 2075 2091	C 2060 2076 2092	D 2061 2077 2093	E 2062 2078 2094	F 2063 2079 2095
80_ 81_ 82_ 83_	2032 0 2048 2064 2080 2096	2033 1 2049 2065 2081 2097	2 2050 2066 2082 2098	3 2051 2067 2083 2099	2052 2068 2084 2100	5 2053 2069 2085 2101	6 2054 2070 2086 2102	7 2055 2071 2087 2103	8 2056 2072 2088 2104	9 2057 2073 2089 2105	A 2058 2074 2090 2106	B 2059 2075 2091 2107	2060 2076 2092 2108	D 2061 2077 2093 2109	E 2062 2078 2094 2110	F 2063 2079 2095 2111
80_ 81_ 82_ 83_ 84_	2032 0 2048 2064 2080	2033 1 2049 2065 2081	2 2050 2066 2082	3 2051 2067 2083 2099 2115 2131	4 2052 2068 2084 2100 2116 2132	5 2053 2069 2085 2101 2117 2133	6 2054 2070 2086 2102 2118 2134	7 2055 2071 2087 2103 2119 2135	8 2056 2072 2088 2104 2120 2136	9 2057 2073 2089 2105 2121 2137	A 2058 2074 2090 2106 2122 2138	B 2059 2075 2091 2107 2123 2139	C 2060 2076 2092 2108 2124 2140	D 2061 2077 2093 2109 2125 2141	E 2062 2078 2094 2110 2126 2142	F 2063 2079 2095 2111 2127 2143
80_ 81_ 82_ 83_ 84_ 85_ 86_	2032 0 2048 2064 2080 2096 2112 2128 2144	2033 1 2049 2065 2081 2097 2113 2129 2145	2 2050 2066 2082 2098 2114 2130 2146	3 2051 2067 2083 2099 2115 2131 2147	2052 2068 2084 2100 2116 2132 2148	5 2053 2069 2085 2101 2117 2133 2149	6 2054 2070 2086 2102 2118 2134 2150	7 2055 2071 2087 2103 2119 2135 2151	8 2056 2072 2088 2104 2120	9 2057 2073 2089 2105 2121	A 2058 2074 2090 2106 2122	B 2059 2075 2091 2107 2123	C 2060 2076 2092 2108 2124	D 2061 2077 2093 2109 2125	E 2062 2078 2094 2110 2126	F 2063 2079 2095 2111 2127
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_	2032 0 2048 2064 2080 2096 2112 2128	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177	2 2050 2066 2082 2098 2114 2130 2146 2162 2178	3 2051 2067 2083 2099 2115 2131 2147 2163 2179	4 2052 2068 2084 2100 2116 2132 2148 2164 2180	5 2053 2069 2085 2101 2117 2133 2149 2165 2181	6 2054 2070 2086 2102 2118 2134 2150 2166 2182	7 2055 2071 2087 2103 2119 2135 2151 2167 2183	8 2056 2072 2088 2104 2120 2136 2152 2168 2184	9 2057 2073 2089 2105 2121 2137 2153 2169 2185	A 2058 2074 2090 2106 2122 2138 2154 2170 2186	B 2059 2075 2091 2107 2123 2139 2155 2171 2187	C 2060 2076 2092 2108 2124 2140 2156 2172 2188	D 2061 2077 2093 2109 2125 2141 2157 2173 2189	E 2062 2078 2094 2110 2126 2142 2158 2174 2190	F 2063 2079 2095 2111 2127 2143 2159 2175 2191
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2196	5 2053 2069 2085 2101 2117 2133 2149 2165	6 2054 2070 2086 2102 2118 2134 2150 2166	7 2055 2071 2087 2103 2119 2135 2151 2167	8 2056 2072 2088 2104 2120 2136 2152 2168	9 2057 2073 2089 2105 2121 2137 2153 2169	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219	C 2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 8B_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2219 2212 2228	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229	8 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214 2230	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231	8 2056 2072 2088 2104 2120 2136 2152 2168 2184 2200 2216 2232	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2233	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235	2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 8B_ 8C_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2196 2212 2228 2244	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213	8 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215	8 2056 2072 2088 2104 2120 2136 2152 2168 2184 2200 2216	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2233 2249 2265	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267	2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 8B_ 8C_ 8D_ 8E_	2032 0 2048 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275	4 2052 2068 2084 2100 2116 2132 2148 2164 2196 2212 2228 2228 2244 2260 2276	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277	6 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214 2230 2246 2262 2278	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279	8 2056 2072 2088 2104 2120 2136 2152 2168 2200 2216 2232 2248 2264 2280	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2233 2249 2265 2281	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251	2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 8B_ 8C_ 8F_	0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2256 2272 2288	2033 1 2049 2065 2081 2097 2113 2129 2146 2177 2193 2209 2225 2241 2257 2273 2289	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2196 2212 2228 2244 2260 2276 2292	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293	6 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214 2230 2246 2262 2278 2294	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295	8 2056 2072 2088 2104 2120 2136 2152 2168 2184 2200 2216 2232 2248 2264	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2233 2249 2265	A 2058 2074 2090 2106 21128 2154 2170 2186 2202 2218 2234 2256 2282	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283	2060 2076 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2300 2316	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319
80_81_82_83_84_85_86_87_88_89_8A_8B_8C_8D_8E_90_91_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305 2321	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306 2322	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2295 2211 2227 2243 2259 2275 2291 2307 2323	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2212 2228 2244 2260 2276 2292 2308 2324	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325	6 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214 2230 2246 2262 2278 2278 2294 2310 2326	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327	8 2056 2072 2088 2104 2120 2136 2152 2168 2224 2200 2216 2232 2248 2264 2280 2296 2312 2328	9 2057 2073 2089 2105 2121 2137 2153 2169 2281 2201 2217 2233 2249 2265 2281 2297 2313 2329	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2268 2288 2298 2314 2330	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2315	2060 2076 2096 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2300 2316 2332	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318 2334	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 8B_ 8C_ 8F_ 90_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2291 2227 2241 2227 2249 2275 2291 2307	4 2052 2068 2084 2100 2116 2132 2148 2164 2196 2212 2228 2244 2260 2276 2292 2308	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309	8 2054 2070 2086 2102 2118 2134 2150 2168 2182 2219 2214 2230 2246 22278 2294 2310	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295	8 2056 2072 2088 2104 2120 2136 2152 2168 2200 2216 2232 2248 2264 2280 2296	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2237 2249 2265 2281 2297	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2347 2363	2060 2076 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2300 2316	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318 2334 2350 2366	F 2063 2079 2095 2111 2127 2143 2155 2191 2207 2223 2239 2255 2271 2287 2303 2315 2351 2367
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 8B_ 8C_ 8F_ 90_ 91_ 92_ 93_ 94_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2336 2352 2368	2033 1 2049 2065 2081 2097 2113 2129 2146 2177 2193 2209 2225 2241 2257 2273 2289 2305 2337 2353 2369	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2308 2322 2338 2354 2370	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291 2307 2323 2339 2355 2371	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2212 2228 2244 2260 2276 2292 2308 2344 2340 2356 2372	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2225 2261 2277 2293 2309 2325 2341 2357 2373	8 2054 2070 2086 2102 2118 2134 2150 2166 2182 2198 2214 2230 2246 2262 2278 2294 2310 2326 2342 2358 2374	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327 2327 2327 2327 2327 2327 2327	8 2056 2072 2088 2104 2120 2136 2152 2168 2200 2216 2232 2248 2264 2280 2296 2312 2328 2344 2360 2376	9 2057 2073 2089 2105 2121 2137 2153 2169 2185 2201 2217 2237 2249 2265 2281 2297 2313 2329 2345 2361 2377	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298 2314 2336 2346 2362 2378	B 2059 2075 2091 2107 2123 2139 2155 2171 2203 2219 2235 2251 2267 2283 2299 2315 2331 2347 2363 2379	C 2060 2076 2096 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2284 2300 2316 2332 2348 2364 2380	D 2061 2077 2093 2109 2125 2141 2157 2173 2285 2221 2237 2253 2269 2285 2301 2317 2317 2333 2349 2365 2381	E 2062 2078 2094 2110 2126 2142 2158 2174 2296 2222 2238 2254 2270 2286 2302 2318 2334 2350 2366 2382	F 2063 2079 2095 2111 2127 2143 2159 2175 2297 2223 2239 2255 2271 2287 2303 2319 2351 2367 2383
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 8E_ 8F_ 90_ 91_ 92_ 93_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2384	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2205 2225 2241 2257 2273 2289 2305 2301 2337 2353	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2308 2338 2354	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291 2303 2333 2355	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2196 2212 2228 2224 2260 2276 2292 2328 2324 2340 2356	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2305 2341 2357	6 2054 2070 2086 2102 2118 2134 2150 2166 2182 2218 2214 2230 2246 2262 2278 2278 2294 2310 2326 2342 2352 2374 2390 2406	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2311 2327 2343 2359 2375 2391 2407	8 2056 2072 2088 2104 2120 2136 2152 2168 2294 2200 2216 2232 2248 2264 2280 2296 2312 2328 2344 2360 2376 2392 2408	9 2057 2073 2089 2105 2121 2137 2153 2169 2281 2201 2217 2233 2249 2265 2281 2297 2313 2329 2345 2361 2377 2393 2409	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298 2314 2330 2346 2362 2378 2394 2410	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2347 2363 2379 2395 2411	2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2284 2300 2316 2332 2348 2364 2380 2396 2412	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365 2381 2397 2413	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 238 2254 2270 2286 2302 2318 2334 2350 2366 2388 2414	F 2063 2079 2095 2111 2117 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335 2351 2367 2389 2415
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 8B_ 8C_ 8E_ 91_ 91_ 92_ 93_ 94_ 95_ 96_ 97_	0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2340 2400 2416	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305 2321 2337 2353 2369 2389 2389 2401 2417	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306 2322 2338 2354 2376 2402 2418	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291 2307 2323 2339 2355 2371 2403 2419	2052 2068 2084 2100 2116 2132 2148 2164 2196 2212 2228 2224 2260 2276 2292 2308 2324 2340 2356 2378 2378 2378 2378 2404 2420	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325 2341 2357 2373 2389 2405 2421	6 2054 2076 2086 2102 2118 2134 2156 2166 2182 2198 2214 2230 2246 2262 2278 2294 2310 2326 2342 2358 2342 2358 2342 2369 2406 2406 2422	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327 2343 2359 2375 2391 2407 2423	8 2056 2072 2088 2104 2120 2136 2158 2184 2200 2216 2232 2248 2264 2280 2296 2312 2328 2344 2360 2376 2376 2408 2408 2408	9 2057 2073 2089 2105 2121 2137 2169 2185 2201 2217 2233 2249 2265 2281 2297 2313 2329 2345 2361 2377 2377 2379 2409 2425	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298 2314 2330 2346 2362 2378 2394 2410 2426	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2347 2363 2379 2395 2411 2427	C 2060 2076 2092 2108 2124 2140 2152 2188 2204 2220 2236 2252 2268 2284 2300 2316 2332 2348 2364 2380 2396 2412 2428	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365 2381 2397 2413 2429	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2266 2302 2318 2334 2350 2366 2382 2398 2414 2430	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335 2351 2367 2383 2399 2415 2431
80_81_82_83_84_85_86_87_88_89_8A_8B_91_92_93_94_95_96_97_98_99_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2384 2400	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305 2321 2337 2353 2369 2389 2389 2389 2401	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306 2322 2338 2354 2370 2386 2402	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2295 2211 2227 2243 2259 2275 2291 2307 2323 2339 2355 2371 2387 2403	4 2052 2068 2084 2100 2116 2132 2148 2164 2180 2212 2228 2244 2260 2276 2292 2308 2324 2340 2356 2372 2388 2404	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325 2341 2357 2373 2389 2405 2405 2437 2453	8 2054 2070 2086 2102 2118 2134 2150 2168 2182 2219 2214 2230 2246 22278 2294 2310 2326 2342 2358 2374 2390 2406 2422 2438 2438 2454	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327 2327 2339 2359 2407 2407 2439 2455	8 2056 2072 2088 2104 2120 2136 2152 2168 2200 2216 2232 2248 2264 2280 2296 2312 2328 2344 2360 2376 2392 2408 2408 2408 2409 2408 2409 2408 2409 2409 2409 2409 2409 2409 2409 2409	9 2057 2073 2089 2105 2121 2137 2153 2169 2217 2233 2249 2265 2281 2297 2313 2329 2349 2361 2377 2393 2409 2441 2457	2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298 2314 2330 2346 2362 2378 2394 2410 2442 2442	2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2331 2347 2363 2379 2395 2411 2443 2443 2459	2060 2076 2076 2079 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2284 2300 2316 2332 2346 2396 2412 2444 2460	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365 2381 2397 2413 2429 2445 2461	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318 2334 2350 2366 2382 2398 2414 2440 2462	F  2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335 2351 2349 2415 2447 2463
80_ 81_ 82_ 83_ 84_ 85_ 86_ 87_ 88_ 89_ 8A_ 90_ 91_ 92_ 93_ 94_ 95_ 96_ 97_ 98_ 99_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2440 2416 2448 2440 2416 2448 2448 2464	2033 1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305 2321 2337 2353 2369 2385 2401 2417 2417 2438 2449 2465	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306 2322 2338 2354 2370 2386 2402 2418 2450 2466	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2291 2227 2243 2259 2275 2291 2307 2323 2355 2371 2387 2403 2419 2435 2451 2467	2052 2068 2084 2100 2116 2132 2148 2164 2180 2212 2228 2244 2260 2276 2292 2308 2324 2340 2356 2372 2388 2404 2420 2436 2452 2468	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325 2341 2373 2389 2405 2421 2453 2469	8 2054 2070 2086 2102 2118 2134 2150 2168 2182 22198 2214 2230 2246 2262 2278 2294 2310 2326 2342 2358 2374 2390 2406 2422 2438 2454 2470	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327 2343 2357 2343 2359 2475 2423 2423 2455 2471	8 2056 2072 2088 2104 2120 2136 2152 2168 2292 2248 2260 2296 2296 2312 2328 2344 2364 2376 2376 2392 2408 2424 2440 2456 2472	9 2057 2073 2089 2105 2121 2137 2153 2169 2281 2201 2217 2233 2249 2265 2281 2297 2313 2329 2345 2345 2377 2393 2409 2425 2457 2473	2058 2074 2090 2106 2122 2138 2154 2176 2202 2218 2234 2250 2262 2298 2314 2330 2346 2362 2378 2394 2410 2426 2452 2458 2452	2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2331 2347 2343 2379 2395 2411 2427 2443 2459 2475	C 2060 2076 2092 2108 2124 2140 2156 2177 2188 2204 2226 2252 2268 2284 2300 2316 2332 2348 2364 2380 2396 2412 2428 2444	D 2061 2077 2093 2109 2125 2141 2157 2173 2285 2221 2237 2253 2269 2285 2301 2317 23349 2365 2381 2397 2413 2429 2445	E 2062 2078 2094 2110 2126 2142 2158 2174 2296 2222 2338 2254 2370 2366 2382 2398 2414 2430 2446	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2351 2367 2383 2399 2415 2431 2447
80_81_82_83_84_85_86_87_88_89_91_92_93_94_95_96_97_98_99_9A_98_9C_	2032 0 2048 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2384 2400 2418 24240 2432 2448	2033 1 2049 2065 2081 2097 2113 2129 2146 2177 2193 2209 2225 2241 2257 2273 2289 2305 2337 2353 2369 2385 2401 2417 2433 2449	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2302 2338 2354 2370 2386 2402 2418 2434 2450 2482 2498	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291 2303 2339 2355 2371 2387 2403 2419 2435 2451 2463 2499	2052 2068 2084 2100 2116 2132 2148 2164 2180 2196 2212 2228 2244 2260 2276 2292 2308 2324 2340 2356 2372 2388 2442 2442 2452 2452 2468 2452	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325 2341 2357 2373 2389 2405 2421 2437 2453 2463 2485 2501	6 2054 2070 2086 2102 2118 2134 2156 2166 2182 2198 2214 2230 2246 2278 2294 2310 2326 2342 2358 2374 2390 2406 2422 2438 2454 2454 2456 2456 2456 2456 2456 2456	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2324 2324 2325 2375 2343 2439 2455 2471 2487 2503	8 2056 2072 2088 2104 2120 2136 2152 2168 2216 2226 2226 2248 2264 2280 2296 2312 2328 2344 2360 2376 2376 2408 2408 2408 2408 2408 2408 2408 2408	9 2057 2073 2089 2105 2121 2137 2153 2169 2285 2201 2217 2237 2249 2265 2281 2297 2313 2329 2345 2361 2377 2393 2409 2425 241 2457 247 2489 2505	2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2282 2298 2314 2330 2346 2362 2378 2394 2442 2458 2442 2458 24490 2506	B 2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2331 2347 2363 2379 2395 2411 2427 2443 2459 2475 2491 2507	2080 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2284 2300 2316 2336 2348 2364 2380 2412 2428 2444 2460 2476 2492 2508	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365 2381 2397 2413 2429 2445 2461 2477 2493 2509	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318 2334 2350 2366 2382 2446 2462 2478 2494 2510	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335 2367 2383 2399 2415 2447 2463 2447 2463 2479 2495
80_81_82_83_84_85_86_87_88_89_8A_95_91_92_93_94_95_99A_98_98_98_	2032 0 2048 2064 2080 2096 2112 2128 2144 2160 2176 2192 2208 2224 2240 2256 2272 2288 2304 2320 2336 2352 2368 2340 2416 2416 2424 2440 2448 2448	2033  1 2049 2065 2081 2097 2113 2129 2145 2161 2177 2193 2209 2225 2241 2257 2273 2289 2305 2369 2385 2401 2417 2433 2449 2465 2481	2 2050 2066 2082 2098 2114 2130 2146 2162 2178 2194 2210 2226 2242 2258 2274 2290 2306 2322 2338 2354 2370 2386 2402 2418 2436 2466 2482	3 2051 2067 2083 2099 2115 2131 2147 2163 2179 2195 2211 2227 2243 2259 2275 2291 2307 2323 2339 2355 2371 2387 2403 2419 2435 2451 2467 2483	2052 2068 2084 2100 2116 2132 2148 2164 2180 2212 2228 2244 2260 2276 2292 2308 2324 2340 2356 2372 2388 2404 2420 2436 2436 2436 2436 2436 2436 2436 2436	5 2053 2069 2085 2101 2117 2133 2149 2165 2181 2197 2213 2229 2245 2261 2277 2293 2309 2325 2341 2373 2389 2405 2421 2453 2469 2485	8 2054 2070 2086 2102 2118 2134 2150 2168 2182 22198 2214 2230 2246 2262 2278 2294 2310 2326 2342 2358 2374 2390 2406 2422 2438	7 2055 2071 2087 2103 2119 2135 2151 2167 2183 2199 2215 2231 2247 2263 2279 2295 2311 2327 2343 2359 2375 2391 2407 2423 2439 2455 2471 2487	8 2056 2072 2088 2104 2120 2136 2152 2168 2200 2216 2232 2248 2264 2280 2296 2312 2328 2344 2360 2376 2376 2392 2408 2424 2450 2450 2450 2450 2472 2488	9 2057 2073 2089 2105 2121 2137 2153 2169 2281 2201 2217 2233 2249 2265 2281 2297 2313 2329 2345 2340 2425 249 2425 249 2425 249 2425 249 249 249 249 249 249 249 249 249 249	A 2058 2074 2090 2106 2122 2138 2154 2170 2186 2202 2218 2234 2250 2266 2282 2298 2314 2330 2346 2362 2378 2394 2410 2426 2442 2458 2474 2490	2059 2075 2091 2107 2123 2139 2155 2171 2187 2203 2219 2235 2251 2267 2283 2299 2315 2347 2367 2475 2475 2475 2475	2060 2076 2092 2108 2124 2140 2156 2172 2188 2204 2220 2236 2252 2268 2332 2348 2300 2316 2332 2348 2349 2442 2428 2428	D 2061 2077 2093 2109 2125 2141 2157 2173 2189 2205 2221 2237 2253 2269 2285 2301 2317 2333 2349 2365 2381 2397 2413 2429 2445 2461 2477 2493	E 2062 2078 2094 2110 2126 2142 2158 2174 2190 2206 2222 2238 2254 2270 2286 2302 2318 2334 2350 2366 2382 2398 2414 2430 2446 2462 2478 2494	F 2063 2079 2095 2111 2127 2143 2159 2175 2191 2207 2223 2239 2255 2271 2287 2303 2319 2335 2351 2367 2383 2399 2415 2431 2447 2463 2479 2495

	<u> </u>	1	2	3	4	5	6	7	8	9	A	В	С	D	E	F
A0₹	2560	2561	2562	2563	2564	2565	2566	2567	2568	2569	2570	2571	2572	2573	2574	2575
A1_ A2_	2576 2592	2577 2593	2578 2594	2579 2595	2580 2596	2581 2597	2582 2598	2583	2584	2585	2586	2587	2588	2589	2590	2591
A3_	2608	2609	2610	2611	2612	2613	2614	2599 2 <b>6</b> 15	2600 2616	$\frac{2601}{2617}$	2602 2618	2603 2619	2604 2620	$\frac{2605}{2621}$	2606 2622	$2607 \\ 2623$
A4_	2624	2625	2626	2627	2628	2629	2630	2631	2632	2633	2634	2635	2636	2637	2638	2639
A5_ A6_	2640 2656	2641 2657	2642 2658	2643 2659	2644 2660	2645 2661	2646 2662	2647 2663	2648 2664	2649 2665	2650 2666	2651 2667	2652 2668	2653 2669	2654 2670	$2655 \\ 2671$
A7_	2672	2673	2674	2675	2676	2677	2678	2679	2680	2681	2682	2683	2684	2685	2686	2687
A8_ A9_	2688 2704	2689 2705	2690 2706	2691 2707	2692 2708	2693 2709	2694 2710	$\frac{2695}{2711}$	2696	2697	2698	2699	2700	2701	2702	2703
AA_	2720	2721	2722	2723	2724	2725	2726	2727	$\frac{2712}{2728}$	$\frac{2713}{2729}$	$\frac{2714}{2730}$	$\frac{2715}{2731}$	$\frac{2716}{2732}$	$\frac{2717}{2733}$	$\frac{2718}{2734}$	$2719 \\ 2735$
AB_ AC_	2736 2752	2737	2738	2739	2740	2741	2742	2743	2744	2745	2746	2747	2748	2749	2750	2751
AD_	2768	$2753 \\ 2769$	$\frac{2754}{2770}$	$2755 \\ 2771$	$\frac{2756}{2772}$	$\frac{2757}{2773}$	2758 2774	$2759 \\ 2775$	2760 2776	$\frac{2761}{2777}$	$\frac{2762}{2778}$	$\frac{2763}{2779}$	$2764 \\ 2780$	$2765 \\ 2781$	$\frac{2766}{2782}$	2767 2783
AE_ AF_	2784 2800	2785	2786	2787	2788	2789	2790	2791	2792	2793	2794	2795	2796	2797	2798	2799
B0_	1	2801	2802	2803	2804	2805	2806	2807	2808	2809	2810	2811	2812	2813	2814	2815
B1_	2816 2832	2817 2833	2818 2834	2819 2835	2820 2836	2821 2837	2822 2838	2823 2839	$\frac{2824}{2840}$	$2825 \\ 2841$	$2826 \\ 2842$	2827 2843	2828 2844	$2829 \\ 2845$	2830 2846	$2831 \\ 2847$
B2_ B3_	2848	2849	2850	2851	2852	2853	2854	2855	2856	2857	2858	2859	2860	2861	2862	2863
B4	2864	2865 2881	2866 2882	2867 2883	2868 2884	2869 2885	2870 2886	2871 2887	2872 2888	2873 2889	2874	2875	2876	2877	2878	2879
B5_	2896	2897	2898	2899	2900	2901	2902	2903	2904	2905	2890 2906	2891 2907	2892 2908	2893 2909	2894 2910	$2895 \\ 2911$
B6_ B7_	2912 2928	2913 2929	2914 2930	$\frac{2915}{2931}$	2916 2932	2917 2933	2918 2934	2919 2935	2920 2936	2921 2937	2922 2938	2923 2939	2924 2940	2925	2926	2927
B8_	2944	2945	2946	2947	2948	2949	2950	2951	2952	2953	2954	2955	2956	2941 2957	2942 2958	2943 2959
B9_ BA_	2960 2976	2961 2977	2962	2963	2964	2965	2966	2967	2968	2969	2970	2971	2972	2973	2974	2975
BB_	2992	2993	2978 2994	2979 2995	2980 2996	2981 2997	2982 2998	2983 2999	2984 3000	2985 3001	2986 3002	2987 3003	2988 3004	2989 3005	2990 3006	2991 3007
BC_	3008	3009	3010	3011	3012	3013	3014	3015	3016	3017	3018	3019	3020	3021	3022	3023
BD_ BE_	3024	3025 3041	3026 3042	3027 3043	3028 3044	3029 3045	3030 3046	3031 3047	3032 3048	3033 3049	3034 3050	3035 3051	3036 3052	3037 3053	3038 3054	3039 3055
BF_	3056	3057	3058	3059	3060	3061	3062	3063	3064	3065	3066	3067	3068	3069	3070	3071
	0	1	2	3	4	5	6	7	8	9	A	В	С	D	E	F
C0_	3072	3073	3074	3075	3076	3077	3078	3079	3080	3081	3082	B 3083	C 3084	D 3085	E 3086	F 3087
C0_ C1_ C2_	3072 3088	3073 3089	3074 3090	3075 3091	3076 3092	3077 3093	3078 3094	3079 3095	3080 3096	3081 3097	3082 3098	3083 3099	3084 3100	3085 3101	3086 3102	3087 3103
C1_ C2_ C3_	3072 3088 3104 3120	3073 3089 3105 3121	3074	3075	3076	3077	3078	3079	3080	3081	3082	3083	3084	3085	3086	3087
C1_ C2_ C3_ C4_	3072 3088 3104 3120 3136	3073 3089 3105 3121 3137	3074 3090 3106 3122 3138	3075 3091 3107 3123 3139	3076 3092 3108 3124 3140	3077 3093 3109 3125 3141	3078 3094 3110 3126 3142	3079 3095 3111 3127 3143	3080 3096 3112 3128 3144	3081 3097 3113 3129 3145	3082 3098 3114 3130 3146	3083 3099 3115 3131 3147	3084 3100 3116 3132 3148	3085 3101 3117 3133 3149	3086 3102 3118 3134 3150	3087 3103 3119 3135 3151
C1_ C2_ C3_ C4_ C5_ C6_	3072 3088 3104 3120 3136 3152 3168	3073 3089 3105 3121 3137 3153 3169	3074 3090 3106 3122 3138 3154 3170	3075 3091 3107 3123 3139 3155 3171	3076 3092 3108 3124 3140 3156 3172	3077 3093 3109 3125	3078 3094 3110 3126	3079 3095 3111 3127	3080 3096 3112 3128	3081 3097 3113 3129	3082 3098 3114 3130	3083 3099 3115 3131	3084 3100 3116 3132 3148 3164	3085 3101 3117 3133 3149 3165	3086 3102 3118 3134 3150 3166	3087 3103 3119 3135 3151 3167
C1_ C2_ C3_ C4_ C5_ C6_ C7_	3072 3088 3104 3120 3136 3152 3168 3184	3073 3089 3105 3121 3137 3153 3169 3185	3074 3090 3106 3122 3138 3154 3170 3186	3075 3091 3107 3123 3139 3155 3171 3187	3076 3092 3108 3124 3140 3156 3172 3188	3077 3093 3109 3125 3141 3157 3173 3189	3078 3094 3110 3126 3142 3158 3174 3190	3079 3095 3111 3127 3143 3159 3175 3191	3080 3096 3112 3128 3144 3160 3176 3192	3081 3097 3113 3129 3145 3161 3177 3193	3082 3098 3114 3130 3146 3162 3178 3194	3083 3099 3115 3131 3147 3163 3179 3195	3084 3100 3116 3132 3148 3164 3180 3196	3085 3101 3117 3133 3149 3165 3181 3197	3086 3102 3118 3134 3150 3166 3182 3198	3087 3103 3119 3135 3151 3167 3183 3199
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_	3072 3088 3104 3120 3136 3152 3168	3073 3089 3105 3121 3137 3153 3169	3074 3090 3106 3122 3138 3154 3170	3075 3091 3107 3123 3139 3155 3171 3187 3203	3076 3092 3108 3124 3140 3156 3172 3188 3204	3077 3093 3109 3125 3141 3157 3173 3189 3205	3078 3094 3110 3126 3142 3158 3174 3190 3206	3079 3095 3111 3127 3143 3159 3175 3191 3207	3080 3096 3112 3128 3144 3160 3176 3192 3208	3081 3097 3113 3129 3145 3161 3177 3193 3209	3082 3098 3114 3130 3146 3162 3178 3194 3210	3083 3099 3115 3131 3147 3163 3179 3195 3211	3084 3100 3116 3132 3148 3164 3180 3196 3212	3085 3101 3117 3133 3149 3165 3181 3197 3213	3086 3102 3118 3134 3150 3166 3182 3198 3214	3087 3103 3119 3135 3151 3167 3183 3199 3215
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235	3076 3092 3108 3124 3140 3156 3172 3188 3204 3220 3236	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251	3076 3092 3108 3124 3140 3156 3172 3188 3204 3220 3236 3252	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264 3280	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3236 3252 3268 3284	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254 3270 3286	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3235 3271 3287	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262 3278 3294	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3300	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254 3270 3286 3302	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307	3084 3100 3116 3132 3148 3164 3196 3212 3228 3244 3260 3276 3292 3308	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262 3278 3294 3310	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_ CE_ CF_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264 3280 3296	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315	3076 3092 3108 3124 3140 3172 3188 3204 3220 3236 3252 3268 3284 3300 3316	3077 3093 3109 3125 3141 3157 3173 3205 3221 3237 3253 3269 3285 3301 3317	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254 3270 3286 3302 3318	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 324 324 3256 3272 3288 3304 3320	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321	3082 3098 3114 3130 3146 3162 3178 3194 3216 3226 3242 3258 3274 3290 3306 3322	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309 3325	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_ CE_ CF_ D0_ D1_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264 3286 3312 3328 3344	3073 3089 3105 3121 3137 3153 3165 3217 3233 3249 3265 3281 3297 3313 3329 3345	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3262 3298 3314 3330 3346	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3331 3347	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3300 3316 3332 3348	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3263 3265 3301 3317 3333 3349	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3335 3351	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3336 3352	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321 3337 3353	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3322 3338 3354	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3340 3356	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309	3086 3102 3118 3134 3156 3166 3182 3198 3214 3232 3278 3294 3310 3326 3342 3358	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_ CE_ CF_	3072 3088 3104 3120 3136 3158 3168 3216 3232 3248 3264 3280 3296 3312 3328	3073 3089 3105 3121 3137 3159 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3254 3254 3266 3282 3298 3314	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3331 3347 3363	3076 3092 3108 3124 3140 3156 3172 3188 3204 3220 3236 3252 3268 3284 3300 3316 3332 3348 3364	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365	3078 3094 3110 3126 3142 3158 3174 3190 3206 3228 3238 3254 3270 3286 3302 3318 3334 3350 3366	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3335 3351 3367	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3336 3352 3368	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3325 3337 3353 3369	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3326 3338 3354 3370	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3340 3356 3372	3085 3101 3117 3133 3149 3165 3181 3197 3213 32245 3245 3261 3277 3293 3309 3325 3341 3357 3373	3086 3102 3118 3134 3156 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3342 3358 3374	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CD_ CC_ CD_ CE_ D1_ D2_ D3_ D4_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3296 3312 3328 3344 3360 3376 3392	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3330 3346 3362 3378 3394	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3347 3363 3379 3395	3076 3092 3108 3124 3140 3156 3172 3188 3204 3220 3236 3252 3268 3284 3300 3316 3332 3348 3364 3380 3396	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3335 3351	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3336 3352	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321 3337 3353	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3322 3338 3354	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3340 3356 3372 3388	3085 3101 3117 3133 3149 3165 3181 3197 3213 32245 3245 3261 3277 3293 3309 3325 3341 3357 3373 3389	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3342 3358 3374 3390	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_ CE_ CF_ D0_ D1_ D2_ D3_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264 3296 3312 3328 3344 3360 3376 3376 3392 3408	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393 3409	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3330 3346 3362 3378 3394 3410	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3347 3363 3379 3395 3411	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3396 3316 3332 3348 3364 3389 3396 3412	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413	3078 3094 3110 3126 3142 3158 3174 3190 3202 3238 3254 3270 3286 3302 3318 3334 3350 3366 3382 3398 3414	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3335 3351 3367 3387 3389 3415	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3352 3368 3352 3368 3340 3416	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3283 3305 3321 3337 3353 3369 3385 3401 3417	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3302 3338 3354 3370 3380 3402 3418	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3293 3307 3323 3339 3355 3371 3387 3403 3419	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3356 3372 3386 3372 3386 3404 3404 3420	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309 3325 3341 3357 3373 3389 3405 3405 3421	3086 3102 3118 3134 3156 3166 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3342 3358 3374 3390 3406 3406 3422	3087 3103 3119 3135 3151 3167 3183 3199 3215 3237 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3423
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ CD_ CF_ D1_ D2_ D3_ D4_ D5_ D6_ D7_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3296 3312 3328 3314 3360 3376 3392 3408 3424 3400	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3345 3361 3377 3393 3409 3425 3441	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3330 3346 3362 3378 3394	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3347 3363 3379 3395	3076 3092 3108 3124 3140 3156 3172 3188 3204 3220 3236 3252 3268 3284 3300 3316 3332 3348 3364 3380 3396	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254 3270 3286 3302 3318 3334 3356 3366 3382 3398	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3335 3351 3367 3383 3399	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 324 3256 3272 3288 3304 3320 3336 3358 3368 3384 3400	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321 3337 3357 3369 3385 3401	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3258 3274 3290 3306 3322 3338 3354 3370 3386 3402	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371 3387 3403	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3340 3356 3372 3388 3404	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309 3325 3341 3357 3373 3389 3405	3086 3102 3118 3134 3156 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3342 3358 3374 3390 3406	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ D1_ D2_ D3_ D4_ D5_ D6_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3296 3312 3328 3344 3360 3376 3392 3408 3404 3404 3456	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393 3409 3425 3411 3457	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3250 3266 3282 3298 3314 3330 3346 3362 3378 3394 3410 3426 3426 3426 3442	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3347 3363 3379 3395 3411 3427 3443 3459	3076 3092 3108 3124 3140 3156 3172 3188 3204 3252 3268 3252 3268 3284 3300 3316 3332 3348 3364 3380 3396 3412 3428 3444 3460	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413 3429 3445 3461	3078 3094 3110 3126 3142 3158 3174 3190 3206 3222 3238 3254 3270 3286 3302 3318 334 3350 3366 3382 3398 3414 3430 3446 3462	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3235 3255 3271 3287 3303 3319 3355 3351 3367 3383 3399 3415 3431 3447 3463	3080 3096 3112 3128 3144 3166 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3336 3352 3368 3352 340 3416 3416 3416 3416 3416 3416 3416 3416	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321 3337 3353 3369 3385 3401 3417 3433 3449 3465	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3258 3274 3290 3306 3326 3338 3354 3370 3386 3402 3418 3434 3450 3466	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371 3387 3403 3413 3435 3435 3451 3467	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3372 3388 3404 3452 3468	3085 3101 3117 3133 3149 3165 3181 3197 3213 32245 3241 3293 3309 3325 3341 3357 3373 3389 3405 3421 3437 3437 3453 3469	3086 3102 3118 3134 3156 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3374 3390 3406 3422 3438 3454 3454 3470	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3423 3439 3435 3439
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CE_ D1_ D2_ D1_ D2_ D4_ D5_ D6_ D7_ D8_ D9_ DA_	3072 3088 3104 3120 3136 3152 3168 3152 3168 3232 3248 3264 3232 3248 3296 3312 3328 3344 3360 3376 3372 3408 3424 3440 3456 3472 3488	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393 3409 3425 3441 3457 3473 3489	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3330 3346 3362 3378 3394 3494 3410 3426 3442	3075 3091 3107 3123 3139 3155 3171 3187 3203 3219 3235 3251 3267 3283 3299 3315 3347 3363 3379 3395 3411 3427 3443	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3306 3316 3332 3348 3364 3380 3412 3428 3428	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413 3429 3445	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318 334 3350 3366 3382 3398 3414 3430 3446	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3239 3255 3271 3287 3303 3319 3351 3367 3383 3399 3415 3431 3447	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3256 3272 3288 3304 3320 3352 3368 3352 3368 3416 3432 3448 3464 3480	3081 3097 3113 3129 3145 3161 3177 3193 3205 3225 3241 3257 3273 3289 3305 3321 3337 3353 3365 3385 3417 3433 3447 3433 3445 3481	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3322 3338 3354 3370 3386 3402 3418 3434 3450	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371 3387 3419 3435 3451 3467 3483	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3398 3324 3356 3372 3388 3404 3436 3436 3436 3436 3436 3436 3436	3085 3101 3117 3133 3149 3165 3181 3197 3213 3229 3245 3261 3277 3293 3309 3325 3341 3357 3373 3389 3421 3437 3453 3469 3485	3086 3102 3118 3134 3150 3166 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3342 3358 3374 3390 3406 3422 3438 3454 3470 3486	3087 3103 3119 3135 3151 3167 3183 3199 3215 3237 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3423 3439 3455 3471 3487
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CB_ CC_ D1_ D2_ D3_ D4_ D5_ D6_ D7_ D8_ D9_ DA_ DB_	3072 3088 3104 3120 3136 3152 3168 3152 3168 3232 3248 3264 3232 3248 3296 3312 3328 3344 3360 3376 3376 3408 3424 3440 3456 3472 3488 3504	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393 3409 3425 3441 3457 3473 3473 3489 3505	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3346 3362 3378 3394 3410 3426 3452 3458 3458 3458 3458 3458 3458 3458 3458	3075 3091 3107 3123 3139 3155 3171 3187 3203 3215 3251 3267 3283 3299 3315 3347 3363 3379 3411 3427 3443 3459 3475 3491 3507	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3300 3316 3348 3364 3380 3396 3412 3428 3444 3460 3476 3492 3508	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413 3429 3445 3461 3477 3493 3509	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318 3334 3350 3366 3382 3398 3414 3430 3446 3462 3478 3494 3510	3079 3095 3111 3127 3143 3159 3175 3191 3207 3239 3255 3271 3287 3303 3319 3351 3367 3383 3399 3415 3431 3447 3463 3475 3495 3511	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3352 3368 3352 3368 340 3416 3432 3448 3448 3464 3496 3512	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3305 3305 3305 3305 3305 3321 3353 349 349 3485 3481 3497 3513	3082 3098 3114 3130 3146 3162 3178 3194 3210 3224 3258 3274 3290 3306 3302 3354 3370 3386 3492 3418 3434 3450 3462 3498 3514	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371 3387 3403 3413 3435 3435 3451 3467	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3372 3388 3404 3452 3468	3085 3101 3117 3133 3149 3165 3181 3197 3213 32245 3241 3293 3309 3325 3341 3357 3373 3389 3405 3421 3437 3437 3453 3469	3086 3102 3118 3134 3156 3182 3198 3214 3230 3246 3262 3278 3294 3310 3326 3374 3390 3406 3422 3438 3454 3454 3470	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3423 3439 3435 3439
C1_C2_C3_C4_C5_C6_C5_C6_C7_C8_C8_C8_C6_C7_CB_C6_C7_C5_C6_C7_C6_C6_C7_C7_C8_C6_C7_C7_C8_C8_C7_C8_C8_C8_C8_C8_C8_C8_C8_C8_C8_C8_C8_C8_	3072 3088 3104 3120 3136 3152 3168 3184 3200 3216 3232 3248 3264 3280 3296 3312 3328 3344 3360 3376 3392 3408 3424 3400 3456 3478 3478 3478 3478 3478 3478 3478 3478	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3345 3361 3377 3393 3445 345 341 3457 3473 3489 3485 3481 3487 3473 3487 3487 3487 3487 3488 3487 3488 3487 3488 3488	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 330 3346 3362 3378 3394 3410 3426 3426 3426 3426 3470 3426 3470 3426 3470 3426 3470 3426 3470 3426 3470 3470 3470 3470 3470 3470 3470 3470	3075 3091 3107 3123 3139 3155 3171 3187 3203 3215 3251 3267 3283 3299 3315 3347 3363 3379 3395 3417 3427 3443 3459 3475 3491 3475 3491 3475 3491 3475 3491 3475 3491 3475 3491 3475 3491 3475 3491 3491 3491 3491 3491 3491 3491 3491	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3306 3316 3348 3348 3348 3444 3460 3476 3492 3508 3524	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413 3429 3445 3461 3473 3493 3509 3525	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318 3350 3366 3382 3398 3414 3430 3446 3462 3478 3498 3510 3526	3079 3095 3111 3127 3143 3159 3175 3191 3207 3223 3235 3271 3287 3303 3319 3351 3367 3383 3393 3415 3431 3447 3463 3475 3495 3511 3527	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3256 3272 3288 3304 3352 3368 3352 3368 3384 3406 3416 3432 3448 3496 3512 3528	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3289 3305 3321 3337 3353 3369 3385 3401 3417 3433 3449 3465 3481 3497 3513 3529	3082 3098 3114 3130 3146 3162 3178 3194 3210 3226 3242 3258 3274 3290 3306 3322 3338 3354 3370 3386 3402 3418 3434 3450 3466 3482 3498 3514 3530	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3339 3355 3371 3387 3403 3419 3435 3451 3467 3483 3499 3515 3531	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3356 3372 3388 3404 3452 3468 3452 3468 3452 3500 3516 3532	3085 3101 3117 3133 3149 3165 3181 3197 3213 3225 3261 3277 3293 3325 3341 3357 3373 3389 3405 3421 3437 3453 3469 3485 3501 3517 3533	3086 3102 3118 3134 3154 3166 3182 3198 3214 3236 3246 3262 3278 3294 3310 3326 3358 3374 3390 3406 3422 3438 3454 3470 3486 3502 3518 3534	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3427 3439 3455 3471 3487 3503 3519 3535
C1_ C2_ C3_ C4_ C5_ C6_ C7_ C8_ C9_ CA_ CD_ CE_ CD_ D1_ D2_ D3_ D4_ D5_ D6_ D7_ D8_ D9_ DB_ DC_	3072 3088 3104 3120 3136 3152 3168 3152 3168 3232 3248 3264 3232 3248 3296 3312 3328 3344 3360 3376 3376 3408 3424 3440 3456 3472 3488 3504	3073 3089 3105 3121 3137 3153 3169 3185 3201 3217 3233 3249 3265 3281 3297 3313 3329 3345 3361 3377 3393 3409 3425 3441 3457 3473 3473 3489 3505	3074 3090 3106 3122 3138 3154 3170 3186 3202 3218 3234 3250 3266 3282 3298 3314 3346 3362 3378 3394 3410 3426 3452 3458 3458 3458 3458 3458 3458 3458 3458	3075 3091 3107 3123 3139 3155 3171 3187 3203 3215 3251 3267 3283 3299 3315 3347 3363 3379 3411 3427 3443 3459 3475 3491 3507	3076 3092 3108 3124 3140 3156 3172 3188 3204 3236 3252 3268 3284 3300 3316 3348 3364 3380 3396 3412 3428 3444 3460 3476 3492 3508	3077 3093 3109 3125 3141 3157 3173 3189 3205 3221 3237 3253 3269 3285 3301 3317 3333 3349 3365 3381 3397 3413 3429 3445 3461 3477 3493 3509	3078 3094 3110 3126 3142 3158 3174 3190 3206 3223 3238 3254 3270 3286 3302 3318 3334 3350 3366 3382 3398 3414 3430 3446 3462 3478 3494 3510	3079 3095 3111 3127 3143 3159 3175 3191 3207 3239 3255 3271 3287 3303 3319 3351 3367 3383 3399 3415 3431 3447 3463 3475 3495 3511	3080 3096 3112 3128 3144 3160 3176 3192 3208 3224 3240 3256 3272 3288 3304 3320 3352 3368 3352 3368 340 3416 3432 3448 3448 3464 3496 3512	3081 3097 3113 3129 3145 3161 3177 3193 3209 3225 3241 3257 3273 3305 3305 3305 3305 3305 3321 3353 349 349 3485 3481 3497 3513	3082 3098 3114 3130 3146 3162 3178 3194 3210 3224 3258 3274 3290 3306 3302 3354 3370 3386 3492 3418 3434 3450 3462 3498 3514	3083 3099 3115 3131 3147 3163 3179 3195 3211 3227 3243 3259 3275 3291 3307 3323 3355 3371 3387 3403 3419 3435 3451 3463 3499 3515	3084 3100 3116 3132 3148 3164 3180 3196 3212 3228 3244 3260 3276 3292 3308 3324 3356 3372 3388 3404 3452 3468 3452 3468 3452 3468 3500 3516	3085 3101 3117 3133 3149 3165 3181 3197 3213 32245 3261 3277 3293 3305 3325 3341 3357 3373 3389 3405 3421 3437 3453 3463 3465 3501 3517	3086 3102 3118 3134 3154 3166 3182 3198 3214 3234 3246 3262 3278 3390 3326 3358 3374 3390 3402 3438 3454 3454 3476 3486 3502 3518	3087 3103 3119 3135 3151 3167 3183 3199 3215 3231 3247 3263 3279 3295 3311 3327 3343 3359 3375 3391 3407 3423 3439 3455 3471 3487 3487 3503 3519

_	- 0	1	2	3	4	5	6	7	8	9	A	В	С	D	E	F
E0_ E1_ E2_	3584 3600 3616	3585 3601 3617	3586 3602 3618	3587 3603 3619	3588 3604 3620	3589 3605 3621 3637	3590 3606 3622 3638	3591 3607 3623 3639	3592 3608 3624 3640	3593 3609 3625 3641	3594 3610 3626 3642	3595 3611 3627 3643	3596 3612 3628 3644	3597 3613 3629 3645	3598 3614 3630 3646	3599 3615 3631 3647
E3_ E4_ E5_ E6_	3632 3648 3664 3680 3696	3633 3649 3665 3681 3697	3634 3650 3666 3682 3698	3635 3651 3667 3683 3699	3636 3652 3668 3684 3700	3653 3669 3685 3701	3654 3670 3686 3702	3655 3671 3687 3703	3656 3672 3688 3704	3657 3673 3689 3705	3658 3674 3690 3706	3659 3675 3691 3707	3660 3676 3692 3708	3661 3677 3693 3709	3662 3678 3694 3710	3663 3679 3695 3711
E7_ E8_ E9_ EA_ EB_	3712 3728 3744 3760	3713 3729 3745 3761	3714 3730 3746 3762	3715 3731 3747 3763	3716 3732 3748 3764	3717 3733 3749 3765	3718 3734 3750 3766	3719 3735 3751 3767	3720 3736 3752 3768	3721 3737 3753 3769	3722 3738 3754 3770	3723 3739 3755 3771	3724 3740 3756 3772	3725 3741 3757 3773	3726 3742 3758 3774	3727 3743 3759 3775
EC_	3776	3777	3778	3779	3780	3781	3782	3783	3784	3785	3786	3787	3788	3789	3790	3791
ED_	3792	3793	3794	3795	3796	3797	3798	3799	3800	3801	3802	3803	3804	3805	3806	3807
EE_	3808	3809	3810	3811	3812	3813	3814	3815	3816	3817	3818	3819	3820	3821	3822	3823
EF_	3824	3825	3826	3827	3828	3829	3830	3831	3832	3833	3834	3835	3836	3837	3838	3839
F0_	3840	3841	3842	3843	3844	3845	3846	3847	3848	3849	3850	3851	3852	3853	3854	3855
F1_	3856	3857	3858	3859	3860	3861	3862	3863	3864	3865	3866	3867	3868	3869	3870	3871
F2_	3872	3873	3874	3875	3876	3877	3878	3879	3880	3881	3882	3883	3884	3885	3886	3887
F3_	3888	3889	3890	3891	3892	3893	3894	3895	3896	3897	3898	3899	3900	3901	3902	3903
F4_	3904	3905	3906	3907	3908	3909	3910	3911	3912	3913	3914	3915	3916	3917	3918	3919
F5_	3920	3921	3922	3923	3924	3925	3926	3927	3928	3929	3930	3931	3932	3933	3934	3935
F6_	3936	3937	3938	3939	3940	3941	3942	3943	3944	3945	3946	3947	3948	3949	3950	3951
F7_	3952	3953	3954	3955	3956	3957	3958	3959	3960	3961	3962	3963	3964	3965	3966	3967
F8_	3968	3969	3970	3971	3972	3973	3974	3975	3976	3977	3978	3979	3980	3981	3982	3983
F9_	3984	3985	3986	3987	3988	3989	3990	3991	3992	3993	3994	3995	3996	3997	3998	3999
FA_	4000	4001	4002	4003	4004	4005	4006	4007	4008	4009	4010	4011	4012	4013	4014	4015
FB_	4016	4017	4018	4019	4020	4021	4022	4023	4024	4025	4026	4027	4028	4029	4030	4031
FC_	4032	4033	4034	4035	4036	4037	4038	4039	4040	4041	4042	4043	4044	4045	4046	4047
FD_	4048	4049	4050	4051	4052	4053	4054	4055	4056	4057	4058	4059	4060	4061	4062	4063
FE_	4064	4065	4066	4067	4068	4069	4070	4071	4072	4073	4074	4075	4076	4077	4078	4079
FF_	4080	4081	4082	4083	4084	4085	4086	4087	4088	4089	4090	4091	4092	4093	4094	4095

#### Powers of Two Table

```
2n
                                                     2-n
                                               n
                                               0
                                       1
                                                     1.0
                                                     0.5
                                                     0.25
0.125
                                       8
                                      16
                                                     0.0625
                                      32
                                               5
                                                     0.03125
                                      64
                                                     0.01562 5
                                    128
                                                     0.00781 25
                                                     0.00390 625
                                    512
                                                     0.00195 3125
                                                     0.00097 65625
                                 1.024
                                             10
                                 2,048
                                             11
                                                     0.00048 82812 5
                                                    0.00024 41406 25
0.00012 20703 125
0.00006 10351 5625
                                 4.096
                                             12
                                 8,192
                                             13
                               16,384
                               32,768
                                             15
                                                     0.00003 05175 78125
                               65,536
                                                     0.00001 52587 89062 5
                                                    0.00000 76293 94531 25
0.00000 38146 97265 625
0.00000 19073 48632 8125
                              131,072
                                             17
                              262,144
524,288
                                             18
                                                    0.00000 09536 74316 40625
0.00000 04768 37158 20312 5
0.00000 02384 18579 10156 25
                           1,048,576
                                             20
                           2,097,152
                                             21
                           4,194,304
                                             22
                          8.388.608
                                             23
                                                    0.00000 01192 09289 55078 125
                         16,777,216
                                             24
                                                     0.00000 00596 04644 77539 0625
                         33,554,432
                                             2.5
                                                    0.00000 00298 02322 38769 53125
                         67,108,864
                                                    0.00000 00149 01161 19384 76562 5
0.00000 00074 50580 59692 38281 25
                                             26
                       268,435,456
                                             28
                                                    0.00000 00037 25290 29846 19140 625
0.00000 00018 62645 14923 09570 3125
                    536,870,912
1,073,741,824
2,147,483,648
                                             30
                                                    0.00000 00009 31322 57461 54785 15625
                                             31
                                                    0.00000 00004 65661 28730 77392 57812 5
                    4,294,967,296
                                             32
                                                    0.00000 00002 32830 64365 38696 28906 25
                   8,589,934,592
17,179,869,184
                                                    0.00000 00001 16415 32182 69348 14453 125
0.00000 00000 58207 66091 34674 07226 5625
                                             33
                   34,359,738,368
                                             35
                                                    0.00000 00000 29103 83045 67337 03613 28125
                   68,719,476,736
                                                    0.00000 00000 14551 91522 83668 51806 64062 5
0.00000 00000 07275 95761 41834 25903 32031 25
0.00000 00000 03637 97880 70917 12951 66015 625
                                             36
                 137,438,953,472
                 274,877,906,944
                                             38
                 549,755,813,888
                                            39
                                                    0.00000 00000 01818 98940 35458 56475 83007 8125
              1,099,511,627,776
2,199,023,255,552
4,398,046,511,104
                                            40
                                                    0.00000 00000 00909 49470 17729 28237 91503 90625
                                                    0.00000 00000 00454 74735 08864 64118 95751 95312 5
0.00000 00000 00227 37367 54432 32059 47875 97656 25
0.00000 00000 00113 68683 77216 16029 73937 98828 125
                                            41
                                             42
              8,796,093,022,208
                                             43
            17,592,186,044,416
                                            44
                                                    0.00000 00000 00056 84341 88608 08014 86968 99414 0625
                                                    0.00000 00000 00028 42170 94304 04007 43484 49707 03125
0.00000 00000 00014 21085 47152 02003 71742 24853 51562 5
0.00000 00000 00007 10542 73576 01001 85871 12426 75781 25
            35,184,372,088,832 70,368,744,177,664
                                            45
                                            46
           140,737,488,355,328
           281,474,976,710,656
                                            48
                                                    0.00000 00000 00003 55271 36788 00500 92935 56213 37890 625
           562,949,953,421,312
                                                    0.00000 00000 00001 77635 68394 00250 46467 78106 68945 3125 0.00000 00000 00000 88817 84197 00125 23233 89053 34472 65625
                                            49
        1,125,899,906,842,624
       2,251,799,813,685,248
                                                    0.00000 00000 00000 44408 92098 50062 61616 94526 67236 32812 5
                                            51
                                                   0.00000 00000 00000 22204 46049 25031 30808 47263 33618 16406 25 0.00000 00000 00000 11102 23024 62515 65404 23631 66809 08203 125 0.00000 00000 00000 05551 11512 31257 82702 11815 83404 54101 5625 0.00000 00000 00000 02775 55756 15628 91351 05907 91702 27050 78125
       4,503,599,627,370,496
      9,007,199,254,740,992 18,014,398,509,481,984
                                            53
                                            54
      36,028,797,018,963,968
                                            55
      72,057,594,037,927,936
                                                    0.00000 00000 00000 01387 77878 07814 45675 52953 95851 13525 39062 5 0.00000 00000 00000 00693 88939 03907 22837 76476 97925 56762 69531 25 0.00000 00000 00000 00346 94469 51953 61418 88238 48962 78381 34765 625
                                            56
    144,115,188,075,855,872
    288,230,376,151,711,744
576,460,752,303,423,488
                                            5.8
                                            59
                                                    0.00000 00000 00000 00173 47234 75976 80709 44119 24481 39190 67382 8125
 1,152,921,504,606,846,976
                                            60
                                                    0.00000 00000 00000 00086 73617 37988 40354 72059 62240 69595 33691 40625
 2,305,843,009,213,693,952
                                                    0.00000 00000 00000 00003 36808 68994 20177 36029 81120 34797 66845 70312 5 0.00000 00000 00000 00001 68404 34497 10088 68014 90560 17398 83422 85156 25
                                            61
   ,611,686,018,427,387,904
                                            62
 9,223,372,036,854,775,808
                                            63
                                                    0.00000 00000 00000 00010 84202 17248 55044 34007 45280 08699 41711 42578 125
18,446,744,073,709,551,616
                                            64
                                                   0.00000 00000 00000 00005 42101 08624 27522 17003 72640 04349 70855 71289 0625
```

### Powers of Two Table

n

```
18,446,744,073,709,551,616
                               36,893,488,147,419,103,232
                                                                         65
                             73.786,976,294,838,206,464
                                                                         68
                              295,147,905,179,352,825,856
                           590,295,810,358,705,651,712
1,180,591,620,717,411,303,424
                                                                         69
                           2,361,183,241,434,822,606,848
                                                                         71
                                                                         72
                           4,722,366,482,869,645,213,696
                           9,444,732,965,739,290,427,392
                                                                         73
                          18,889,465,931,478,580,854,784
                          37,778,931,862,957,161,709,568
                          75,557,863,725,914,323,419,136
                                                                         76
                        151,115,727,451,828,646,838,272
302,231,454,903,657,293,676,544
                         604,462,909,807,314,587,353,088
                                                                         79
                      1,208,925,819,614,629,174,706,176
                                                                         80
                      2,417,851,639,229,258,349,412,352
                                                                         81
                      4,835,703,278,458,516,698,824,704
                                                                         82
                                                                         83
                      9,671,406,556,917,033,397,649,408
                     19,342,813,113,834,066,795,298,816
                                                                         84
                     38,685,626,227,668,133,590,597,632
77,371,252,455,336,267,181,195,264
                                                                         85
                                                                          86
                   154,742,504,910,672,534,362,390,528
                                                                         87
                   309,485,009,821,345,068,724,781,056
                                                                          88
                    618,970,019,642,690,137,449,562,112
                                                                          RQ
                 1,237,940,039,285,380,274,899,124,224
                                                                          90
                 2,475,880,078,570,760,549,798,248,448
                                                                          92
                 4,951,760,157,141,521,099,596,496,896
                9,903,520,314,283,042,199,192,993,792
19,807,040,628,566,084,398,385,987,584
                                                                          93
                                                                          94
                39,614,081,257,132,168,796,771,975,168
                                                                          95
                79,228,162,514,264,337,593,543,950,336
                                                                          96
              158,456,325,028,528,675,187,087,900,672
                                                                          97
               316,912,650,057,057,350,374,175,801,344
                                                                          98
               633.825,300,114,114,700,748,351,602,688
                                                                          99
                                                                        100
            1,267,650,600,228,229,401,496,703,205,376
2,535,301,200,456,458,802,993,406,410,752
5,070,602,400,912,917,605,986,812,821,504
                                                                        101
                                                                         102
           10,141,204,801,825,835,211,973,625,643,008
                                                                         103
           20,282,409,603,651,670,423,947,251,286,016
                                                                         104
           40,564,819,207,303,340,847,894,502,572,032
81,129,638,414,606,681,695,789,005,144,064
                                                                         105
                                                                         106
          162,259,276,829,213,363,391,578,010,288,128
                                                                         108
         324,518,553,658,426,726,783,156,020,576,256
                                                                         109
       649,037,107,316,853,453,566,312,041,152,512
1,298,074,214,633,706,907,132,624,082,305,024
2,596,148,429,267,413,814,265,248,164,610,048
                                                                         110
                                                                         111
       5,192,296,858,534,827,628,530,496,329,220,096
                                                                         112
     10,384,593,717,069,655,257,060,992,658,440,192
20,769,187,434,139,310,514,121,985,316,880,384
                                                                         113
      41,538,374,868,278,621,028,243,970,633,760,768
                                                                         115
    83,076,749,736,557,242,056,487,941,267,521,536
166,153,499,473,114,484,112,975,882,535,043,072
332,306,998,946,228,968,225,951,765,070,086,144
                                                                         117
                                                                         118
                                                                         119
     664,613,997,892,457,936,451,903,530,140,172,288
  1,329,227,995,784,915,872,903,807,060,280,344,576
                                                                         120
2,658.455,991,569.831,745.807,614,120,560,689,152
5,316.911,983,139,663,491,615,228,241,121,378,304
10,633.823,966,279,326,983,230,456,482,242,756,608
                                                                         121
                                                                         123
                                                                         124
 21,267,647,932,558,653,966,460,912,964,485,513,216
 42,535,295,865,117,307,932,921,825,928,971,026,432
                                                                         125
                                                                         126
 85,070,591,730,234,615,865,843,651,857,942,052,864
170,141,183,460,469,231,731,687,303,715,884,105,728
                                                                         128
340.282.366.920.938.463,463,374,607,431,768,211,456
```

Decimal   Hex   Binary   EBCDIC   ASCII   Change   PTTC/EBCD   PTTC/ Correspondence	<del></del>	т —	1	1	T	1		
Decimal   Hex   Binary   BECDIC   ASCII   change   PTTC/EBCD   Correspondence		1				Eight bit	<u> </u>	
Decimal New Binary   EBCDIC   ASCII   Change   PTTC/EBCD   Correspondence	<b>!</b> _			l		data inter-		PTTC/
0	Decimal	Hex	Binary	EBCDIC	ASCII	change	PTTC/EBCD	
2	0	00	0000 0000	NUL	NUL	NUL		
2			0001	SOH	soн	NUL	space	space
3			0010	STX	STX		_	•
S				1	•	@		,,
6	1				1		2	2
7			i e	1	-	space		
8	3		1	1	1		_	
9				DEL				
10				DIE			4	5
11	l '	1		1	1	D (over menitus)		
12	1		1		•	P (odd pority)		
13	3	1					3	1
14	13		1				6	
15	14	0E	1			o (odd parity)		
16	15	0F	1				,	8
17	16	10	0001 0000	DLE	I .		8	4
19	17	11	0001	DC1	DC1		_	
20			0010	DC2	DC2	H (even parity)	•	
21	1		0011	TM	DC3	H (odd parity)	9	l 0
22		1		RES	DC4	( (even parity)		
23					1	( (odd parity)		
24						ĺ	(EOA)	(EOA),9
25								
26			1	l i				
27				4 .				
28						l <u></u>		i i
29						X		
30	1						upper case	
31						8		_ ⊼
32				1 1			(FOT)	(TOT)
33						1		
34						FOT	<b>.</b>	'
35								İ i
36       24       0100       BYP       \$       S (even parity)       S       n         37       25       0101       LF       %       S (odd parity)       s       n         38       26       0110       ETB       &       t       u         39       27       0111       ESC       '       u       e         40       28       1000       (       u       e         41       29       1001       )       u       e         42       2A       1010       SM       *       v       d         43       2B       1011       CU2       +       T         44       2C       1100       ,       w       k         45       2D       1101       ENQ       -       4         46       2E       1111       BEL       /       x       c         48       30       0011       000       form feed       y       1         50       32       0010       SYN       2       x       c         51       33       0011       3       L       L	3				#		1	v
37		24		BYP		S (even parity)	7	. ^ l
38	37	25				S (odd parity)	S	n
39		26	0110	ETB		' '		
41       29       1001       )       u       e         42       2A       1010       SM       *       v       d         43       2B       1011       CU2       +       T       w       k         44       2C       1100       ,       4       w       k         45       2D       1101       ENQ       -       4         46       2E       1110       ACK       .         47       2F       1111       BEL       /       x       c         48       30       0011 0000       0       form feed       y       1         50       32       0010       SYN       2       z       h         51       33       0011       3       L       L         52       34       0100       PN       4       L			0111	ESC	•			
42       2A       1010       SM       *       v       d         43       2B       1011       CU2       +       T       w       k         44       2C       1100       ,       4       w       k         45       2D       1101       ENQ       -       4         46       2E       1110       ACK       .         47       2F       1111       BEL       /       x       c         48       30       0011 0000       0       form feed       y       1         50       32       0010       SYN       2       z       h         51       33       0011       3       L       L         52       34       0100       PN       4       L					(			
43       2B       1011       CU2       +       T         44       2C       1100       ,       4         45       2D       1101       ENQ       -       4         46       2E       1110       ACK       .         47       2F       1111       BEL       /       x       c         48       30       0011 0000       0       form feed       y       1         50       32       0010       SYN       2       z       h         51       33       0011       3       L       L         52       34       0100       PN       4       L						ļ	u	
44       2C       1100       ,       ,       4       w       k         45       2D       1101       ENQ       -       4       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .							v	d l
45				CU2	+	T		
46       2E       1110       ACK       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .       .<				ENC			w	k
47     2F     1111     BEL     /     oform feed form feed     x     c       48     30     0011 0000     1     form feed form feed     y     1       50     32     0010     SYN     2     z     h       51     33     0011     3     L       52     34     0100     PN     4						4		
48     30     0011 0000     0001       49     31     0001     0001       50     32     0010     SYN     2       51     33     0011     3       52     34     0100     PN     4   form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed form feed feed form feed feed form feed feed feed feed feed feed feed fee								
49     31     0001     1     form feed     y     1       50     32     0010     SYN     2     z     h       51     33     0011     3     L       52     34     0100     PN     4     L				DEL		form food	Х	c
50   32   0010   SYN   2							17	
51 33 0011 3 L 52 34 0100 PN 4				SYN		rom reed		
52   34   0100   PN   4				~~~		_L	L	"
				PN		_		İ
53   35   0101   RS   5   ,						<b>,</b>		
54   36   0110   UC   6						İ		

1					Eight bit		
	- 1				data inter-		PTTC/
Decimal	Hex	Binary	<b>EBCDIC</b>	ASCII	change	PTTC/EBCD	Correspondence
55	37	0011 0111	EOT	7		(S) (SOA), comma	ъ
56	38	1000		8			
	39	1001		9		1	
	3A	1010	CITA	:	\ (even parity) \ (odd parity)	index	index
	3B 3C	1011 1100	CU3 DC4	;	< (even parity)	ilidex	HIGGA
	3D	1101	NAK	=	< (odd parity)	(B) (EOB)	
	3E	1110		>			
63	3F	1111	SUB	?	Ì		•
	40	0100 0000	space	@	EOA	N .,-	!
	41 42	0001 0010		A B	B (even parity)		
	43	0010		C	B (odd parity)	i	m
	44	0100		D	" (even parity)		
	45	0101		E	" (odd parity)	k	
	46	0110		F		1	v
	47	0111		G			
	48	1000		H I		m	,
	49 4A	1001 1010	¢	l _J	ļ	n	r
	4B	1011	۲.	K	R		
	4C	1100	<	L	j	0	i
	4D	1101	(	M	2		
	4E	1110	+	N			
	4F	1111	]	0	line feed	p	a
	50	0101 0000	&	P Q	line feed	q	o
	51 52	0001		R	Interced	r	s
83	53	0010		S	J		
	54	0100		Т			
85	55	0101	Ì	U	*		
86	56	0110		v		•	
87	57	0111		W		\$	w
88	58	1000		X			
89	59 5A	1001 1010	!	Z	Z (even parity)		
90 91	5A 5B	1010	\$	โ	Z (odd parity)	CRLF	CRLF
92	5C	1100	*	1	: (even parity)		
93	5D	1101	)	j	: (odd parity)	backspace	backspace
94	5E	1110	;	Λ		idle	idle
95	5F	1111	<u> </u>	-			
96	60	0110 0000	-,		ACK	&	j
97	61 62	0001 0010	/	a b		a	g
98 99	63	0010	ł	c	F	-	
100	64	0100		d		ъ	
101	65	0101		e	&		
102	66	0110	1	f			
103	67	0111		g h		c d	f p
104	68	1000 1001		i i		u u	F
105	69 6A	1010	1:	j	V (even parity)		
106 107	6B	1011	1.	k	V (odd parity)	e	
107	6C	1100	%	1	6 (even parity)		_
109	6D	1101	-	m	6 (odd parity)	f	q
110	6E	1110	>	n		g	comma
111	6F	1111	?	0		h	1 /
112	70	0111 0000 0001		p q	shift out	<i>"</i>	<u>'</u>
113 114	71 72	0001		r	N (even parity)		1
	1	0010	1	s	N (odd parity)	i	у
115	73	0011					

		<del> </del>	1	·	r =		
	]		İ		Eight bit		
Decimal	Hex	Binary	EBCDIC	ASCII	data inter- change	PTTC/EBCD	PTTC/
117	75	0111 0101	- DODIO			111C/EBCD	Correspondence
118	76	0111		u v	. (odd parity)	(A) maria	
119	77	0111		l w		y,period	-
120	78	1000		x			
121	79	1001		y			
122	7A	1010	l:	z		horiz tab	tab
123	7B	1011	#	{	<b>†</b>	110112 140	lau
124	7C	1100	@	1		lower case	lower case
125	7D	1101	,	}	>		lower case
126	7E	1110	=	<b>~</b> ′			
127	7F	1111	"	DEL	:	delete	
128	80	1000 0000					
129	81	0001	a		SOM	space	space
130	82	0010	b		A (even parity)	=	±, [
131	83	0011	c		A (odd parity)		
132	84	0100	d		! (even parity)	<	@
133	85	0101	е		! (odd parity)		
134	86	0110	f				
135	87	0111	g			;	#
136	88	1000	h		X-ON	:	%
137	89	1001	i				
138	8A	1010					
139 140	8B 8C	1011			Q	%	&
140	8D	1100 1101			•	,	1 .
142	8E	11101			1		¢
143	8F	1110				>	*
144	90	1001 0000			horiz tab	*	
145	91	0001	j		horiz tab	*	\$
146	92	0010	k		nonz tao		
147	93	0011	1	Î	I	(	)
148	94	0100	m		-		'
149	95	0101	n	İ	)	)	Z
150	96	0110	0		, i	(EOA),"	(
151	97	0111	p	i		<b>O</b> (************************************	`
152	98	1000	q				
153	99	1001	r	1			
154	9A	1010			Y (even parity)		
155	9B	1011		l	Y (odd parity)		
156	9C	1100	İ	1	9 (even parity)	upper case	upper case
157	9D	1101			9 (odd parity)		
158	9E	1110				<b>A</b> 4	
159	9F	1111			WD II (	© (ЕОТ) ¢	© (EOT)
160 161	A0	1010 0000			WRU (even)	Ç	T
161	A1 A2	0001	~	j	WRU (odd)		
163	A2 A3	0010 0011	S t		E	9	
164	A3 A4	0100	t u	- 1	ند	?	Х
165	A5	0100	v	1	%	S	_N
166	A6	0110	w	- 1	,0	S T	N U
167	A7	0111	x		ĺ	1	U
168	A8	1000	y	l			
169	A9	1001	z			U	E
170	AA	1010		l	U (even parity)	v	D
171	AB	1011	ļ	[	U (odd parity)		_
172	AC	1100		-	5 (even parity)	W	к
173	AD	1101	1		5 (odd parity)		
174	AE	1110	1	- 1			
175	AF	1111	1	- 1		X	C
176	В0	1011 0000	1				
177	B1	0001	ļ		return	Y	L
178	B2	0010	1		M (even parity)	Z	Н

Series/1 Model 5 4955 Processor and Processor Features Description GA34-0021-0 READER'S COMMENT FORM

Your views about this publication may help improve its usefulness; this form will be sent to the author's department for appropriate action. Using this form to request system assistance or additional publications will delay response, however. For more direct handling of such requests, please contact your IBM representative or the IBM Branch Office serving your locality.

Possible topics for comment are:

Clarity Accuracy Completeness Organization Index Figures Examples Legibility

What is your occupation?	
Number of latest Technical Newsletter (if any) concerning this publication:	
Please indicate your name and address in the space below if you wish a reply.	•

Thank you for your cooperation. No postage stamp necessary if mailed in the U.S.A. (Elsewhere, an IBM office or representative will be happy to forward your comments.)

## Your comments, please . . .

This manual is part of a library that serves as a reference source for systems analysts, programmers, and operators of IBM systems. Your comments on the other side of this form will be carefully reviewed by the persons responsible for writing and publishing this material. All comments and suggestions become the property of IBM.

Fold

Fold

First Class Permit 40 Armonk New York

## **Business Reply Mail**

No postage stamp necessary if mailed in the U.S.A.

IBM Corporation Systems Publications, Dept 27T P.O. Box 1328 Boca Raton, Florida 33432



Fold

Fold



**International Business Machines Corporation** 

General Systems Division 5775D Glenridge Drive N. E. P.O. Box 2150 Atlanta, Georgia 30301 (U.S.A. only)