

PC Paintbrush®

ZSoft Corporation

1950 Spectrum Circle, Suite A-495

Marietta, Georgia 30067

(404) 980-1950

Copyright Notice

Both the program and the manual are proprietary, copyrighted material, and no part of either may be reproduced, transmitted, stored or translated into any other computer or foreign language without the express written permission of ZSoft Corporation.

Copyright © 1985 ZSOFT CORPORATION

Customer Policy

We try our best to have satisfied customers. If you have any questions or problems, please call our listed telephone number any time. If we are unavailable at the time, we will return your call as soon as possible.

For those of you interested in getting the latest revisions of PC Paintbrush™, we offer two update policies. We have a one time update policy that may be purchased for \$30.00 or we have a one year policy for \$60.00. For the one year policy, you receive all the latest versions of PC Paintbrush™. To take advantage of either policy, you must send in a signed license agreement. We try to have 2 to 3 updates per year for all our software.

License Agreements

If you do not send us your signed license agreement, we can not send you our newsletter or update information. Please take the time and return the license. We are much more pleasant over the telephone with a signed license agreement in hand.

In the Mill

The list of computers and printers supported by FRIEZE™ and PC Paintbrush™ continues to grow. Please contact us if your card or printer is not yet supported.

Table of Contents

Chapter 1 Introduction	1-1
1.1 PC Paintbrush.....	1-1
1.2 Rules of the Game	1-1
Chapter 2 Installation	2-1
2.1 Making the Working Copy	2-1
2.1a Getting Started - Two Drive PC	2-2
2.1b Getting Started - Hard Disk	2-3
2.1c Getting Started - One Drive PC, PCjr	2-3
2.2 PCINSTAL	2-4
2.3 Running PC Paintbrush	2-6
2.4 Post-installation	2-7
Chapter 3 Guided Tour	3-1
3.1 Creating a Drawing	3-1
3.2 Printing Your Drawing	3-6
3.3 Saving Your Drawing.....	3-6
3.4 Clearing the Screen	3-6
3.5 Quitting PC Paintbrush	3-7
3.6 Final Comments	3-7
Chapter 4 Objects on the Screen	4-1
4.1 The Cursor	4-1
4.2 The Toolbox	4-1
4.3 Drawing Widths	4-1
4.4 Colors and Color Patterns.....	4-2
4.5 Scroll Bars	4-2
4.6 Menus	4-3
Chapter 5 Special Screen Features	5-1
5.1 Scroll Bars	5-1
5.1a Recommended Use for Scroll Bars	5-1
5.2 The Double Click Option	5-2

Chapter 6 The Tools	6-1
6.1 Introduction to the Scissors and Pick Tool	6-1
6.2 Using the Scissors and Pick Tool	6-2
6.2a Saving and Restoring Cutouts	6-4
6.2b Modifying Your Cutout	6-7
6.2c Transparent and Opaque Paste	6-11
6.2d Double Click Option	6-12
6.3 The Airbrush	6-13
6.4 Text	6-14
6.4a Text - Style Menu	6-16
6.4b Text - Size Menu	6-19
6.5 The Color Eraser	6-20
6.6 The Eraser	6-22
6.7 The Paintbrush	6-23
6.8 The Paint Roller	6-25
6. The Curve	6-27
6.10 The Line	6-29
6.11 The Hollow Box	6-31
6.12 The Filled Box	6-32
6. The Rounded Box	6-33
6.14 The Rounded Filled Box	6-34
6.15 The Hollow Circle/Ellipse	6-35
6.16 The Filled Circle/Ellipse	6-36
Chapter 7 The Menus	7-1
7.1 Undo	7-1
7.1a Local Undo	7-1
7.2 Page	7-2
7.2a Save as/Load From	7-2
7.2b Merge Pic	7-5
7.2c Show Screen	7-6
7.2d Print	7-6
7.2e Clear	7-7
7.2f Quit	7-7
7.3 Edit	7-7
7.4 Style	7-8
7.5 Size	7-8
7.6 Pick	7-8
7.7 Misc	7-9
7.7a Set Speed	7-9

7.7b	zoom-in/ZOOM-in.....	7-9
7.7c	Brush Shapes.....	7-11
7.7d	Edit Pattern.....	7-11
7.7e	Get Pattern and Save Pattern	7-13
7.7f	Adj. Palette.....	7-15
7.7g	Adj. Aspect.....	7-17
7.8	The Function Keys	7-18
7.8a	Constraining.....	7-20
Chapter 8 FRIEZE Printer Driver.....		8-1
8.1	A Quick Introduction to FRIEZE	8-1
8.2	Changing Printers	8-2
Chapter 9 Using the FRIEZE Options		9-1
9.1	Setting the Viewport - V.....	9-1
9.2	Saving and Restoring Pictures	9-3
9.2a	S - Save	9-3
9.2b	R - Restore	9-4
9.3	Printout.....	9-4
9.3a	P - Print	9-4
9.3b	H, W - Height and Width	9-5
9.3c	M - Left Margin.....	9-7
Chapter 10 Changing FRIEZE Defaults		10-1
10.1	Running Setcolor	10-1
10.2	Setting the Height and Width Defaults	10-2
10.3	Color Map Settings	10-3
10.3a	Mapping Textures for a Black and White Printer.....	10-4
10.3b	Color Map for Color Printers.....	10-6
10.4	Making a Color Chart for Your Printer	10-9
10.4a	16 Color Cards	10-9
10.4b	4 Color Cards	10-11
10.4c	2 Color Cards.....	10-12
Chapter 11 Notes for Special Hardware		11-1
11.1	Notes for Plotters	11-1
11.2	Running Setcolor	11-1
11.2a	Altering the Height and Width	11-2
11.2b	Pen Colors	11-3
11.3	Notes for PrintaColor Printers	11-5

11.4	Notes for Serial Printers.....	11-5
Chapter 12	FRIEZE - Special Notes	12-1
12.1	Using FRIEZE with SuperCalc3	12-1
12.2	FRIEZE Technical Information.....	12-2
12.3	FRIEZE Slide Shows and Multiple Printouts ..	12-2
Chapter 13	Improving Your Printout.....	13-1
13.1	Coloring	13-1
13.2	Sizing	13-3
Chapter 14	Common Questions and Problems.....	14-1
14.1	Tablets.....	14-1
14.2	Mice.....	14-2
14.3	Plotters	14-3
14.4	Printers.....	14-5
14.5	PCjr.....	14-5
14.6	General Problems.....	14-6
Appendix A	- File Extensions	A-1
Appendix B	- Saving and Restoring Pictures.....	B-1
Appendix C	- Special Menu Options.....	C-1

1. Introduction

1.1 PC Paintbrush

PC Paintbrush™ is a free-hand drawing program for the IBM Personal Computer and compatibles. The program requires:

- 320K memory
- One disk drive
- A graphics display
- DOS 2.0 or above
- A mouse, joystick or digitizer

High resolution displays WILL require more memory.

This user's manual is divided into two sections. The first half of the manual describes how to install and run PC Paintbrush. The second half describes FRIEZE™, (pronounced "Freeze") the program used for printing PC Paintbrush pictures and for transferring pictures from other programs.

In the first part of the manual, Chapter 2 gives a step by step procedure to install PC Paintbrush for your combination of graphics display and printer. Read that chapter first and follow the instructions before trying the program. The subsequent chapters describe PC Paintbrush's capabilities.

The second half of the manual explains FRIEZE but these chapters can wait since Chapter 2 includes FRIEZE installation. If you are dissatisfied with your printed results, read the FRIEZE chapters to find out how to customize your printout.

Both FRIEZE™ and PC Paintbrush™ are included on your PC Paintbrush distribution disks.

1.2 Rules of the Game

Although PC Paintbrush supports a number of drawing

devices such as mice, joysticks or digitizers for input, it is simplest to refer to your drawing device as a **mouse**. Please translate references to the mouse into your own terms.

Since constantly writing out "your right mouse button" gets a bit boring, we have replaced the words with some pictures. We have:

your mouse - 

press the left mouse button - 

press the right mouse button - 

When PC Paintbrush and FRIEZE ask questions, the Esc key is special. It always stops the current action, and returns to the program or the next higher menu level. For example, press Esc whenever you make a serious typing error. You may also use the Esc key to stop graphics printouts.

Notes:

- * If you have a joystick, keep the stick straight up when PC Paintbrush begins. (Alignment takes place during the initial screen creation.)
- * If you have a three button mouse, only the outer two buttons are used by PC Paintbrush.
- * If you have a light pen or digitizer with one button or tip switch, each time you select a tool, the first press in the drawing area has the same effect as . Following presses are treated as .

2. Installation

The PC Paintbrush installation procedure, PCINSTAL, explained in this chapter allows you to create working copies of PC Paintbrush. **This should be done first.** Find the appropriate installation process for a two drive PC, single drive PC, PCjr or hard disk and follow the instructions. Once the installation is completed, the original PC Paintbrush disks should be placed somewhere for safekeeping, and you should then use your working copies of PC Paintbrush.

2.1 Making the Working Copy

What you need in hand

PC Paintbrush master disks (1 and 2)
Mouse driver disk (possibly)
2 blank diskettes (unless you have a hard disk)
DOS system disk

Note: We supply a number of drivers for drawing devices on PC Paintbrush disk 2. However, if yours is not included in the list below, you need the driver disk provided with your drawing device.

Table 2.1

We provide drivers for:	
Disc Instruments MicroLynx	Kurta Pen Mouse
GTCO Digipad	Logitech Mouse
Joystick	Sunmapad MM1201
Key Tronic KB5153 Keyboard	Sunmapad MM961
Keyboard	

To use the keyboard as your drawing device with PC Paintbrush, see the file named MOUSEK.DOC on disk 1.

Note: In the following sections, it is important to note that some instructions are displayed in a different type style. For example, **COPY**. When you see this type style, make sure you type everything exactly as you see it, spaces included.

2.1a Getting Started - Two Drive PC

1. Turn on the computer and put the DOS disk in drive A and a blank disk in drive B. Answer the date and time questions, if asked.
2. At the A> prompt, type **FORMAT B:/S** and press the Enter key. Press the Enter key when ready and the formatting begins. When the formatting is complete, type **Y** and insert your other blank disk in drive B. Press the Enter key when ready. When the formatting is complete type **N** to return to the A> prompt.
3. Remove the DOS disk from drive A and insert PC Paintbrush disk 1. Insert a formatted disk into drive B and type **COPY A:.* B:** then press the Enter key. Wait for all files to be copied and when complete, insert PC Paintbrush disk 2 in drive A and the other formatted disk in drive B. Type **COPY A:.* B:** and press the Enter key when ready. When the copying is complete, you are returned to the A> prompt.
4. Take the master disks and **put them somewhere safe**. Label your work-

ing copies of PC Paintbrush and from now on, these copies are referred to as disk 1 and disk 2. Insert disk 1 into drive A. If needed, put your mouse disk or disk 2 into drive B.

Now you are ready for the installation procedure, PCINSTALL. The instructions are found in Section 2.2.

2.1b Getting Started - Hard Disk

1. If your computer can boot from the hard disk, just turn it on and answer any questions. Otherwise, insert your boot disk in drive A, turn on the computer, then answer any questions.
2. Make your hard disk the default drive. For example on an IBM PC-XT, type C: to make C the default. Now create a subdirectory for PC Paintbrush by typing:

```
C:  
C>CD \  
C>MD PBRUSH
```

3. Insert PC Paintbrush disk 1 in drive A and type:

```
C>CD \PBRUSH  
C>COPY A:*.*
```

4. Insert PC Paintbrush disk 2 in drive A and repeat step 3.
5. If your mouse is not listed in Table 2.1, insert your mouse disk, instead of PC Paintbrush disk 2, in drive A and follow the instructions.

Now you are ready for the installation procedure, PCINSTAL. The instructions are found in Section 2.

2.1c Getting Started - One Drive PC, PCjr

1. Turn on the computer and put the DOS disk in the drive. Answer the date and time questions, if asked.
2. At the A> prompt, type **FORMAT B:/S** and press the Enter key. When prompted, place a blank disk in the drive and press the Enter key. When the formatting is complete, type **Y**, remove the disk and replace it with the other blank disk. Press any key when ready. When the formatting is complete, type **N** and press the Enter key and you are returned to the A> prompt.
3. Insert PC Paintbrush disk 1. Type **COPY A:.* B:** followed by the Enter key. Your computer now refers to your blank disk in the drive as B, and the PC Paintbrush master disk 1 as A. Insert each disk as instructed. When copying is complete, remove disk 1 and replace it with PC Paintbrush disk 2 and type **COPY A:.* B:** followed by the Enter key. Follow the same procedure but use your other blank disk. This process may take a while, so be patient. When the copying is complete, take the master disks and **put them somewhere safe**. From now on your working copies of PC Paintbrush are referred to as disk 1 and disk 2. Make sure you label them.

Now you are ready for the installation procedure, PCINSTAL. The instructions are found in Section 2.

2.2 PCINSTAL

Once you have made either backup copies of PC Paintbrush or copied PC Paintbrush to your hard disk, you are ready for PCINSTAL.

1. At the DOS prompt, type **PCINSTAL**. Press the space bar at the opening screen and the PCINSTAL menu appears.

```
PC Paintbrush Install Menu
(c) 1985, ZSoft Corporation

1. Drawing Device ..... Joystick
   Drawing Device Port ..... GAME1

2. Display Adapter ..... IBM Color Card (2.8)
   Display Adapter Mode ..... 640x200 2 color

3. Printer ..... Epson LQ-1500 Printer
   Printer Mode ..... 240 dpi

4. Printer Port ..... LPT1

5. Save Current Settings / No More Changes

Please Enter Number to Change: █
```

Press Esc to quit (making no changes)

2. Select your:

* Drawing Device - choice 1. After pressing "1" a menu of drawing devices appears. Press the number or letter that corresponds to your drawing device, or press "0" to see

another page of drawing devices. After your choice is made, you are returned to the main menu.

- * Display Adapter - choice 2. Follow the same procedure as you did for the drawing device.
 - * Printer - choice 3. Follow the same procedure.
 - * Printer Port - choice 4. Follow the same procedure.
3. When the main menu shows the correct list of devices, select option 5 in order to save the setup to your disk.
 4. You may be asked to place either your mouse disk or disk 2 in drive A. Place disk 1 in drive A if asked.

PCINSTAL does three things. First PCINSTAL customizes FRIEZE for the printer you are using. If you have a single or two drive PC, it transfers the mouse driver to your working disk. If you have a hard disk, it transfers your mouse driver to your PBRUSH subdirectory. Finally, it creates a batch program named PAINT.BAT that automatically runs FRIEZE and PC Paintbrush.

2.3 Running PC Paintbrush

If your display adapter card has a BIOS Emulator program, such as GMBIOS for Tecmar or QCI for QuadColor, then you must run this program **before** you run FRIEZE or PC Paintbrush. You may choose to add this program into PAINT.BAT so that it is run everytime before FRIEZE or PC Paintbrush. Consult your display adapter hardware manual and determine if you need to run this program.

If you have a two drive PC, follow these instructions to run PC Paintbrush:

1. If the computer is off, insert disk 1 and turn on the power. Answer any questions, if asked, then type **PAINT** and press the Enter key.
2. If the computer is on, insert disk 1 in the default drive and type **PAINT** and press the Enter key.

If you have a hard disk, follow these instructions to run PC Paintbrush:

```
C>C:  
C>CD \PBRUSH  
C>PAINT
```

If you have a single drive or PCjr, follow these instructions to run PC Paintbrush:

1. If the computer is off, insert disk 1 and answer any questions. Now type **PAINT** and press the Enter key.
2. If the computer is on, insert disk 1 and type **PAINT** and press the Enter key.

2.4 Post-installation

Once you have installed PC Paintbrush for your hardware (printer and video display) you probably never need to reinstall it. You can then remove PCINSTAL.EXE file from your program disk. Do this by placing your working copy of PC Paintbrush in drive A and type:

```
A>DEL PCINSTAL.EXE
```


Deleting this file creates more room for pictures on the disk.

Note that disk 2 contains all the various fonts. You may want to use these fonts when running PC Paintbrush. See Section 6.4 on using the fonts on disk 2. Otherwise, use disk 1 to run PC Paintbrush.

Again, please keep your master copies of PC Paintbrush somewhere safe. If something happens to your working copies, repeat the installation procedure discussed in section 2.1 using your master copies. If you make any changes such as changing drawing devices or printers, you must rerun PCINSTAL to make the changes. See Chapter 8 for additional information.

3. Guided Tour

Here is your chance for a quick introduction to PC Paintbrush. Insert PC Paintbrush disk 1 in drive A> and type **PAINT**. The PC Paintbrush screen appears:



As you move , a mark, which is your cursor, moves across the screen. Your cursor varies, depending on the tool you are using and whether or not it is in the drawing area.

Note: Any time you make a mistake, select the Undo menu at the top of the screen by pressing . If you change your mind and do not want to undo your drawing, reselect the Undo menu. Whenever you change tools, only what you created with the current tool is erased.

3.1 Creating a Drawing

Let's draw a grandfather clock. Move your cursor to the sec-

tion in the bottom left hand corner of the screen. This section shows the various drawing widths, and the current drawing width is indicated by . Change drawing widths by pressing  (the left button) on top of the first drawing width. The new drawing width is now indicated by .

Now, change tools. Select the hollow circle by pressing  on top of the circle. The active tool is the one that is highlighted. Your cursor appears as a "+" in the drawing area. Move your cursor so that it is in the middle of the drawing area and press . This sets the center of the circle. Hold down the Shift key and slowly move your cursor away from the center. When the circle is about the size of the circle in figure 1, press  and your circle is drawn.

Next, go to the text tool which is the one that is a **T**. Press  on top of the tool to activate it. An open box appears in the screen. See figure 2.

Now move  to the top of the screen to the Size menu. Select this menu by pressing  on top of the menu name. A list of size selections appears. Select approximately a 17 point size - press  on this size option. The current size is indicated by . See figure 3.

Move your cursor inside the circle and to the top of it and press . The open box moves to this point. Use your keyboard and type **12**. The text tool treats your keyboard just as a typewriter, so if you make a mistake, use the backspace key. Continue this procedure until you have typed in the **3, 6, 9** and **12**, creating the face of the clock. See figure 4.

Select the line tool and move to the center of your circle. Press  and the line moves to this point. Move your cursor in the direction of the **12**. Paste the line on the screen by pressing . Reposition the line so that you draw another line in the direction of the **3** - paste the line on the screen by pressing . You have now completed the hands of the clock. See figure 5.






Select the hollow box tool and move underneath the face of the clock. Press  to fix one corner of the box and press  to paste the box on the screen. This is shown in figure 6.






Reselect the line tool to outline the face of the clock and the hollow box. See figure 7.

Continue using the line tool and move to the top of the box that you just drew and press . Move to the original point and draw another diagonal line, this time in the opposite direction. See figure 8.

Pick the filled circle tool and move just under the end of one line. Press  under the line to move the center of the circle to this point. Barely move  and then press  to paste a small circle at the end of the line. Create another circle at the end of the other line, creating the pendulums. This is displayed in figure 9.


Now that you have drawn your clock, you may fill in some of the areas. To do this, select the paint roller tool. Move to the bottom of the screen and select a different color. Press  on top of the desired color. Move to the area you wish to paint and press  in that area. See figure 10.





3.2 Printing Your Drawing

If you want to print your picture, move your cursor to the Page menu. Press  and seven different options appear. Highlight the Print option by pressing  over the name. If your printer is ready, select OK to get a copy of your picture.



Enter print options...

Height:	<input type="text" value="5.50"/>	<input type="button" value="Normal"/>
Width:	<input type="text" value="7.50"/>	<input type="button" value="Sideways"/>
Margin:	<input type="text" value="0.00"/>	
	<input type="button" value="OK"/>	<input type="button" value="CANCEL"/>

3.3 Saving Your Drawing

If you want to save your picture, move to the Page menu and press . This time, select the Save as... option and a list of names appears. Initially this list is empty. Move to the bottom of the list and select ??. When the Use File box appears, use your keyboard to type a name. For example, type in **CLOCK** and press the Enter key. For future editing, your picture is available through the Load from... option in the Page menu.

3.4 Clearing the Screen

If you are finished with your picture and are ready to continue with PC Paintbrush, move to the Page menu and select the Clear option. Select OK to clear your screen or select CANCEL if you change your mind.

3.5 Quitting PC Paintbrush

If you are finished drawing, select the Quit option in the Page menu. You are asked if you are sure, so select Yes if you wish to quit. You are then returned to DOS - the A> prompt.

3.6 Final Comments

This example is just the beginning to using PC Paintbrush. There are other tools to use as well as additional menu options. Chapters 4-7 give you more detailed information on using the tools and menus.


4. Objects on the Screen

4.1 The Cursor

The cursor is the object on the screen that moves as you move your mouse. The cursor appears differently in the drawing area depending on what drawing tool you choose. It always appears as an arrow outside the drawing area.

4.2 The Toolbox

To draw on the screen, use tools selected from the group of pictures on the left--the toolbox. The toolbox contains tools that draw, fill, airbrush, erase, set type, and rearrange the items on the screen. To select a tool from the toolbox, position your cursor on top of the tool's picture then press .




4.3 Drawing Widths

The available drawing widths are displayed in a box on the lower left corner of the screen. The current width is marked by an arrow - . When you draw unfilled objects such as lines, boxes, circles or use the spray paint can, the width determines the thickness of the object. To select a specific width, place the cursor on top of the desired width and press .

Undo

Page Edit Style Size Pick Misc



4.6 Menus

The words at the top of the screen are various menus which allow you to change the way some tools operate. These menus are called **pull-down** or **drop-down** menus because of the way they work. To pick an item from the menu:

1. Move the cursor to the menu and press  then release the button.
2. Move  (your mouse) until the desired selection is highlighted.
3. Press .

Some of the handier menu options include:

- * Undo. It allows you to rectify your mistakes.
- * Quit. It is found in the Page menu. Use this option when you wish to quit PC Paintbrush. Select YES to quit, NO if you change your mind.

- * Clear. It is found in the Page menu. Clear clears your screen to the background color.

The menus are discussed in Chapter 7.


Undo Page Edit Style Size Pick Misc

5. Special Screen Features

5.1 Scroll Bars

Your picture area is at least as large as the screen. Your drawing area is just a window on the entire picture. Scroll bars lets you move around in the drawing area so that you can edit your entire picture.

Scroll bars are made of three different parts: the gray bar, the white area inside the gray bar and the arrows on each end.



The gray area represents your entire picture. The white area inside represents the window or drawing area. It is sized proportionately with the gray area. Thus, if you have a small picture (about one screen), then your white area is large, taking more of the gray area. If your picture is larger, then the white area will be smaller since the drawing area represents a smaller piece of the screen.

5.1a Recommended Use for Scroll Bars

You can scroll through your picture three different ways. You can use the arrows on either Scroll bar. Move your cursor to an arrow and hold down  on top of the arrow. This pulls the white area in that direction, so if you selected the arrow pointing up, your picture moves, pulling the white area towards the up area, moving the window up.

You can also use the white box to scroll. Go to either white area and hold down . Now "drag" the white box - keep holding  and move the Scroll bar. Note how your picture moves. This method of moving is best for smaller pictures and when you are in Zoom mode. See Section 7.7b for information on zoom-in and ZOOM-in.

When you have a rather large picture, then it is best to use the gray area to scroll. Select a gray area and press . Your window moves in 1/2 page increments towards the cursor.

5.2 The Double Click Option

The double click option is actually a shortcut to some PC Paintbrush features. To use the double click option, press  twice quickly over the tool or color palette. Double click works with:

1. The pick tool. See Section 6.2.
2. The color eraser tool. See Section 6.5.
3. The eraser tool. See Section 6.6.
4. The paintbrush tool. See Section 6.7.
5. The color palette. See Section 7.7d.



6. The Tools

The tools are found to the left of the drawing area. To select a tool, place the cursor on top of a tool's picture and press . When you choose a tool, it becomes highlighted.

6.1 Introduction to the Scissors and Pick Tool

The scissors and pick tool work similarly. Both work with the Edit and Pick menus to let you:


1. Select any part of a picture and move it or copy it. See Section 6.2.
2. Save your cutout for future use, discussed in Section 6.2a.
3. Modify your cutout. For example, you can take a cutout out and enlarge it or you can rotate it 90 degrees. See Section 6.2b.
4. Section 6.2c gives you information on transparent and opaque paste.



6.2 Using the Scissors and Pick Tool

The scissors and pick tool only differ from one another in how you define the cutout. The scissors tool uses freehand line to surround an area while the pick tool uses a rubber band box.

1. Select either the scissors or pick tool. When you move your cursor into the drawing area, your cursor appears as a plus for the scissors tool and a rubber band box for the pick tool.
2. For the scissors tool, press  and draw a line around the area you want to select. For the pick tool, press  to set the fixed point. Use the rubber band box to surround the rectangular area you wish to select.



3. When you are finished surrounding your object with the scissors, press . Although you surrounded an object in a free hand manner, you see a box appear on your screen. Only the object that you defined and not the entire box gets moved. For the pick tool, press  to define the area.

- * If you make a mistake defining the object, move your cursor outside of the box and then press .
- * If you want to leave a copy of your cutout behind rather than moving it, hold down the Shift key and then press . When you move the cutout, a copy of the cutout stays behind and you also have a cutout to move. Once you have moved the cutout from the original position, release the Shift key.

Now you are able to place your cutout anywhere on the screen. From here on, the pick and scissors tool work the same way. Move your cursor (now an arrow) to the inside of the box. Hold down  for a transparent paste and  for an opaque paste (see Section 6.2c on transparent and opaque paste) and push your object anywhere on the screen. Release .

To make multiple copies of the cutout, hold down the Shift key and press  for a transparent copy and  for an opaque copy. Then repeat the same procedure.

To brush your object on the screen, hold down the Ctrl key and press  for a transparent brush and  for an opaque paste and rub the object across the screen.

The scissors and pick tool can also be used with the Edit and Pick menus. See the next section for complete instructions. Keep in mind that every option available to the pick tool is also available to the scissors tool, so any reference to the pick tool also applies to the scissors tool.

6.2a Saving and Restoring Cutouts

If you want to save a cutout on disk for later:

1. First, select the Name is... option from the Edit menu. Move to the ?? at the bottom of the menu.
2. When the Use file box appears, type in a valid DOS file name and press the Enter key.
 - * By default, each file name receives the .PCC extension, so if you do not specify an extension, your cutout receives .PCC. If you do not want your cutout to have an extension, then type "." at the end of your file name. For example, type HOUSE. and then press the Enter key.
3. Now select the pick tool and define the cutout you wish to save. Remember, you can use the options from the Pick menu to make alterations to your cutout before saving it. See the next section for information on using the Pick menu options.
4. Go to the Edit menu and select Cut or Copy.
 - * Cut removes your cutout from the screen and saves it to disk. Copy saves your cutout to disk but leaves it on your screen.

You have now saved your cutout. Note that you should specify a new name for each cutout that you want to save. Otherwise,

when you select Cut or Copy, the new cutout gets saved to the name currently present in Name is...

When you want to use this cutout in the future:

1. Select Name is... from the Edit menu. Highlight the cutout you want and press .
2. Select Paste from the Edit menu. Note that the pick tool is now active. Your cutout should appear in the upper left corner of the drawing area.
3. Now you can place your cutout on the screen. Press  for a transparent paste and press  for an opaque paste. You can place it once on your screen or paste it continuously.

If you are using a single drive or two drive computer and you save many cutouts and pictures, you eventually run out of room on your disk. When this happens, you receive the error message:

ERROR
Write Error

If you have a single drive computer, replace the disk in the A> drive with another disk. Now repeat the same procedure as above to save your cutout.

If you have a two drive PC, you have two choices:

1. Replace the disk in the A> drive with another disk. Repeat the same procedure as above to save your cutout.
2. Insert a disk in the other drive.

Select the Name is... option in the Edit menu. The top line of the menu is: **A:_____**. Highlight this line and press .

3. When the Use file box appears, type in the drive location of the new disk and press the Enter key. For example, if the new disk is in drive B>, type **B:** and press the Enter key. Now repeat the above procedure to save your cutout.

Hint: If you are saving pictures on a hard disk, see the section on PBRUSH.CNF in Appendix A. This feature gives you advice on saving pictures in specific subdirectories for your convenience. It can also be useful for users with a two drive computer.

Note: You may also save pictures using the Save as... and Load from options in the Page menu. See Section 7.2a on using these options. You may also save or restore the pictures using FRIEZE. See Chapter 9 for additional information.

6.2b Modifying Your Cutout


Using the options from the Pick menu you can do the following to your cutout:

1. Rotate
2. Flip Horizontal
3. Flip Vertical
4. Inverse
5. Shrink + Grow
6. Tilt
7. Clear


To use the scissors or pick tool and a Pick menu option:

1. Select the pick tool by pressing  on top of the tool.
2. Define the area you want to manipulate with the rubber band box. Press  to set the fixed point and  to set the defined area on the screen.
3. Select the Pick menu and choose an option.


* Rotate rotates the defined area 90 degrees.




- * Flip Horizontally/Vertically flips the defined area from side to side or top to bottom.




- * Inverse causes the colors to invert. For example in monochrome, black becomes white and white becomes black.




- * Shrink + Grow creates another rubber band box. Move the second box around the screen with  until you are satisfied with the size. Press  to set the fixed point and press  to "shrink" or "grow" the defined area inside the second box.



- * Tilt creates a dotted parallelogram on the screen. Move until you are satisfied with the amount of tilt. Press to tilt the defined area.



- * Clear "clears" your original picked area. Using this option prevents the original object (the one you defined) from peeking out from behind the altered area.



The Pick menu options Rotate, Flip Horizontal, Flip Vertical and Inverse may each be active simultaneously.

The Shrink+Grow and Tilt options work singly; they can not be used together nor with any other Pick menu options except Clear. If you choose Shrink+Grow (or Tilt), your object becomes fixed on the screen.

Clear may be used with any options. It is best to experiment with different combinations.

6.2c Transparent and Opaque Paste

You have two ways to brush or move your cutout:

1. **Transparent paste.** With a transparent paste, **any** pieces of the saved cutout that have the same color as the **current** background color do not get placed onto the screen.
2. **Opaque paste.** An opaque paste treats your background color just as any other color.


If you followed the correct procedure to move or brush your cutout, you used a transparent paste. To use an opaque paste:

1. Define the cutout using the pick tool.
2. Move your cursor inside the rubber band box.
3. Now press  and not . Now hold down the Ctrl key and  and brush your cutout across the screen.

To get a better idea of the difference in transparent and opaque paste:

1. Create a simple drawing. Then define the area using the pick tool.
2. Move your cursor inside the box and press . Hold down the Ctrl key and  and brush your cutout across the screen.
3. Now, using the same cutout, press  inside the box. Brush it across the

screen, holding down the Ctrl key and . You should be able to tell the difference.




6.2d Double Click Option

The pick tool also has a double click option. When you double click the pick tool, you see the full screen. Note that there is no cursor present, allowing you to photograph or print your screen (using FRIEZE - See Chapter 8) without printing your cursor. To exit this mode, press the Esc key. This option is not the same as the Show Screen option in the Page menu. See Section 7.2c for complete instructions.



6.3 The Airbrush

The airbrush produces a random spray of dots on the screen. The spray continues as long as  is held. Select a larger width to produce a lighter spray on a larger area.





6.4 Text

The text tool turns your screen and keyboard into a typewriter. You may use this tool just as you do a typewriter. After you select the text tool, the text cursor appears as an open box in the drawing area. Place  cursor (a plus sign) at the point you wish to type. Press  and the open box moves to that point. Now, use your keyboard to type anything you want.

The default Style type is a Roman font. Fonts are either stroke fonts or bit mapped fonts. A bit mapped font contains the word "bit" while all others are stroke fonts. The default size depends on your graphics card and what mode you run. The choice of sizes depends on the font you choose. Bit fonts have different size options than stroke fonts. On disk 1, there are at least two different fonts: Roman (the default) font and Bit8x8 font. The remaining fonts are on disk 2.

The text tool works with the Style and Size menus. To change fonts and typeface, use the Style menu (See Section 6.4a). The Size menu has various type sizes to use (See Section 6.4b).

Things to keep in mind while using the text tool:

1. You must be using the text tool to use any of the options from either the Style or Size menu.
 2. Your  cursor must be in the drawing area to type.
 3. If you change color, size, font or style, all your current type changes, too.
- * If you change tools, reselect the text tool, select Undo twice, reposition the open box (pressing ) or scroll the screen, then your type is

“frozen.” Subsequent changes to color, size, font or style does not affect that text.

4. Although you may activate more than one Style option, you may select only one option at a time. To activate more than one option, reselect the menu until all options you want are activated.
 - * When an option is activated, it is indicated by a check - ✓.
5. If you select a menu, but do not wish to make any changes, move your cursor off the menu and press  or select another menu.
6. **The current drawing width affects your text.** Smaller drawing widths are more appropriate with smaller text whereas a larger drawing width is more appropriate with larger text.

6.4a Text - Style Menu

The first option in the Style menu is Font selection. To change fonts, highlight this option and press **↵**. The available list of fonts appears. The remaining fonts are on disk 2 (unless you installed PC Paintbrush on a hard disk). If you have a one drive system:

1. Replace disk 1 with disk 2.
2. Select the Style menu and the various fonts on disk 2 are displayed.
3. Move your cursor until the font you want is highlighted. Then press **↵**. If you exit PC Paintbrush with disk 2 in the default drive, you may be instructed to insert a disk with a batch file. If this occurs, insert disk 1 and press any key and you are returned to DOS.

If you have a two drive system, you have two choices. You may replace disk 1 with disk 2 and follow the instructions for a one drive system. Or you can change directory locations. First place disk 2 in drive B. Then:

1. Select Font in the Style menu.
2. Select the top line (it probably reads: **A:_____**) and press the Enter key.
3. When the Enter search directory box appears, change to another drive. For example, type **B:** and press the Enter key to change to drive B. The menu of available fonts on disk 2 appears.

Not all the fonts options can be seen on the screen simultaneously. To see more fonts, press  on one of the arrows () or () that are to the right of the font selections. These arrows move the menu up or down.

The Style menu works differently, depending on what type of font you are using, stroke or bit mapped. If you are using a stroke font, your typing options are one of:

1. Light,
2. Medium or
3. Bold

And any of:

1. Italic
2. Underline
3. Outline
4. Kerning
5. Shadow

You may use only one of the Light, Medium or Bold options at a time. Select the Style menu and move your cursor until one of the three is highlighted. Press  to choose one. The activated one is indicated by .

The other five options may be used in any combination. You may either choose none, one or more. Selecting one of these options the first time activates it (indicated by ) and selecting it again deactivates it.

Selecting Italic italicizes your text while Underline simply underlines your text. Outline outlines your text - the background color is outlined by the foreground color. Kerning places your text closer together. Shadow is similar to Outline, but the background color lays slightly over one edge of the foreground color.

PC Paintbrush

PC Paintbrush Italic

PC Paintbrush Underline

PC Paintbrush Outline

PC Paintbrush Kerning

PC Paintbrush Shadow


If you choose a bit mapped font, your Style options are:

1. Proportional
2. Opaque

Proportional is similar to Kerning. The text is placed closer together. However, Proportional does not work with all bit mapped fonts. Opaque highlights the text characters with the background color. If Opaque is not used, then the text is placed over the picture immediately behind them.

6.4b Text - Size Menu

The Size menu gives you various sizes to type. If you are using a stroke font, the range of smallest to largest depends on your graphics card and what mode you are using. If you are using a bit mapped font, you actually have two options to change the size. You may change the height, width or both. The X options change the width of your text while the Y options change the height of your text. You may choose any combination.




Note: With FRIEZE, you may change the height and width of printout, so the Size options may not correspond to printout size.



6.5 The Color Eraser

The color eraser is used to erase selected colors. The foreground color **only** is replaced by the background color. The color eraser is sensitive to width settings so you may change a small or large area. The cursor size in the drawing area reflects the width setting.



Hint: The color eraser is useful for changing one color to another without changing any other colors. For example, if you want to change blue to red:


1. Select blue as your foreground color and red as your background color.
 - * Remember, to change the foreground color, place the cursor on the desired area and press . To change the background color, press .
 - * Press  in the foreground area to return to changing the foreground color.
2. Move the color eraser over the area

you wish to change, holding down . In the above example, only blue changes to red. This technique is very useful when you have many small spots which need filling.

You can constrain the eraser to erase in a horizontal or vertical manner by holding down the Shift key as you erase.


If you want to change every occurrence on the screen of one color to another color, then you can use the double click option. Follow this procedure:

1. Select the color you wish to change as your foreground color and select the color you are changing to as your background color.
 2. Press  over the color eraser twice (double click) and everything in the drawing area that is the foreground color is changed to the background color.
- * In the above example, when you press  twice in a row over the color eraser, everything that is blue changes to red.




6.6 The Eraser

The eraser is used to erase more than one color at a time. Every spot the eraser touches is changed to the background color. Rub the eraser over an area while holding . The eraser is also sensitive to width settings, so the cursor reflects the various sizes in the drawing area.



The eraser also has a double click option although it is different than the color eraser's. When you press  twice on top of the tool, a box appears in the screen. This double click option allows you to clear your screen, so select OK if you want to clear your screen, or CANCEL if you want to return to the drawing area without clearing your screen. This double click option is a short cut to Clear found in the Page menu. See Section 7.2d for additional information.

You can constrain the color eraser to erase in a horizontal or vertical manner by holding down the Shift key as you erase.




6.7 The Paintbrush

The paintbrush works similarly to a bristle paintbrush. Select a color and width. Hold down  and you may draw free hand shapes.

You can change the shape of the brush two different ways. One way to change brush shapes is to:

1. Select the Brush Shapes option in the Misc menu.
2. When the various options appear, select any stroke shape by pressing  over the desired shape.




Your second option for changing brush shapes is to use the double click option:

1. Double click the paintbrush tool. The various brush shapes appear in the drawing area.
2. Select any shape by pressing  over the shape.

The different brush shapes allow you to vary your free hand


drawings. The default brush shape is the black square in the upper left corner of the box. The greater the drawing width, the longer the brush stroke. The cursor resembles the brush shape, so if the brush shape is a circle, for example, the cursor is a circle in the drawing area.

You can constrain the paintbrush to move in a horizontal or vertical manner by holding down the Shift key as you paint.



6.8 The Paint Roller

The paint roller is used to color in any shape. Place the cursor inside the area you wish to fill and press . Your object is filled with the foreground color. For the paint roller, use  only to cover patterned areas.



If your area has any openings, the paint leaks and fills the screen. In that case, either wait for the paint to stop leaking and use the Undo menu or press the Esc button to stop the filling and then use the Undo menu.

- * Any object that was just filled since selecting the paint roller is affected by selecting Undo. Therefore, if you are satisfied with an object you fill, reselect the paint roller to continue filling in more objects.

To fix your opening so that the paint does not leak again, use the Misc menu and choose one of the Zoom options. See Section 7.7 on The Misc Menu for additional information.

Hint: If you paint a shape with a color pattern and decide to change the color to either another pattern or a solid color, press  and **not** . Otherwise, you may find that only a few lines of the object are filled or that the colors blend together.


You may also find that after you fill an object, that some of the paint leaks out of the object but does not fill the entire screen. This occurs when the color pattern has one or more colors in common with the outline of the object that you wish to fill. To prevent this from happening, first fill the object with a color that neither the object nor the desired color pattern has. Then select the desired color pattern and fill the object by pressing .




6.9 The Curve

The curve tool allows you to draw curved lines as opposed to only straight lines. To draw curved lines:

1. Select the curved line tool. Your cursor appears as a plus in the drawing area.
2. Press  to set one end of the curve. You then see a rubber band line with a plus at your cursor spot.



3. Move your cursor to another point and press . This sets the two endpoints of your curve. Note that an arrow now points to the first endpoint.
4. Move your cursor to set the angle of the curve into that first endpoint. When you are satisfied with angle, press . Note that the arrow moves to the second endpoint.




5. Now set the other angle and the entire curve. When curve and the angle are acceptable, press  and your curve is pasted on the screen.
- * Pressing  backs you up one step at a time. Pressing  three times always lets you start over.





6.10 The Line


The line tool is used to draw connected or separate lines. Press  to position the fixed point. Press  to paste the line on the screen. Although the rubber band line on the screen is always thin, the actual line thickness is determined by the drawing width.



The F1 and F2 keys may be used with the line tool. F1 marks the point where your cursor is, and F2 remembers that marked point. This feature is useful for doing “sunburst” drawings. Let’s say you want to draw a spider web. Using the F1 and F2 keys, you may create the web so that each line originates from the same point.


1. Begin in the middle of the drawing area and press  to set the point.
2. Then, press the F1 key to mark the point. Draw a line from the middle and press  to paste the line on the screen. Notice that the fixed point moves to the end of your line.
3. Press the F2 key and the fixed point of your line moves back to the one originally marked by F1. Continue until you have several lines begin-

ning from the middle. Remember to press F2 each time before drawing a line from the middle.




4. You may finish the spider web using the line or paintbrush tool.

You can constrain your line to move in a horizontal or vertical manner by holding down the Shift key as you draw your line.




6.11 The Hollow Box

The hollow box is used to draw squares or rectangles on the screen. Pressing  moves the fixed point, while  pastes the box onto the screen. The drawing width affects the width of a box - the thicker the width, the thicker the sides of the box. However, the rubber band box which is the drawing area always appears as a thin box.




If you want to draw a square, hold down the Shift key as you move your cursor. Press  when you are satisfied with the size of your square.


Hint: If the Shift key does not make a perfect square, the default aspect ratio is probably wrong. See Section 7.7g for information on adjusting the aspect ratio.



6.12 The Filled Box


The filled box works similarly to the hollow box tool. However, when you paste down the box, by pressing **⌘**, the box is filled with the foreground color. Remember that you can draw solid squares by holding down the **Shift** key.





6.13 The Rounded Box


The rounded box is drawn in the same way the hollow and filled boxes are drawn. Press  to set the fixed point and press  to paste the rounded box on the screen.






6.14 The Rounded Filled Box

The rounded filled box is used just like the rounded box except the box is filled with the foreground color when you press .





6.15 The Hollow Circle/Ellipse

When you move your cursor into the drawing area, it appears as a plus. To draw a circle or an ellipse:

1. Select the hollow circle. When you move your cursor into the drawing area, you see a rubber band circle.
2. Press  to set the center of your circle.
3. Stretch the rubber band circle or ellipse until it is the size you want.
4. Press  to paste your circle or ellipse on the screen.

The aspect ratio of your circle or ellipse depends on how you move your cursor. Hold down the Shift key to create perfect circles. Once you are satisfied with the size of the circle, press . If the Shift key does not produce perfect circles, see Section 7.7g to adjust the aspect ratio.





6.16 The Filled Circle/Ellipse

The filled circle works in the same manner as the hollow circle except that the circle/ellipse is filled with the foreground color. Hold down the Shift key to draw perfect filled circles.



7. The Menus

The menus are found across the top of the drawing area. Several of these are used with specific tools, such as the pick tool and the Edit menu. To select a menu, move your cursor until a menu is highlighted. Select an option and press  and the menu unfolds.

Any time you select a menu but decide not to use a menu option, move your cursor off the menu, or select another menu.

7.1 Undo

The Undo menu allows you to change your mind. The Undo menu “undoes” everything since selecting a new tool. For example, if you draw several squares but decide you do not want them, select the Undo menu. If you change your mind and decide to keep the squares, select the Undo menu again and your squares reappear.

Hint: If you are using the same tool for a period of time, reselect the tool every once in a while. Otherwise using the Undo menu deletes all your work. By reselecting the tool periodically, selecting the Undo menu deletes only your most recent work.

7.1a Local Undo

Local Undo turns your cursor into a selective eraser and lets you undo your latest work. To use Local Undo:

1. Press the Backspace key. Your cursor turns into a square with an “X” in it. The size of this square depends on the current drawing width.
2. Move your cursor over the area you

wish to undo and press . Rub the local undo box on the screen just as you would the eraser (Section 6.6).

3. When you are finished, release  and you are returned to drawing with the same tool.

Local Undo only erases what you have drawn since selecting a tool. So, if you used the hollow box tool then the hollow circle tool, you would only be able to use the Local Undo on the hollow circles.

Note: Local Undo does not work with the text tool.

Hint: We often use Local Undo to clean up slight mistakes. It is particularly helpful in cleaning up stray dots made by the airbrush.

7.2 Page

The Page menu has 7 options:

1. Save as...
2. Load from...
3. Merge Pic
4. Show Screen
5. Print
6. Clear
7. Quit

7.2a Save as/Load From

The Save as... and Load from... options save and restore your pictures to and from disk. When you select Save as..., the entire picture is saved to your disk. To save a picture using this option:

1. Select the Page menu. Move your cursor until Save as... is highlighted.

Press .

2. A list of file names appears. Initially this list is empty. Move your cursor to ?? and press .
3. When the Use file box appears, type in a name and press the Enter key.
 - * If you do not specify an extension such as .PCX, then by default, your picture receives the .PCX extension.
 - * If you do not want your picture saved with an extension, type the name followed by ".". For example: **Graph.**
4. You may save pictures over previously saved pictures.
 - * Highlight the name of the file you wish to overwrite and press  to select it. You are then asked **Write over existing file?** Select **Yes** to overwrite the picture or **No** if you change your mind.

If you are using a single drive or two drive computer and you save many cutouts and pictures, you eventually run out of room on your disk. When this happens, you receive the error message:

ERROR
Write Error

If you have a single drive computer, replace the disk in the A> drive with another disk. Now repeat the same procedure as above to save your picture.

If you have a two drive computer, you have two choices:

1. Replace the disk in the A> drive with another disk. Repeat the same procedure as above to save your cut-out.
2. Insert a disk in the other drive. Select the Name is... option in the Edit menu. The top line of the menu is: **A:_____** if you have a single or two drive PC and is **C:\PBRUSH_____** if you have a hard disk.
3. Highlight this line and press . When the Enter search directory box appears, type in the drive location of the new disk. For example, if the new disk is in drive B>, type **B:** and then press the Enter key. Now repeat the above procedure to save your cutout.

You may choose to put all your pictures on the same disk. If so, follow the same procedure. If you exit PC Paintbrush with a disk in the default drive other than disk 1, you may be asked to insert a disk with a batch file. If this occurs, insert disk 1, press any key and you are returned to DOS.

Note: You may also save pictures using the scissors or pick tool with the Edit menu. See Section 6.2 on using these options. You may also save or restore pictures using FRIEZE. See Chapter 9 for additional information.

To restore a picture using the Load from... option:

1. Select the Page menu and move your cursor until Load from... is highlighted. Press .
2. A list of previously saved pictures

appears on the screen. Move your cursor until the name of the file you wish to restore is highlighted and press .

3. If more than 7 pictures listed were saved, use  and  to the right to see more the file names.
4. If your picture was saved onto a different disk, make sure that the disk is in the default drive. Or, if your picture is on a different drive, select the line that initially reads:
A: _____ if you have a single or two drive PC. This line initially reads:
C: **PBRUSH** _____ if you have a hard disk. When the Enter search directory box appears, change drives by typing in the drive name, such as: **B:** and then press the Enter key. Now you are able to select the picture you wish to restore.

Hint: If you are saving pictures on a hard disk, see the section on PBRUSH.CNF in Appendix A. This features gives you advice on saving pictures in specific subdirectories for your convenience. It can also be useful for users with a two drive computer.

7.2b Merge Pic

The Merge Pic feature is strictly for Lotus 1-2-3 and Symphony users. To use Merge Pic:

1. Run your spreadsheet and create then save a graph. You do not need to view the graph.
2. Run PC Paintbrush and select Merge Pic.

3. If the graph was saved in a different directory, change directories via the file box.
4. Select the graph you just saved. It will show up on the screen after a brief wait.

The background color of your graph is determined by PC Paintbrush's background color. You can embed a graph in a larger document. Just Clear the screen to the desired size, then position the drawing area, using the Scroll bars. Do not forget that Merge Pic uses one entire screenful for the graph.

7.2c Show Screen

Show Screen allows you to see the entire screen and not just the drawing area. Press the Esc key to return to the drawing area. Scroll bars allows you to draw in the areas covered by the menus, tool, drawing widths and color palette. The Show Screen option lets you see the complete screen. Remember, if your picture is larger than one screen, you will only see one screen and not the entire picture.

When you are in Show Screen mode, you can still draw with the active tool. For example, this allows you to draw complete circles that normally would be clipped if you were in the normal drawing area. The pick tool has a Show Screen double click option that is slightly different. See Section 6.2 for additional information.

7.2d Print

You can print your screen by using the Print option. Select OK to print or CANCEL if your printer is not ready. If the printout is unsatisfactory, see Chapter 9 for information on using FRIEZE.

The Print box lets you specify your height, width and left margin - measured in inches. It also lets you print your picture

sideways or normal. To change the height, width or left margin, point your cursor the present value and press . Then type in a new value. For example, if you want your picture to be eight inches high, type **8**. When you have made all the changes, select **OK**. If you make a mistake, select **CANCEL**.

7.2e Clear

When you want to clear your drawing area of everything, choose **Clear**. When asked if you are sure, select **OK** if you are sure and **CANCEL** if you do not want your screen cleared. Your screen is cleared to the background color, so if your current

The other **Clear** options allow you to clear your screen to a different height and width. This option lets you create and edit pictures larger than one screen. When you select a picture size, you can select pixels (**PELS**) or inches (**IN**) or millimeters (**MM**). The inches and mm settings refer to **printout size** when using a 1:1 screen to printer ratio. If you switch printers, then these sizes may no longer be accurate. When it comes time to print your picture, the **Print** box lets you adjust printout size. Again, be aware that your selection in **Clear** determines the optimal printout size.

Note that **PC Paintbrush** lets you create a large picture. For example, using a 16 color **IBM EGA** board, a picture of size 2000x3000 pixels will take up 3 million bytes of disk storage for the temporary file [(4x2000x3000)/8]. Therefore, this large image capability should be used with discretion and preferably a hard disk.

7.2f Quit

When you are ready to exit **PC Paintbrush**, select **Quit**. You are asked if you are sure, so select **Yes** if you do want to quit, **No** if you change your mind.

7.3 Edit

The Edit menu is used with the pick tool. The Edit menu has four options:

1. Cut
2. Copy
3. Paste
4. Name is...

You must be using the scissors or pick tool to use any Edit menu option. See Section 6.2 for a detailed discussion on using the Edit menu with these tools.

7.4 Style

The Style menu is used in conjunction with the text tool. The Style options vary, depending whether you are using a bit mapped font or a stroke font. See Section 6.4 for additional information.

7.5 Size

The Size menu is used with the text tool. The various options depend on the font you are using - a bit mapped font or a stroke font. See Section 6.4 for a more detailed explanation.

7.6 Pick

The Pick menu is used with the scissors and pick tool. The options are:

1. Rotate
2. Flip Horizontal
3. Flip Vertical
4. Inverse
5. Shrink + Grow
6. Tilt
7. Clear

You must be using the either the scissors or pick tool to use the Pick menu options. See Section 6.2 for additional information.

7.7 Misc

The Misc menu has nine options:

1. Set Speed
2. zoom-in
3. ZOOM-in
4. Brush Shapes
5. Edit Pattern
6. Get Pattern
7. Save Pattern
8. Adj. Palette
9. Adj. Aspect

7.7a Set Speed

Set Speed is used only with a joystick, so if you are using another drawing device, you are unable to choose this option. Using this option allows you to set the joystick to a satisfactory speed. When you select this option the line appears:

Set speed (00...99):

Type a number and press the Enter key. Entering a number around 50 results in average speed for your joystick/cursor movement. 00 is the slowest speed and 99 is the fastest. Experiment with various rates to determine what speed is the most comfortable for you.


7.7b zoom-in/ZOOM-in

These two options are similar to one another and are helpful in doing fine detailed drawings. To use either option:

1. Select either zoom option by pressing . Once you select an option, the

menu folds up.

2. When you move your cursor into the drawing area, your cursor appears as a hollow box. Use this box to surround the area you want to zoom-in. Press  over the area. The upper left hand corner of the drawing area is converted to the area you zoomed-in. The rest of the drawing area becomes a blown up view of that area.



3. You may now alter your area. Press  to change one square at a time to a different color. Pressing  changes the square to the current background color while pressing  changes the square to the foreground color. You may hold down either mouse button and rub an area. You may see how your area is being changed by watching the upper left hand corner of the drawing area.
4. If you want, pick different foreground and background colors to make more changes.
5. Once you are satisfied with your

changes, select **Accept** at the top of the screen. If you make a mistake, select **Undo**.

Scroll bars can be used with either zoom-in or Zoom-in. Scroll bars let you scroll through your entire drawing area so you do not have to select **Accept** and then reselect one of the zoom options to make additional changes. Scroll bars work in the usual manner, the white box indicates the size of the zoomed-in area with respect to the entire drawing area. The white box is small, indicating the zoomed area is a small portion of the entire area. Remember, for best results, use the white area of Scroll bars while in either zoom mode. See Section 5.1a.

Note: Once you select **Scroll bars**, **Undo** will not delete your previous changes, only your most recent work.

When you use the paint roller tool and the paint leaks, the zoom options are useful to fix the areas where the paint leaked. Also, use the zoom options to do delicate touch ups to your drawings. The zoom-in and ZOOM-in options differ only in the amount of magnification they provide.

7.7c Brush Shapes


The **Brush Shapes** option is used with the paintbrush tool. Using this option allows you to create various free hand drawings. See Section 6.7 for additional information.

7.7d Edit Pattern

Each color or pattern in the color palette is actually an 8X8 matrix. With the **Edit Pattern** option, you can change the matrix, creating different patterns. If you want to create new patterns:

1. Select any solid color or pattern you wish to change from the color palette. Make sure it is the foreground color.

2. Select the Edit Pattern option from the Misc menu. The pattern then appears on the screen in two ways. The individual squares (matrix) on the left are enlarged versions of the pattern. The right hand box shows the pattern how it will look in the picture.



3. Select any combination of foreground and background colors. You can change only the pattern on the left. Press  to change a square to the background color and press  to change a square to the foreground color.
- * For best results, use solid colors as foreground and background colors when editing.
 - * You can create patterns that appear to be different colors. For example, pick any pattern or color as the foreground color. Next, choose the Edit pattern option. Then select light cyan as your foreground color and yellow as your

background color. Alternate between cyan and yellow - in a checkerboard manner. When you are through, the new color appears to be a pastel green.

4. You can see the alterations by viewing the pattern on the right.
5. Once you are satisfied with your new pattern, reselect the Misc menu. The new pattern takes the place of the old pattern in the color palette.

A short cut to selecting Edit Pattern is a double click option. To use the double click option:

1. Go to the color or color pattern you wish to edit. Your cursor appears as an arrow in the color palette.
2. Press  twice over the desired color pattern. The 8x8 matrix of the color or color pattern appears.
3. Edit your pattern as you would if you had picked Edit pattern.

You may use your new color patterns as long as you are running PC Paintbrush, or until you change palettes (see the next section on changing palettes). The next time you run PC Paintbrush, the color palette is set to the original (default) color palette. You may save any new color patterns so that they are available the next time you run PC Paintbrush. See the next section for saving your changes.

7.7e Get Pattern and Save Pattern

The Get Pattern option is composed of a list of various sets of color patterns. Originally the list is made of three options:

1. DEF2

2. DEF4
3. DEF16

One of these patterns choices is the default depending on your graphics card. All options may not be available, this is also dependent upon your graphics card. For example, if you installed PC Paintbrush for two colors, you should not select a palette that has four or sixteen colors. If you choose one that can not be used with your card, you may receive the error message:

ERROR
Not found

Press  and no harm is done. More than likely, the pattern will look wrong. If so, reselect your correct default setting.

Once you select from the list, your color pattern setting changes. If you select an option, and you receive neither an error message nor a change in pattern setting, then you reselected the current setting. If this occurs when you first choose Get Pattern, then you selected the default palette. Remember your default setting in case you make any alterations (through the Edit Pattern option) and want them saved to your default setting.

You may switch between sets of patterns. Any change does not affect anything in the drawing area. This allows you to use more than one setting in a single picture.

You may create new patterns with the Edit Pattern option. Once you create a pattern that you want to keep, select the Save Pattern option. To use the Save Pattern option:

1. Select Save Pattern from the Misc menu.
2. A list of previously saved pattern settings appears on your screen. Initially, this list is only the original list of settings that are found in Get Pat-

tern.

3. To overwrite a previously saved pattern setting, simply select that setting name. When you wish to retrieve the setting, select Get Pattern and select the name.
4. To save your pattern setting under a different name, select ?? at the bottom of the list. When the Use file box appears, type in a name and press the Enter key.

7.7f Adj. Palette

The adjust palette option lets you adjust the current color palette. Depending upon your graphics card, you get one of two possible options. One option consists of two boxes, initially the box on the left is black and the one on the right is white. The other option consists of three boxes, labeled red, green and blue.

With the foreground/background option, you can change the background color or the screen colors. Press inside the foreground box to change the intensity of the screen colors. This box allows you three different palettes of two intensity levels for a total of six options. Press  to set the palette to zero. Press inside the background box to alter the color that is usually black. This box allows you sixteen different changes. You may select various combinations of colors and intensity levels. Once you are satisfied with a palette, select OK. If you are not satisfied with any options and want the original palette, press CANCEL.

With the Red/Green/Blue option, you can change the appearance of one color at a time. You can make a color anywhere in the screen a different shade or color. Follow this procedure:

1. Select the Adj. Palette option in the Misc menu.

2. Before pressing , move your cursor to a color anywhere on the screen that you wish to alter. Press  on that color. If you pick the color black, everything that is black changes.

3. Go to the red, green and blue boxes. Press  in any box to make a change. Each time you press , you increment one intensity level of color. If you press  while in a square, it resets that color to zero. For instance, decide to change white by pressing  on top of a white spot. Go to the blue box and press . This resets the level of blue to zero. Now, go to the green box and press  and then . Do the same for the red box. This mixes equal parts of green and red and no parts of blue, producing a low intensity shade of yellow. Increase red and green (by pressing ) in equal parts to produce a higher intensity of yellow. Note that some boards have more selections than others.

4. Once you are satisfied with the shade of yellow, reselect the Misc menu. Experiment with other colors by using different parts of red, blue and green.

Hint: When changing a color, do not try changing a dither or pattern. Dithers and patterns are made of two or more colors, so when you select one of these to change, you actually only select one of the colors in that dither or pattern.

7.7g Adj. Aspect


The aspect ratio of a screen or printer is the ratio of the height of one pixel to the width of one pixel. Thus, an aspect ratio of 1 means your dots are square (most laser printers have a 1:1 aspect ratio). An aspect ratio of 2 would imply tall and skinny pixels such as an IBM color card in 640x200.

Aspect ratio is used to determine:

1. The ratio of height and width for stroke characters.
2. The ratio of height and width for fat box sides.
3. The shape of circles and squares.

To change the aspect ratio:

1. Place your cursor at the upper right inside the aspect ratio box.



2. Press  and pull the the box left or right. You should see the box move and the aspect ratio setting change.

3. Press OK to accept the new ratio, CANCEL to return the old value.

To check your aspect ratio, try drawing a circle. Be sure to hold down the Shift key while drawing your circle on the screen. If you get an elliptical shape, reset the aspect ratio and try again until you get a perfect circle.

7.8 The Function Keys

The function keys, F1, F2, F5-F8 can be used with PC Paintbrush.

1. The F1 and F2 keys are primarily used with the line tool. F1 marks the spot while F2 remembers the point marked by F1. These two keys are useful for doing "sunburst" drawings. See Section 6.10 on the line tool for more information.
2. The F5 and F6 keys each place a grid on the screen, F5 places a more closely spaced grid than F6. Press F5 (or F6) to place a grid in the drawing area. Press F5 (or F6) again to remove the grid. You can use both simultaneously.

Your foreground and screen colors affect your grid. For best results, use identical foreground and screen colors. (Do not use black.) Then when you press F5 or F6 to draw a grid, it appears as black on your screen. If your screen is black and your foreground color is another color, the grid usually appears as the foreground color. See Table 7.1 below for some examples on how the grid is

affected by the foreground and screen colors.

When you want to remove the grid from the screen, make sure that your foreground color is the same color that you used when you first invoked the grid. Otherwise, you get another grid invoked by the new foreground color. To remedy this situation, press F5 (or F6) again, to release that grid, then select the original foreground color and press F5 (or F6) to release the original grid.

If you draw over some of the grid points while it is on your screen, when you remove the grid, those points may remain in your drawing. If you wish to remove them, select one of the zoom options in the Misc menu and change the grid points to a desired color or use the colored eraser.

Table 7.1

Screen Color	Foreground Color	Grid Color
White	Light Green Dark Blue Light Red White	Light Magenta Yellow Dark Cyan Black
Black	Light Green Light Blue White	Light Green Light Blue White
Light Blue	Black Light Red Light Blue	Dark Magenta Black

This table represents only a few of the different combinations. Experiment to find which foreground and screen colors work best for you. You may find some combinations do not work well. For best results, we recommend that you set the screen and the foreground colors the same. After implementing the grid, you can change the foreground color and continue drawing.

3. The F7 and F8 keys limit your cursor movement so that you can draw only between invisible grid points. These keys are useful with the F5 and F6 keys so that you can draw diagonal lines between grid points. Also, use these keys to aid in drawing three dimensional frame drawings. F7 gives you narrow movement while F8 is for wide movement. To implement either grid snap, press F7 (or F8). To release the grid snaps, press F7 (or F8) again.

7.8a Constraining

You can limit your cursor movement so that it is easier to do certain drawings.

1. The F7 and F8 keys limit your movement between grid points. See the previous section for more information.
2. The Shift key contains movement

with most tools. For example, you can draw perfect squares and circles by holding down the Shift key. You can also constrain your movement in a horizontal or vertical direction with the paintbrush tool, line, color eraser and eraser. To constrain movement, hold down the Shift key and then move in either a horizontal or vertical direction. Even your slightest movement locks you into one direction. If so, release the Shift key and start again. See Chapter 6 for complete information.

You may use the Shift key with either of the grid snaps, F7 or F8. These constraints are helpful when you need to make specific drawings.

8. FRIEZE Printer Driver

FRIEZE is a self-contained program for printing PC Paintbrush pictures and for importing pictures from other programs for enhancement. Pictures can be stored and later retrieved for editing with PC Paintbrush or used in slide shows. With FRIEZE you can:

1. Print any PC Paintbrush screen or a subsection of any screen:
 - * normal or sideways,
 - * reduced or enlarged from 1 inch by 1 inch to 2 feet by 300 feet and
 - * with a left margin that you specify.
2. Save the screen or a piece of the screen to disk.
3. Restore a previously saved picture from the disk to the screen.

FRIEZE attaches itself to the PC-DOS operating system, so you can use it for printing or saving pictures from most other graphics programs.

8.1 A Quick Introduction to FRIEZE

Here is your chance to see what FRIEZE can do.

1. Run PC Paintbrush. This ensures that FRIEZE is loaded in memory. Select the Show Screen option in the Page menu.
2. Invoke FRIEZE by pressing the Shift

and PrtSc/* keys together. The FRIEZE menu appears at the top of the screen:

FRIEZE - H,M,PR,S,W,V:

3. Then select either:
 - * S to save a picture on the screen. Next, type any valid DOS file name and then press the Enter key and your picture is saved.
 - * R to restore a saved picture on the screen. Type the name of the file and then press the Enter key to restore a picture. Remember to include any extensions if you are restoring a picture from PC Paintbrush.
4. Select P to print the screen. In the Print option, select:
 - * C to print in character mode.
 - * N to print in normal or portrait mode.
 - * S to print in sideways or landscape mode.

You can press the Esc key to back out of FRIEZE. See Chapter 9 for a more detailed discussion of using FRIEZE.

8.2 Changing Printers

You customized FRIEZE for your printer through the PCINSTAL procedure in Chapter 2. However, if you change from one printer or plotter to another, you need to rerun PCINSTAL and follow the same procedure but change only

option 3. Then make sure you choose option 5 to save the setup to your disk.

Once you complete PCINSTAL, you must "reboot" your computer by inserting your DOS disk and press the Ctrl/Alt/Del keys. Rebooting eliminates the resident copy of FRIEZE. Rerunning FRIEZE (by typing **PAINT**) then loads a new resident copy of FRIEZE. Remember, PCINSTAL customizes FRIEZE for your printer.

9. Using the FRIEZE Options

FRIEZE works independently of PC Paintbrush to let you print and save any piece of the screen.

You invoke FRIEZE by pressing the Shift and PrtSc/* keys simultaneously. The top of the screen then shows the FRIEZE menu:

FRIEZE - H,M,PR,S,W,V:

Each character in the prompt line stands for a FRIEZE command:

H...Height
M...Margin
P...Print
R...Restore
S...Save
W...Width
V...Viewport

These menu options are described in the next three sections. It is helpful to remember that the Esc key lets you change your mind before any changes to FRIEZE are saved.

9.1 Setting the Viewport - V

With FRIEZE's viewport, you can restrict attention to a subsection of the screen. For example, you can isolate a specific detail of a picture and print an enlarged or reduced version of it by moving the viewport. By default, FRIEZE works on the entire screen.

First, make sure your display is showing graphics. Then to set the viewport, follow these steps:

1. Call FRIEZE by pressing the Shift

and PrtSc/* keys together. The FRIEZE prompt line appears across the top of the screen.

2. Press V. FRIEZE displays the viewport as a box. Initially, the viewport covers the entire screen.
3. To move the upper left corner of the viewport, use the cursor direction keys. (◀ ▶ ▲ ▼)

- * To move the the cursor faster, hold down the Shift key as you press a cursor direction key.

- * To move the cursor even faster, hold down the Ctrl key as you press a cursor direction key.

Note: Ctrl ▲ and Ctrl ▼ are not available.

4. To move the lower right corner of the viewport, first tap the space bar, then use the cursor direction keys. If you want to return to moving the upper left corner, tap the space bar. (Tapping the space bar toggles you between moving the upper left corner and the lower right corner of the viewport.)

5. Once you are satisfied with the size of the viewport, press the Enter key and FRIEZE defines the area you specified as the viewport.

- * If you change your mind, press the Esc key instead of the Enter key and you are returned to the FRIEZE menu. Press the Esc key

again to return to the main program.

Until you change the viewport again or reboot, all further FRIEZE commands operate on the area previously defined by the viewport.

9.2 Saving and Restoring Pictures

FRIEZE lets you save and restore pictures to and from disk, in PC Paintbrush format. This feature allows you to save a picture from another program (using FRIEZE) and then load the picture while running PC Paintbrush. With PC Paintbrush features, you can edit the picture and save it to disk using the Save as... option in the Page menu. The Load from... option in the Page menu allows you to retrieve FRIEZE pictures.

When you save a picture, only the portion of the screen in the viewport is saved. When you restore a picture, the picture is placed on the screen in the upper left corner of the viewport. See Section 9.1 on Setting the Viewport.

9.2a S - Save

The Save command saves pictures in FRIEZE format. To save a picture:

1. Call FRIEZE by pressing the Shift and PrtSc/* keys together.
2. Type **S** and the line appears:

FRIEZE - Save to =
3. Type a valid DOS file name to save the picture. Then press the Enter key.

* The area inside the viewport is the only portion of the picture saved. See Section 9.1 on Setting the Viewport.

9.2b R - Restore

The Restore command allows you to restore screen and cut-outs saved by PC Paintbrush as well as other pictures saved by FRIEZE. To restore a picture:

1. Call FRIEZE by pressing the Shift and PrtSc/* keys together.
2. Type **R** and the line appears:

FRIEZE - Restore from =

3. Type the name of the picture you wish to restore.

- * Any valid DOS file name is accepted, including those with path names. Make sure you include the extension if you are restoring a PC Paintbrush picture.
- * The picture is placed on the screen inside the viewport. See Section 9.1 on Setting the Viewport.

FRIEZE beeps a few times if the file does not contain a picture in FRIEZE format or your picture can not be found. If this occurs, check to see if the disk containing your picture is in the proper drive.

9.3 Printout

Once you have a picture, use the P option to print it. The H and W options let you specify the height and width of your picture, while the M options allows you to specify the left margin.

9.3a P - Print

Screens can be printed in three ways:

- * Characters - Use this option if your "picture" is actually a screen of text characters. This option calls the standard DOS print-screen routine.
- * Normal - Used for printing graphics. Also known as portrait mode.
- * Sideways - Used for printing graphics. Also known as landscape mode. This option yields the most efficient use of paper.

You can expect strange results if you call for a character printout in graphics mode and vice versa.

To print a picture:

1. Call FRIEZE by pressing the Shift and PrtSc/* keys together.
2. Type **P** and the line appears:

FRIEZE C,N,S=

3. After selecting C, N or S, press the Enter key and FRIEZE accepts the choice and begins printing.
- * If you wish to stop printing for any reason, press the Esc key.

9.3b H, W - Height and Width

Each printed screen is 5 1/2 inches wide by 7 1/2 inches high unless you reset the height and width values. You may enlarge or reduce the printed image in 1/4 inch increments by resetting FRIEZE's height and width values before printing.

To reset the height and width values, follow these steps:

1. Call FRIEZE by pressing the Shift and PrtSc/* keys together.
2. Press H to set the height or W to set the width. One of these prompts appears:

FRIEZE - Print height (¼") =
or
FRIEZE - Print width (¼") =

3. Type the number of quarter inches you want for the height or width of your printed picture.

* For example, if you want the printed image to be 5 inches high, type **H**, then type a height value of **20** (20x¼ inch = 5 inches.)

4. Press the Enter key and FRIEZE accepts the values.

Unless you change the default values, each time you load FRIEZE, the height and width values are reset to 22 and 30 respectively (5½ by 7½ inches). You can change these default settings by following the steps described in Chapter 10 on Setting and Saving FRIEZE Defaults.

Note: Since you never want a printout that is 1.5" high or wide, values for height and width between 1 and 6 provide integer pixel zoom (i.e. 1:1, 2:1, 3:1,...). These integer values are often preferred for most attractive results when pictures contain a lot of text. For example, if your picture is 320x200 dots, specifying a height and width of 2 produces a printout with 640x400 dots on the paper. For graphics pictures, non-integer values are recommended. See Chapter 13 for further information.

9.3c M - Left Margin

You can use FRIEZE's M command to set the left margin of your printed pictures in $\frac{1}{4}$ inch increments. To set the left margin:

1. Call FRIEZE by pressing the Shift and PrtSc/* keys together.
2. Press M and the line appears.

FRIEZE - Left Margin ($\frac{1}{4}$ " =

3. Type the number of quarter inches that you want for the left margin.

* For example, if you want the left margin to be 3 inches, type **12** ($12 \times \frac{1}{4} \text{ inch} = 3 \text{ inches}$).

4. Press the Enter key and FRIEZE accepts the values.

Until you change the margin value or reboot, all printed screens reflect the last margin value set.

10. Changing FRIEZE Defaults

When you first run PC Paintbrush, the printout height, width, colors and patterns are set to default values through FRIEZE. However, you can change the default values through a program in FRIEZE named Setcolor.

10.1 Running Setcolor

To make any changes to the default values, follow this procedure to use Setcolor:

1. At A> prompt, type **FRIEZE** and press the Enter key. This ensures that FRIEZE is loaded in memory. You can not use Setcolor unless FRIEZE is in memory.
2. Type **SETCOLOR** and press the Enter key. The Setcolor menu appears:

```
Setcolor (C)1984 ZSoft Corp.
  Default  Selection
A. Set new sizes
B. Set new color correspondence
C. Save settings as default
Pick one:█

      Color Map
-->  0      1      2      3      4      5      6      7
    Black  Blue   Green  Cyan   Magenta Red   Brown  DarkGrey
      15      1      2      3      4      5      6      7

      8      9     10     11     12     13     14     15
--> LtGrey LtBlue LtGreen LtCyan LtMag  LtRed  Yellow  White
      8      9     10     11     12     13     14     0

-----Current sizes: H= 22  W= 30-----
```

Press Esc to Exit

- * Option A allows you to change the default height and width values, discussed in Section 10.2.
- * Option B allows you to change your color map, discussed in Section 10.3.
- * Option C saves your changes, so the next time you run FRIEZE, the new values are your default values.

FRIEZE stays in memory until you reboot, so once you load FRIEZE either by typing **FRIEZE** or running PC Paintbrush, it is not necessary to reload FRIEZE everytime before using Setcolor.

Note: If you are using a plotter instead of a printer, please see Section 11.1 on Special Notes for Plotters. Using FRIEZE yields slightly different results.

10.2 Setting the Height and Width Defaults

The default height and width values are measured in units of quarter inches. The default height value is 22 or 5½ inches and the default width value is 30 or 7½ inches. You may change the height and width any time through FRIEZE (see Section 9.3b) or you may change FRIEZE's default values using Setcolor.

Once the Setcolor menu appears, you are ready to change the default values. To change the height and width values:

1. Run Setcolor, then select A - Set new sizes. Setcolor asks for a new **height** value. Type in a value and press the Enter key.

- * For example, if you want your picture to be 8 inches high, type **32** ($32 \times \frac{1}{4} = 8''$).
 - * If you do not want to change the height value, type the old value and press the Enter key.
2. Now Setcolor asks for a new **width** value. Type in a value and press the Enter key.
 - * If you want your picture to be 10 inches wide, type **40** ($40 \times \frac{1}{4} = 10''$).
 - * If you do not want to change the width value, enter the old value and press the Enter key.
 3. To save the new default values, press C and the new values are saved to disk.
 - * If, for any reason, you decide not to save the values you just set, press the Esc key instead of pressing C and you return to DOS.

10.3 Color Map Settings

If you have a color printer, FRIEZE takes each screen color and translates it into a similar printer color. If you have a black and white printer, FRIEZE converts each screen color into a black and white pattern. If you are not satisfied with the FRIEZE translations, you can use Setcolor to change the color or pattern setting. This section shows you how to change the color map in the Setcolor menu. For color printer users, the next section shows you how your printer interprets printer color codes, so you can select exactly what printer color you

want matched with each screen color.

The number of printer colors or printer patterns that can be used at one time is limited to the number of screen colors in PC Paintbrush. For example, if you have installed a 4 color card (4 screen colors) then you can use only four printer colors or four printer patterns.

10.3a Mapping Textures for a Black and White Printer

When FRIEZE prints any picture on a black and white printer, it prints each **screen** color as a pattern. For example, light red is printed as pattern 13 and dark blue is printed as pattern 1, by default. The patterns, numbered from 0 to 15, are shown in Table 10.1. Remember, if you are using a two or four color card, your printer prints only two or four patterns at a time.

Table 10.1

0	1	2	3
4	5	6	7
8	9	10	11
12	13	14	15

As you can see, pattern 13 is a diagonal pattern. Pattern 1 is composed of diagonal lines while pattern 0 is white, meaning no printing. You may change the default color map so that you may assign any pattern to any color. Once you run Setcolor, you are ready to change the color map setting.

1. When you run Setcolor, the menu appears (see Section 10.1). The bottom half of the menu is the color map, consisting of three different parts. The top two rows of each section are the screen color codes. The middle rows of each section are the screen colors and the bottom rows are the printer color codes. Printer color codes correspond to the pattern numbers found in Table 10.1.
2. Use the pattern diagrams in Table 10.1 to determine which printer pattern you want to assign to each screen color.
 - * In the example below, cyan, which is screen code 3, is printed as a fine vertical line, which is pattern 5.
3. Press B - Set new color correspondence to make color map changes. Setcolor asks for the screen color number to change.
 - * Press 3, for example, to change cyan. Then press the Enter key.
4. Setcolor asks for the number corresponding to a pattern.
 - * To make cyan a fine vertical line,

press 5 followed by the Enter key.

- * If you want to change more patterns, select B again and repeat the same procedure.
5. To save these changes to disk, select option C of Setcolor.
 - * If you decide not to save the values selected, press the Esc key instead of C and you return to DOS.

If you installed a 2 or 4 color card, those 2 or 4 screen colors are the only colors that have any effect on the printer color codes.

10.3b Color Map for Color Printers

When you print with a color printer, FRIEZE automatically maps the screen colors so that the printed colors are similar to those displayed on the screen. You may assign new printer colors to the screen colors through Setcolor. This section should be used in conjunction with Section 10.4 to get the printout you want.

1. Run Setcolor and the menu appears. (See Section 10.1). The bottom half of the menu is the color map, consisting of three different parts. The top two rows of each section are the screen color codes. The middle rows of each section are the screen colors and the bottom rows are the printer color codes.
 - * Printer color codes are hexadecimal numbers, meaning the first sixteen numbers (0-15) are represented by single digits, 1-9 and A-F. (See table below.) For

example, the number 11 is B and 14 is E in a hexadecimal system. Each of the sixteen screen colors is represented by one of these hexadecimal digits. However, FRIEZE uses two digits rather than only one digit when printing. This allows you to put any two digits together. Putting two different digits together can appear to the human eye as a different color. For instance, an IBM Color Printer interprets printer color code 1 as yellow and printer color code 4 as red. Therefore, 11 prints as solid yellow and 44 prints as solid red. A color code of 14 (or 41) alternates yellow and red, thus appearing as orange.

Table 10.2

Decimal	Hexadecimal	Decimal	Hexadecimal
0	0	8	8
1	1	9	9
2	2	10	A
3	3	11	B
4	4	12	C
5	5	13	D
6	6	14	E
7	7	15	F

Note: Not all printers interpret printer color codes the same. Section 10.4 determines how your printer interprets printer color codes.

* Another example, an IBM Color

Printer interprets 0 as white and 8 as black. 00 prints as solid white and 88 prints as solid black while 80 (or 08) appears to print as gray. This technique of putting two colors together to make another "color" is called dithering. Dithering is also used in PC Paintbrush so that it seems that you have more screen colors.

Note: Dithering an already dithered screen color may cause unsatisfactory results such as stripes or other interference in patterns in the final printed color. For best results, use only solid screen colors to dither with one another. You must put two digits together, otherwise a single digit is interpreted by FRIEZE as the single digit and a 0.

2. Now that you know about the Setcolor menu, it is time to make some changes. Select B - Set new color correspondence.
3. Setcolor asks for a screen color number (from the top rows of the Setcolor menu), so if you want to change cyan for example, type **3** and press the Enter key.
4. Now Setcolor asks for a color number which is a combination of two hexadecimal digits (from the bottom rows of the Setcolor menu). Typing the same two digits produces a solid color while two different digits produces a dither. (Section 10.4 shows you the way to determine how the printed colors and printer color codes are related.) Type in two hexadecimal digits and press the Enter key.

5. If you want to change any more colors, select B again and repeat the same procedure. Once you are finished making changes, select C to save your changes to disk.

- * If you decide not to save the values selected, press the Esc key instead of C and you are returned to DOS.

10.4 Making a Color Chart for Your Printer

The last section explains how to change your color map in the Setcolor menu. This sections explains how your printer interprets those printer color codes (hexadecimal digits). To do this, it is necessary to make a color chart with PC Paintbrush and change your color map in Setcolor. Determine if you have a 16 color card, 4 color card or monochrome card in your computer and follow the instructions.

Note: If you are using a serial printer, see Section 11.2 for additional information on making a color chart.

Hint: If you are unhappy with the changes you make in Setcolor, you may return to the original default map. Rerun PCINSTAL and reselect your printer which is option 3. Don't forget to select option 5. Next, reboot your computer by inserting your DOS disk and pressing Ctrl/Alt/Del. Reinsert PC Paintbrush disk 1 and rerun PC Paintbrush. You may then change the printer color codes through Setcolor or leave them unchanged.

10.4a 16 Color Cards

If you have a 16 color card:

1. Run Setcolor and then select option B of the Setcolor menu - Set new color correspondence. Setcolor asks for a screen color number (from

the top rows of the Setcolor menu). Start with screen color 0 and press the Enter key.

2. Setcolor now asks for a color number which is from the bottom row of the Setcolor menu. Type in **00** and press the Enter key.
3. Repeat this procedure, this time selecting screen color 1 and mapping it with printer number 11. Continue until all sixteen screen colors are mapped with the hexadecimal digits. Remember when you get to screen color 10, it should be mapped with AA. When you are finished, your Setcolor menu should look like the one below.

Setcolor (C)1984 ZSoft Corp.

Default Selection

A. Set new sizes
B. Set new color correspondence
C. Save settings as default
Pick one: █

Color Map							
0	1	2	3	4	5	6	7
-->Black	Blue	Green	Cyan	Magenta	Red	Brown	DarkGrey
14	11	22	33	44	55	66	77
8	9	10	11	12	13	14	15
-->LtGrey	LtBlue	LtGreen	LtCyan	LtMag	LtRed	Yellow	White
88	99	AA	BB	CC	DD	EE	FF

Current sizes: H= 22 W= 30

Press Esc to Exit

4. When you have mapped all sixteen screen colors, select option C so that the changes are saved to disk.
5. Now run PC Paintbrush by typing

PAINT at the A> prompt. Use the filled box tool to create sixteen boxes, each filled with one of the sixteen screen colors. Do not select dithers!

6. When your printer is ready, select Print from the Page menu.

You now have a copy of how your printer interprets the printer color codes. For example, let's say your printer printed the screen color black (screen color 0) as red. Then you know that your printer thinks that the printer number 00 is red. If your printer printed the screen color green as yellow, then you know that your printer thinks that the printer color code 22 is yellow. You can print any screen color as any color you want by resetting the color map in the Setcolor menu. Once you know the various color mappings, you can also create dithers. In this example, selecting 0 and 2 together would appear as orange.

10.4b 4 Color Cards

If you have a 4 color card, you need to do four experiments in order to determine how your printer interprets printer color codes. The four screen colors used by PC Paintbrush are:

1. Black - screen color code 0
2. Light Cyan - screen color code 11
3. Light Magenta - screen color code 12
4. White - screen color code 15

These are the only colors that have any effect on the printed colors. To make one color map using these four possibilities:

1. Run Setcolor and then select option B of the Setcolor menu - Set new color correspondence. Setcolor asks for a screen color number, begin with black (screen color code 0) and map it with color number 00.

2. Continue this procedure until all four screen colors are mapped; 12 is mapped with printer color code 11, color 13 with code 22 and color 15 with code 33.
 - * Select **C** to save these changes to disk.
3. At the A> prompt type **PAINT** to run PC Paintbrush. Use the filled box tool to create 4 boxes using the 4 screen colors.
4. When your printer is ready to print, select Print from the Page menu.

Now you have one color map, so you should be able to determine what printer color codes 0, 1, 2 and 3 mean to your printer. Repeat this procedure three more times to cover the other twelve possibilities. Your four experiments of mapping screen colors 0, 12, 13 and 15 to printer color codes are:

1. 00, 11, 22 and 33
2. 44, 55, 66 and 77
3. 88, 99, AA and BB
4. CC, DD, EE and FF

Once you complete the four color maps you have four copies of how your printer interprets printer color codes, covering all sixteen possibilities. Using these color maps and your dither knowledge, you should be able to produce satisfactory printouts.

10.4c 2 Color Cards

Monochrome cards make it difficult when determining how your printer interprets printer color codes. If you feel industrious, you may create eight experiments to cover all sixteen printer color codes. Your other option is to just be satisfied with your printed results.

With a monochrome card, you have only two colors, black, which is screen color code 0 and white, which is screen color code 15. These two screen colors are the only ones that have any effect on the printed colors. Therefore, it is necessary to make eight color maps to determine printer color code interpretations. So, for the diligent:

1. Run Setcolor and then select option B of the Setcolor menu - Set new color correspondence. Setcolor asks for a screen color number, map screen color 0 with 00 and screen color 15 with 11.
 - * Select C to save your color map to disk.
2. At the A> prompt type **PAINT** to run PC Paintbrush. Use the filled box tool to create 2 boxes using the 2 screen colors.
3. When your printer is ready to print, select Print from the Page menu.

Now you have one color map, so you should be able to determine what printer color codes 0 and 1 mean to your printer. Repeat this procedure seven more times to cover the other fourteen possibilities. Your eight experiments of mapping screen colors 0 and 15 to printer color codes are:

1. 00 and 11
2. 22 and 33
3. 44 and 55
4. 66 and 77
5. 88 and 99
6. AA and BB
7. CC and DD
8. EE and FF

Use your eight color maps to make satisfactory printouts.

11. Notes for Special Hardware

11.1 Notes for Plotters

Plotters are fairly easy to get running if you follow some simple steps and diagnostics. This discussion assumes that you have a serial plotter; parallel plotter owners can ignore the cabling, handshaking and baud rate discussions.

Make sure that your cable is a full RS-232 spec cable (not a three-wire connection), and also make sure that it has Xon-Xoff handshaking enabled on the dip switches. Finally, run the MODE command to set the appropriate serial speed before running PC Paintbrush.

11.2 Running Setcolor

When you first run FRIEZE, the printout height, width and colors are initially set to default values. However, changing these default values when a plotter is installed yields different results than installing a printer. The default values are changed through a program in FRIEZE named Setcolor. Follow this procedure to use Setcolor:

1. At the A> prompt, type **FRIEZE** and press the Enter key. This ensures that FRIEZE is loaded in memory.
2. Type **SETCOLOR** and press the Enter key. The Setcolor menu appears:

```

Setcolor (C)1984 ZSoft Corp.
  Default Selection

A. Set new sizes
B. Set new color correspondence
C. Save settings as default
Pick one: █

      Color Map
--> 0   1   2   3   4   5   6   7
    Black Blue Green Cyan Magenta Red Brown DarkGrey
     0   1   2   3   4   5   6   1

      8   9  10  11  12  13  14  15
--> LtGrey LtBlue LtGreen LtCyan LtMag LtRed Yellow White
     2   3   4   5   6   1   2   3

Current sizes: H= 22 W= 30

Press Esc to Exit

```

- * Option A allows you to change the default height value, discussed in Section 11.2a.
- * Option B allows you to change your color map, discussed in Section 11.2b.
- * Option C saves your changes, so the next time you run FRIEZE, the new values are your default values.

Note that FRIEZE remains in memory until you reboot your system. Therefore, once you run FRIEZE, simply type **SET-COLOR** at the A> prompt without rerunning FRIEZE. If, for any reason, you reboot, you must reload FRIEZE by running PC Paintbrush or FRIEZE.

11.2a Altering the Height and Width

Unlike printers, the height and width of printout is set by the plotter. For the HP7475 plotter, the height and width is set using the P1 and P2 buttons on the plotter. Changing the width, W with FRIEZE has no effect on printout. However, changing the height, H with FRIEZE alters the density of the picture. To alter the density, you may change the height value any time through FRIEZE (see Section 9.3b) or you may change FRIEZE's default value for the height using Setcolor.

To alter the density:

1. Run Setcolor. Once the menu appears, select option A - Set new sizes.
2. Setcolor asks for a new height value. Type in a value and press the Enter key.
 - * A value of 1 produces widely spaced lines. This is good for checking color mapping, for example.
 - * You can type in any value, but a value of between 2 and 6 is recommended as one of these values produce higher quality pictures.
5. Setcolor then asks for a new width value. Type in any value and press the Enter key, since the width value has no effect on printout.
6. To save the new default value, press C and the new value is saved to disk.
 - * If, for any reason, you decide not to save the value you just set, press the Esc key instead of pressing C and you are returned to DOS.

11.2b Pen Colors

Plotters have a simple color correspondence. You should use Setcolor so that the pen color correspond to your screen colors.

1. When you run Setcolor, the menu appears (see Section 11.1). The bot-

tom half of the menu is the color map, consisting of three different parts. The top two rows of each section are the screen color codes. The middle rows of each section are the screen colors and the bottom rows are the pen colors. The number of colors you may print with is limited to the number of pen colors that your plotter has.

2. Select option B - Set new color correspondence. Setcolor asks for a screen color number - from the top row. Type in a number from 0 to 15 and press the Enter key. For example, if you want to change the pen color used for cyan, type in **3** and press the Enter key.
3. Setcolor now asks for a pen color. Select the pen number (single digit) you want matched with cyan. Typing in **1** means cyan is printed with pen 1.
 - * If you type **0**, your plotter does not use any pen. This is equivalent to printing with the color white.
 - * You may map more than one screen color to one pen color.
4. Select option B again to make more changes.
5. To save these changes to disk, select option C of Setcolor.
 - * If you decide not to save the values selected, press the Esc key instead of C and you are returned to DOS.

11.3 Notes for PrintaColor Printers

PrintaColor printers have 128 different colors. To determine what screen color is printed with each printer color, run the PrintaColor test pattern. Since the printer color codes used in Setcolor are hexadecimal, you need to translate the printer color codes into base 10 numbers.

11.4 Notes for Serial Printers

When using a serial printer, FRIEZE uses standard DOS printer outputs for printing. You need to first set the baud rate used by the serial communications interface using the DOS MODE program.

1. For example, if your printer is connected to COM1 (set in option 4 of PCINSTAL) and requires 9600 baud with no parity and eight data bits, you need to type:

A>MODE COM1:9600,N,8

For additional information, see your DOS manual on MODE commands.

Once you set the baud rate, you can run PC Paintbrush. You need to set only the baud rate each time you reboot the system.

12. FRIEZE - Special Notes

12.1 Using FRIEZE with SuperCalc3

SuperCalc3 suffers from the dreaded two beep problem. This may happen when you try saving or restoring pictures from SuperCalc3. If you get two beeps, either your picture is not saved to disk or you are unable to restore your picture.

This problem lies entirely in PC-DOS. The problem occurs when SuperCalc3 is performing a DOS command when you try saving or restoring a picture. Since DOS is running, serious damage results if FRIEZE calls DOS again.

To prevent the two beep problem from occurring:

1. At the A> prompt, type **FRIEZE** and press the Enter key. This ensures that FRIEZE is loaded in memory.
2. Run SuperCalc3. Now, wait until the picture is just finished being drawn on the screen. Then press the Shift and PrtSc/* keys. Timing is important for best results. Select either a save or restore command and type the name of the file you wish to save or restore.

FRIEZE stops SuperCalc3 as soon as you press the Shift and PrtSc/* keys, so if you do not have a complete picture, press the Esc key and allow SuperCalc3 to finish. Then press the Shift and PrtSc/* keys again. If necessary, repeat this until you have a complete picture.

12.2 FRIEZE Technical Information

FRIEZE uses a different number of beeps to indicate errors. If an error occurs that you can not explain, please make a note of the number of beeps that occur so that you can inform someone from our support group.

In general, you should be able to realize a problem has occurred by the fact that FRIEZE has beeped. Two things to keep in mind:

1. Beeps from FRIEZE imply that the error is not the fault of FRIEZE, but your hardware. The most common problem is a bad printer cable. If you get 4 beeps and no printer activity, check your cable.
2. The most common error message is 2 beeps. This is a DOS conflict problem. This occurs when you tried saving or restoring a picture while your program is talking with DOS. Try saving or restoring again at a different program juncture.

12.3 FRIEZE Slide Shows and Multiple Printouts

FRIEZE is controlled by a unused interrupt vector in the PC. You can thus call FRIEZE and invoke any of the FRIEZE functions under program control, rather than from the keyboard. FRIEZE uses interrupt 16 (decimal). Invoke FRIEZE by placing 75 in AH, the function number in CL and the arguments in AL and ES:BX. The most common calls are:

1. 0 - Print a screen. Set AL = 0, 1 or 2.

2. 1 - Restore a picture. Set AL=1, set ES:BX pointing to the file name.
 3. 2 - Save a picture. Set AL=2, set ES:BX pointing to the file name.
- * For example, to print a picture:

```
MOV AH,75  
MOV CL,0  
MOV AL,1  
INT 16
```

13. Improving Your Printout

We get a large number of questions from customers interested in improving the printout from PC Paintbrush. In particular, PC Paintbrush supports so much different hardware and FRIEZE is capable of so many print variations that it is difficult to deliver a default printout that is exemplary for every printer and display. We believe our default printout is acceptable, for beautiful results you will need to do a little work.

Let's examine how to optimize printout in stages, based on common questions:

13.1 Coloring

Q1. The colors on my printout are different from the colors on my screen.

A1. If you have a color printer and display this can often happen. Particularly if your display has an extensively changeable palette such as the 64 shade IBM EGA board. To get best color correspondence, use the Setcolor program provided with PC Paintbrush and FRIEZE. Setcolor lets you adjust the color correspondence - which printer color is used for which screen color.

Please read the Setcolor section before continuing.

Note that color printers have approximately 32 different shadings available with the Setcolor dither capability. You might want to try all 32 different values to see how your printer responds to each dither combination.

Further note: We have found that PC Paintbrush and FRIEZE can interfere with each other when it comes to printing patterns. If you have a color printer we suggest you use one of two techniques:

1. Restrict your drawing to solid colors only, and use whatever dithers you like for printout through Setcolor.
 2. Use any patterns you like for drawing, but via Setcolor, set FRIEZE so it only prints solids for each on-screen color (this means use double digits - no dithers). This may restrict you to only seven different color choices for your printer. You can make up the difference by using the Edit Pattern abilities of Paintbrush to change on-screen appearance.
- Q2. I don't like the shading patterns used for some colors on my black and white printer.
- A2. The best we can do here is offer a suggestion. Note that FRIEZE supports 16 different shading patterns. If you want different ones, run Setcolor and select the desired patterns. Hopefully, you are not using all 16 already.
- Q3. I am missing lines on my printout.
- A4. This is usually caused by one of two things.
1. You may have set print width or height too small. In that case, when FRIEZE shrinks the picture for printout it can lose line information. Try Shrink+Grow to see how this works. Often just increasing print size will solve this problem. One way to check this is pull down the Clear from the Page and switch from pixels to inches. If your picture size in inches is greater than your selected print size, you have found the problem.

2. You may instead have a color mapped to a very light shading pattern, in which case so little of the color shows up on the printout that it seems to have dropped off some information. Try running Setcolor and setting all colors (except white) to shading pattern 0, which is solid black, then reprinting to see if that might be your problem.

13.2 Sizing

- Q1. Circles on the screen turn into ovals (ellipses) on the printout.
- A1. This means that your printout aspect ratio is incorrect. You can change that aspect ratio by changing the print dimensions. Usually you want to increase the print dimensions for large images and decrease them for normal screen-size pictures. Since large images are printed out by default at 1:1 ratio this can often cause aspect ratio distortion. Note that if you decrease the print size of a large image (beyond the default print size) you are almost certainly dropping off some picture information.
- Q2. Although pictures look pretty good, the text looks irregular and uneven.
- A2. This is usually caused by poor choice of print sizes. For text modes we generally recommend that you select integral multiplication factors (see below) and ignore the fact that the aspect ratio is slightly off (see above).

You can select integral multiplication factors in one of two ways.

1. Using FRIEZE manually, you can set print height and width to a number-between 1 and 6. This causes an

expansion ratio of 1:1 to 6:1. In all cases no information will be lost and text should look attractive. To print the screen from within FRIEZE double click the pick tool to see the entire screen and then invoke FRIEZE manually with the Shift and PrtSc/* keys. (see the FRIEZE sections).

2. Using the options in the Clear option.
See the next question.

Q3. What are the best print sizes to pick for a specific picture?

A3. This depends on your combination of printer and picture resolution. With the Clear box you can determine printer resolution easily. The numbers in inches and millimeters in the clear dialog box tell you what a 1:1 ratio would be (1 dot printed for each dot on the screen). Thus, set your clear display to inches and sizes to 1.0 inches in both dimensions then see what the vertical and horizontal printer resolutions are by switching to PELS (don't actually clear the screen).

Let's call these PrinterVert and PrinterHoriz.

Now suppose your picture has size in pixels of Vres and Hres (vertical and horizontal resolution).

The larger your printout, the better its appearance to within certain limits.

Suppose you are printing a single screen. This has the advantage that you can print it normal (portrait) or sideways (landscape). Sideways generally takes better advantage of the paper since monitors are shaped like sideways paper. If you print sideways, we suggest making the print width a multiple of the number of vertical dots. Thus:

1. Best Print Width = $(Vres / \text{PrinterHoriz}) * \text{int}(\text{PrinterHoriz} * \text{PaperWidth} / Vres)$.
2. Best Print Height = Best Print Width / Monitor Aspect Ratio.

The Monitor Aspect Ratio is the ratio of the height of the monitor screen to the width of the monitor screen. You can determine this just by measuring the screen with the PC Paintbrush menus on it.

Let's take an example. Suppose you have an Epson MX-80 printer and an IBM color monitor you are using at 640x200 resolution. The Epson printer prints at 72 dots per inch vertically and 120 horizontally and has 8 inch wide paper. An IBM color monitor has a height/width ratio of approximately 3:4 or .75. Note that yours may vary from this number.

Thus the best print situation in this case would be:

1. Print Sideways.
2. Best Print Width = $(200 / 120) * \text{int}(120 * 8 / 200) = (200 / 120) * 4 = 6.67$ inches.
3. Best Print Height = $6.67 / .75 = 8.9$ inches.

Note: If you call FRIEZE manually, you could just set the print width to 4 which implies an integer multiplier of 4 as we found in the print width calculations.

If you optimize the size horizontally instead of vertically the calculations become:

1. Best Print Height = $(Hres / \text{PrinterVert}) * \text{int}(\text{PrinterVert} * \text{PaperLength} / Hres)$.

2. Best Print Width = BestPrintHeight
* Monitor Aspect Ratio.

If you are printing a large image, or want to print a screen-sized image in normal rather than sideways:

1. Best Print Width = (Hres/
PrinterHoriz) * int(PrinterHoriz *
PaperWidth / Hres).
2. Best Print Height = BestPrintWidth
* Monitor Aspect Ratio.

Assume we want to print an 800 by 1000 image on this same Epson printer and we are looking at the same IBM color monitor. Then,

1. Best Print Width = $(800 / 120) * \text{int}(120 * 8 / 800) = 800 / 120 * 1 = 6.67$
inches.
2. Best Print Height = $6.67 * .75 = 5$
inches.

Suppose this calculation gives you an integer multiplier of 0. Then you do not have enough printer resolution to print each dot of the entire picture. In this case you can either shrink the picture proportionately (make the vertical resolution an integer multiple) or print the picture in multiple passes, using FRIEZE manually. We advise shrinking the picture, but do notice that some information will be lost if you do so.

14. Common Questions and Problems

There are several problems that may occur when using PC Paintbrush and FRIEZE. This chapter helps you deal with those problems.

14.1 Tablets

Q1. My cursor does not move on the screen.

A1. There are many possible causes for no cursor movement.

- A) If the program was installed incorrectly, the cursor will not move. Reinstall the program through PCINSTAL, the instructions are found in Chapter 2. Note that there are four choices for Summagraphics tablets and four choices for GTCO tablets.
- B) If you are using a tablet, it is possible that the BAUD rate was not reset by the program. In order to solve this situation, turn off the power on your tablet and unplug the tablet. Plug in the tablet and now try using your cursor.
- C) It is possible that your tablet driver was not run before using PC Paintbrush. Your tablet driver was loaded into the PAINT.BAT program through the installation procedure, PCINSTAL. When you type **PAINT** to start PC Paintbrush, your tablet driver is loaded at this time. If you entered PC Paintbrush in some other manner, your tablet driver is not run. Reboot and rerun PC Paintbrush by typing **PAINT** at the A> prompt. This loads both FRIEZE and your tablet driver.
- D) Check all connections to see if your tablet is plugged in properly. If that tablet is not plugged in properly, turn off the power and unplug the tablet. Then plug it

back in and retry using your cursor.

- Q2. My cursor moves correctly in the horizontal (or vertical) direction, but moves in opposite directions in the vertical (or horizontal) direction.
- A2. If your tablet was installed as a 12x12 tablet, for example, but is a 6x9 tablet, your movement can be limited in either the vertical or horizontal direction. Rerun PCINSTALL and reinstall the proper drawing device, including the right size.
- Q3. My tablet does not work with the PCjr.
- A3. The BAUD rate for the PCjr on a serial port is at most 4800. PC Paintbrush requires that the BAUD rate be set at 9600. At this time, there is not a solution, so a tablet does not work with the PCjr. In the near future, a driver will be available from ZSoft to solve this situation.

14.2 Mice

- Q1. I move my mouse, but the cursor does not respond.
- A1. There are three possible situations that may cause your cursor to not move.
 - A) If you installed the mouse to the wrong port, your cursor will not move. Rerun PCINSTALL and check which port you installed your mouse, if necessary, reinstall the proper port.
 - B) Check PCINSTALL and make sure you installed the proper drawing device. Reinstall, if necessary.
 - C) You may have installed your mouse on a port that is not active on your computer. Check your port.

Note: In any of these situations, you can check your PAINT.BAT program to see what mouse was loaded. In

order to find out, at the A> prompt, type **TYPE PAINT.BAT** and press the Enter key. The program contents are displayed on your screen. If you find the wrong mouse loaded, repeat PCINSTAL in Chapter 2 to load the correct mouse. You may need to reboot if you ran the wrong mouse driver.

- Q2. My serial mouse does not work with the Corona PC.
- A2. The Corona serial port is not set correctly at the factory for input devices. To solve this, reset the jumpers inside the computer to allow for input devices. Consult your Corona manual for proper and complete instructions.
- Q3. My serial mouse does not plug into my IBM AT.
- A3. Most serial mice use a standard 25 pin serial connector while the IBM AT has a 9 pin serial connector. You can purchase an adapter from local IBM dealers.

14.3 Plotters

- Q1. My computer beeps four times when I attempt to plot with FRIEZE.
- A1. Your plotter cables are either nonstandard plotter cables or they are loose. Make sure your cable is securely connected. You should use a standard IBM to Hewlett Packard cable.
- Note:** Instead of an error message, FRIEZE beeps when a problem occurs. The number of beeps indicates different problems. See Chapter 12 for additional information.
- Q2. The plotter does not even pick up a pen. The error light starts blinking before anything happens.
- A2. This is certainly caused by either an improper cable or the wrong speed (baud rate) for your serial port. Check your cable carefully, and rerun the MODE command to

set the baud rate for your port. Note that some mouse drivers have a tendency to reset the baud rate on all the serial ports when they begin. Also, you might want to check PCINSTAL and make sure you selected the correct communications port for your plotter (only if the error light did not start blinking).

Q3. The plotter picks up a pen, sometimes draws and then stops moving; the error light begins blinking.

A3. This is caused by the plotter not responding to Xon/Xoff protocol. Make sure the dip switch in (the back of) the plotter is set appropriately to allow Xon/Xoff.

Q4. The plotter picks up a pen and then very slowly begins moving it, possibly without printing anything.

A4. Reset your print height to a number between 1 and 6. For fastest results, use a height of 1. You can get this simply by following this procedure:

1. Press the Shift-PrtSc/* keys. This invokes FRIEZE.
2. Select H - set height. Then type 1 followed by the Enter key.

Q5. The plotter is using the wrong colors for printout, or no colors at all, even though it picks up the pens and moves each of them down the page.

A5. Run Setcolor and recheck your color correspondence. The factory settings are arbitrary and probably incorrect for your pen colors. Read the section in the manual about Setcolor and plotters. Note that you do not need to reboot after running Setcolor, just start PC Paintbrush up again and check the new color settings.

Q6. There are white lines running horizontally across the paper.

A6. This is caused by having too small a height setting (or

your pens have totally dried out). Try a setting closer to 4 or 5 (versus recommended 2-3) if your pens are getting a bit old, or if you are using thin pens.

14.4 Printers

Q1. My Okidata printer does not work with PC Paintbrush.

A1. Two possibilities may cause this to happen.

- A) It is possible that you installed the wrong printer.
- B) If you have a Model 84 Okidata, it may not be able to handle graphics output. You need to upgrade your printer. Your Okidata dealer has graphics Eprom's in order to upgrade your printer.

Q2. When printing, my Epson, IBM Graphics or Okidata printers insert a blank line between every line of graphics.

A2. Your automatic line feed switch on your printer is on. Turn off this switch. Another possibility is that your line width is too large for the paper. Reset the value to accommodate the width of your paper.

14.5 PCjr

Q1. Often times I get an insufficient memory message with my PCjr.

A1. This happens if the additional memory was not loaded correctly. Follow the steps in the back of your manual for proper installation.

Note: If you are using IBM's add-on memory option of 256K, you can not run the latest version of PC Paintbrush in the 16 color mode if FRIEZE is loaded. In fact, you may need more than 256K memory to run the latest version of PC Paintbrush with your PCjr. If you want to run PC Paintbrush without loading FRIEZE, do not

type **PAINT**. Instead, type the first and third lines of PAINT.BAT. To determine what these lines are, at the **A>** prompt, type **TYPE PAINT.BAT** and press the Enter key. The contents of PAINT.BAT are displayed on your screen.

- Q2. When trying to use the 320x200, 16 color mode, the screen flashes.
- A2. The program was not installed with at least 32K RAM to video display. Reinstall and allocate at least 32K RAM for video display. Follow the directions at the back of your PCjr manual.

14.6 General Problems

- Q1. I installed PC Paintbrush on a hard disk. When I try retrieving pictures, fonts, cutouts or palettes, I receive a **Not Found** message.
- A1. PC Paintbrush searches for your picture on the main directory of the hard disk and not the subdirectory. For example, you want to retrieve a picture named GRAPH that you saved while in the PBRUSH subdirectory. Select the top line of the Page menu that reads: **A:_____** or another drive or subdirectory location. When the New search directory box appears, type in **C:\PBRUSH** and press the Enter key. Now your picture should be available through the Load from... option in the Page menu.
- Q2. When copying PC Paintbrush disk 1 in the installation procedure, not all PC Paintbrush files fit on my disk. (I get an insufficient disk space message.)
- A2. Delete any files that have either a PCX or BAS extension. The PCX files are picture files and the BAS files are slide show files and are not needed to run PC Paintbrush. At the **A>** prompt type, **DEL *.BAS** and press the Enter key to delete the BAS files. Type **DEL *.PCX** and press the Enter key to delete the picture

files.

- Q3. When I invoke **FRIEZE**, either it does not appear or if it does appear, it locks up the program.

- A3. It is possible that **FRIEZE** and one or more graphics programs are in memory. Remember, once you run **FRIEZE** it stays in memory until you reboot. If more than **FRIEZE** is present in memory, it may overlap with one of the programs and can not run. Insert DOS and reboot your system (by pressing the Ctrl/Alt/Del keys) and rerun **FRIEZE** (by typing **FRIEZE**).

- Q4. I want to move files from PC Paintbrush into another graphics program and vice versa.

- A4. You can not move files from one graphics program into another unless the program specifically supports the other. You can export files from another program into PC Paintbrush. Preferably, they should have the same number of colors.

Appendix A - File Extensions

Basically, there are six file extensions that should become familiar to you. These extensions are created by default, depending on the file contents.

1. **.PCX.** This file extension is used when you save a screen through the Save as... option in the Page menu.
2. **.PCC.** This extension is created when you Cut or Copy a cutout with the scissors or pick tool and save it to disk.
3. **.FNT.** The fonts, included mostly on disk 2, have the .FNT extension.
4. **.PAL.** When you retrieve a palette or create a new palette through the Save Pattern option in the Misc menu, the palette is saved with the .PAL extension.
5. **.PIC.** This extension is for Lotus pictures loaded from Merge Pic in the Page menu.
6. **.CNF.** This extension is for the optional PBRUSH.CNF file. This file gives you the ability to specify default subdirectories for your PC Paintbrush operations. For example, you can put for your fonts in one subdirectory, saved cutouts created through the pick or scissors tool in another subdirectory and pictures saved in Save as... in the Page menu in yet another subdirectory. To take advantage of this file, PBRUSH.CNF should be placed in your PBRUSH subdirectory if you have a hard disk or on your default drive if you have a floppy based system. PBRUSH.CNF contains lines of text, each line indicates while files are the subject followed by an equals sign and then the drive or subdirectory choices. Possible file sets are:
 1. **FONT** =subdir default font subdirectory.
 2. **PIX** =subdir default PCX subdirectory.

3. CUTOOUT = subdir default cut-paste subdirectory.
4. TEMP = subdir default temporary file subdirectory.

For example, we use the following setup:

```
P=\SSHOW  
F=\PBRUSH\FONTS  
TEMP = B:
```

This file lets us use the \SSHOW directory for pictures, \PBRUSH\FONTS for font information and floppies for temp files. (Since we share a network.) We store cutouts in the default, PBRUSH, directory. Note the mixing of full names and abbreviations in this list. Also note that a drive with no subdirectory name refers to the root, \, directory.

If you have a floppy based system, we would suggest something like:

1. If you plan on manipulating images bigger than one screenful:

```
Font = A:  
Pix = A:  
Cutout = A:  
Temp = B:
```

This lets the possible large temp files to have all of drive B and let the pictures, fonts and cutouts coexist of A.

2. Or,

```
Font = A:  
Pix = B:  
Cutout = B:  
Temp = B:
```

This lets you put a data disk in drive B and the PC Paintbrush disk in drive A.

Appendix B - Saving and Restoring Pictures

There are three ways to save and restore pictures:

1. The scissors and pick tool and Edit menu. First select the Name is... option in the Edit menu. Next select ?? at the bottom. When the Use file box appears, type in a file name and press the Enter key. Now define the cutout that you want to save using either tool. Then select either the Cut or Copy option in the Edit menu and choose the scissors or pick tool. To restore the picture, choose Paste from the Edit menu. Select the name of the file you wish to restore from Name is... in the Edit menu. Next select the scissors or pick tool and your picture becomes available to paste. This procedure is discussed in Section 6.2a.
2. The Save as... and Load from... options in the Page menu. Once you have completed the picture that you want to save, select Save as... then select ?? at the bottom. Type in the name of the file and press the Enter key when the Use file box appears. The entire screen, including the menus, tools, drawing widths and color palette is saved, along with your picture. To restore a picture, select the Load from... option and choose the name of the file you wish to restore.
3. FRIEZE gives you access to save and restore pictures. To implement FRIEZE, press the Shift and PrtSc/* keys together. The FRIEZE menu appears at the top of your screen.

FRIEZE - H,M,PR,S,W,V:

To save your picture, press S and the line appears:

FRIEZE - Save to =

Type in the name of the picture and press the Enter key. To restore a picture, press the Shift and PrtSc/* keys together. Press R and type in the name of the picture you wish to restore. If you restore a picture from PC Paintbrush, be sure to include the extension.

Appendix C - Special Menu Options

These items appear in the menu options.

1. **??**. This option lets you specify a name for your picture, cutout and color palette.
2. **Use file box**. When you select **??**, this box appears on your screen. Type in the name for your picture, cutout, or color palette. For example, type **BOX.PCX** to save a picture. Press the Enter key and your picture is saved to disk.
3. **A:_____** or **C:\PBRUSH_____**. This option tells you what drive you are using and lets you change drive locations. If you want to access a picture from drive **B>**, for example, select this option.
4. **Enter search directory**. This box appears when you select **A:_____**. Type in the drive location, so if your picture is on disk in drive **B>**, type **B:** and press the Enter key. Until you change drives again, this line will then read **B:_____**. If you have a hard disk, this line remains in the same subdirectory until you change it again.
5. **▲** and **▼**. These arrows appear on the side of some menu options. If the menu has more than seven files saved, not all can be listed on the screen at the same time. These arrows let you see the additional names. Press **↵** on top of either arrow to move you through the file names.

Index

A

A:_____	C-1
Adj. Aspect	7-17
Adj. Palette, Misc Menu	7-15
Airbrush Tool	6-13
Altering the Height, Plotters	11-2

B

Background Color	4-2
Bold, Style Menu	6-17
Brush Shapes, Misc Menu	6-25, 7-11

C

C, FRIEZE	9-5
Changing:	
Background Colors	4-2
Brush Shapes	6-25
Color Maps, Black and White Printers	10-4
Color Maps, Color Printers	10-6
Color Palettes	7-13
Colors	6-20
Fonts	6-16
Foreground Colors	4-2
FRIEZE Defaults	10-1
Height and Width	9-5, 10-2
Height, Plotters	11-2
Patterns	7-11
Pen Colors, Plotters	11-3
Plotters	8-2
Printers	8-2
Sizes	6-19

Tools	6-19
Characters Mode	9-5
Clear, Page Menu	7-7
Clear, Pick Menu	6-9
CNF	A-1
Color Chart, 16 Color Card	10-9
Color Chart, 2 Color Cards	10-12
Color Chart, 4 Color Cards	10-11
Color Eraser	6-22
Color Map Settings, Color Printers	10-6
Color Map Settings, Black and White Printers	10-4
Colors and Color Patterns	4-2
Constraining Cursor Movement	7-20
Copy	6-4
Ctrl/Alt/Del keys	8-3
Cursor	4-1
Curved Lines	6-27
Cut	6-4
Cut and Paste	6-1

D

DEF16	7-13
DEF2	7-13
DEF4	7-13
Digitizer	1-2
Dithering	10-8
Double Click:	
Color Eraser	6-22
Color Pattern	7-13
Eraser	6-21
Paintbrush	6-23
Pick Tool	6-12
Drawing	3-1
Drawing Devices	1-1
Drawing Widths	4-1

E

Edit Menu	6-1, 7-7
Edit Menu:	

Copy	6-4
Cut	6-4
Name is	6-4
Paste	6-5
Edit Pattern, Misc Menu	7-11
Eraser	6-21
Esc Key	1-2, 9-1
Exiting PC Paintbrush	7-7

F

F1	6-29, 7-18
F2	6-29, 7-18
F5	7-18
F6	7-18
F7	7-20
F8	7-20
File extensions:	
CNF	A-1
FNT	A-1
PAL	A-1
PIC	A-1
PCC	A-1
PCX	A-1
Filled Box	6-32
Filled Circle/Ellipse	6-36
Filled Rounded Box	6-34
FlipHorizontal, Pick Menu	6-8
Flip Vertical, Pick Menu	6-8
FNT	A-1
Fonts	6-16
Foreground Color	4-2
FRIEZE:	
Capabilities	8-1
Defined	8-1
Height	9-5, 10-2
Menu	9-1
Plotters	11-1
Width	9-5, 10-2
Function Keys:	
F1	6-29, 7-18

F2	6-29, 7-18
F5	7-18
F6	7-18
F7	7-20
F8	7-20

G

Get Pattern, Misc Menu	7-13
------------------------------	------

H

H, FRIEZE	9-5, 10-2
Hard Disk, Installation	2-3
Height, FRIEZE	9-5, 10-2
Hexadecimal Digits	10-6
Hollow Box Tool	6-31
Hollow Circle/Ellipse	6-35

I

Improving Your Printout	13-1
Installation:	
Hard Disk	2-3
PCjr	2-3
Single Drive PC	2-3
Two Drive PC	2-2
Inverse, Pick Menu	6-8
Italic, Style Menu	6-17

J

Joystick	1-2
Joystick, Set Speed	7-9

K

Kerning, Style Menu	6-17
---------------------------	------

L

Left Margin, FRIEZE.....	9-7
Light Pen.....	1-2
Light, Style Menu.....	6-17
Line Tool.....	6-29
Load from..., Page Menu.....	7-2
Local Undo.....	7-1

M

M, FRIEZE.....	9-7
Making the Working Copy.....	2-1
Medium, Style Menu.....	6-17
Menus.....	4-3, 7-1
Menus:	
Edit.....	6-1, 7-7
Misc.....	7-9
Page.....	7-2
Pick.....	6-7, 7-8
Size.....	6-19, 7-8
Style.....	6-16, 7-8
Undo.....	3-1, 7-1
Merge Pic, Page Menu.....	7-5
Misc Menu.....	7-9
Misc Menu:	
Adj. Aspect.....	7-17
Adj. Palette.....	7-15
Brush Shapes.....	6-25, 7-11
Edit Pattern.....	7-11
Get Pattern and Save Pattern.....	7-13
Set Speed.....	7-9
zoom-in/Zoom-in.....	7-9
Mouse.....	1-2
Moving a Cutout.....	6-2

N

N, FRIEZE.....	9-5
Name is.....	6-4
Naming a Cutout.....	6-4

New search directory.....	C-1
Normal Mode.....	9-7

O

Opaque Paste.....	6-11
Opaque, Style Menu.....	6-18
Outline, Style Menu.....	6-17

P

P, FRIEZE.....	9-4
Page Menu.....	7-2
Page Menu:	
Clear.....	7-7
Load from.....	7-2
Merge Pic.....	7-5
Print.....	7-6
Quit.....	7-7
Save as.....	7-2
Show Screen.....	7-6
Paint Roller Tool.....	6-25
Paintbrush Tool.....	6-23
PAL.....	A-1
Paste.....	6-5
PC Paintbrush Screen.....	3-1
PC Paintbrush, defined.....	1-1
PCC.....	A-1
PCINSTALL.....	2-1, 2-5
PCjr, Installation.....	2-3
PCX.....	A-1
Pen Colors, Plotters.....	11-3
Pick Menu.....	6-7, 7-8
Pick Menu:	
Clear.....	6-9
Flip Horizontal, Vertical.....	6-8
Inverse.....	6-9
Rotate.....	6-8
Shrink + Grow.....	6-8
Tilt.....	6-9
Pick Tool.....	6-1

Print, Page Menu	7-6
Print, FRIEZE	9-4
PrintaColor Printers	11-5
Printer Color Codes	10-6
Printer Patterns	10-4
Program Requirements	1-1
Proportional, Style Menu	6-18

Q

Quit, Page Menu	7-7
-----------------------	-----

R

R, FRIEZE	9-4
Rebooting your System	8-3
Restore, FRIEZE	9-4
Restoring Cutouts	6-4
Restoring Pictures	7-2, 9-4, B-1
Rotate, Pick Menu	6-7
Rounded Box	6-33
Rounded Filled Box	6-34
Running Setcolor	10-1

S

S, (Save) FRIEZE	9-3
S, (Sideways) FRIEZE	9-5
Save as, Page Menu	7-2
Save Pattern, Misc Menu	7-13
Save, FRIEZE	9-3
Saving Cutouts	6-4
Saving Pictures	7-2, 9-3 B-1
Saving Pictures, Single Drive PC	6-5
Saving Pictures, Two Drive PC	6-5
Scissors Tool	6-1
Scroll Bars	5-1
Serial Printers	11-5
Set new color correspondence	10-5
Set Speed, Misc Menu	7-9
Setcolor	10-1

Setcolor Menu	10-1
Setting the:	
Height	9-5
Left Margin	9-7
Viewport	9-1
Width	9-5
Shadow, Style Menu	6-17
Shift Key, Constraining Movement	7-20
Show Screen, Page Menu	7-6
Shrink + Grow, Pick Menu	6-8
Sideways Mode	9-5
Single Drive PC:	
Installation	2-4
Saving Pictures	7-2, 9-3, B-1
Saving Cutouts	6-4, B-1
Size Menu	6-19, 7-8
Size Menu, X and Y Options	6-19
Special Menu Options:	
A:_____	C-1
Enter search directory	C-1
Use file Box	C-1
Stopping:	
Paint Leaking	6-25
PC Paintbrush	7-7
Printout	1-2
Style Menu	6-16, 7-8
Style Menu:	
Bold	6-17
Font	6-16
Italic	6-17
Kerning	6-17
Light	6-17
Medium	6-17
Opaque	6-18
Outline	6-17
Proportional	6-18
Shadow	6-17
Underline	6-17
Sunburst Drawings	6-29
SuperCalc3	12-1

T

Technical information	12-2
Text Tool	6-14
Three Button Mouse	1-2
Tilt, Pick Menu	6-9
Toolbox	4-1
Tools	6-1
Tools:	
Airbrush	6-13
Color Eraser	6-20
Curve	6-27
Eraser	6-22
Filled Box	6-32
Filled Circle/Ellipse	6-36
Hollow Box	6-31
Hollow Circle/Ellipse	6-35
Line	6-29
Paint Roller	6-25
Paintbrush	6-23
Pick	6-1
Rounded Box	6-33
Rounded Filled Box	6-34
Scissors	6-1
Text	6-14
Transparent Paste	6-11
Two Drive PC:	
Installation	2-2
Saving Pictures	7-2, 9-3, B-1
Saving Cutouts	6-4

U

Underline, Style Menu	6-17
Undo Menu	7-1
Update policy	I-1
Use file Box	C-1

V

V, FRIEZE	9-1
Viewport	9-1

W

W, FRIEZE	9-5, 10-2
Width, FRIEZE	9-5, 10-2

Z

zoom-in, Misc Menu	7-9
ZOOM-in, Misc Menu	7-9

PC PAINTBRUSH II FOR MINDSET II MANUAL ADDENDUM

The reference manual for PC PAINTBRUSH II is included and provides all of the instructions for using this program. The directions contained in these few pages, however, supersede ALL of the startup and installation instructions in that manual, especially pages 2-1 through 2-8.

Introduction

The use of the PC PAINTBRUSH II disk is described below. With it you can run PC PAINTBRUSH II, make copies of data diskettes (including making a backup of PC PAINTBRUSH II), or prepare new diskettes for use with your MINDSET system. Additionally, some new, unique features have been added to make this version of PC PAINTBRUSH II especially suited to video applications.

Input Devices

PC PAINTBRUSH II can be used with the MINDSET Mouse or a MINDSET-compatible digitizing tablet.

WHEN USING THE TABLET AS YOUR POINTING DEVICE: pressing the pen on the tablet is the same as pressing the LEFT mouse button. Pressing the pen on the tablet while simultaneously holding down the ALT key on the keyboard is the same as pressing the RIGHT key on the mouse.

PC PAINTBRUSH II ADDENDUM

Starting the Program

To begin, place the Program Diskette in the left diskette drive (drive A) and turn down the latch. If the power to your MINDSET is off, turn it on using the switch at the rear of the keyboard. If power is already on, press the ALT key and hold it down while you press the RESET key. In either case, the computer will load programs from the Program Diskette and begin to operate.

When the startup programs are loaded, the screen will show a menu of choices. These are:

MENU

1. Execute PC PAINTBRUSH II
2. Change the PC PAINTBRUSH II defaults
3. Create a new Data Diskette
4. Copy a Diskette
5. Exit to DOS
6. Display Document Updates

Press a number and then RETURN:

Backing up your Program Diskette

It is important to make a backup copy of your PC PAINTBRUSH II Program Diskette before doing anything else. To do this,

PC PAINTBRUSH II ADDENDUM

start the program as described above and choose option 4, "Copy a Diskette."

The program will ask you to place the "source" diskette in drive A and the "destination" diskette in drive B. The source diskette is the one you wish to copy. The source diskette in this case is your PC PAINTBRUSH II Disk 1 Program Diskette and is already in drive A. Place a blank diskette in drive B. When you are ready, press any key. The program will copy your Program Diskette to the blank disk.

When it is done the program will ask you if you wish to copy another diskette.

Type "Y". The program will ask you again to place the source diskette in drive A and the destination diskette in drive B. Remove the PC Paintbrush II Disk 1 from drive A as well as the copied diskette from drive B.

Place PC Paintbrush II Disk 2 in drive A and turn down the latch. Place a second blank formatted disk in drive B and turn down the latch. Press a key.

When you are done, answer "N" when the program asks you to if you wish to copy another diskette.

Remove the diskettes from the drives. Label your copied diskettes as your working copies. Place the original diskettes in a safe place so that you can make additional copies if your working diskette is damaged.

Place your working PC Paintbrush II Disk

PC PAINTBRUSH II ADDENDUM

1 in drive A and follow the instructions for "Starting the Program," above.

Selecting the Program Options

PC PAINTBRUSH II can use all of the MINDSET graphics modes. The default mode is 640x400 with 4 colors. If you wish to change the graphics mode, select option 2. It will allow you to change not only screen mode, but to select the input device and printer type.

Option 2 is used to run the PCINSTAL program, so you may ignore the directions for starting PCINSTAL on page 2-5 of the manual.

Remember, you must use your working diskettes to make any configuration changes. Your original diskettes cannot be changed.

PC PAINTBRUSH II comes ready to use with the MINDSET Mouse and the Quadjet printer. If you have a different printer or wish to use the MINDSET tablet as an input device, you should use option 2 to change these defaults. The system will prompt you to re-boot the system after changing the defaults.

To prepare a data diskette for use with the computer, press 3 followed by the RETURN key. Then just follow the instructions presented on the screen.

To copy a data diskette, press 4 and then the RETURN key. Just follow the instructions presented on the screen.

When you are through with the

PC PAINTBRUSH II ADDENDUM

operation you requested, the menu will be displayed so you can make your next choice.

Installing PC PAINTBRUSH II on your Hard Disk

You may use PC PAINTBRUSH II from your MINDSET hard disk if you have one. To install it, use the following directions.

1. Boot your system from the hard disk by pressing ALT-RESET.
2. At the C> prompt, place your PC PAINTBRUSH II Program Disk 1 in drive A.
3. Type A: and press RETURN.
4. At the A> prompt, type HDINSTAL followed by the RETURN key.
5. The program will copy the proper files to your hard disk and tell you when it is done.
6. At the A> prompt, type C: followed by the RETURN key.
7. At the C> prompt, type CD\PBRUSH, followed by the RETURN key.
8. At the C> prompt type: COPY CON PBRUSH.CNF, followed by the RETURN key. Then type the following lines, each line followed by the RETURN key:

```
FONT=C:\PBRUSH  
PIX=C:\PBRUSH  
CUTOUT=C:\PBRUSH
```

PC PAINTBRUSH II ADDENDUM

TEMP=C:\PBRUSH

Now press the F6 function key,
then press the RETURN key

Running PC PAINTBRUSH II from your Hard Disk

1. Boot your system from the hard disk.
2. At the C> prompt, type CD\PBRUSH followed by the RETURN key.
3. At the C> prompt, type PAINT followed by the RETURN key.
4. PC PAINTBRUSH II will load and execute.

NOTE: To change the PC PAINTBRUSH II defaults for color mode, printer, or input device once you have installed PC PAINTBRUSH II to your hard disk: follow steps 1 and 2 above, then at the C> type PCINSTAL followed by the RETURN key.

New Features

Several new features have been added to PC PAINTBRUSH II to make it more useful in video applications. The first is the ability to adjust the color palette entries so that any of the 512 MINDSET colors can be used. In addition to setting the colors, any or all of them can be set as "keyed" colors, allowing background video to show through. These options are explained in the following pages.

PC PAINTBRUSH II ADDENDUM

Adj. Palette

The ADJ. PALETTE (ADJUST PALETTE) feature allows you to change the default colors present in the color palette at the bottom of the screen. ADJ. PALETTE is found in the MISC. MENU.

The MINDSET has the capability to display 512 different colors (four or sixteen at a time) on the PC PAINTBRUSH II screen, depending on which mode is selected (see page 8 of this addendum for screen modes and colors supported on the Mindset). When the ADJ. PALETTE submenu is selected, the following menu appears:

KEY BIT	ON	OFF
RED	GRN	BLU
OK	CANCEL	

Where: RED = The red color component
GRN = " green " "
BLU = " blue " "
KEY = Indicator for whether this color is "keyed"

Move the point of the arrow cursor to whichever basic (solid) color you wish to change. The hot spot is the point of the arrow. Click the mouse button once. Now move the cursor up and position it over the RED, GRN or BLU boxes.

Click the left mouse button to gradually reduce the designated component (red, green, or blue) in the color selected for adjustment.

Click the right mouse button to gradually increase the designated component.

If you are using a tablet, select the basic color to be modified by pointing to it and pressing the pen. Then move the cursor over the RED, GRN, or BLU boxes.

Press the pen to gradually reduce the designated component (red, green, or blue) in the selected color.

Hold the ALT key and press the pen to gradually increase the designated component.

Move the cursor to the KEY box. Click the left mouse button to toggle the setting of the KEY attribute for the color (see "Keyed", below, for an explanation of what keying does).

Click the OK box to retain palette changes, CANCEL to reset the previous palette settings.

NOTE: There are eight available graphic display modes for the MINDSET (below):

SCREEN MODE	RESOLUTION	COLORS
1	640 * 200	2
2	640 * 400	2
3	320 * 200	4
4	320 * 400	4
5	640 * 200	4
6	640 * 400	4
7	320 * 200	16
8	320 * 400	16

PC PAINTBRUSH II ADDENDUM

VIDEO SIGNAL CONTROL:

Keyed

This option is only valid when your MINDSET is connected to the Video Production Module.

When this option is selected (as indicated by the ON box being highlighted to the the right of the item), the MINDSET allows the background video signal to show through those colors for which the "key" attribute is enabled (see "Adj. Palette", on page 7).

As an example, suppose you create a screenful of text over a black background. The text can be any color, type, size, etc., allowed. If you have selected the "key" attribute for the black color, then selecting "Genlock On" in the "Screen Type" option in the "Page" menu, will make it appear that your text has been created over whatever incoming video signal you supply.

As many or as few colors as you wish can be keyed simultaneously.

Avoid keying the two colors at the far left of the 32 color choices at the bottom of the screen (these are black (top) and white (bottom) by default). These are the two colors used to draw most of the menus. If either of these colors are keyed, the menus may be hard to read.

Screen Type

PC PAINTBRUSH II ADDENDUM

"Screen Type" is a submenu found under the Page Menu. This submenu allows you to modify the way the image is displayed. There are four options on this submenu which can be selected "ON" or "OFF":

INTERLACE: When ON, the computer image is output to the monitor in interlaced fields; that is, first, all of the even-numbered scan lines are displayed, then all of the odd-numbered scan lines. If you are intending to videotape the image, you should select interlace ON. When interlace is ON, it is normal for the image to flicker a bit.

Those screen modes (2,4,6,8) which have 400 scan lines must have interlace ON in order to display the entire image. Interlace is ON by default whenever you start PC Paintbrush II in any of these modes, HOWEVER THE INTERLACE OPTION WILL INDICATE "OFF" (this is a bug in the program). Selecting interlace ON or OFF will still work correctly in these modes, and once selected manually, the option will display the correct ON/OFF indication.

GENLOCK: When ON, you will be able to see the external video signal "through" any colors which are keyed (see the "Adj. Palette" feature above). When OFF, you will never see the external video signal, even if you have selected certain colors to be keyed.

B/W ONLY: When ON, only a black and white image is displayed. When OFF, a color image is displayed.

PC PAINTBRUSH II ADDENDUM

FIXED PHASE: Certain patterns of color may flicker strongly on a composite monitor. Setting fixed phase ON may reduce the flicker, however, it will affect the way thin vertical lines are displayed (it will make them jagged).

Miscellaneous

When in a 16-color mode, patterns are only 4 pixels wide by 8 pixels tall rather than the 8x8 matrix used in the other modes. Therefore, when you are editing a pattern while in a 16-color mode, you will only be able to modify the leftmost 4 pixels of the matrix.